

Tutorials for Origin

Copyright © 2016 by OriginLab Corporation

All rights reserved. No part of the contents of this book may be reproduced or transmitted in any form or by any means without the written permission of OriginLab Corporation.

OriginLab, Origin, and LabTalk are either registered trademarks or trademarks of OriginLab Corporation. Other product and company names mentioned herein may be the trademarks of their respective owners.

OriginLab Corporation
One Roundhouse Plaza
Northampton, MA 01060
USA
(413) 586-2013
(800) 969-7720
Fax (413) 585-0126
www.OriginLab.com

Table of Contents

Tutorials for Origin.....	1
Table of Contents.....	iii
1 Getting Started	1
1.1 My First Graph.....	1
1.2 Graph Templates and Batch Plotting	5
1.3 Data Selection	8
1.4 Merge and Arrange Graphs	12
1.5 Publishing Graphs	17
1.6 3D and Contour	20
1.7 Gadgets.....	23
1.8 Curve Fitting.....	25
1.9 Peak Analysis.....	29
1.10 Statistics	32
1.11 Analysis Template	36
1.12 Apps in Origin.....	38
2 Video Tutorials	41
3 User Interface	43
3.1 Origin GUI	43
4 Data Analysis.....	59
4.1 Gadgets.....	59
4.2 Curve Fitting.....	132
4.3 Signal Processing	337
4.4 Peak Analysis.....	429
4.5 Data Manipulation	480
4.6 Analysis Templates	536
4.7 Analysis Themes	550
4.8 Batch Processing	553
5 Statistics	573
5.1 Descriptive Statistics	573
5.2 Hypothesis Tests.....	607
5.3 ANOVA.....	618
5.4 Nonparametric Tests.....	655
5.5 Survival Analysis	666
5.6 Multivariate Analysis	679
5.7 Power and Sample Size.....	716
5.8 ROC curve.....	722
6 Graphing	725
6.1 Plotting	725
6.2 Axis.....	831
6.3 Compare Graphs Dynamically by Changing Data Filters	858
6.4 Layers.....	874
6.5 Graph Template and Theme	904
6.6 Line and Symbol	905
6.7 Column, Bar and Pie	1013
6.8 Multi-Axis and Multi-Panel.....	1102
6.9 Contour.....	1173
6.10 Statistics	1252
6.11 Polar	1474
6.12 3D Graphs	1567

6.13	Plot Functions with Parameters Defined in a Worksheet.....	1774
6.14	Windrose Graph	1780
6.15	2D Vector Graph	1791
6.16	Piper Diagram	1793
6.17	Waterfall	1798
6.18	Open-High-Low-Close-Volume Stock Chart	1813
7	Data Management.....	1821
7.1	Working with Multi-Sheet Workbooks	1821
7.2	Adding Objects to Worksheet.....	1828
8	Data Exploration.....	1835
8.1	Data Reader Tool.....	1835
8.2	Use Data Cursor to Show the Difference between the Data	1839
9	Importing Data.....	1847
9.1	ASCII	1847
9.2	Tutorial: Importing Data.....	1859
9.3	Import Data from a Database.....	1868
9.4	Import Data from a Database for Analysis	1882
9.5	Importing Multiple Files into Workbooks Cloned from Active Workbook	1898
9.6	SQL Editor for Database Analysis	1901
9.7	Digitizer	1914
9.8	Update Database Importing By LabTalk Substitution	1940
9.9	Update Graph By Reimport Data From Database	1951
10	Exporting and Presentation.....	1979
10.1	Exporting	1979
10.2	Presentation	1987
11	Collaboration and Connectivity.....	1995
11.1	Connectivity.....	1995
12	Programming.....	2013
12.1	LabTalk.....	2013
12.2	Origin C	2017
12.3	X-Functions	2063
Index	2125

1 Getting Started

If you are new to Origin, or have used a much older version in the past, it is highly recommended that you start with these tutorials. Once you have familiarized yourself with the interface and key concepts of graphing and analysis introduced in these lessons, you can then move on to other chapters that cover Origin features in more detail.

At the end of each lesson, we ask you to save the project. Please work through the tutorials sequentially as some build on previous lessons.

- [My First Graph](#)
- [Graph Templates and Batch Plotting](#)
- [Data Selection](#)
- [Merge and Arrange Graphs](#)
- [Publishing Graphs](#)
- [3D and Contour](#)
- [Gadgets](#)
- [Curve Fitting](#)
- [Peak Analysis](#)
- [Statistics](#)
- [Analysis Template](#)
- [Apps in Origin](#)

1.1 My First Graph

In this first lesson, we will generate some data, create a graph, do some simple customization of the graph, and save the data and graph as an Origin project.

1.1.1 Generate data and graph


1. Launch Origin. You will see an empty workbook with one worksheet containing two columns.
2. Right-click on column A, expand the context menu if needed, and select **Fill Column with: A set of Numbers...**





You can turn off collapsible menus by unchecking the **Enable Collapsible Menus** check box on the **Miscellaneous** tab of the **Tools:Options** dialog.

3. In the dialog, set **From** as -10, keep **To** as 10, set **Increment** as 0.1. Click **OK** to close the dialog. Column A will be filled with numbers in the specified range.




- We will now set column B as a function of column A. Double-click in **F(x)** label row of column B. This will place you in edit mode for that cell. Type the formula:




- Now let us create a graph. Click on the header of column B to select the entire column. Then click the **Line** button  in the **2D Graphs** toolbar docked at the bottom left of the interface. A graph window will open, with the data plotted as a line.




1.1.2 Customize the graph


- We will now do some simple customization of the graph. Right-click on the X axis, and from the context menu, select **Hide Grids**. This will add grid lines for the X axis. Do the same for Y axis.
- Click on the line plot to select it. Then from the **Style** toolbar docked at top middle of the interface, change the color to **Blue** by using the **Line/Border Color**  button.
- Change the width to **3** by using the the **Line/Border Width** drop-down list .
- Single-click inside the layer, but not on the grid lines or plot. You may need to click once to deselect your plot and then again to select the layer. The graph layer will be selected, and this will be indicated by selection handles. Change the layer background color to **LT Yellow** by using the **Fill Color** button  in the **Style** toolbar.
- In column A, double-click the cell for **Long Name** and type **my x**.


6. For column B, type **my y** into **Long Name**, **mV** into **Units**, and **Sine Wave** into **Comments**.
7. Click and select the graph window. The X and Y axis title and legend on graph will be updated accordingly. Your graph should look like below:




1.1.3 Explore data graphically

1. Let us now explore the data graphically. Make sure the graph window is active by clicking on the title bar.
 - Hold the **Z** key down and use the mouse wheel to zoom in and out on the X axis.
 - Hold the **X** key down, and use mouse wheel to pan across the x axis.
 - 💡 Hold the **Shift** key down along with **Z/X** keys to zoom/pan in Y direction.
 - Bring the plot back to full scale by clicking the **Rescale** button  in the **Graph** toolbar docked to the right side of the interface.
 - 💡 Use shortcut **CTRL+R** to rescale plots in the graph layer.



2. Click the **Data Reader**  button from the **Tools** toolbar docked to the left side of the interface.
3. Place the cursor on the curve. You can now use arrow keys to move the cursor along the data plot and read coordinate values. Or, you can click anywhere on the curve to read the coordinate values at that location.



1.1.4 Save the Project

We will now save this Origin project for later use.

1. Move mouse over to the Project Explorer bar on the left side of the work space to expand it.
2. Right click on the **Folder1** in the upper **folders panel** and choose **Rename** from the context menu. Type **My First Graph** to rename the folder.
3. Choose menu **File: Save Project** to save the project. Give the project a name such as **Getting Started Tutorials**.



Files created by the user such as projects, graph templates, fitting functions etc are by default saved in the **User Files Folder (UFF)**. You can find the **UFF** and other useful folder locations in the **System Path** tab of the **Tools:Options** dialog.

1.2 Graph Templates and Batch Plotting

In this lesson we will learn about graph templates, and also how to perform batch plotting.


1.2.1 Graph Templates


Let's start with the project file we saved in [lesson one: My First Graph](#). Click to select the graph window.




You can quickly open recently-saved project files from the **File: Recent Projects** list.

1. Double-click on the axis tick label to open the **Axis Dialog**.
2. Press the **Ctrl** key and select the **Top** and **Right** icons in the left list box. Choose the **Line and Ticks** tab and select the **Show Line and Ticks** check box then press **OK**.



3. Now let's save the graph as a template. Right-click on the graph title bar, and choose **Save Template As...** from the context menu.
4. In the dialog, set the **Template Name** as **My Line** and click **OK** to save the template.
5. We will now generate a new column of data. Activate the worksheet, right-click on the gray area to the right of the columns, and select **Add New Column** from the context menu.
6. Click inside the **F(x)** cell of this column, then right-click and select **Open Dialog...** from the context menu. You can use the shortcut **Ctrl+Q** instead of the context menu.
7. In the dialog, use the **Variables: Add Range Variable by Selection** menu item to open the **Select from Worksheet** dialog. Then select the first two columns in this worksheet, click the  button to confirm selection and click **OK** accepting the default setting for **Insert Mode**. Two range variables will be added to the **Before Formula Scripts** panel of the dialog.
8. Enter the the following expression into the top panel:

r2/r1




9.



Use the **Formula: Load Samples** menu in this dialog to view various examples on setting column values. The **Function** menu offers a large selection of functions. You can also search for suitable functions using the search button located in the top right side of the formula edit box.

10. Click **OK** to close the dialog and see the values in column C. Type **sin(x)/x** into the **Comments** cell of the column.
11. Click on the header of column C to select the entire column. From the menu, choose **Plot: Templates > User** and from the drop-down menu select the **My Line** template we created before. A new graph will be created using data from column C.




1.2.2 Batch Plotting

In this section, we will perform batch plotting by first creating one graph and then cloning that graph using other data.

1. Go to **Project Explorer**. In the upper panel, right-click on the root level and choose **New Folder**.

- Right-click on newly created folder, select **Rename**, and assign the name **Batch Plotting**. Click on the empty folder to open it.
- Using **Windows Explorer** outside of Origin, navigate to the folder <Origin EXE Path>\Samples\Import and Export\. Press the **Shift** key and choose the following three files:
 - S15-125-03.dat
 - S21-235-07.dat
 - S32-014-04.dat
- Drag and drop the selected files onto the Origin workspace. The selected files are imported into three new workbooks.



Note: To import data files by drag-and-drop, [you must not be running Origin as an administrator](#).

- Select one of the workbooks, then click on the header of column B and drag the mouse to column D, selecting all three columns. Then select the menu: **Plot > 2D: Multi-Y: 3Ys Y-YY**.



Origin will look to the left of the selection to find the X column and plot the selected data against the the 1st column in the worksheet.


- Double-click inside the layer to open the **Plot Details** dialog. In the left panel, we can see there are three layers. Expand **Layer1** and choose the plot under it. Then in the right panel, change the line width by choosing the **Line** tab and setting **Line Width** as **3**. Repeat the line width setting for the plots in the other two layers by selecting them from the left panel. Click **OK** to close the dialog and apply the settings.
- Now we will clone this graph using data in the other workbooks. Right-click on the title bar of the graph and select **Duplicate:Batch Plotting**, and then choose **Duplicate with New Books**.

8. In the dialog, press the **Shift** key and select the two workbooks in the top box.



You can set the **Match Plot Columns by** drop-down appropriately to find worksheets in the project that match the data configuration of the current graph.

9. Click **OK**. If prompted to rescale the axes to show all data, answer **Yes** and click **OK**. Two similar graphs will be created with data from the other two books.




10. From the menu, choose **File: Save Project** and save your modified project.

1.3 Data Selection

In this lesson we will learn about flexible ways of selecting data for plotting.

1.3.1 Plotting Data from Multiple Worksheets

1. Let's start with the project we saved in [lesson two: Graph Templates and Batch Plotting](#). Select any workbook, and make sure no data columns are selected. You can click in the gray area outside of columns to remove selection.
2. Select menu **Plot > 2D: Line: Line**. The **Plot Setup** dialog will open.
3. Click the  button on the right side to expand the upper panel if it is not already open.
4. Set the **Available Data:** drop-down list in the left panel to **Worksheets in Folder**.



To pick up worksheets from anywhere in your project, set the drop down to **Worksheets in Project**.


5. Hold down shift key and select all three data sheets named **Trial Run 1**, **Trial Run 2** and **Trial Run 3**.


- Using the check boxes in the middle panel, assign *Time* as **X** and *Position* as **Y**. Click **OK** button to create the graph.



This dialog has a third bottom panel which can be used to assign data to different layers in a multi-layer graph. If that panel is open, you can simply collapse it and then click **OK** to create the graph.






- We will now customize the legend for this graph. Right click on the legend and select **Legend: Update Legend...**
- In the dialog that opens, set **Auto Legend Transition Mode** as **Custom**. Then click the  button on the right of **Legend Custom Format (@D, @LU etc)** edit box, and in the fly-out menu select **@WS: Sheet Display Name**.
- In the edit box, type a hyphen - after the string **@WS**, and again click the right arrow button. This time select **@LD"Sample": Sample**, which corresponds to column header row *Sample* in the worksheet. Click the **OK** button. The legend will now display the sheet name and the sample name.




1.3.2 Using another Column to Set Color of a Plot

- Go to **Project Explorer**. In the upper panel, right-click on the root level and choose **New Folder**.
- Right-click on newly created folder, select **Rename**, and assign the name **Data Selection**. Click on the empty folder and open it.


3. Click **Import Single ASCII** button  and browse to <Origin EXE Path>\Samples\Graphing folder and select the file *US Mean Temperature.dat* and import it.
4. We want to plot the positions of US major cities (columns *Longitude* and *Latitude*) as a scatter plot and then colormap the data points with the annual mean temperature (column *Annual*). Click on the header of column named **January** and drag and expand the selection all the way to the column named **December**. Then right click to choose **Hide/Unhide Columns: Hide**.
5. Select the *Longitude* columns, then right-click and select **Set As: X**.
6. Select the *Latitude* and click **Scatter** button  on the bottom left toolbar to create the plot of longitude vs. latitude.
7. Double-click on any of the data points to bring up **Plot Details - Plot Properties** dialog.
8. With the data plot node [*US Mean Temperature.dat*]... under *Layer1* selected in the left panel, activate the **Symbol** tab on the right panel. Click the **Symbol Color** drop-down and in the fly-out, switch to the **By Points** tab.
9. Click the **Color Mapping** drop-down and select **Color Mapping: Col(P): "Annual"**. Click **Apply** to see the effect, still keeping the dialog open.



10. Let us now set the axes lengths to scale with the range of X and Y values represented in the graph. Click to select *Layer1* node on the left panel. Then go to the **Size/Speed** tab on the right side. Check the **Link Axis Length to Scale with X:Y Ratio** box and keep the ratio as *1*. Click **OK** to exit the dialog and see the effect.
11. The colormap by default is set to *Rainbow*. Click on any data point in the graph, and then click on the **Palette** toolbar button  in the **Style** toolbar. Select the *Temperature* palette to better reflect the data. Click anywhere on the graph to deselect the plot.





You can add a map to a graph using the [Maps Online](#) App. [This blog post](#) is a good place to start.



- From the menu, choose **File: Save Project** and save your modified project.

1.3.3 Selecting Multiple Non-adjacent Columns for Plotting

- Open a new workbook window by clicking on the **New Workbook** button  in the **Standard** toolbar.
- Click the **Import Excel** button  on **Standard** toolbar. In the file dialog that opens, browse to `<Origin EXE Path>\Samples\Import and Export` folder and select the file *United States Energy (1980-2013).xls*. Make sure that the **Show Options Dialog** check box is checked, and press **OK**.
- In the import options dialog that opens, expand the **Column Headers** node. Set the **Index of Rows for Long Name** drop-down to 3, and the **...Units** drop-down to 4. Then set the drop-downs for **...Comment From** to 1 and **...Comment To** to 2.
- Check **Apply Header to All Sheets** so that these settings are used for every sheet in the Excel file.



- Press **OK** to import the file. Then go to the first sheet named *Oil*. Hold the **Ctrl** key to select *Crude Oil Production*, *Oil Consumption* and *Total Oil Production* columns.

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)	G(Y)
Long Name	Year	Crude Oil Prod	Estimated Petr	Oil Consumpt	Refinery Capac	Total Oil Produ	Proved Reserv
Units		1K Barrels/Day	1K Barrels/Day	1K Barrels/Day	1K Barrels/Day	1K Barrels/Day	1B Barrels
Comments	Source: U.S. Energy Information Administration						
F(X)=							
1	2013	7441.4904	-6618.3613	18961.1285		12342.7571	30.529
2	2012	6496.6967	-7371.5197	18490.2136	-17736.37	11118.6939	26.544
3	2011	5644.7918	-8753.6067	18882.0725	17736.37	10128.4657	23.267
4	2010	5481.8712	-9484.537	19180.126	17583.79	9695.589	20.682
5	2009	5349.8329	-9641.315	18771.4	17671.55	9130.0849	19.121
6	2008	5000.0628	-10934.0379	19497.9641	17593.847	8563.9262	21.317
7	2007	5076.9908	-12210.9752	20680.378	17443.492	8469.4027	20.972
8	2006	5087.8685	-12371.0947	20687.418	17338.814	8316.3233	21.757
9	2005	5181.5178	-12477.219	20802.1615	17124.87	8324.8425	21.371



- Then go to menu **Plot > 2D: Multi-Panel: Stack...** and accept default settings in the dialog, to create a stacked plot.

Save your project file.

1.4 Merge and Arrange Graphs


In this lesson we will create some graphs, merge them, and then arrange layers in the merged graph. We will also save the graph as a cloneable template to quickly re-create the graph from similar data.

1.4.1 Import data and create graphs

- Open the project file we saved in [lesson three:Data Selection](#). In **Project Explorer**, create a new folder under the root folder and rename it as **Merging Graphs**. Click on the empty folder to open it.
- Click the **New Workbook**  button on the Standard toolbar.
- With the blank workbook active, click the **Import Single ASCII** button  on the **Standard** toolbar. In the file dialog, navigate to the folder `<Origin EXE Path>\Samples\Statistics` and select *automobile.dat*. Click **Open** to import the file.



You can uncheck the **Show Options Dialog** check box in the file dialog to prevent the ASCII options dialog from popping up. The default settings will be used next time you import a file into a new book.

4. Click on the header of column C to select the entire column. Click the **Scatter** button  on the **2D Graphs** toolbar to create a scatter graph.
5. Click on the scatter plot to select it, then right-click on the plot and select **Change X:** **[automobile]automobile!G(Y):EngineDisplacement** from the context menu to change the X data. A reminder message pops up asking if you would like to rescale the graph. Select **Yes** and press **OK**.



Reminder messages have multiple options. If you select **Yes**, and do the same in the future, **no need to ask again**, the dialog will not show again. You can reactivate all reminder messages from the menu **Help: Reactivate Reminder Messages**.

6.



7. Select the legend and press the **Delete** key to delete it.
8. We will now make copies of this graph and change the data in the copies. First go back to the worksheet, and press the **X** button on the top right of the title bar, and in the dialog that pops up, select **Hide**. This simply hides the window from the interface.




Hidden windows are displayed with a dimmed icon in the lower panel of Project Explorer. You can double-click on the entry to re-open the window.

9. Right-click on the graph window title bar and select **Duplicate** to create a copy. Do this two more times, so you end up with four graph windows.
10. Select the menu **Window: Tile Vertically** to arrange the 4 graphs without overlap.
11. Use the **Change X/Change Y** menu described before, to change X/Y designations for the copy graphs as below, and rescale when promoted:
 - o Copy 1: Change Y to *[automobile]automobile!D(Y):0^60 mph*
 - o Copy 2: Change X to *[automobile]automobile!E(Y):Weight*
 - o Copy 3: Change X to *[automobile]automobile!F(Y):Gas Mileage*
12. Activate the graph of Power vs. Weight. Let's do some customization. Double-click on the data plot to open the **Plot Details** dialog. Change the plot properties as follows:

- Change Symbol Shape to circle and **Symbol Color** to olive.
- Set **Transparency** to 55%.

Press **OK** to close the dialog.

13. Double-click on the Y axis to open the **Axis** dialog. Change the axis properties as follows:
- Activate the **Tick Labels** tab. Press the **Ctrl** key on the keyboard and click **Bottom** and **Left** in the left table to select both axes.
 - In the **Display** sub-tab, select **Engineering:1k** for **Display**.
 - Check the **Set Decimal Places** check box and set **Decimal Number** to 0. Press **OK** to close the dialog.



14. Now we can copy the customized formats from this graph to the other three graphs. Right-click on a blank area of the graph such as outside the axes, and select **Copy Format: All Style Formats** from the context menu.
15. Select **Edit: Paste Format (Advanced)...** from the main menu. In the **Apply Formats** dialog that opens, change **Apply Scope** drop-down at the bottom to **All Graphs in this Folder**. Click the **Apply** button to paste the format to the other graph, and then click **Close**.

1.4.2 Merge and arrange graphs

1. We will now merge these 4 graphs windows. Select **Graph: Merge Graph Windows** from the main menu.
2. The **Merge Graph Windows** dialog opens. Accept the default settings and click **OK**. A new graph window with 4 layers is generated.

3. Now we will re-arrange the 4 layers in the merged graph. Select **Graph: Layer Management** from the main menu. The **Layer Management** dialog will open.
4. Activate the **Arrange** tab, then expand the **Spacing (in % of Page Dimensions)** branch. Set as follows:
 - Horizontal Gap = 15
 - Vertical Gap = 15
 - Left Margin = 10
 - Right Margin = 5
 - Top Margin = 5
 - Bottom Margin = 15


Click the **Apply** button.

5. Activate the **Display** tab. Press the **Ctrl** key on the keyboard and select all 4 layers in the **Layer Selection** table on the left. Then select the **Scale Elements** checkbox under the **Option** branch. Set **Scale Mode** to **Fixed Factor** and set the **Fixed Factor** to 1.




If you drag and resize a graph layer, or the layer gets resized when merging, text fonts and other graph objects get rescaled. You can control this behavior at the layer level of the Plot Details dialog by clicking on the **Display** tab and modifying the settings in the **Scale Elements** group.


6. Click the **Apply** button. Click OK to close the dialog.



The merged graph should now appear as below:



7. Activate the *automobile* workbook by double-clicking on the icon in the lower panel of Project Explorer. Select column B, then right click and select **Filter: Add or Remove Filter** to add a filter.
8. Click on the filter icon at the top-left corner of the column header. In the context menu that appears, click **Select All** once to de-select all items, and then select the **Honda** checkbox and click OK, to only show rows where Make is *Honda*. All other rows will be hidden, and all graphs will update to reflect the change in the data.



1.4.3 Cloneable Template and Smart Plotting

1. Let us now save the final merged graph as a template. Right click on its window title bar and select **Save Template As**. This will open the `template_saves` dialog.
2. Make sure **Mark as Cloneable Template** is selected and **Match Plot Columns by** is set to **Long Name**. Enter *MyMergeGraph* for **Template Name** and click **OK**. A message is dumped to the Message Log telling you the template is saved.



Cloneable Templates save the column positions or column names along with all other graph properties. This allows for duplication of complex graph arrangements from other data with same arrangement of column positions or names.

3. Activate the *automobile* workbook. Select the filter on column B and select both *Honda* and *Lexus* and click OK to show both makes.
4. With the book still active, select **Plot > Templates User: MyMergeGraph** from the main menu. A new graph is created, with the same data assignments and formats as present in the previous merged graph.


Save your project file.

1.5 Publishing Graphs

In this lesson we will learn about some of the options available for publishing graphs.


1.5.1 Pasting Graphs in Other Applications


1. Open the project file saved from [lesson four: Merge and Arrange Graphs](#). Click to select the last graph window that you created.
2. Use the menu **Edit:Copy Page**, or the shortcut **CTRL+J**, to copy the graph page.
3. Launch Microsoft® WORD, then press **Ctrl+V**. The graph will be pasted as an embedded object in Word.
4. Double-click on the graph in Word. A new instance of Origin will be launched. Note that in this instance, only the graph and data related to the graph are available in the project.
5. Use menu **Format: Page Properties** to open the **Plot Details** dialog in the page level. Then in the right panel, change the background color by choosing the **Display** tab and setting **Color** as **LT Gray**. Click OK.
6. From the menu, choose **File: Exit & Return to Document1**. This will close the instance of Origin, and the graph image in the document will be updated.
7. In the Word document, de-select the graph and press **Enter** to move to a new line in the document. Under the **Home** tab click the **Paste** icon, then select **Paste Special** from the drop-down.
8. In the dialog that opens, select **Picture (Enhanced Metafile)** and click OK. This will paste the Origin graph as a picture object. Double-clicking on the image will open the **Format Pictures** dialog.



When the Origin graph is placed as an embedded object in applications such as Word or PowerPoint, all the data associated with the graph are also saved with the Word document. This provides the flexibility of double-clicking and editing the graph in a new instance of Origin. However, if many graphs are placed as objects in a document, the document file size will become large if there is a lot of data associated with the graphs.

1.5.2 Sending Graphs to PowerPoint

1. With the graph window active in Origin, press the **Send Graphs to PowerPoint** button .
2. Accept all default settings in the opened dialog and click **OK**. The graph will be pasted as a new slide in the PowerPoint file.
3. Right-click on the graph title bar (in Origin) and select **Add Shortcut to Favorites**. This will add a **Favorites** folder to the project, visible in **Project Explorer**.



4. In **Project Explorer**, select the **My First Graph** folder. Then select the graph window, right-click on the title, and **Add Shortcut to Favorites** folder. Add shortcuts from other graph windows in the project as desired.
5. Go to **Project Explorer** and activate the **Favorites** folder. In the bottom panel, without selecting any item, right-click on the white area and choose **View:Extra Large Icons** from the context menu. This will show the graphs as extra large icons.



Double-click on the icons in **Favorites** folder to open the graph for viewing or editing. Right-click on the icon or the graph window title bar for a context menu command to go to the original folder for that graph.

6. Right-click on the **Favorites** folder in the upper panel of **Project Explorer** and choose **Send Graphs to PowerPoint**. Accept defaults in the dialog that opens. All graphs in the folder will be

sent to PowerPoint. Note that you can do this operation in any folder, and not just the Favorites folder.



The dialog for sending graphs to PowerPoint has options for selecting all graphs in the project, specifying graphs by name, and placing the graphs on duplicate copies of a specific slide PowerPoint file slide that you can prepare prior to the operation.

1.5.3 Slide Show in Origin


1. Right-click on the **Favorites** folder in the upper panel of **Project Explorer** and choose **Slide Show of Graphs** from the context menu.
2. Accept defaults in the dialog. The slide show will start. Use arrow keys to view the next or previous graph in the sequence.



In the bottom panel of Project Explorer, switch to **Details** view (right-click in a empty location and choose **View: Details**). Right-click on the lower panel title bar and enable **Slide**. Note that you can drag to reorder the columns. Use the added **Slide** column to arrange the order of the graphs. Click on the slide column header once, and then you can drag and rearrange the graph entries to set the order. This order will be followed for operations such as slide show, pushing graphs to PowerPoint, and exporting.

1.5.4 Exporting Graphs

1. Go back to Project Explorer and select the **Merging Graph** folder in the upper panel.
2. Activate the graph and choose **File: Export Graphs** and change the following dialog box settings.
 - Select **Portable Document Format (*.pdf)** from the **Image Type** drop-down list.
 - Change the **Select Graph(s)** drop-down to **All in Active Folder**.
 - Expand the **Image Size** branch and enter **5** in the **Fit Width** text box.




3. Click the **OK** button to close the dialog.
4. Click on the **Messages Log** tab on the left side of the interface. The export path will be displayed there. By default, this will be your User Files Folder (UFF) path. Copy the path, then go to **Windows Explorer** and paste the path to open the folder. You can then view the PDF files that were exported from Origin.

Save your project file.

1.6 3D and Contour

In this lesson we will learn how to plot 3D, contour, and profile plots. Data for such plots can be organized as XYZ columns or an array of cells in a worksheet, or in a matrix window.


1.6.1 3D Surface

1. Start with the project saved from the previous lesson and add a new folder named **3D and Contour**. Click to open the empty folder.
2. Click the **New Workbook**  button on the Standard toolbar.
3. Import the file `<Origin EXE Path>\Samples\Matrix Conversion and Gridding\XYZ Random Gaussian.dat`.
4. Right-click on the header of column C and select **Set as: Z** from the context menu.
5. Keep column C highlighted. Then select the menu **Plot > 3D: Surface: 3D Color Map Surface** to create a surface plot.
6. Double-click on the layer icon on the upper left corner of the graph page, indicated by **1**, to open the **Layer Contents** dialog box.

- In the left-hand panel, select **C(Z)**. In the middle section, click the drop-down arrow next to the **A** button. From the drop-down, select **3D Scatter/Trajectory/Vector**. Click the **Add Plot** button




to add the plot to the right-hand panel.



- Click **OK** to close the dialog. The graph will now display the individual data points on the surface.
- Hold the **R** key and use the mouse to freely rotate the surface plot.




1.6.2 Image Profile


- Click on the **New Matrix** button  in the **Standard** toolbar to open a new matrix window.
- Select the menu **File: Import: Image to Matrix**, then browse to *<Origin EXE Path>\Samples\Image Processing and Analysis* folder and select *cell.jpg* file and import it into the matrix.
- With the matrix active, select the menu **Plot > 2D: Profile: Image Profiles**. An image profile graph will be created, and the **Image/Contour Profile** dialog will open.
- In the dialog, select the **HLine** tab then make the horizontal line thicker by expanding the **Width** branch and changing **Pixels** to **50**.



You can add multiple horizontal, vertical, or arbitrary lines using the buttons in the dialog. The graph layers will display overlaid curves for the profiles in the appropriate layers. Profile plots can also be made from data in a matrix or worksheet.


1.6.3 Contour and Surface Plots from Virtual Matrix


- Click on the **New Workbook** button  to create a new workbook.
- Click on the **Import Wizard** button . In the dialog that opens, choose the ... button  next to **File** box, browse to *<Origin EXE Path>\Samples\Graphing* folder, choose *waterfall.dat* file. Click **Finish** to import the file.





The **Import Wizard** can be used to parse an ASCII file to extract variables from header lines. The file you chose already has a predefined filter which is applied when you click the Finish button.

3. Move the cursor to the upper left corner of the workbook until the shape of the pointer changes as in the following image, and click to select all columns of the worksheet.



4. Select menu **Plot > 2D: Contour: Contour - Color Fill**. This will open the **plotvm** dialog box, where you need to specify the data organization for your **Virtual Matrix**, as the data is contained in a worksheet instead of a matrix window.
5. Change **Y Values in** to **Column Label**, and then set **Column Label** to **Excitation Wavelength(nm)**.
6. Click the **OK** button to apply the settings and create the contour graph.
7. Click the **Enable/Disable Speed Mode** button  one time from the right-hand toolbar, to turn off the speed mode setting for the graph.
8. Go back to the workbook with waterfall data. Keep the whole worksheet highlighted and this time select the menu **Plot > 3D: Surface: 3D Color Map Surface with Projection**.
9. The **plotvm** dialog opens. Note that the **Theme** box on the top of dialog is set as **<sheet>**. This is because the settings used last time were saved in the worksheet. Click **OK** to accept the same settings. A surface graph with contour projection will be created.
10. Double-click on the contour projection to open the **Plot Details** dialog. Note that on the **Surface** tab, the **Flat** check box is checked, and an offset of 100% has been applied. This setting makes the data plot appear as a flat contour on top of the cube. Click **OK** to close **Plot Details**.




 Data from different matrices or virtual matrices can be plotted in the same 3D graph layer by specifying an appropriate offset value for each, and further specifying which datasets to flatten. This allows to examine related data together in the same graph.

11. Double click on the **Z** axis to open the **Axis** dialog. Switch to the **Scale** tab and set the **To** value to 4000 and click OK. This allows better viewing of the 3D surface. The contour project will stay on the top plane of the cube.

1.6.4 3D Function Plot

1. Select the menu **File: New: Function Plot: 3D Function Plot**.
2. In the dialog box, click the triangle button  next to the **Theme** box on the top. Then select **Mexican Hat(System)** in the context menu to load the settings for this example.
3. Press **OK** to create the plot.

 A parametric function can be added to an existing graph, thus allowing you to combine such plots with real data. Visit [3D Function Gallery](#) to view and download more examples.


Save your project file.


1.7 Gadgets

In this lesson, we will use gadgets to perform exploratory analysis of data in a graph.

1.7.1 Integrate Gadget

1. Start with the project saved from the previous lesson and add a new folder named **Gadgets** at the root level in Project Explorer, then go to that folder.


2. With the new workbook active, click the **Import Single ASCII** button  on the **Standard** toolbar and import the file <Origin EXE Path>\Samples\Curve Fitting\Multiple Gaussians.dat.
3. We will add long names for the datasets. Enter "Peak 1" in the **Long Name** label row of column B. Click and select the long name cell. Then move the mouse to the lower-right corner of the cell so that the cursor changes to "+". Click the left mouse button and drag from column C to E. Origin will auto-fill the names as *Peak 2*, *Peak 3* and *Peak 4*.
4. Click and drag on the column headers to highlight columns B to E. From the main menu, select **Plot > 2D: Multi-Y: Stacked Lines by Y Offsets** to create a stacked lines graph.
5. With the graph active, select **Gadgets: Integrate...** from the main menu.
6. Accept the default settings and press the **OK** button. A region-of-interest (ROI) box will be placed on the graph. Move and/or resize the ROI to cover a desired range of the data.
7. Click on the triangle button at the top-right corner of the ROI box and select **Preferences** to re-open the dialog.
8. In the **Output** tab, expand the **Output Quantities to** branch and select the **Append to Worksheet** check box . Click **OK** to close the dialog box.
9. When there are multiple plots in a layer, the gadget acts on the active data plot by default. In this case, the active plot is *Peak 1*. To change the data to Peak 3 for example, click on the triangle button at the top-right corner of the ROI box and select **Change Data: Plot(3): Peak 3** from the context menu.



10. Click on the triangle button again and select **New Output for All Curves**. A workbook with integration results for all curves will be generated. Click the triangle button and select **Go to Report Worksheet** to switch to the output workbook.
11. Click the **X** button at the top-right corner of the ROI box in the graph to remove the gadget.

1.7.2 FFT Gadget

1. Start with a new workbook, and import the file *<Origin EXE Path>\Samples\Signal Processing\Chirp Signal.dat*.
2. Highlight column B, then select **Plot > 2D: Line: Line** from the main menu to create a line graph.
3. With the graph active, select **Gadgets: FFT** from the main menu. Accept defaults in the dialog that opens, and click **OK**. An ROI box will be placed on the graph, and another graph named FFTPREVIEW will be created, displaying the FFT result.
4. In the top right corner of the FFTPREVIEW graph, uncheck **Log Scale**. Then reposition the source line graph and FFTPREVIEW window side by side. Move and resize the ROI to cover a small range of the beginning of the data curve.
5. Now you can use the arrow keys to move the ROI to the right, while watching the FFT result update in the other graph.





Save the project file.



1.8 Curve Fitting

In this lesson we will learn how to perform linear and nonlinear regression.


1.8.1 Linear Fit with Outliers

1. Start with the project saved from the previous lesson, and add a new folder at the root level in Project Explorer named **Curve Fitting**.
2. Import the file *<Origin EXE Path>\Samples\Curve Fitting\Outliers.dat*.
3. Select the 2nd column and create a scatter plot.
4. Select the menu item **Analysis: Fitting: Linear Fit**. In the dialog that opens, accept default settings and click **OK** to perform the linear fit.

- In the graph, right-click on the fitting results table and select **Quantities in Table**. Remove all entries except **Intercept**, **Slope** and **Pearson's r** (use CTRL + select for multiple selections). Click **OK** and resize the results table as needed.
- Now click the **Mask Points on Active Plot** button  on the left side toolbar and mask the point at the right bottom, which is distinctly separated from the rest of data points.
- The lock on the top left of the graph page turns yellow  indicating that the data has changed, but the fit results are in need of an update.
- Hit the ESC key to switch the cursor back to pointer mode. Then click on the yellow lock, and from the fly-out menu select **Recalculate Mode: Auto**. The fit results will be updated.


 You can update all pending operations in a project by clicking on the **Recalculate** button  located in the Standard toolbar.

- Go back to the graph and use the masking tool to mask the outlier point towards the top. You will notice that the results automatically update. Your graph should now look similar to this image:



1.8.2 Nonlinear Curve Fit


- Start with a new workbook, and import the file `<Origin EXE Path>\Samples\Curve Fitting\Gaussian.dat`.
- Highlight the column named *Amplitude* and make a scatter plot.
- Go back to workbook, highlight column named *Error*, then right click and select **Set As: Y Error** from the context menu.


4. Place the mouse cursor close to the right edge of the highlighted column. The cursor will change to . At this point, drag and drop the column onto the graph. The data will be added as error bars on the scatter plot.
5. Now let's fit this data. Select the menu **Analysis: Fitting: Nonlinear Curve Fit** to open then **NLFit** dialog.
6. In **Function Selection** page, set **Category** drop down to **Peak Functions**, and set the **Function** drop down to **Gauss**.
7. Click **Fit** button to perform fitting and choose **No** in the prompt dialog, to keep the graph window active.
8. Now we want to fix y_0 as 0 and update the results. Click on the green lock on the top left of the graph page, and select **Change Parameters**.
9. The dialog re-opens with the settings that were used last time the operation was performed. Go to the **Parameters** tab, check the **Fixed** box for y_0 and enter **Value** as 0.

NO.	Param	Meaning	Fixed	Value
1	y_0	offset	<input checked="" type="checkbox"/>	0
1	xc	center	<input type="checkbox"/>	26



10. Click the **Fit** button to update the file and close the dialog. From the updated table on the graph, we can see that $y_0 = 0 \pm 0$.


1.8.3 Global Fit with Parameter Sharing

1. Start a new workbook and import the file *<Origin EXE Path>\Samples\Curve Fitting\Exponential Decay.dat*.
2. Drag and select the three Y columns and create a line plot.
3. We want to fit all three data plots simultaneously over the x range of 0.4 s to 1.0 s. In the **Tools** toolbar docked to the left side of the interface, click the down arrow button on the right of **Selection on Active Plot** button . From the fly-out, choose **Selection on All Plots**. Go to the graph and drag and draw a rectangle to roughly cover the x range of 0.4 to 1.0, including all the three curves in the process.



4. Press **CTRL+Y** to quickly launch the **NLFit** dialog. Then set **Category** as **Exponential** and **Function** as **ExpDec1**.
5. Click on **Data Selection** under the **Settings** tab, expand the **Input Data** node and you will find all three curves are added. You can expand the **Range#** node to further adjust data ranges either by row index or by x value.

 If no range selection has been made on the multiple plots, Origin will only pick up the active data plot from the graph layer containing multiple plots. In that case you can click the  button on the right side of **Input Data** and select **Add all plots in active page**.


6. Change **Multi-Data Fit Mode** to **Global Fit with Same Function**, switch to the **Parameters** tab and click the **Fit until converged** button  to fit all three curves simultaneously, keeping the dialog open.
7. You can share parameters during a global fit. Check the **Share** box for the time constant **t1**. You will notice that the time parameter for the other curves has been removed from the parameters list.
8. **PROBLEM OCCURS HERE** Click the **Fit** button and select **Yes** in the prompt that appears, to switch to report sheet. If the prompt does not come up, you can click on the green lock in the graph and select **Go to Results**.
9. Scroll down to the *Summary* table in the report. You will find that all time constants **t1** share the same values.

Summary ▼

	y0		A1		t1		k	tau
	Value	Standard Error	Value	Standard Error	Value	Standard Error	Value	
Decay 1	97.76426	1.04512	75.32799	11.78854	0.28532	0.03567	3.5049	0.19777
Decay 2	50.44112	1.39417	107.39208	16.22812	0.28532	0.03567	3.5049	0.19777
Decay 3	14.46759	0.73292	43.06541	7.60772	0.28532	0.03567	3.5049	0.19777

10. Now click on the down arrow button beside the **Summary** node and choose **Create Copy as New Sheet**. A new worksheet with the fit results will be added to the book.

11. Select column D, E and create a column plot to display how the amplitude parameter (A1) changed across the three datasets.




1.9 Peak Analysis

In this lesson we will perform fitting, including deconvolution of overlapping peaks and baseline correction.

1.9.1 Multiple Peak Fit with Deconvolution

1. Let's continue with the project file we saved in the previous lesson. Create a new folder in Project Explorer, rename it as **Peak Analysis**, then go to the empty folder.
2. In a new workbook, import the file `<Origin EXE Path>\Samples\Spectroscopy\HiddenPeaks.dat`.
3. Highlight column B and create a line plot.
4. With the graph window active, click **Analysis: Peaks and Baseline: Multiple Peak Fit**. This will open the **Multiple Peak Fit** dialog. Set the **Peak Function** drop-down as *Gauss* and click **OK**.
5. A **Get Points** dialog will open within the graph window. Note that you can re-position this dialog within the window. Double-click on a peak center to select it. Select a total of 7 peaks as in the following image, including two hidden peaks:




If you click the **Open NLFit** button in the **Get Points** dialog, the NLFit dialog will open with the peak centers initialized with your selection. You can further control the fitting process as desired.

6. After selecting all seven peaks, click the **Fit** button. A fit report will be added to the workbook.


1.9.2 Fit Peaks with Baseline

1. This part of the lesson assumes you have OriginPro. Start with a new workbook and import the file *<Origin EXE Path>\Samples\Spectroscopy\Peaks_on_Exponential_Baseline.dat*.
2. Highlight column B and then click **Analysis: Peaks and Baseline: Peak Analyzer**. This will open the **Peak Analyzer** dialog, and a preview window displaying the selected data.
3. In the bottom panel, select the **Fit Peaks (Pro)** choice under **Goal**. The top panel will update, displaying a map of the steps involved in the peak fitting process.
4. Click **Next**. On the **Baseline Mode** page, select **User Defined** for **Baseline Mode**. Click **Next** to go to the **Create Baseline** page. You can then see in the preview window that 8 anchor points connected by a red line, are added to the spectrum. This is the baseline created using the current settings.



Now click the **Prev** button to go back to the **Baseline Mode** page to adjust the baseline mode settings.

- Click the **Find** button below **Number of Points to Find**, to find the baseline anchor points in the spectrum. Eight (8) anchor points are added.
- Clear the **Enable Auto Find** checkbox and then click the **Add** button to add one or more anchor points on the spectrum. Double-click on the tail of the spectrum like the following image to add 1 anchor point.



- Note that you can also select and delete anchor points. Click **Done** to return to the **Peak Analyzer**.
- Select the **Snap to Spectrum** checkbox to force anchor points to snap to the closest data point in the spectrum. Click **Next**.
- On the **Create Baseline** page, select **Fitting** for **Connect by**. Select **ExpDec2** for **Function** under the **Fitting** branch. Click **Next** twice to go to the **Find Peaks** page.
- Click the **Find** button. Two (2) peaks are found in the preview.




There are several options available for peak finding including a 2nd derivative method to find overlapping peaks. You can also view the 2nd derivative curve, and turn on smoothing to help find peaks in noisy data.

- Click **Next** to go to the **Fit Peaks** page. Accept defaults and click **Finish** to perform peak fitting. A graph containing fitting results is generated.



You can click the **Fit Control** button to control the fitting process including fixing and sharing parameters, and specifying bounds and constraints.

- Now, let's customize the **Fitting Results** table to hide some peak properties we don't want to display. Right-click on the table and select **Peak Report Field...** from the context menu. The **Peak Report Field** dialog will open, listing all properties that can be included in the table. You can remove or change the order properties in this dialog. Select **Peak Gravity Center** and click the **Remove** button to hide it. Do the same for **Peak Area by Integrating Data(%)**. Press **OK** to update the table in the graph.



Save your project file.

1.10 Statistics

Origin provides many tools for statistical analysis. Advanced statistical tools are available in OriginPro. In this lesson, we will work with tools available in standard Origin.

1.10.1 Descriptive Statistics

- Start with the project saved from the previous lesson, create a new folder in Project Explorer and rename it as **Statistics**. Open the empty folder.
- Create a new workbook and import the file `<Origin EXE Path>\Samples\Statistics\body.dat`.
- Drag and select the first **5** rows of column **D(Height)**. Basic statistics (average, sum, count) for your selected data will be displayed in the status bar at the bottom right side of the interface.






You can right-click on the statistics listed in the status bar to customize what quantities to display there.


	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	name	age	gender	height	weight
Units					
Comments					
Fixes					
Sparklines					
1	Kate	12	F	146	
2	Lose	12	F	150	
3	Jane	12	F	136	
4	Sophia	12	F	163	
5	Grace	12	F	128	
6	Tom	12	M	148	
7	James	12	M	150	

Statistics dialog box summary:

- Average: 144.6
- Sum: 723
- Count: 5
- Min: 128
- Max: 163
- Std: 14.6
- Median: 146

- 4.
5. From the menu, select **Statistics: Descriptive Statistics: Statistics on Columns**. In the dialog, select the **Input** tab, then expand **Range 1**. Click on the interactive button  to the right of **Data Range**. Return to the worksheet, then drag and select columns **D** and **E**. Click the interactive button again to restore the dialog.
6. In the **Group** control, click the triangle button  and select **B(Y): age**. Click the button again and select **C(Y): gender**. In the list, select **..."gender"** in the **Group** box, then use the **Move Up** button  to move it to the top.
7. Click **OK** to generate the report.


Variable	Count	Mean	Standard Deviation	Sum	Minimum	Median	Maximum
age	5	144.6	12.40890	723	128	146	163
gender	5	145.3333	9.4291	726	136	148	150
height	5	154.2	3.70193	771	150	153	163
weight	2	155.5	3.62553	311	150	155.5	159
weight	2	134	8.48828	268	148	134	180
weight	1	163	0	163	153	153	163
height	3	147.3333	13.51966	442	128	146	159
height	4	151	7.67401	604	143	156.5	169
height	7	151	5.58658	497	150	156	170
weight	5	168.8	4.71169	844	153	163	180
weight	1	168	0	168	168	168	168
weight	2	170.5	3.63553	341	168	170.5	173

8. Click the downward-pointing triangle button  on the right of the **Descriptive Statistics** node in the report sheet and select **Digits...** from the context menu.
9. In the opened dialog, change **Digits** to **Set Decimal Places=** and set **Decimal Number** as **1**. Click **OK** to update the display format in all tables of the report.




The numeric display in all report sheets can be globally set using the **Digits in Report** control on the **Numeric Format** tab of the **Options** dialog accessible from the **Tools: Options** main menu.

1.10.2 Normality Test



1. Create a new workbook by clicking the **New Workbook** button .
2. Double-click in the **F(x)** label row of column A. This will put you into edit mode for that cell. Type the formula:


```
nint(100+20*normal(100))
```

3. The column will be filled with random integer numbers centered around 100.
4. Highlight column A and click **Statistics: Descriptive Statistics: Normality Test** to open the dialog. The selected column is set as **Input Data** automatically. Accept default settings and click **OK**. This will generate the report sheet for **Normality Test**. The footnote under the **Shapiro-Wilk** table indicates that this data is normally distributed, as expected.



1.10.3 Frequency Counts


1. Activate **Sheet1** of the workbook from the previous section. Keep column A highlighted, then click **Statistics: Descriptive Statistics: Frequency Counts**.
2. Accept all default settings in the dialog and press **OK**.
3. In the result sheet, highlight the column **C(Y)**. On the **2D Graphs** toolbar, click the triangle button next to the **Column** button , then choose **Column + Label**  to create a column graph with labels. This will create a histogram plot with counts as labels.






The **Plot: Statistics** menu provides multiple histogram plot options when a worksheet is active. This **Frequency Counts** tool provides an alternate way to first perform counting, and then plot a histogram from the results. This allows for more flexibility and customization such as adding labels to the columns.

1.10.4 One Way ANOVA

1. Create a new workbook and then click on the **Import Single ASCII** button . Browse to <Origin EXE Path>\Samples\Statistics folder. Change the drop-down list next to the **File Name** to **Text File (*.txt)**.



2. Select the file **nitrogen.txt**
3. Select the menu **Statistics: ANOVA: One Way ANOVA** to open the **One Way ANOVA** dialog. In the **Input** tab, set **Input Data** to **Indexed**. Press the triangle button to the right of **Factor** and select **A(X): plant**. Press the triangle button to the right of **Data** and select **B(Y): nitrogen**.




The **ANOVA** dialog box provides two options for input mode: **Indexed** or **Raw**. You can refer to the [FAQ-333: What is indexed versus raw data and how to I transform from one to another?](#) to learn more about how data can be arranged for either mode.

4. In the **Means Comparison** tab of the dialog, select the **Tukey** check box. Then switch to the **Plots** tab and select **Means Comparison Plot**. Click **OK** to close the dialog and generate the report.
5. Go to the report sheet **ANOVA1Way1**. From the result, we can draw following conclusions:
 - The ANOVA table (**Overall ANOVA**) reports a p-value that is smaller than 0.05, hence at least two of the four groups have significantly different means.

Overall ANOVA					
	DF	Sum of Squares	Mean Square	F Value	Prob>F
Model	3	1995.36652	665.45551	12.86214	6.99338E-7
Error	76	3932.05317	51.73754		
Total	79	5928.41969			

Null Hypothesis: The means of all levels are equal.
 Alternative Hypothesis: The means of one or more levels are different.
 At the 0.05 level, the population means are significantly different.

- Double-click on the **Means Comparison Plot** to open it. The red plots indicate significantly different mean values. **PLANT4** has the smallest mean and is significantly different from the other three groups.




Save your project file.

1.11 Analysis Template


In this lesson we will learn how create an **Analysis Template** and re-use it for new data.

1. Continue with the project file saved from the previous lesson. Create a new folder in Project Explorer and rename it as **Analysis Template**. Open the empty folder.
2. Create a new workbook and import the file <Origin EXE Path>\Samples\Curve Fitting\Sensor01.dat.
3. Highlight column B and select **Plot > Templates: User Templates: My Line** to create a line graph from the graph template *My_Line.otp* that we saved in [lesson 1](#).
4. With the graph window active, select **Analysis: Fitting: Linear Fit** from menu. This will bring up the **Linear Fit** dialog.
5. In the **Fit Control** tab, select the **Fix Intercept** check box to force the fitted curve go through (0,0). Select **Auto** for **Recalculate**. Click **OK** to perform the linear fit. The fitted curve and a result table will be added to the graph.
6. Right-click on the result table and select **Quantities in Table** from the context menu. In the dialog, remove all entries other than **Slope** and **Adj. R-Square**, then click **OK** to update the table.
7. Double-click on the X axis to open the **Axis** dialog. With the **Scale** tab active, hold down the **Ctrl** key and select both **Horizontal** and **Vertical** in the list box on the left. Change **Rescale** to **Auto**


and click OK. This is to make sure the axis range will update when data changes.



8. Select the legend on the graph and delete it.
9. Go back to the source workbook. Right-click on any one of the sheet tabs and select **Add Graph as Sheet** from the context menu.



10. In the **Graph Browser** dialog that opens, select **Active Folder** from the location drop-down list. Only the line graph in the current folder will be displayed. Select the graph and click **OK** to insert it as an embedded graph inside a new worksheet.



11. Now we have source data and all analysis results in one book. Let's save it as an Analysis Template. Select **File: Save Workbook as Analysis Template...** from menu. Save the workbook as *My Sensor Analysis.ogw*.



Any work book which has an operation linking input and output, indicated by a lock on output sheets or columns, can be saved as an analysis template. The simplest example would be a sheet where column value calculations have been performed.

12. Now use the **File: Recent Books** menu command to open **My Sensor Analysis.ogw**. The analysis template will open. Note that the date sheet, results and graphs are empty.
13. With the first data worksheet active, import another data file *<Origin EXE Path>\Samples\Curve Fitting\Sensor02.dat*.
14. The linear regression results and the embedded graph will update automatically, because we had set the **Recalculate** mode in the linear fit tool to **Auto**.





Analysis templates can be used manually to process one file at a time, or can be used to perform batch analysis of multiple data files or datasets. Please view the [Batch Processing tutorial](#) to learn more.

Save your project file.

1.12 Apps in Origin

In this lesson we will install and use an App from the **File Exchange** area of OriginLab's website.


1. Start with the project saved from last lesson, and add a new folder named **3D Ellipsoid** at the root level of Project Explorer.
2. Select **Tools: Apps on File Exchange** from the main menu. A selection of Apps available from the [File Exchange website](#) will be listed. Select **3D Confidential Ellipsoid** to open the web page for this App.
NOTE: If you do not see this App listed in the menu, simply choose the last menu item to open the main page of the File Exchange area, and then scroll down or search for this App.
3. Click the download button on the App page. Open the folder containing the downloaded file, then drag-and-drop the file onto the Origin workspace. An icon named **3D Confidential Ellipsoid** will show in the **Apps Gallery** window docked to the right end of the workspace.
4. Now import the file `<Origin EXE Path>\Statistics\Fisher's Iris Data.dat` into a new workbook.
5. Select **Plot > Templates: System Template Library** from the main menu. In the **System Templates** dialog, expand the **Graph Template -> 3D Symbols & Bars & Vectors** node, then select **gl3d**. Click the **Plot Setup...** button at the bottom left corner of the dialog.
6. In the **Plot Setup** dialog that opens, set column C, D, and A as the X, Y, and Z columns, respectively. Click the **Show Plot List** button  to expand the dialog (if it is not already expanded), click the **Add** button, then click **OK** to create a 3D scatter plot.



7. Double-click on the scatter to open the **Plot Details** dialog. On the **Symbol** tab, click on the **Color** drop-down list, and then select the **By Points** tab. Then click on **Indexing**, and from the drop-down, select **Col(E) "Species"**. Click **OK** to close the dialog.
8. Click the **3D Confidential Ellipsoid** button in the Apps Gallery. This will open the **Plot 3D Confidence Ellipsoid** dialog. Accept the default settings and click **OK**. Three ellipsoid are added

Tutorials for Origin

to the graph, each envelops the group of data with the same color. You can hold the **R** key and then use the mouse to rotate the plot.



Save your project file.

We hope this set of **Getting Started** tutorials has been helpful in providing you with a broad overview and introduction to key features in Origin. We recommend that you continue with [more advanced tutorials](#) in the categories that are most relevant to your work.

2 Video Tutorials

To get started quickly with Origin, you could watch the videos in the following table:

Title	Description
Introduction to Origin	Learn how to quickly start using Origin from importing data, customizing column label rows, creating a multi-panel graph, selecting part of the data, performing integration, finding and fitting peaks, and using Recalculate to perform fitting with altered parameters.
Importing Data	Learn how to import ASCII file, customize your Import ASCII dialog settings and save them for future reuse, and use the Import Wizard to import data file and customize the import settings.
Creating a Graph	Learn how to create a graph using the graph toolbars or the Plot Details dialog, add data to an existing graph, and plot groups of plots by label.
Customizing a Graph	Learn how to add a layer title, resize a layer, change the axes properties, save a graph as a template and reuse it, customize a graph by using theme, change the plotting order, customize a single data point or a grouped data plot.
Interpolation	Learn how to change line connection to interpolate data and use Interpolate Gadget to perform data interpolation. Also, interpolate new Y data from given X data based on specified XY range.
Linear Fitting*	Learn how to perform a linear fit with outlier removal.
Nonlinear Curve Fit Tool	Learn how to fit with a built-in fitting function and change the NLFit settings using Change Parameters. Also, learn how to define and fit with a user-defined function.
Creating an Analysis Template	Learn how to set up a workbook for repetitive analysis using a linear regression example.
Batch Processing	Learn how to create an analysis template, and use this template to batch process multiple data files.
Introduction to OriginPro	Learn about all of the extended analysis tools in the areas of peak fitting, surface fitting, statistics, signal processing and image processing offered in OriginPro.

Note: Please visit the [video tutorial page](#) on our website for a complete and most up-to-date list of video tutorials.

3 User Interface

- [Tutorial:Origin_GUI](#)

3.1 Origin GUI

3.1.1 Summary

This tutorial will introduce you to the Origin workspace. You will learn about the different kinds of Origin windows that make up a Project, how to manipulate these windows with Project Explorer, how to manipulate layers and plots with Object Manager and how to manage Apps with Apps Gallery.

Minimum Origin Version Required: Origin 2016 SR0

3.1.2 What you will learn


This tutorial will show you how to:

- Manipulate Workbooks
- Create Graph Windows
- Manage workspace with Project Explorer
- Manipulate Layers and Plots with Object Manager
- Manage Apps with Apps Gallery

3.1.3 Origin Application: Title Bar and Status Bar

The **Origin Title Bar** displays the Origin(Pro) version, any open project name and the current folder within that project (if any) along with the standard Window controls for moving, sizing and closing the window.

The **Status Bar** appears at the bottom of Origin's Window and displays messages, the state of Auto Update, overview of the statistics on selected worksheet cells, Child Window Theme (if any), Last active Workbook, Current Window and Angular Units indicator.





You can select what shows in the Status Bar by right-clicking on the Bar and selecting (or clearing) items from the context menu. You can copy the displayed basic statistics by selecting Copy Statistics from the context menu. The copied data are TAB separated between quantity and values, with each key value pair separated by a CRLF delimiter.

3.1.4 Windows

3.1.4.1 Dynamic menus according to the active child window

The Origin menu dynamically changes according to the active Child Window. Some menus (Help, File, Edit, etc.) appear on all Child Window menus, although their content may change.

1. Click on the **New Project** button  on the **Standard Toolbar**.
2. The workbook window is the active window. Note that there are 13 menu items.
3. Click on the **New Graph** button  on the **Standard Toolbar**. A new window called **Graph1** is created. Note that there are 11 menu items displayed.

Thus, we say that the menus are "context sensitive." They will change depending on which type of Child Window is active.

Note: New Child Windows may be added by selecting the **File: New** menu option or clicking the appropriate button on the **Standard Toolbar**. All Child Windows have standard controls for moving and sizing and windows can be placed anywhere within the Origin workspace. The **Window** menu has options (cascade, tile) for arranging child windows within the workspace. In the central Origin Workspace is where you will find all Origin Child Windows which can include:

Workbooks - The Origin workbook is the primary structure for organizing your data. Each workbook is composed of one or more, up to 255 worksheets.

Graphs - With Origin, you can create over 60 graph types, each from a built-in graph template. Graph windows can be embedded in a worksheet cell.


Matrices - The Origin matrix holds data and images and is required for many 3D graph types.

Notes - Notes windows are a text-only Origin child window useful for recording analysis procedures, making notes to students and colleagues, etc. You can embed notes windows in a worksheet cell.

Layouts and Excel (If you have Excel installed)

3.1.4.2 Workbook


The Origin workbook is the primary structure for organizing your data. Each workbook is composed of one or more Origin worksheets. Each worksheet, in turn, is composed (usually) of one or more worksheet columns or datasets. Columns in Origin have different column types, such as X, Y, Z, yError, etc. These plotting designations determine how the data are treated when creating a graph.



To get familiar with manipulating Origin workbooks, try the following:

1. Select **File: New** from the menu and choose *Worksheet* to create a new worksheet.

2. Select **File: Import: Single ASCII** to bring up the **Open** dialog. Browse to the `\Samples\Curve Fitting` subfolder of the Origin program folder. Highlight the file `Gaussian.dat` and click the **Open** button to import the data into the Origin worksheet.
3. On import, sparklines were automatically turned on, allowing you to quickly view the shape of the data; the sheet name became the name of the file; and as needed an additional column was added to the worksheet. You can see from the **Long Name** that the 3rd column represents data error. To set this column as an Error Column, click the column title to highlight the column, right-click to bring up a fly-out menu, and then select **Set As: Y Error**.
4. Plotting data in Origin is now easy; highlight column B and C (Y and Y error), then select **Plot: Symbol: Scatter** from the menu to create a scatter plot with error bar.




3.1.4.3 Graph

The Graph window is a container for graphical depictions of your experimental data and your analysis results. Graph windows may contain a single plot in a single graph layer or they may contain multiple plots in multiple graph layers.


The graph layer is the fundamental unit of the Origin graph. The layer is comprised of a set of axis scale values, one or more data plots, and any included text labels, drawing objects, graph legends/color scales, button objects, etc. Graph layers can be created, sized, and moved independently of one another, allowing you a great deal of latitude in charting your data.

To learn how to organize layers in a graph window, try the following:

1. Create a new workbook, and import the file *Linear Fit.dat* from the *\Sample\Curve Fitting* folder. You can see that there are three Y columns and one X column after import; each Y column will use the left-most X column as its X coordinates.
2. Highlight columns B and C, and select **Plot: Multi-Panel: Vertical 2 Panel** to plot the curves. This is a two layer graph. While a graph can have multiple layers, only one layer is active at any given time. You can perform operations on the active layer, such as resizing, changing the plot color, etc. When working on a layer, the active layer is denoted by a depressed layer *n* icon in upper left corner of the graph window.



3. To rearrange these two layers, with the graph window active, select the menu item **Graph: Layer Management** to bring up the dialog. Activate the **Arrange** tab, on the middle panel. Enter 2 in the *Column* edit box. Enter 1 in the *Row* edit box and click the **Apply** button. After you click the **OK** button, the graph layers are arranged horizontally.



Most often you will use the worksheet for tabulating and manipulating your data, while you will use the graph window for plotting your data.

3.1.4.4 Matrix

The Origin matrix window is a container for one or more Origin matrices. Each matrix window contains one or more matrix sheets, and each matrix sheet can contain one or more matrix objects. The matrix object itself, is a vector of Z values. These Z values are related to one another in the X and Y dimensions by their relative row and column positions in the matrix. Matrices are a precursor to constructing Origin's 3D graph types such as contour graphs and color-mapped surfaces, and since they are used in depiction and manipulation of 3D data, they are used by Origin in image processing and analysis. We will show you how to use the Origin Matrix to create a 3D plot in a [later tutorial](#).

3.1.5 Toolbars

The Customize Toolbar dialog box handles displaying or hiding toolbars and toolbar buttons.

1. Select **View: Toolbars** from the Origin menu. The **Customize Toolbar** dialog opens.
2. Check the box next to **Column**. This toolbar now appears in the workspace.
3. Make the **Button Groups** tab active.
4. Scroll to select **AutoUpdate** in the Groups list.

5. Click and drag the one button which appears in this group and drop the button next to the green version of this button without the red line, on the **Standard Toolbar**. You can drag buttons back and forth.
6. Click **Close**.

All these toolbars may be dragged away from their docked positions to become floating windows. Floating windows have additional controls besides the X to hide a window. A **push-pin** control can allow or prevent docking and a minimize button can roll-up a window to save space and restore the window when it is needed.

3.1.5.1 Toolbar Reference

Below are the most commonly used toolbars.

Standard Toolbar




Worksheet Data Toolbar



Graph Toolbar



Format Toolbar




Style Toolbar




Tools Toolbar (vertical on the left side of the Origin workspace)



2D Graphs Toolbar



3D and Contour Graphs Toolbar



Mask Toolbar



3.1.6 Project Explorer

Project Explorer is a tool to help you organize your Origin data. It is particularly useful if you are working with a project that contains numerous child windows. Use Project Explorer to develop a folder structure to organize the child windows in your project.


3.1.6.1 Open/Close Project Explorer

When you first start Origin, Project Explorer displays docked to the edge of the workspace. You can dock it to any other edge or float it in the workspace. Because Project Explorer uses some of your workspace, you may want to close Project Explorer, even if you have already created a folder structure. To close/open Project Explorer, click the **Auto Hide** button to pin the **Project Explorer**, then press **Alt + 1** or select menu item **View: Project Explorer**.


3.1.6.2 Change the Display Properties of Project Explorer

The project explorer can be auto-hidden, hidden, floating or docking. In another aspect, it has vertical and horizontal alignment.


1. Select **Customizing Graphs.opj** in *<Origin EXE Folder>\Samples\Graphing* folder.
2. By default the **Project Explorer** is auto hidden, move mouse over to the **Project Explorer** bar in the left of work space to expand it.
3. Click the **Auto Hide** button to pin the **Project Explorer**, so it will be always displayed.



4. Select the **Window Position** drop-down and select **Floating** to make the Project Explorer float over the work space, and you can freely move its position:




5. Right click on the title bar of the floating Project Explorer and select **Horizontal Alignment**:



Note: Other dockable windows (Object Manager, Apps, Quick Help, Message Log, Smart Hint Log, etc.) have the similar controls to change the display properties.


3.1.6.3 Browse Origin windows in Project Explorer

There are two panels in Project Explorer: the folders panel and the contents panel, which displays all objects in the active folder. When you start a new Origin session, you can click the new workbook , new graph or new matrix button to create some blank windows, and then you can see these window's icons in the contents panel. Double-click the icon to hide/view the window.



3.1.6.4 Add a Sub Folder in Project Explorer

To create a new folder, right-click on the project folder (or a subfolder) in the folder panel, and select **New Folder** from the shortcut menu.



Once you have created one or more subfolders, you can move child windows between folders by dragging & dropping them within the Project Explorer workspace.

3.1.7 Object Manager

Object Manager provides a hierarchy structure to help you view and manipulate layers and plots in the active graph window. It is particularly useful if the graph contains multi-layers and each layer contains multi-plots.

3.1.7.1 Open/Close Object Manager


When you first start Origin, Object Manager is docked to the right edge of the workspace. Like Project Explorer, you can dock it to any other edge or float it in the workspace. To close/open Object Manager, select menu item **View: Object Manager**.

3.1.7.2 Manipulate layers and plots in Object Manager

Object Manager works interactively with active graph window. Selecting layer or plot in graph window will highlight the corresponding item in Object Manager and vice versa. This makes it very easy to select an item and then show or hide it.

For example, try the following:

1. Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Multiple Axis and Multiple Panel**. Activate the *Dot Chart with Multiple Datasets* graph window.
2. Select plot in graph window, the corresponding items will be highlighted in Object Manager. Select items in Object Manager, the corresponding plot or layer will be highlighted in graph.
3. In Object Manager, Uncheck the checkbox before 2007 plot of Layer1 to hide this plot.
4. Right click on 2006 plot of Layer1 and select **Show Plots with Same Name Only** to hide all plots named 2007.
5. Right click on 2006 plot of Layer1 again and select **Show All Plots**. All 2007 plots are back.






The plot names in Object Manager is the Auto Legend Translation mode set in the graph. Therefore same name or not depends on what the legend translation mode is used.


Besides using Object Manager to turning on or off layers or plots, it can also be used to:

- Change plot orders by right clicking on a plot and selecting **Move Up/Move Down**
- Change plot type by right clicking on a plot and selecting **Change Plot To**
- Go to source workbook/matrix book by right clicking on a plot and selecting **Go to xxx**
- Double click on an item to open corresponding node in Plot Details dialog for further customization or use context menu to open Useful dialogs.




3.1.8 Apps

Apps are custom applications for Origin that perform specific graphing and/or analysis tasks. Apps are not pre-installed with Origin. Users can browse available Apps in [File Exchange](#) center of the OriginLab website and download them to install. When Apps get installed, they will be visible in the **Apps Gallery** window of the Origin interface.



Each installed App will be displayed as an icon in the gallery window. You can simply click on the icon to launch the App and right-click on the icons for other options such as hiding or uninstalling the App.



3.1.9 Quick Help

The **Find** window can also be toggled on/off from the **View** menu. Use this window to type in keywords and locate a list of FAQs.

1. Click the **Auto Hide** button to pin the **Quick Help**, and then select **View: Quick Help** or **Alt + 5** to hide the **Quick Help** window.
2. Press **Alt + 5** to show the **Quick Help** window again.
3. In the **Find** edit box, type in the following keywords: **add data**
4. Double-click on the "**What are the different ways by which I can add data plots to an existing graph?**" Origin's Help file opens.

3.1.10 Messages Log

The **Messages Log** window shows messages about operations including Output Information, Results and Errors. It displays messages that are not sent to the Script Window or the Command Window. To close/open **Messages Log**, press **Alt + 6** or select menu item **View: Messages Log**.

1. Open a new workbook, highlight the A(X) and B(Y) columns, right-click and choose **Fill Columns With: Row Numbers** from the shortcut menu.
2. Highlight the columns and from the Main Menu, choose Plot: Line: Line. A simple line plot is drawn.
3. Select **File: Export Graphs...** from the main menu to open the **ExpGraph** dialog. In this dialog, keep the default settings and click **OK** to export the graph.
4. The Output Information is reported to the **Messages Log** window.

4 Data Analysis

4.1 Gadgets

- [Global Vertical Cursor](#)
- [Integrate Gadget](#)
- [Curve Intersection Gadget](#)
- [Rise Time Gadget](#)
- [Interpolate Gadget](#)
- [Cluster Gadget](#)
- [Quick Fit Gadget](#)
- [Quick Peaks Gadget](#)
- [Quick Sigmoidal Fit Gadget](#)
- [Using Multiple Gadgets](#)

4.1.1 Global Vertical Cursor

4.1.1.1 Summary

The Vertical Cursor gadget can be used to read X and Y coordinate values for data points in stacked panel plots or contained in multiple graphs simultaneously.



4.1.1.2 What You Will Learn


This tutorial will show you how to:



- Use the vertical cursor gadget to read XY coordinates for multiple graphs and output the results.
- Link/Unlink graphs when using the vertical cursor gadget.
- Move or relocate the cursor line among the linked graph windows.


4.1.1.3 Steps


1. Open Origin and choose **File:Import:Import Wizard**. For the **Data Source**, browse to *<Origin Folder>/Samples/Curve Fitting* and add the **Step01.dat** and **Step02.dat** files. The import filter **Data Folder:Step** is automatically selected. Set **Import Mode** to **Start New Books**.


2. Click the **Next** button, navigate to the **File Name Options** page, clear the check box before **Rename Long Name for Book Only**, then click the **Finish** button to import both files into two workbooks, and the columns will be designated XY XY by the import filter.
3. Click the **New Folder** button  on the **Standard** toolbar to create a new file folder in this project, this folder should be open and named as Folder 2.
4. While Folder 2 is open, click the **Import Wizard** button  on the **Standard** toolbar to import **Step03.dat** file also under the path <Origin Folder>/Samples/Curve Fitting similar to steps 1 and 2.
5. Go to Folder 1 in **Project Explorer**, activate the workbook with long name **Step01.dat** and highlight the whole worksheet. Select **Plot:Multi-Panel:Stack** from the menu item to open the **Plotstack** dialog.
6. Under the **Plot Assignment** branch, enter **3** for **Number of Plots in Each Layer**, accept other settings as default and click **OK** to create a stacked graph.
7. Similarly create two other stacked graphs for the other two workbooks. So now we have Graph1, Graph2, and Graph3 for workbooks Step01.dat, Step02.dat and Step03.dat respectively.
8. Activate Graph1 and choose **Gadgets:Vertical Cursor** to open the **Vertical Cursor** dialog.



9. Click the **Link/Unlink Graphs** button  in this dialog and open the **Graph Browser**, you can choose whether to link or unlink a graph to the current active graph.
10. Select Graph2 and Graph3 in the left panel and click the  button to add the two graphs as linked graphs to Graph1. Click **OK**.



Note: You can also unlink graphs in this dialog by using the  button to remove a graph from the right panel.






On the upper right-hand corner of each linked graph, a  icon appears to indicate that it belongs to a group of linked graphs.

11. Make sure Graph1 is active and the **Vertical Cursor** dialog is open, the asterisk before the graph name marks the current active plot on which the cursor is on. Enter **25** as the X value, uncheck the box before **Snap Cursor to Nearest X** and click the **Move Cursor to X** button



to read the data points in each plot when X=25.

X	Y	Name	Graph	Status
25	0.05595	Sensor A y	Graph1	<input checked="" type="checkbox"/>
25	0.10394	Sensor B y	Graph1	<input checked="" type="checkbox"/>
25	0.21568	Sensor C y	Graph1	<input checked="" type="checkbox"/>
25	0.39314	Sensor D y	Graph1	<input checked="" type="checkbox"/>
25	0.67007	Sensor E y	Graph1	<input checked="" type="checkbox"/>
25	0.81397	Sensor F y	Graph1	<input checked="" type="checkbox"/>
25	0.99419	Sensor G y	*Graph1	<input checked="" type="checkbox"/>
25	1.04738	Sensor H y	Graph1	<input checked="" type="checkbox"/>
25	0.06279	Sensor A y	Graph2	<input checked="" type="checkbox"/>
25	0.13419	Sensor B y	Graph2	<input checked="" type="checkbox"/>
25	0.24344	Sensor C y	Graph2	<input checked="" type="checkbox"/>
25	0.37798	Sensor D y	Graph2	<input checked="" type="checkbox"/>
25	0.63732	Sensor E y	Graph2	<input checked="" type="checkbox"/>
25	0.8559	Sensor F y	Graph2	<input checked="" type="checkbox"/>
25	0.97876	Sensor G y	Graph2	<input checked="" type="checkbox"/>
25	1.02927	Sensor H y	Graph2	<input checked="" type="checkbox"/>
25	0.04517	Sensor A y	Graph3	<input checked="" type="checkbox"/>
25	0.08923	Sensor B y	Graph3	<input checked="" type="checkbox"/>
25	0.20779	Sensor C y	Graph3	<input checked="" type="checkbox"/>
25	0.38576	Sensor D y	Graph3	<input checked="" type="checkbox"/>
25	0.63895	Sensor E y	Graph3	<input checked="" type="checkbox"/>
25	0.83746	Sensor F y	Graph3	<input checked="" type="checkbox"/>
25	0.96896	Sensor G y	Graph3	<input checked="" type="checkbox"/>
25	1.03511	Sensor H y	Graph3	<input checked="" type="checkbox"/>

12. Click the **Add Tag and Label** button  to add tags at X=25 for all linked graphs.
13. Click the **Output Report** button  and then the **Go to Report Worksheet** button  to generate and open the results worksheet. The XY coordinates of all plots in linked graphs are listed in the report sheet.
14. Activate Graph2, click on the  icon and select **Move Cursor Line here**, the cursor line will be moved to Graph2.
15. In the **Vertical Cursor** dialog, double click any row of **Graph3** to activate its graph window. Select the previously added tag, press the **Delete** key to delete the tag, click on the  icon and select **Go to Cursor Line Window** to go back to Graph2 where the cursor is currently on. You can see that the tags in linked graphs are deleted.

4.1.2 Integrate Gadget

4.1.2.1 Summary


The Integrate Gadget performs numerical integration of a data plot to calculate the area under the curve. You can select an arbitrary range of the data plot using the region of interest (ROI) object displayed in the graph.

4.1.2.2 What you will learn

- How to easily integrate a data plot on a rectangular region.
- How to specify the integration limits and baseline.
- How to display the integral curve inside the ROI.
- How to calculate quantities including: peak area, peak height, peak center, and FWHM.


4.1.2.3 Integrate and output the quantities

1. Start with a new workbook and import the Origin sample data *Multiple Peaks.DAT* which is located in <Origin Program Folder> \Samples\Curve fitting.
2. Highlight the Col(C) and select **Plot: Line: Line** from the Origin menu to draw a graph.




3. Select **Gadgets: Integrate** from the Origin menu when a graph is active, to bring up the **Integrate: addtool_curve_integ** dialog box.


In **Integration** tab, choose **Restrict to Rectangle** in the **Integral Curve** drop-down list to plot the integral curve within the rectangle.





4. Click **OK** button. You will see that a yellow rectangle and a blue integral curve are added to the plot. The integral area is filled with gray, and the value is shown at the top of the rectangle.



5. Move the yellow region of interest rectangle to set the region for the single peak you want to integrate.




6. Click the triangle button  at the top right corner of the ROI tool to open the fly-out menu and choose **New Output**. Then the **Gadget Integration Results** will display in the **Script Window**.




4.1.2.4 Integrate with a data plot baseline

1. Start with a new workbook and import the file *<Origin Program Folder>\Samples\Spectroscopy\Peaks with Base.DAT*


2. Highlight Col(B) and Col(C) and select **Plot: Line: Line** from the Origin menu to draw a graph.



3. Select **Gadgets: Integrate** from the Origin menu when a graph is active, to bring up the **Integrate: addtool_curve_integ** dialog box.
4. In **Baseline** tab, choose **Use Existing Dataset** for the **Mode**. Then select *Plot(2): Base* as **Dataset** and click **OK** button.



- Click the triangle button  and select **Expand to Full Plot(s) Range** in the fly-out menu to integrate the total area for the curve.



4.1.3 Curve Intersection Gadget

4.1.3.1 Summary

When there is more than one curve in a graph layer, you might want to calculate the intersection data points of these curves. Since Origin 8.6, a new gadget **Intersect** is available to calculate the intersection points of the input curves on the graph.

Minimum Origin Version Required: Origin 8.6 SR0

4.1.3.2 What you will learn


This tutorial will show you how to:

- Use the Intersect gadget on a graph.
- Tag the intersection points.
- Output the intersection points to worksheet.


4.1.3.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open **Tutorial Data.opj** and browse to the **Curve Intersection Gadget** folder in **Project Explorer** (PE).
2. Highlight the Col(A)~col(D) in workbook **Book6**, and then click **Plot:Line:Line** to plot a line graph.




3. Select **Gadgets: Intersect...** from the main menu to open the dialog. Go to the **Options** tab.





4. Check the **Intersection Label** check box in the **Options** tab, set **Size** as 15, set **Type** as Y and set **Rotate(deg.)** as 0.




5. Click **OK** button to go back to the graph window. The yellow ROI box will be added onto the graph.





6. Click the Arrow button  at the top right of the ROI box, select **Expand to Full Plot(s) Range** from the context menu. The ROI box will be expanded to cover full plot range as shown below.



7. Click the Arrow button  at the top right of the ROI box. Select **Preferences...** from the context menu to open the **Intersect Preferences** dialog. Go to the **Output To** tab and input *[Book6]Intersections* in the **Result Worksheet Name** box.



8. Click **OK** button to go back to the graph window. Click the arrow button  at the top right of the ROI box, select **New Output** from the context menu.
9. The results will be output to the **Script Window**. Click the arrow button  again, select **Go To Report Worksheet** from the menu. The X and Y coordinates of the intersection points will be listed in the results worksheet.

	A(X)	B(Y)	C	D
Long Name	Intersection X	Intersection Y	Curves	Intersection Method
1	14.73898	-0.26305	Book6_B vs. Book6_C	Linear
2	26.4802	0.32401		
3	35.95356	0.79768		
4	25.56476	0.02267	Book6_B vs. Book6_D	
5	39.1559	-0.6852		
6	23.06123	0.15306	Book6_C vs. Book6_D	
7				
8				

4.1.4 Rise Time Gadget

4.1.4.1 Summary


The Rise Time Gadget can be used to analyze the rising and falling stages of a step-like signal in a graph. With this gadget, you can intuitively select an area on the graph with a rectangle, and then calculate the rise time or fall time within that area.


Minimum Origin Version Required: OriginPro 2015 SR0

4.1.4.2 What you will learn


- How to select a specific region of the signal by moving and resizing a region of interest (ROI).
- How to mark **Rise Time (Fall Time)** and **Rise Range (Fall Range)** in the graph.
- How to switch the tool between **Rise Time** and **Fall Time**.
- How to output analysis results of **Rise Time (Fall Time)**.

4.1.4.3 Analyze Rise Time


1. Start with a new workbook and click the  button to import the **Step Signal with Random Noise.dat** file under the <Origin EXE Folder>\Samples\Signal Processing path.
2. Highlight Column B and select **Plot: Line: Line** in the menu to create a graph.




3. Double-click the X axis to open the **Axis** dialog box. Go to the **Scale** tab and set the axis range and major ticks as shown in the image below.




4. Click the **OK** button and the graph will be updated as shown below:



- Select **Gadgets: Rise Time** from the Origin menu to open the **Rise Time: addtool_rise_time** dialog box. Go to the **Display on Graph** tab, and click the **Rise Time** and **Rise Range** check boxes.



- Click **OK** button, and you will see that a yellow rectangle is added to the plot. Move the rectangle horizontally on the rise signal step.





In the graph, you can see the **Rise Time** and **Rise Range** values are shown at the top of the rectangle.

The two blue vertical lines go through the two indicators marking the **Rise Time**.

The two blue horizontal lines that display the **Low Reference Level** and **High Reference Level** go through the two indicators marking the **Rise Range**.


The two red horizontal lines display **Low State Level** and **High State Level**.


7. Click the triangle button  at the top right corner of the rectangle. Then select **New Output**. The results will be output to the **Script Window**.




4.1.4.4 Analyze Fall Time


1. This gadget also allows you to get the fall time and fall range in a graph. Move the rectangle horizontally on the fall signal step.



- Click the triangle button  and select **Preferences** in the fly-out menu to open the **Rise Time Preferences** dialog. Go to the **ROI Box** tab and select **Fall Time** in the **Tool** drop-down list.



3. Click the **OK** button, the **Fall Time** and **Fall Range** values are shown at the top of the rectangle.



4. Click the triangle button  and select **New Output**. The results will be output to the **Script Window**.

4.1.5 Interpolate Gadget

4.1.5.1 Summary

Origin supports the interpolate gadget to perform quick interpolation on a ROI (Region of Interest) range when a graph is active. And you can easily change the interpolate region by moving the ROI.


4.1.5.2 What you will learn

- How to easily interpolate data points on a rectangular region.
- How to quickly find out an interpolated Y value from any given X value.
- How to output the interpolated values to **Script Window**, **Result Log**, or a specified worksheet.


4.1.5.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open **Tutorial Data.opj** and browse to the **Interpolate Gadget** folder in **Project Explorer (PE)**.
2. Highlight the Col(A) and col(B) in workbook Book1R and plot a **Line +Symbol** graph.





3. Select **Gadgets: Interpolate** from the Origin menu when a graph is active, to bring up the **Interpolate: addtool_curve_intep** dialog box.
4. Go to the **Interpolate/Exterpolate Options** tab. Choose **Cubic Spline** for the **Method**, and then select **Interpolate/Extrapolate to Rectangle Edge** for **Fit Limits To**.




- Click **OK** button. It will add an interpolation line onto the plot. And the Y values of interpolation line at right and left are shown at the top of the rectangle region.



- You can change the data range by moving or resizing the yellow region of interest rectangle, the interpolated curve displayed will update as the ROI is being moved. Click the triangle button  and select **Expand to Full Plot(s) Range** in the fly-out menu to interpolate the total area for the curve.



7. This gadget also allows you to find Y values from a given X value. Select **Interpolate X/Y** in fly-out menu to open the **Interpolate Y from X** dialog. You can enter multiple X values and click the **interpolate** button. This tool will output the interpolated Y values for each of the X values.



8. The interpolated Y values can be output to **Script Window**, **Result Log**, or a specified worksheet.

4.1.6 Cluster Gadget

4.1.6.1 Summary

Origin supports the Cluster Gadget to perform simple statistics on a region of interest (ROI) in a graph. The gadget can also be used to edit, clear, mask, or categorize data points. The statistics results are dynamically updated as the ROI object is moved or resized.

Minimum Origin Version Required: Origin 2016 SR0 (Pro only)

4.1.6.2 What you will learn

- How to perform simple statistics on a region of interest (ROI) in a graph.
- How to edit the data points such as clear, or mask points in graph using menu options or buttons.
- How to view or output the statistic for points inside and outside of the ROI.
- How to categorize data points and color map points with the categorical data

4.1.6.3 Perform basic statistics


Tutorials for Origin

1. Start with a new workbook and import the Origin sample data *Categorical Data.dat* which is located in <Origin Program Folder> \Samples\Graphing.
Right-click on Col(D) and select **Sort Worksheet: Ascending**. Then you will see the worksheet is sorted by the category of *Drug*.
2. Pressing **Ctrl** key, highlight three parts of the Col(B) separately.


The screenshot shows a data table with the following columns: A (Age), B (Recovery), C (Gender), and D (Drug). The data is sorted by Drug. Three vertical regions in column B are highlighted with pink boxes and labeled 'first part', 'second part', and 'third part'.

	A (Age)	B (Recovery)	C (Gender)	D (Drug)
1	20	11	Male	Drug A
2	23	12	Female	Drug A
3	45	29	Male	Drug A
4	60	39	Female	Drug A
5	57	38	Male	Drug A
6	32	19	Female	Drug A
7	36	20	Male	Drug A
8	44	30	Female	Drug A
9	59	41	Male	Drug B
10	34	21	Male	Drug B
11	43	31	Male	Drug B
12	23	11	Male	Drug B
13	22	13	Female	Drug B
14	60	42	Female	Drug B
15	44	32	Female	Drug B
16	34	18	Female	Drug B
17	21	12	Male	Placebo
18	45	36	Female	Placebo
19	44	35	Male	Placebo
20	35	23	Female	Placebo
21	36	22	Male	Placebo
22	23	14	Female	Placebo
23	60	46	Male	Placebo
24	58	45	Female	Placebo
25				


3. Select **Plot: Symbol: Scatter** from the main menu to create a graph. The graph with three plots display the recovery for each drug.




- Right-click on the graph legend and select **Properties** to open **Object Properties** dialog. Then edit the legend as shown below. Click **OK** button.




- Select **Gadgets: Cluster** from the Origin menu to bring up the **Cluster: addtool_cluster** dialog box. Choose **Circle** in the **Shape** drop-down list of the **ROI Box** tab.





6. Click **OK** button. It will add a yellow circle for **ROI** on the plot and bring up the **Cluster Gadget** dialog.



7. Move the yellow circle to the region for which you want to get statistics and see the results shown on the **Inner Points** tab of the dialog.





8. Click the **Output Statistics Report** button . The results are output to the Result Log, Script Window, and the Cluster workbook.
9. Click the **Go to Report Worksheet** button , then the **Cluster** workbook will be shown.


	A	B	C(Y)	D(Y)	E(Y)	F(Y)
Long Name	Region	Data	N	Sum (Y)	Mean (Y)	Median (Y)
1	Inner Points	Recovery--Drug A	2	59	29.5	29.5
2	Inner Points	Recovery--Drug B	2	63	31.5	31.5
3	Inner Points	Recovery--Placebo	2	71	35.5	35.5
4	Inner Points	All Plots	6	193	32.16667	31.5
5						

4.1.6.4 Exclude the data points in a cluster

In this section, we will show you how to exclude a specific plot from the cluster. Based on the example above, we will do simple statistics on *Recovery of Drug A* and *Recovery of Drug B*, excluding *Recovery of Placebo*.

1. Click the **Data** menu in the **Cluster Gadget** dialog and uncheck **Plot(1)** and **Plot(2)**. The first and second rows become gray in the lower panel, and they can no longer be manipulated by the buttons in the dialog.
2. Click **Mask Data Points** button . The *Recovery of Placebo* data points in the ROI are masked and the color becomes red. At the same time the statistics results for *Recovery of Placebo* become missing values.




3. Click the **Output Statistics Report** button . The results are output to the Result Log, Script Window, and the Cluster workbook.

4.1.6.5 Get statistics results for points outside of the ROI

1. Click **Settings: Preferences** from the **Cluster Gadget** dialog's menu to open the **Cluster Manipulation Preferences** dialog.


- Go to the **Calculation** tab. Click the **Calculate Outer Points** check box.



- Click the **OK** button, the statistics results for points out of the ROI are shown on the **Outer Points** tab of the dialog.

The screenshot shows the 'Cluster Gadget: Editing Inner Points - Recovery--Placebo' dialog box with the 'Outer Points' tab selected. The table displays statistics for various input legends.


Input Legend	N	Sum (Y)	Mean (Y)	Median (Y)	SD (Y)
Recovery--Drug A	6	139	23.16667	19.5	12.41633
Recovery--Drug B	6	146	24.33333	19.5	13.76466
Recovery--Placebo	6	162	27	22.5	14.96667
All Plots	18	447	24.83333	20.5	13.02598

- Click the **Output Statistics Report** button . The results for inner and outer points are shown in the Result Log, Script Window, and the Cluster workbook.

4.1.6.6 Color data points in different regions


You can categorize data points from graph directly and output the Categorical group column to the source worksheet, and further map symbol characters to the categorical group column.

Create a new workbook and re-import the sample data <Origin Program Folder>\Samples\Graphing\Categorical Data.dat. Highlight Column(B) and plot a Scatter graph.




Data points cluster into 4 groups. We will use the **Create Categories** feature of **Cluster Gadget** to create a categorical column according to the cluster groups and map symbol color to this column.

- Select **Gadgets: Cluster** to bring up the **Cluster: addtool_cluster** dialog. Choose **Circle** in the **Shape** drop-down list of the **ROI Box** tab. Click **OK** button to add a yellow circle for ROI on the plot and bring up the **Cluster Gadget** dialog.
- Move and adjust the size of the ROI box to circle only the first cluster of data points at the low-left corner.




Click the **Create Categories** button  on the **Cluster Gadget** dialog to open the **Create Categorical Value** dialog. Enter **Group** for **Category Group Name** and **1** for **Category**.



Click the **OK** button. A new categorical column named "Group" is added to the source data sheet and data points inside ROI are tagged as "1" in this **column(Group)**.

	A(X)	B(Y)	E(Y)	C(Y)	D(Y)
Long Name	Age	Recovery	Group	Gender	Drug
Units					
Comments			Categories		
F(x)=					
Sparklines					
Categories			Unsorted		
1	20	11	1	Male	Drug A
2	23	12	1	Female	Drug A
3	22	13	1	Female	Drug B
4	23	11	1	Male	Drug B
5	21	12	1	Male	Placebo
6	23	14	1	Female	Placebo
7	36	20	--	Male	Drug A
8	32	19	--	Female	Drug A
9	34	18	--	Female	Drug B
10	34	21	--	Male	Drug B

- Repeat step 2 for the rest of 3 clusters and tag them as 2, 3, 4 in sequence.




The source worksheet should look like the following.


	A(X)	B(Y)	E(Y)	C(Y)	D(Y)
Long Name	Age	Recovery	Group	Gender	Drug
Units					
Comments			Categories		
F(x)=					
Sparklines	[Sparkline]				
Categories			Unsorted		
6	23	14	1	Female	Placebo
7	36	20	2	Male	Drug A
8	32	19	2	Female	Drug A
9	34	18	2	Female	Drug B
10	34	21	2	Male	Drug B
11	36	22	2	Male	Placebo
12	35	23	2	Female	Placebo
13	45	29	3	Male	Drug A
14	44	30	3	Female	Drug A
15	44	32	3	Female	Drug B
16	43	31	3	Male	Drug B
17	44	35	3	Male	Placebo
18	45	36	3	Female	Placebo
19	57	38	4	Male	Drug A
20	60	39	4	Female	Drug A

Close **Cluster Gadget**.


- Now we will color-map data points to **column(Group)**. Double click on the scatter to open the **Plot Details** dialog. Go to **Symbol** tab. Select **By Points** tab from **Symbol Color** drop-down list. Then select **Col(E): "Group"** under the **Indexing** drop-down list.



Click **OK**.



5. Delete the original legend. Select **Graph: Legend: Categorical Values** to bring up the **legendcat** dialog. Select checkboxes **Symbol(Edge) Color**. Click **OK**. The scatter plot with new legend should look like following.



4.1.7 Quick Fit Gadget

4.1.7.1 Summary

The Quick Fit gadget can be used to quickly perform curve fitting within the ROI (Region of Interest) range.

Minimum Origin Version Required: Origin 8.6 SR0

4.1.7.2 What you will learn


This tutorial will show you how to:


- carry out linear fit with the Quick Fit gadget.
- carry out nonlinear curve fit using Quick Fit gadget.
- save and reuse a dialog theme.


4.1.7.3 Steps


Linear Fit


1. Open Origin and choose **File:Import:Import Wizard**. For the **Data Source**, browse to *<Origin Folder>/Samples/Curve Fitting* and add the **Step01.dat**. Note that when this file is selected, the import filter **Data Folder: step** is automatically chosen (this is shown in in the **Import Filters for Current Data Type** box). Click **Finish** to import the file.
2. Highlight through column A to F and click the  button to generate a scatter plot.




3. Select **Gadgets: Quick Fit: 1 Linear(System)** from the main menu to add a region-of-interest (ROI) box on the graph. Click the arrow button  and select **Expand to Full Plot(s) Range** from the fly-out menu to expand the ROI box to the full plot range.





- Click the arrow button  and select **Preferences...** from the fly-out menu. This opens the **Quick Fit Preferences** dialog. In this dialog, go to the **Label Box** tab, select **Equation with Values** for the **Equation** drop-down list.








- Go to the **Report** tab, select **Worksheet** for the **Output To** drop-down list.



- Click **OK** to close this dialog. Click the arrow button  to select **New Output** from the fly-out menu. This outputs the plot fitting results "Sensor 01" to the report worksheet and adds a label box to the graph window. The label box reports your analysis results.




7. Select the label box on the graph and delete it. Click the arrow button  and select **Preferences...** from the fly-out menu. This opens the **Quick Fit Preferences** dialog. In this dialog, go to **Label Box** tab, uncheck the **Add Label Box to Graph** check box and click **OK**.
8. Click the triangle button  to select **Change Data: Plot(2) Sensor B y** from the fly-out menu, so that a linear fit is performed on the data plot Sensor B y. Note that a best-fit line is added to the plot.
9. Click the arrow button  and select **New Output** from the fly-out menu. The fitting results of plot "Sensor B y" are output to the report worksheet.
10. Repeat your previous steps, selecting **Change Data: Plot(3) Sensor C y** from the fly-out menu. Choose **New Output** option from the fly-out menu to output the fitting results of plot "Sensor C y" to the report worksheet.
11. Click the arrow button  and select **Go to Report Worksheet**. You will see the fitting results of all three plots in the report worksheet.




	A	B	C	D	E	F	G(Y)	H(yEr?	I(Y)	J(yEr?
Long Name	Function	Input	Range	Output	Equation	Weighting	Intercept	Intercept-Error	Slope	Slope-Error
1	Linear	Sensor A y	[1*38*]	Linear Polynomial Fit of conc01	$y = -0.00289 + 0.00194*x$	No Weighting	-0.00289	0.00393	0.00194	1.14325E-4
2	Linear	Sensor B y	[1*38*]	Linear Polynomial Fit of conc02	$y = -0.02068 + 0.00478*x$	No Weighting	-0.02068	0.00442	0.00478	1.27723E-4
3	Linear	Sensor C y	[1*38*]	Linear Polynomial Fit of conc03	$y = -0.00389 + 0.00882*x$	No Weighting	-0.00389	0.00451	0.00882	1.29786E-4


Nonlinear Curve Fit


1. Start with a new workbook and import the Origin sample data **Gaussian.DAT** which is located in *<Origin Program Folder>\Samples\Curve fitting* path.
2. Highlight the Col(B) and select **Plot: Symbol: Scatter** from the Origin menu to draw a graph.





3. Select **Gadgets: Quick Fit: 4 Peak - Gauss (System)** from the Origin menu to add a ROI box to the graph.





4. Click the arrow button  to select **Expand to Full Plot(s) Range** from the fly-out menu to expand the ROI box to the full plot range.





- Click the arrow button  and select **Preferences...** from the fly-out menu. This opens the **Quick Fit Preferences** dialog. In this dialog, go to the **ROI Box** tab, and set the **Parameter List** as below.





- Click **OK** to close this dialog. Click the arrow button  and select **New Output** from the fly-out menu. A label box will be added to the graph as shown below.





- Click the arrow button  and select **Preferences...** from the fly-out menu. This opens the **Quick Fit Preferences** dialog again. In this dialog, go to the **Label Box** tab, choose **Use ROI Box Tab Settings** for **Parameter Table**. Click **OK** to close this dialog.




8. Click the arrow button  and select **Update Last Output** from the fly-out menu. The Label box will be updated and only the parameters "xc" and "FWHM" will be displayed.




9. Click the arrow button  and select **Save Theme** from the fly-out menu. In the **Theme Save as...** dialog, set the **Theme Name** as *My_Gauss* and click **OK**.



10. Go back to the worksheet, highlight col(C) and select **Plot: Symbol: Scatter** from the top menu. This draws a scatter graph.
11. Click on the new plot to activate it and select **Gadgets: Quick Fit: 9 My_Gauss** to load the theme. A ROI box will be added to the graph with parameters *xc* and *FWHM* displaying above the ROI.

- Click the arrow button  to select **Expand to Full Plot(s) Range** from the fly-out menu to expand the ROI box to the full plot range, and then select **New Output** from the fly-out menu to output the result. You can see that our theme is applied as the label box on the graph only reports the values of parameter "xc" and "FWHM".



4.1.8 Quick Peaks Gadget

4.1.8.1 Summary

The Quick Peaks gadget can be used to pick peaks, subtract baseline, integrate the peaks and/or fit peaks in a ROI (Region of Interest). It is also possible to use this tool in combination with the **Peak Analyzer**. Please refer to [this tutorial](#) for details.




Minimum Origin Version Required: Origin 2015 SR1


4.1.8.2 What you will learn

This tutorial will show you how to:

- Find and subtract baseline for spectrum with the Quick Peaks gadget.
- Find peaks on the graph with the Quick Peaks gadget.
- Customize preference settings.


4.1.8.3 Steps


1. Create a new workbook by clicking the **New Workbook** button . Click the **Import Single ASCII** button  and import the **Zircon.dat** file in the *<Origin Folder>\Samples\Spectroscopy* path. Both buttons are located on the **Standard** toolbar.
2. Highlight Col(B) and plot a line graph with the **Line**  button on the **2D Graphs Toolbar**.
3. Select **Gadgets: Quick Peaks** from the main menu and open the **Data Exploration: addtool_quickpeaks** dialog.
4. On the **Baseline** tab, set **Mode** to **2D Derivative**, and then set **Range** to **Full Plot Range**. Click **OK** to apply.




5. The peaks within the yellow ROI box will be found and marked. Resize the ROI box so that it covers X range[0,7000] as shown in graph below, the baseline and peak finding need a further


refinement.



- Click the triangle button  and select **Preference** from the fly-out menu, so you can further adjust the **Smoothing Method** in **Baseline** tab follows the graph:




click Apply to apply, and further adjust the values in **Find Peak** tab:



7. Click **OK** to apply the settings and close the dialog, the baseline and peaks finding are better than before which can be attribute to the optimizing **Threshold** and **Maximum Anchor Points** for


Baseline and **Threshold Height%** for Find peak:




- Click the triangle button  and select **New Output** from the fly-out menu to output the peak finding results to a report worksheet.

Return to the gadget fly-out menu and select **Go to Report Worksheet** to view the quantities output :

Peak ID	Peak Row	Peak X	Peak Y	Height	Peak Area	FWHM
				Peak Height from Baseline		
Peak 1	94	355.3057	5883.32381	4019.38518	105810.63852	31.85037
Peak 2	138	440.1582	6622.58143	4579.30486	212770.49866	38.0693
Peak 3	431	1005.199	9687.95699	7641.00995	262292.12444	31.93732
Peak 4	1077	2250.989	8735.86589	6521.97313	477231.3539	49.19588
Peak 5	1230	2546.044	9375.11743	7460.46176	686897.33207	67.08458
Peak 6	1685	3423.496	7014.48113	3883.05102	160646.49519	37.93742
Peak 7	1858	3757.121	7245.12389	3742.14765	359968.10298	153.43826
Peak 8	2470	4937.343	12846.63008	6434.46253	432380.73801	42.80683
Peak 9	3226	6395.264	16607.24058	3959.88794	180348.37354	27.24009
Peak 10	3250	6441.547	36844.54608	24051.37853	1.07438E6	37.18174

- Activate the graph window to which the gadget was applied, click the triangle button  and select **Subtract Baseline**, click **OK** for pop-up window, the baseline was subtract from the data:

Click cross button on the top left corner to close the gadget. The finished graph is shown like this:



Note: For advanced fitting options, you can [combine Quick Peaks gadget with Peak Analyzer](#).

4.1.9 Quick Sigmoidal Fit Gadget

4.1.9.1 Summary

The Quick Sigmoidal Fit gadget can be used to quickly perform a sigmoidal fit on a portion of your graph that you define interactively as your region of interest (ROI).

Minimum Origin Version Required: Origin 2015 SR0

4.1.9.2 What you will learn


- How to use the Quick Sigmoidal Fit gadget on a graph.
- How to select your fitting options.
- How to switch to the NLFit dialog.
- How to output the fitting result.
- How to find X/Y values on the fit curve.

4.1.9.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Quick Fit


1. Open **Tutorial Data.opj** and browse to the **Quick Sigmoidal Fit Gadget** folder in **Project Explorer (PE)**.
2. Highlight Col(A) through Col(D) in the workbook **DoseResponseN** and from the menu choose **Plot:Symbol:Scatter** to plot a scatter graph.




3. Double-click the X axis to open **Axis** dialog. In the **Scale** tab, set the **Type** as *Log10* and click **OK** button to close the dialog.




4. Click the **Rescale** button  to show the plot with the proper scale.




5. Select **Gadgets: Quick Sigmoidal Fit...** from the main menu to open the **addtool_sigmoidal_fit** dialog box. Select the function *Logistic5* from the **Function** drop-down list on the **Settings** tab.





6. Click the **ROI Box** tab and uncheck the parameters x_0 , h , and s under the **Parameter List** branch.





- Click the **Fit Curve** tab, select **Mean, SD** from the **Plot Type** drop-down list and **Source Book, New Sheet** from the **Output Fit Curve To** drop-down list.





- Click **OK** to add the ROI box to the graph. At the top right corner of the ROI box, click the Arrow button  to select **Expand to the Full Plots Range** from the menu. The ROI box will cover the full data range on the graph.





9. Click the arrow button  again to select **Preferences...** from the menu. This opens the **Sigmoidal Fit Preferences** dialog box. In this dialog, click the **Report** tab and set **Output To** as *None*.



10. Click **OK** to close the dialog box. Click the arrow button  to select **Change Function: Logistic** and change the fitting function to *Logistic*. The label text on top of the ROI box will update automatically.






11. Click the arrow button  to select **New Output** and output the fitting result to the worksheet and graph.




Connect to NLFit

When using the Quick Sigmoidal Fit gadget you can easily switch to the NLFit tool. This makes it easy to get a detailed fit report using the current fitting settings in the gadget.

1. Redo step 1 through step 8 as shown above.
2. Click the arrow button  to select **Switch to NLFit...** to open the **NLFit** dialog with the inherited settings.





- Click the **Fit** button to perform curve fitting. The results are output to the result sheets and the source graph.




Find X/Y

With his gadget you can also quickly find X/Y values on the fitted curve.

1. Redo step 1 through step 8 as shown in the first section.
2. Click the arrow button  to select **Find X/Y...** from the menu to open the **Find X/Y** dialog.



3. Select the **Worksheet** radio box and enter 40;45;50 for **Y**, then click **Find X** to show the corresponding X values in the empty **X** box. Then, click the **Output** button and the X and Y values are output to the specified worksheet.



4. Click the **Go** button beside the **Worksheet** radio box to open the **Find X/Y** workbook. Click the **Close** button to close the **Find X/Y** dialog.

	A(X)	B(Y)
Long Name	Found X	Specified Y
Units		
Comments	FindX of Logistic5 Fit on "Response 1"	
1	7.95304E-7	40
2	9.84936E-7	45
3	1.21139E-6	50
4		
5		
6		

4.1.10 Using Multiple Gadgets

4.1.10.1 Summary

Multiple gadgets can be used in combination to achieve certain goals. To avoid overlapping of several gadget windows over same plot, we can arrange them into different layers to layout them onto different panels. The results from all other gadgets can be eventually added to the last gadget window and kept updated at each new output. In this tutorial, we will illustrate an example to show how we can combine the use of **Quick Peaks**, **Quick Fit** and **Intersect** gadgets to find the intersection point between the baseline and slope of a curve.

Minimum Origin Version Required: Origin 2016 SR0


4.1.10.2 What you will learn

This tutorial will show you:

- how to simultaneously use multiple gadgets to analyze same data.
- how to output Gadget analyzed results onto a specific graph and keep them updated.
- how to find the intersection point of baseline with the linear fitting of a curve.


4.1.10.3 Create a layout for multiple gadget windows


1. Start with a new workbook and import the file `\Samples\Curve Fitting\Gaussian.dat`.
2. To avoid overlapping the gadgets in one graph, we are going to prepare a multi-layer graph as shown below with same data in each layer.
3. Click and select the second column and use the menu item **Plot:Multi-Curve:4 Panel** to create a 4 panel plot.



Note: To make the explanation of following steps more clear, we marked above figure with blue font to help you distinguish the layers in the graph.


- Go back to the workbook, select the **Amplitude** column, and position the cursor at the edge of

the column, until you see the cursor turn into . Then you can drag-and-drop the column into layer 2 on the graph page and click **OK** to close the appeared dialog box. Do it again to add the plot to layer 3 in the panel, and then click the bottom right area to select the unwanted layer 4 and use the **Delete** key on the keyboard to delete it.




4.1.10.4 Using Quick Peaks gadget to find baseline


1. Select **Gadgets:Quick Peaks** from the Origin menu when layer 1 is active to bring up the **Data Exploration:addtool_quickpeaks** dialog box. According to the lineshape of this curve, spline connection would be a better choice for fitting the baseline. To do so, go to the **Baseline** tab, choose **Spline** in the **Connect Method** drop-down list to connect anchor points with spline method.





2. Since we do not want to create new columns in the source sheet to save baseline data at every new output, we can save the result to a new workbook and the newly created baseline data will replace existing data instead. To do so, go to **Output to** tab, uncheck the **Append to Worksheet** box and check the **Output Baseline to Worksheet** to output baseline data into a new book QkPeak with sheet name as Baseline.



3. Click **OK** to close the dialog box. Place the mouse cursor over the edge of the Region of Interest (ROI), when the cursor turns into a double arrow icon, you can resize the box as needed.





4. Click the triangle button  at the top right corner of the ROI to open the fly-out menu and choose **New Output(O)** to output baseline data.




4.1.10.5 Using Quick Fit to find the linear fit of the curve


1. Activate the second layer by clicking on the layer icon **2** on the top left corner of the graph or directly click on the plotting area of top right panel.
2. Select **Gadgets:Quick Fit:Linear(System)** from the Origin menu to bring up the **Quick Fit** ROI, and adjust the position and range of appeared ROI properly to perform linear fitting over the left half of the peak envelope.




3. Click the triangle button  at the top right corner of the ROI to open the fly-out menu and choose **Preferences** to customize **Quick Fit Preferences** dialog box.
4. Since we do not need other unnecessary output about this linear fitting, we can go to the **Label Box** tab, uncheck **Add Label Box to Graph**.







5. For the same purpose, to avoid outputting summary report we can go to the **Report** tab, choose **None** in the **Output To** drop down list and click **OK** to close the dialog box.




- Return to the triangle button  at the top right corner of the ROI, choose **New Output(O)** to output linearly fitted results to worksheet.

4.1.10.6 Using Intersect gadget to find intersection point


- Before we apply the **Intersect** gadget, the first step to do is to add the fitted baseline and linearly fitted line from last two gadgets to the third plot. To do so, click on the layer icon  on the top left corner to activate layer 3. Right click on the layer icon  to choose **Layer Contents** to bring up **Layer Contents-Layer 3** window. Select the data with long name **QuickFit Y1** and **Baseline Y of Amplitude** and add them to the right panel through the right arrow icon .





- Click **OK** to close the window and the fitted baseline and linear line will display in the third layer.





3. Select **Gadgets:Intersect** from the Origin menu when layer 3 is active to bring up the **Data Exploration:addtool_curve_intersect** dialog box. Click **OK** to close the dialog box and it will bring up **Intersect** Gadget ROI.





4. Position and resize the ROI properly to have the intersection point between baseline and slope inside the box. To exclude other intersection points with the original curve, go to the triangle button  at the top right corner of the ROI and uncheck **Plot(1) Amplitude** from the context menu of **Change Data**.





- Return to the triangle button  at the top right corner of the ROI, choose **New Output(O)** to output the result of intersection point between baseline and linearly fitted line.



4.1.10.7 Update the output

1. Click on the layer icon **1** to activate layer 1, reposition **Quick Peaks** ROI to create a new baseline. Then go to the triangle button  at the top right corner of the ROI, choose **New Output(O)** to output the newly created baseline.
2. Click on the layer icon **2** to activate layer 2, reposition **Quick Fit** ROI to the other side of the curve so it will create a new linear fit line. Then go to the triangle button  at the top right corner of the ROI, choose **Update Last Output(O)** to output linearly fitted line result.
3. Click on the layer icon **3** to activate layer 3, reposition **Intersect** ROI to have the intersection point between newly created baseline and linearly fitted line inside the box. Then go to the

triangle button  at the top right corner of the ROI, choose **New Output(O)** to output the result of new intersection point.



4.2 Curve Fitting

4.2.1 Linear and Polynomial Fitting

- [Linear Fitting and Outlier Removal](#)
- [Linear Fit for Kinetic Models](#)

4.2.1.1 Linear Fitting and Outlier Removal

Summary

An outlier is typically described as a data point or observation in a collection of data points that is "very distant" from the other points and thus could be due to, for example, some fault in the measurement procedure. Identification and removal of outliers is often controversial, and is typically "more acceptable" in situations where the model used to describe the data is well known and well accepted.

What you will learn

This tutorial will show you how to:


- Perform linear regression on a set of data points
- Examine the Residuals Table in the output and "identify" outliers
- Use the Masking Tool to remove the outlier points
- Use the Recalculation mechanism to automatically update the result after outlier removal

The procedure described in this tutorial is also applicable to other fitting tools such as Polynomial and Nonlinear Fitting


Steps

1. Start with a new workbook and import the file *\Samples\Curve Fitting\Outlier.dat*.
2. Click and select the second column and use the menu item **Plot: Symbol: Scatter** to create a scatter plot.
3. With the graph active, use the menu item **Analysis: Fitting: Linear Fit...** to bring up the Linear Fit dialog. Note that if you have used the Linear Fit dialog before, there will be a fly-out menu and you need to select the **Open Dialog...** sub menu.


4. In the **Fit Control** tab, clear the **Apparent Fit** check box.



5. In the **Residual Analysis** tab in the dialog, and check the **Standardized** check box.




6. Change the **Recalculate** drop-down at the top of the dialog to **Auto** and press the **OK** button at the bottom of the dialog. The dialog will close and linear regression will be performed on the data.




7. Select the **FitLinearCurve1** result sheet in the data workbook and scroll to the right side to view the **Standardized Residual** column. You will note that the value in row 6 of this column is -2.54889:

	A(X1)	B(Y1)	C(X2)	D(Y2)	E(Y2)
Long Name	Independent Var	Linear Fit of Outlier	Independent Var	Regular Residual	Standardized Res
Units					
Comments					
Parameters	Fitted Curves Plot				
1	0.79	1.43673	0.79	0.23327	0.13281
2	0.79813	1.44455	2.16	0.08563	0.04875
3	0.80626	1.45236	2.56	1.08092	0.61539
4	0.81438	1.46018	3.57	0.28951	0.16483
5	0.82251	1.468	4.43	-0.14762	-0.08404
6	0.83064	1.47582	5.23	-4.47705	-2.54889
7	0.83877	1.48363	5.55	-0.31482	-0.17923
8	0.8469	1.49145	6.06	0.44467	0.25316
9	0.85503	1.49927	6.67	2.41798	1.37662
10	0.86315	1.50709	7.61	0.48391	0.2755


8. Make the graph active and then click and hold down the mouse left button on the "Regional Mask Tool" button in the Tools toolbar. Select the "Masked Points on Active Plot" submenu which will be the first item in the fly-out menu:



9. With the above submenu selected, go to the graph and click on the 6th data point to mask the point (note that you can drag out a rectangle around the point).



Masking this point changes the input data to the linear fit operation and the auto update mechanism will trigger. The linear fit will be repeated with this particular masked point left out. The fit curve in the graph and the parameters table will automatically update. The resulting graph should look like this:



4.2.1.2 Linear Fit for Kinetic Models

Summary

Non-linear kinetic models are widely used across many disciplines of natural science, such as, physics, chemistry, biology. Experimentally, all the crucial parameters in kinetic models are obtained through fitting the raw data. The intuitive way to fit the raw data is to do a non-linear fit with the expression directly from the kinetic equation. Alternatively, linear fit can be applied if we can transform the equation in the way that the dependent variable related to independent variable linearly. Minimum Origin Version Required: Origin 2015

What you will learn

This tutorial will show you how to:

- Perform linear fit on same non-linear kinetic model using different linear transformations.
- Perform apparent linear fit on non-linear kinetic models.

Linear fit for Langmuir model

Identify transformed independent and dependent variables

Langmuir model is described by the non-linear equation below:

$$y = \frac{ym * K * x}{1 + K * x}$$

where ym , K are the parameters we want to obtain through fitting.

To perform linear fit on Langmuir model, we can transform it into linear equation in two different ways:

1. Transform it into traditional linear Langmuir equation:

$$y = -\frac{1}{K} \frac{y}{x} + ym$$


where the independent variable is y/x , dependent variable is y , slope is $-1/K$ and intercept is ym .

2. Transform it into double reciprocal linear Langmuir equation:

$$\frac{1}{y} = \frac{1}{ym * K} \frac{1}{x} + \frac{1}{ym}$$

where the independent variable is $1/x$, dependent variable is $1/y$, slope is $1/(ym*K)$ and intercept is $1/ym$.

Create new independent and dependent variable data


1. Open a new workbook.
2. Click the *Import Single ASCII* button  to bring up the **Open** dialog. Browse to `\Samples\Curve Fitting` folder and select the file *LangmuirModel.dat*. Make sure the **Show Options Dialog**: check box is selected and click **OK** to open the **impASC** dialog. Select **No** from **Add Sparklines** drop-down list under **Import Options** node and click **OK** to finish importing.
3. Use **Ctrl+D** to bring up **Add New Columns** dialog, enter 4 and click **OK** to add 4 columns to store transformed XY dataset later.
4. For traditional linear Langmuir model transformation, the independent variable is now y/x and dependent variable is still y . Type y/x and y as the long name for column C and D respectively so that it will show as X axis title, Y axis title respectively in later plot.
5. Type $\text{Col(B)}/\text{Col(A)}$ in **F(x) =** formula cell in column C to set the value for independent variable y/x , and press **ENTER**. Highlight column C, right click and select **Set As:X** to make it as the default X dataset for plotting column D.
6. Type Col(B) in **F(x) =** formula cell in column D to set the value for dependent variable y , and press **ENTER**.

- For double reciprocal linear Langmuir model transformation, the independent variable is $1/x$ and dependent variable is $1/y$. Similarly, make the long name of column E , F as $1/x$, $1/y$, respectively, and set their column values as $1/Col(A)$ and $1/Col(B)$ accordingly. Set column E designation as X .
- The worksheet is then as following:


	A(X1)	B(Y1)	C(X2)	D(Y2)	E(X3)	F(Y3)
Long Name	x	y	y/x	y	1/x	1/y
Units						
Comments						
F(x)=			Col(B)/Col(A)	Col(B)	1/Col(A)	1/Col(B)
1	0.1	0.93919	9.39192	0.93919	10	1.06474
2	0.12	1.12371	9.36425	1.12371	8.33333	0.88991
3	0.14	1.14885	8.20608	1.14885	7.14286	0.87044
4	0.16	1.40556	8.78476	1.40556	6.25	0.71146
5	0.18	1.35436	7.5242	1.35436	5.55556	0.73836
6	0.2	1.46774	7.33868	1.46774	5	0.68132
7	0.22	1.60306	7.28662	1.60306	4.54545	0.62381
8	0.24	1.64389	6.84954	1.64389	4.16667	0.60831
9	0.26	1.73117	6.65836	1.73117	3.84615	0.57764
10	0.28	1.88119	6.71852	1.88119	3.57143	0.53158
11	0.3	1.76906	5.89686	1.76906	3.33333	0.56527
12	0.32	1.76835	5.52611	1.76835	3.125	0.5655
13	0.34	1.91588	5.63494	1.91588	2.94118	0.52195

Linear fit on transformed linear data

- First, we will perform linear fitting on traditional linear Langmuir transformation. Highlight column D and select **Plot:Symbol:Scatter** to make a scatter plot.
- To perform linear fitting, select **Analysis:Fitting:Linear Fit:Open Dialog** to bring up the **Linear Fit** dialog box and click **OK** to close dialog. In the appeared prompt, choose **No** and click **OK**.



3. Similarly, to perform linear fit on double reciprocal linear Langmuir transformation, highlight column F follow the steps above to create a scatter plot and then do a linear fit.




The coefficients in Langmuir model are then can be calculated using corresponding slope and intercept expressions.


Apparent linear fit on original non-linear data

Alternatively, we can use apparent linear fit to directly perform linear fit on raw non-linear kinetic data by customizing only the axis scales. Take Langmuir kinetic model for example, based on double reciprocal Langmuir linear transformation we found that the inverse of original dependent variable $1/y$ is in linear relationship with the inverse of original independent variable $1/x$. Therefore, if set the X scale as $1/x$ and set the Y scale as $1/y$, raw Langmuir kinetic data would appear with linearity.


1. To perform apparent linear fit on Langmuir kinetic raw data, highlight column *B* and select **Plot:Symbol:Scatter** to make a non-linear scatter plot.




2. Double click on the X axis to bring up **Axis** dialog, set **From** as *0.08* and **To** as *3*. Then select **Custom Formula** from the **Type** drop-down list and input $1/x$ as the **Direct Formula** and $1/x$ as the **Inverse Formula**. Choose **Fixed From** in the **Rescale** drop-down list. Click **OK** to close the dialog.




3. As can be see from the plot, the default X axis ticks are not well separated. To make the ticks of X axis display reasonably, we will create a dataset to set the positions of ticks. To do so, activate *LangmuirModel* worksheet and use Ctrl+D to add one more column. Enter dataset 0.1, 0.15, 0.2, 0.3, 0.4, 0.7, 1, 3 in newly added column G.
4. To use column G as major tick positions for X axis, double click on the X axis to bring up **Axis** dialog. Then go to **Major Ticks** node choose **By Custom Positions** from **Type** drop-down list and choose *[LangmuirModel]LangmuirModel!G* from the **Dataset** drop-down list.




5. Click **Vertical** icon on left panel, similarly, choose **Custom Formula** from **Type** drop-down list and input 1/x in both **Direct Formula** and **Inverse Formula** boxes. Click **OK** to close the dialog box.



- To perform apparent linear fit, select **Analysis:Fitting:Linear Fit:Open Dialog** to bring up the **Linear Fit** dialog box. In the **Fit Control** tab, we can see that by default the **Apparent Fit** box is checked.



7. Click **OK** to close dialog and choose **No** radio box in the prompt, then click **OK** to close it.



Solutions for other non-linear kinetic models

Freudlich equation

The non-linear kinetic equation for Freudlich model is as below:

$$\ln(y) = \ln(K) + \frac{\ln(x)}{n}$$

where the independent variable is $\ln(x)$, dependent variable is $\ln(y)$, slope is $1/n$ and intercept is $\ln(K)$, K and n are the coefficients to be determined.

Apparent linear fit is recommended since Ln scale is a build-in scale setting. To fit this non-linear kinetic model, use apparent fit with X and Y axis scales both set to be Ln scales.

Alternatively, you can perform linear fit after you calculate the Ln value of both X and Y dataset. See the example of Langmuir model above for details.

Lagergren's pseudo-first order

The non-linear kinetic equation for Lagergren's pseudo-first order model is as below:

$$\log(q_{e,exp} - y) = \frac{\log(q_{e,fit}) - k_1 * x}{2.303}$$

where the independent variable is x , dependent variable is $\log(q_{e,exp} - y)$, slope is $-k_1/2.303$ and intercept is $\log(q_{e,fit})/2.303$, $q_{e,exp}$ is known constant, $-k_1$ and $q_{e,fit}$ are the coefficients to be determined.

Apparent linear fit is recommended since Log scale is a build-in scale setting. To fit this non-linear kinetic model, first calculate $q_{e,exp} - y$ and then use apparent fit with only Y axis scale set to be Log scale.

Alternatively, you can firstly calculate $\text{Log}(q_{e,exp} - y)$ and use this newly created data to do linear fit directly. Refer to the example of Langmuir model above for details.

Ho's pseudo-second order

The non-linear kinetic equation for Freundlich model is as below:

$$\frac{x}{y} = \frac{1}{k_2 q_e^2} + \frac{x}{q_e}$$

where the independent variable is x, dependent variable is x/y, slope is $1/q_e$ and intercept is $1/(k_2 q_e^2)$, k_2 and q_e are the coefficients to be determined.

To linearly fit this model, you have to firstly calculate x/y and use this newly created data to perform linear fit.

Alternatively, we can transform this equation into the form below:

$$\frac{1}{y} = \frac{1}{k_2 q_e^2} \frac{1}{x} + \frac{1}{q_e}$$

where the independent variable is 1/x, dependent variable is 1/y, slope is $1/(k_2 q_e^2)$ and intercept is $1/q_e$.

For this transformation, we can either perform linear fit once we created new independent variable data as 1/x and new dependent variable data as 1/y. Or we can perform apparent linear fit by set both X and Y axis scales as 1/x scale. Please refer to Langmuir model for more details.

4.2.2 Nonlinear Fitting

- [Nonlinear Curve Fit Tool](#)
- [Nonlinear Fitting with System Function](#)
- [Global Fitting with Parameter Sharing](#)
- [Global Fit for Different Functions with Shared Parameters](#)
- [Parameters Initialization using LabTalk in NLFit](#)
- [User Defined Fitting Function](#)
- [Fitting One Dataset as a Function of Other Datasets](#)
- [Fitting With Multiple Independent Variables](#)
- [User Defined Fitting Function using GNU Scientific Library](#)

- [Fitting with NAG Special Function](#)
- [Fitting Integral Function with parametric limit using NAG Library](#)
- [Fitting with Integral using NAG Library](#)
- [Fitting with Integral using LabTalk Function](#)
- [Fitting with Two Integrals using LabTalk Function](#)
- [Fitting with Summation](#)
- [Fitting Complex Function](#)
- [Fitting with Convolution](#)
- [Quoting Built-in Functions in Your New Function](#)
- [Fit Function with Non-constant Background](#)
- [Fitting with Piecewise Functions](#)
- [Fit Curve Through Certain Points](#)
- [Distribution Fit with the Probability Density Function and Cumulative Distribution Function](#)
- [Fitting Integral Function with a Sharp Peak](#)
- [Fitting with a Piecewise Linear Function](#)
- [Fitting with an Ordinary Differential Equation](#)
- [Fitting with Convolution of Two Functions](#)
- [Parameter Initialization for Rational Functions](#)
- [Surface Fitting with Multiple Peaks](#)
- [Nonlinear Multiple Variables Fitting](#)
- [Modifying Derived Parameters in Build-in Functions](#)
- [Fit Multiple Datasets by Fitting One and then Using Those Fit Parameters for Other Datasets](#)
- [Implicit Fitting with Three Variables](#)
- [Nonlinear fitting using Orthogonal Distance Regression](#)

4.2.2.1 Nonlinear Curve Fit Tool

Summary

Nonlinear fitting in Origin is performed using the NonLinear Fitting (NLFit) dialog box. The NLFit tool contains more than 200 built-in fitting functions used in many different disciplines.


Minimum Origin Version Required: 8.5

What you will learn


- How to fit with a built-in fitting function.
- How to change NLFit setting using Recalculate.
- How to define and fit with a user-defined function.

Use a built-in function to fit the data


1. Click **File:Open...** to open the **Intro_to_Nonlinear Curve Fit Tool.opj** from the **\Samples\Curve Fitting** folder and select the **Built-In Function** folder from the Project Explorer window.
2. With the **Graph1** active, select the menu item **Analysis: Fitting: Nonlinear Curve Fit** to bring up the **NLFit** dialog, and then select **Gauss** from the **Function** drop-down list:





3. In the **Parameter** tab, initial parameter values are automatically assigned, because the built-in functions have parameter initialization code.
If you go to the **Residual** tab, you can see the current residuals and decide whether the current fit results are acceptable.




4. Note that a fitted curve drawn using the initial parameter values, is shown in the graph.




- Click the **Fit until converged** button . To see if the fitting operation was successful, click the **Messages** tab and note the number of iterations, reduced chi-sqr value, R² value, etc.




- Click the **OK** button. The **FitNL1** report sheet is created with fit results including parameter values and fit statistics.



7. Reopen the Nonlinear Curve Fitting dialog by clicking on the green lock icon on the upper left corner of the graph and selecting **Change Parameters**.




8. Go to the **Parameters** tab, change the value of x_c to 25 (note that by double-clicking in the cell, you can edit the value) and select the **Fixed** check box.



9. Once again, click the **Fit until converged** button  and then **OK**.


10. In the report sheet, you can see that fixing the value of xc to 25 results in a Standard Error of 0.




Define and fit with a user-defined function

In this section, we will show you how to define your own fitting function and use it in the Nonlinear Curve Fit tool. Our function: $y=y_0+a*\exp(-b*x)$


1. Open Project Explorer (**View: Project Explorer**), and select the **User-Defined Function** folder.
2. In the menu, select **Tools: Fitting Function Builder...** to bring up the Fitting Function Builder dialog box.
3. On the Goal page, click **Create a New Function**, then click the **Next** button to go to the **Name and Type** page.




4. On the **Name and Type** page, click **New** to create a category for the new fitting function, then name the function and select a Function Type.
 - Set **MyFunction** as the **Function Name**.
 - Select **Expression** from the **Function Type list**. Note that the left panel displays Hints regarding Function Type.
 - Click the **Next** button to go to the **Variables and Parameters** page.




- On the **Variables and Parameters** page, make sure **Independent Variables** reads x and **Dependent Variables** reads y . Then input the comma-separated values y_0, a, b into the **Parameters** text box. Click the **Next** button.





- On the **Function Body** page, perform the following operations:


- Set the **Initial Values** for parameters as shown below.
- In the **Function body** edit box, enter $y_0+a*\exp(-b*x)$.
- Use **Quick Check** to check the validity of a function. After entering a value for the independent variables, click the **Evaluate** button  to quickly check the validity of the fitting function.





7. Click the **Finish** button to finish defining the function.
8. Highlight column A and B, select the menu item **Analysis: Fitting: Nonlinear Curve Fit** to bring up the **NLFit** dialog. Select the function **MyFunction** on the **Function Selection** page, under the **Settings** tab:




9. By successively clicking the **1 iteration button**, you can see the change in parameter values as well as the increasing conformance of the fitted curve.
- o Click the "1 Iteration" button .



- Click the "1 Iteration" button  again.



- Click the **Fit until converged** button .



10. Click the **OK** button and the FitNL1 report sheet of fitting results is created. Here, you will find best-fit parameter values and other fit statistics.

4.2.2.2 Nonlinear Fitting with System Function

Summary

The NLFit dialog is an interactive tool which allows you to monitor the fitting procedure during the non-linear fitting process. This tutorial fits the Michaelis-Menten function, which is a basic model in Enzyme Kinetics, and shows you some basic features of the NLFit dialog. During the fitting, we will illustrate how to perform a Global Fit, which allows you to fit two datasets simultaneously and share some parameter values.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn


This tutorial will show you how to:


- Import a single ASCII file.
- Perform a global fit with shared parameters.




- Select a fitting range and fit part of the data.
- Use the Command Window to perform a simple calculation.

Steps


Import the file


- Open a new workbook.
- Click the *Import Single ASCII* button  to bring up the **Open** dialog. Browse to `\Samples\Curve Fitting` folder and select the file *Enzyme.dat*. Make sure to check the **Show Options Dialog** checkbox at the bottom of the dialog, and then click **Open**.
- In the **impASC** dialog, expand **Import Options: Header Lines** nodes, and select **3** from *Comments From* drop down.
- Click OK to import the file.



	A(X)	B(Y)	C(Y)
Long Name	[S]	V	V
Units	μM	$\mu\text{M}/\text{min}$	$\mu\text{M}/\text{min}$
Comments	Substrate	No Inhibitor	Competitive Inhibition
Sparklines			
1	0.5	580	350
2	2	1180	690
3	4	1485	970
4	6	1630	1175
5	8	1740	1345
6	10	1810	1500

Plotting the Data

- Select columns B and C and plot as a scatter plot by clicking the  button.



Fitting with the Michaelis-Menten Function

The single-substrate Michaelis-Menten function is a basic model used in enzyme kinetics studies.

$$v = \frac{V_{max}[S]}{K_m + [S]}$$


The parameter v is the reaction velocity, $[S]$ is the substrate concentration, V_{max} is the maximal velocity, and K_m represents the Michaelis constant. Parameters V_{max} and K_m are important enzyme properties and their values can be determined by fitting the M-M function to a v vs. $[S]$ curve. While there is no M-M fitting function in Origin, we can use a more general model, the built-in *Hill* function to perform the fit:

$$v = V_{max} \frac{x^n}{k^n + x^n}$$


where n is the cooperative sites. For a single-substrate model, we fix $n = 1$, thus simplifying the model so that it behaves like the M-M function.

There are two curves, one is the reaction without an Inhibitor and the other is the reaction with a Competitive Inhibitor. We will use the NLFit tool to fit these two curves simultaneously. Since for competitive inhibition reactions, the maximum velocity is the same as with no inhibition, we can share the V_{max} value during the fitting procedure and perform a *Global Fit*.


- With the graph active, select the menu item **Analysis: Fitting: Nonlinear Curve Fit** to bring up the NLFit dialog. Select *Hill* function from *Growth/Sigmoidal* category on the **Settings: Function Selection** page.




- On the **Settings: Data Selection** page, click the triangular button next to the **Input Data** and choose **Add all plots in active page** to set the data range.




- Select *Global Fit* from **Multi-Data Fit Mode** drop-down list on the **Settings: Data Selection** page.



- Switch to the **Parameters** tab, check the **Share** box on the Vmax row. These *Share* check boxes are only available when using *Global Fit* mode. Check the **Fixed** box for n and n₂, and make sure their values are 1.



Click the *Fit* button to generate the analysis reports. A table of fit parameters is pasted to the original graph (only the fit parameter values table is shown in the following figure.)




From the fit result, we can conclude that the maximum velocity is $2162.8 \mu M/min$. The value of K_m for the no inhibitor model is $1.78 \mu M$. The value K_m for the competitive inhibitor model is $4.18 \mu M$.

Fitting Lineweaver-Burk Plot

As we know, the model parameters can also be estimated by the Lineweaver–Burk or double-reciprocal plot. The Lineweaver–Burk plot takes the reciprocal of both sides of the M-M function and plots by $1/v$ vs. $1/[S]$:

$$\frac{1}{v} = \frac{1}{V_{max}} + \frac{K_m}{V_{max}[S]}$$

This is actually a linear function:




We will use the No Inhibitor data to illustrate how to calculate K_m and V_{max} by L-B plot.

- Go back to the raw data worksheet and add two more columns by clicking the button. Right-click on column D and select **Set As: X** from the context fly-out menu to set it as an X column. Right-click on column E again and select **Set Column Values** to bring up the **Set Values** dialog. In the dialog edit box, enter: $1/Col(A)$ and set the **Recalculate** mode as *None*, since we don't need to auto update the reciprocal values in this example.


Similarly, set column E's values as $1/Col(B)$. Enter the long name for column D & E as $1/[S]$ & $1/V$, respectively. And then we have:


	A(X1)	B(Y1)	C(Y1)	D(X2)	E(Y2)
Long Name	[S]	V	V	1/[S]	1/V
Units	μM	$\mu M/min$	$\mu M/min$		
Comments	Substrate	No Inhibitor	Competitive Inhibition		
Sparklines					
1	0.5	580	350	2	0.00172
2	2	1180	890	0.5	8.47458E-4
3	4	1485	970	0.25	6.73401E-4
4	6	1630	1175	0.16667	6.13497E-4
5	8	1740	1345	0.125	5.74713E-4
6	10	1810	1500	0.1	5.52486E-4

- Highlight columns D & E and click  button to create a scatter plot.




From the above equation, we know there is a linear relationship between $1/v$ and $1/[S]$, so we can use the NLFit tool to fit a straight line on this plot. (You can also use the Fit Linear tool from **Analysis: Fitting: Fit Linear**)

- Bring up the NLFit dialog again, select *Line* function from *Polynomial* category, and then click the *Fit* button  directly to generate results.




Tutorials for Origin


From the plot, one may doubt that this is the best fit curve since there is a point located far away. Actually, the right side of L-B plot is low substrate concentrations area, the measurement error may be large, so we'd better exclude these points during fitting.





- Click the lock icon on the graph upper-left corner, and select *Change Parameters* to bring back NLFit dialog.



In **Settings: Data Selection** page, click the  button on **Input Data** node, and then choose *Reselect All Data from Graph* from fly-out menu.




Then the NLFit dialog rolls up and your cursors become  when you move to the graph page. Click and draw a rectangle to select data points you want to fit. The input range is labeled by vertical lines. You can also click-and-move these lines to change the input range.



Click the  button on **Select Data in Graph** window to go back to NLFit dialog.



- Click the *Fit* button on the NLFit dialog to recalculate the result. You can see from the graph that the report table was updated.



- Since the intercept of the fitted curve is $1/V_{max}$, it is equal to $4.76191E-4$ in this example. To get the V_{max} value, select **Window: Command Window** to open the command window, type

$1/4.76191E-4 =$

and press ENTER:

```
//--2009-8-19 12:56
1/4.76191E-4=;
>>1/4.76191E-4=
1/4.76191E-4=2099.9976900025
>>
```

Origin returns the value 2099, which is close to what we got above, 2160. (When fitting the hill function above, we shared V_{max} when fitting two datasets. If you fit the No Inhibitor data only, this value will be closer.)

4.2.2.3 Global Fitting with Parameter Sharing

Summary




The term "global fitting" generally refers to simultaneous curve fitting operations performed on multiple datasets. Because datasets remain distinct, they may or may not "share" parameter values during the fit process. When a parameter is shared, a single parameter value is calculated for all datasets; When a parameter is not shared, a separate parameter value is calculated for each dataset. By contrast, "concatenated fitting" is performed by combining all datasets into a single dataset. Because curve fitting operations are performed on a single dataset, only a single set of parameter values is returned.


What you will learn

This tutorial will show you how to:

- Select multiple datasets for fitting.
- Select different fitting modes.
- Perform global fit with parameter sharing.

Steps

1. Create a new workbook by clicking the  button.
2. Click the  to import the file **Enzyme.dat** in the <Origin EXE Folder>\Samples\Curve Fitting\ folder.
3. Highlight column B and C and click the  button to generate a scatter plot.
4. Keep the graph window activated and select the **Analysis: Fitting: Nonlinear Curve Fit** menu item to open the **NLFit** dialog.
5. In the **Function Selection** page, choose the **Hill** function from the **Growth/Sigmoidal** category.
6. Go to the **Data Selection** page, click the triangle button next to the **Input Data** selection box and choose **Add All Plots in Active Layer**, to add both plots as input data.
7. Select **Global Fit** mode from the **Multi-Data Fit Mode** drop-down list:



8. In the **Advanced** page, set the **Recalculate** mode to **Auto**.


9. Go to the **Parameters** tab. Check the **Fixed** check box for n and n_2 to fix their values to 1.

Param	Meaning	Share	Fixed	Value	Error
Vmax	Max velocity	<input type="checkbox"/>	<input type="checkbox"/>	1960	--
k	Michaelis constant	<input type="checkbox"/>	<input type="checkbox"/>	2.59016	--
n	Cooperative sites	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	--
Vmax_2	Max velocity	<input type="checkbox"/>	<input type="checkbox"/>	1910	--
k_2	Michaelis constant	<input type="checkbox"/>	<input type="checkbox"/>	5.56098	--
n_2	Cooperative sites	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	--

10. Click the **Fit** button to fit curves. You will get these results from the **Parameters** table of the report worksheet:


		Value	Standard Error	t-Value	Prob> t	Dependency
V	Vmax	2091.96109	33.62032	62.22311	--	0.66992
	k	1.52432	0.13786	11.05711	--	0.66992
	n	1	0	--	--	0
	Vmax	2428.49265	81.97136	29.62611	0	0.89747
	k	5.86377	0.56737	10.33497	5.36612E-9	0.89747
	n	1	0	--	--	0

11. The fitted curves will be added to the original data plot.



12. In this case, the maximum velocity V_{max} may be the same, so we could share this parameter value when fitting.

- Click the green lock icon in the report worksheet and select **Change Parameters** to bring back the **NLFit** dialog.




- In the **Parameters** tab, check the **Share** check box for *V_{max}*.

Param	Meaning	Share	Fixed	Value	Error
V _{max}	Max velocity	<input checked="" type="checkbox"/>	<input type="checkbox"/>	1960	--
k	Michaelis constant	<input type="checkbox"/>	<input type="checkbox"/>	2.59016	--
n	Cooperative sites	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	--
k ₂	Michaelis constant	<input type="checkbox"/>	<input type="checkbox"/>	5.56098	--
n ₂	Cooperative sites	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	--

- Click the **Fit** button again to update results. You can see the *V_{max}* values for both curves are the same. The asterisk in the parameter name indicates that this parameter is shared:

		Value	Standard Error	t-Value	Prob> t	Dependency
V	V _{max} *	2162.82534	42.2049	51.24584	--	0.76631
	k	1.78077	0.19046	9.35003	--	0.63991
	n	1	0	--	--	0
	V _{max} *	2162.82534	42.2049	51.24584	0	0.76631
	k	4.18392	0.33106	12.63784	1.07513E-10	0.60034
	n	1	0	--	--	0

- The fitted curve will automatically update.



4.2.2.4 Global Fit for Different Functions with Shared Parameters

Summary

This tutorial is aimed at solving the following problem: do global curve fitting on two or more curves using different function for each curve, but sharing some parameters, the shared parameter was common to all the datasets. This problem arises in a wide variety of scientific fields such as fitting for anisotropy spectrum.

Minimum Origin Version Required: Origin 2015 SR1

What you will learn

This tutorial will show you how to:

- Select multiple datasets for global fitting.
- Set a switch parameter which connect all functions.
- Perform global fit with parameter sharing for multiple fitting functions.

Steps

1. Create a new workbook by clicking the  button.
2. Click the  to import the file **MultiFunctionsFit.dat** in the <Origin EXE Folder>\Samples\Curve Fitting\ folder.


- Highlight column A, B and C and select the **Analysis: Fitting: Nonlinear Curve Fit** menu item to open the **NLFit** dialog.

The user defined fitting function will be built in next 3 steps, the functions are built based on the quantitative model below :

$$Col(B) : L_1 = \frac{A_1 e^{-t/t_0} + B_1}{A_2 e^{-t/t_0} + B_2}$$

$$Col(C) : L_2 = A_2 e^{-t/t_0} + B_2$$

- In the **Function Selection** page, choose the **<new...>** function from the **User Defined** category.
- Enter "GlobalFit" as the function name, and set the Function Model and Function Type follows the graph below:



Then, click **Next** to go to the variables and parameters page.

6. Set the variables and parameters follows the graph below:

The screenshot shows a dialog box titled "Fitting Function Builder - Variables and Parameters - GlobalFit". It contains several input fields and a checkbox. The "Independent Variables" field is set to "t", "Dependent Variables" is set to "y", and "Parameters" is set to "A1,B1,A2,B2,t0,s". The "Derived Parameters" and "Constants" fields are empty. There is a checkbox labeled "Peak Function" which is currently unchecked. At the bottom, there are buttons for "Cancel", "<< Back", "Next >>", and "Finish".


Then, click **Next** to go to the Expression Function page.

7. Type the expression which contained formula of L_1 and L_2 in the function body box:


$$s * (A1 * \exp(-t/t0) + B1) / (A2 * \exp(-t/t0) + B2) - (s-1) * (A2 * \exp(-t/t0) + B2)$$

The parameter s is a switch for global fitting, if $s=1$, the L_1 is used for fitting, if $s=0$, L_2 is used for fitting. The value of s will be controlled in the following fitting procedure. Set the Initial Value of A1

and B1 to 0. Then, click **Finish**.



- Back to **NLFit** dialog, select GlobalFit function in User Defined Category. Go to the Data Selection Page, Select Global Fit mode from the Multi-Data Fit Mode drop-down list:



9. Go to the **Parameters** tab. Check on the **Share** check box for A2, B2 and t0, then Check on the **Fixed** box for s and s_2 to fix their values to 1 and 0, respectively. The setting of s will control fitting Col(B) using L_1 while fitting Col(C) using L_2 .

Settings Code Parameters Bounds

Auto Parameter Initialization

Double click cells to change operator. Right click cells for more c


NO.	Param	Meaning	Share	Fixed	Value	Error
1	B1	?	<input type="checkbox"/>	<input type="checkbox"/>	0	--
1	A2	?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	1	--
1	B2	?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	1	--
1	t0	?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	1	--
1	s	?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	1	--
2	A1_2	?	<input type="checkbox"/>	<input type="checkbox"/>	0	--
2	B1_2	?	<input type="checkbox"/>	<input type="checkbox"/>	0	--
2	s_2	?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	0	--

10. Click the **Fit** button to fit curves. You will get these results from the **Parameters** table of the report worksheet:

		Value	Standard Error
L1	A1	2.5887072951	0.1678709978
	B1	0.4959001021	0.0052845018
	A2*	-12.6787277087	0.1035113131
	B2*	8.9810129162	6.5535940841E-4
	t0*	3.3462910396	0.0113070784
	s	1	0
L2	A1	0	0
	B1	0	0
	A2*	-12.6787277087	0.1035113131
	B2*	8.9810129162	6.5535940841E-4
	t0*	3.3462910396	0.0113070784
	s	0	0

share

- The fitted curves will be added to the graph window. You can check the fitted curve for Col(B)/ L_1 and Col(C)/ L_2 in Sheet **FitNL1** by double clicking the Graphs.



4.2.2.5 Parameters Initialization using LabTalk in NLFit

Summary

In previous Origin versions, one can only initialize fitting parameters with Origin C code. Since Origin 9.0 SR1, it is also supported to use LabTalk script to initialize parameters. This implement is especially useful when one wants to use worksheet values for the initial parameters.

In this tutorial, three adsorption uptake curves at three different temperatures were measured, and the results are exported in three .txt files. The experimental conditions are stored in the same .txt file as header info. We are going to fit the data to the isothermal-spherical model, according to the following equation:

$$y = 1 - \frac{6}{\pi^2} * \exp\left(-\frac{\pi^2}{T} * x\right)$$

, where y is the normalized mass uptake (mg/g), x is the time span (s), T is the time constant (1/s), and the fitting parameter.

There is an empirical equation describing the relationship between the temperature and time constant, which is:

$$T = 25000 - 58 * Temp$$

For the uptake curve at each temperature, we will calculate T from this equation and use it as the initial value for the curve fitting.

Minimum Origin Version Required: Origin 9.0 SR1

What you will learn

This tutorial will show you how to:


- Create a user-defined fitting function and use Labtalk script to do parameter initialization.
- Use values in worksheet for initialized parameters.

Steps

Write Parameter Initialization Script for a User-Defined Fitting Function

1. Select **Tools:Fitting Function Builder**(or press **F8**) to open the **Fitting Function Builder**, in the **Goal** page, select **Create a New Function** and click **Next**.
2. In the **Name and Type** page, make sure the function is created under the **User Defined** category, name the function **UptakeCurveFit**, keep the **Function Model** as **Explicit**, and select **Origin C** for **Function Type**. Click the **Next** button.
3. In the **Variables and Parameters** page, keep the **Independent Variables** and **Dependent Variables** as the default **x** and **y**, respectively. Set the **Parameters** to **T** and click **Next**.
4. In the **Origin C Fitting Function** page, type in the following equation in the **Function Body** edit box, and then click **Next**.

```
y = 1 - 6/(pi^2)*exp(-(pi^2/T)*x)
```



- In the **Parameter Initialization Code** page, select the **Use Labtalk** radio button to enable the use of Labtalk script. In the **Initialization Code** edit box, type in the following script:

```
//Code to be executed to initialize parameters

//Get the current worksheet page.
range rpage=ry.getpage();

//Get the data worksheet
range rlayer=ry.getlayer();

//Get the data worksheet index
int inext=rlayer.index;
```

```

//Make sure the data workbook is active

win -a %(ry.getpage()$);

//Make sure the data worksheet is active

page.active=inext;

//Active column 2 in the data worksheet

wks.col=2;

//Get the temperature as a string from column comment

string str1$ = wks.col.comment$;

//Get the string of the temperature number

string str2$ = str1.Left(3)$;

//Substitute the string variable to a double number

double Temp = %(str2$);

//Use the empirical equation to calculate the initial value of T

T=25000 - 58 * Temp;

//Check whether parameter initialization script runs successfully


type -b "Experimental temperature is $(Temp) K, so the initial value of T
is $(T)."
```

Notes: The *ry* in the script above is an auto-defined range variable for the input data range of parameter *y*, the syntax for such range variable is *r+parameter name*. For example, if the parameter name is *Temp*, the range variable should be *rTemp*.

7. Click **Finish** to create the user defined fitting function **UptakeCurveFit**, you could find its .fdf file in the **User Files Folder**.

Fit Data with the User Defined Fitting Function


1. Create a new Origin project by clicking the  button on the **Standard** toolbar. Click the  button (or **File:Import:Import Wizard** or press **Ctrl+3**) to open the **Import Wizard**.
2. In the **Data Source**, select the **UptakeCurve_343K.txt** as the **File**, which is located under path *<Origin Folder>\Samples\Curve Fitting*. Click **Next** button to navigate to the **Header Lines** page. Set the **Long Names**, **Units**, and **Comments** as **3**, **4**, and **1 to 1**, respectively.




3. Click **Finish** to import the data file. Note that the experimental temperature is stored as the comment of column 2, which will be retrieved by the Labtalk script for parameter initialization in the **UptakeCurveFit** fitting function.

	A(X)	B(Y)
Long Name	Time	Normalized Mass Uptake
Units	s	mg/g
Comments	Temperature	343K
Sparklines		
1	64.39925	0.29192
2	435.21421	0.74227
3	594.89529	0.83493
4	788.28682	0.88557
5	931.9998	0.91681
6	1167.97295	0.94698
7	1462.49584	0.96853
8	1867.02124	0.96314
9	2273.32089	0.99331
10		

- Highlight column B and select **Analysis:Fitting:Nonlinear Curve Fit** (or press **Ctrl+Y**) to open the **NLFit** dialog, select **User Defined** for **Category** and **UptakeCurveFit(User)** as **Function**.
- An attention box pops up and shows the experimental temperature and the calculated initial value of time constant.



- Go to the **Parameters** tab, see that the initial parameter for T is 5106, which is calculated from the experimental temperature. This indicates the parameter initialization script is successfully called.
- Go to the **Code** tab and select the **Parameter Init** section, there you could double check the parameter initialization script by clicking the  button.
- Click **OK** to close the attention box, and click **Fit** to carry out the fit.

Create an Analysis Template and Do Batch Processing

1. Go to the report sheet **FitNL1** which is generated from previous steps, click the triangle button right to the **Summary** table and choose **Create Copy as New Sheet**. A new sheet will be created, delete column A in the new sheet and rename it as **Result**.

	B(Y)	C(yEr?)	D(Y)	E(Y)
Long Name	T	T	Statistics	Statistics
Parameters	Value	Standard Error	Reduced Chi-Sqr	Adj. R-Square
1	5034.71487	690.3704	0.00391	0.91875
2				
3				

2. Keep the workbook active and select **File:Save Workbook as Analysis Template** to save this workbook as **MyUptakeFit.ogw**.
3. Create a new Origin project and select **File:Batch Processing** to open the **batchProcess** dialog.
4. Load the analysis template **MyUptakeFit.ogw**, select the files **UptakeCurve_343K.txt**, **UptakeCurve_373K.txt**, and **UptakeCurve_403K.txt** under the *<Origin Folder>\Samples\Curve Fitting* path, choose **File Name** for **Dataset Identifier** and make sure the other settings are the same according to the image below:

Batch Processing Mode

Repeatedly Import into Active Analysis Template Window
 Load Analysis Template

Analysis Template D:\Documents and Settings\originlab\Desktop\MyUptakeFit.ogw

Data Source Import From Files

Use Import Setting in Workbook

File List
D:\Program Files\OriginLab\Origin95R0\Samples\Curve Fitting\UptakeCurve_403K.txt
D:\Program Files\OriginLab\Origin95R0\Samples\Curve Fitting\UptakeCurve_343K.txt
D:\Program Files\OriginLab\Origin95R0\Samples\Curve Fitting\UptakeCurve_373K.txt

Dataset Identifier File Name

Data Sheet UptakeCurve_343K

Result Sheet Result

Contents from Result Sheet will be appended to the Output Sheet in another book, specified below

Output Sheet [Summary]Results!

Delete Intermediate Workbook

Options

Starting Row of Output Sheet 1

Clear Output Sheet on Start

Append Label Rows

When Output Sheet is Excel, check this box to append labels from Result Sheet

- Click **OK** to carry out the batch processing, for every file being executed, the attention box pops up and indicates the initial value being used, click **OK** every time to close the attention box and continue the batch processing. Finally, a summary report will be created:

The screenshot shows a window titled "Summary" with a table of results. The table has columns for Long Name, Parameters, Dataset, T Value, T Standard Error, Statistics (Reduced Chi-Sqr), and Statistics (Adj. R-Square). The data is as follows:

Long Name	Parameters	Dataset	T Value	T Standard Error	Statistics (Reduced Chi-Sqr)	Statistics (Adj. R-Square)
1		UptakeCurve_403K.bt	1954.30438	176.04279	3.45543E-4	0.98809
2		UptakeCurve_343K.bt	5034.71487	690.3704	0.00391	0.91875
3		UptakeCurve_373K.bt	2821.73125	210.70923	5.37589E-4	0.98522
4						
5						

4.2.2.6 User Defined Fitting Function

Summary

Besides the [200+ built-in fitting functions](#), you can also create your own fitting functions in Origin. Origin provides two tools for fitting with user defined function:

- [Simple Fit App](#)

Simple Fit App provides a much more convenient way to fit simple functions that can be expressed in the form $y = f(x)$, you only need to type your formula, specify the initial values and then generate fitting reports immediately. You can learn how to use this App in the linked File Exchange page.

- [NLFit tool](#).

NLFit tool is a powerful fitting wizard which allows you to define more complex fitting functions and control the fitting process in every possible way. For fitting user defined function in **NLFit** tool, you will need to create it in [Fitting Function Builder](#) first.

In this tutorial, we will mainly illustrate how to create a user-defined fitting function in **Fitting Function Builder**, carry out nonlinear curve fit with it and also show how to fix a parameter for curve fitting using **NLFit** tool.

Minimum Origin Version Required: Origin 2016 SR0

What You Will Learn

This tutorial will show you how to:

- Create a user-defined fitting function using the **Fitting Function Builder**.
- Carry out nonlinear curve fit with user-defined fitting function.
- Fix a parameter for nonlinear curve fit.

Steps

The data we are going to fit is **ConcentrationCurve.dat** file under *<Origin EXE Folder>\Samples\Curve Fitting* path.

The fitting function to be created and used is shown below:

$$y = A \exp(2.303kx - k_m) \sqrt{2.303 + \frac{C}{(x - C_0)}}$$

in which

y is the dependent variable


x is the independent variable

and A, k_m, k, C, C_0 are all fitting parameters.


Create a Fitting Function

In this section, we will show how to create the user defined fitting function in the **Fitting Function Builder**. But it is also possible to create user defined fitting function with the **Fitting Function Organizer**(Tools:Fitting Function Organizer or press **F9**).

1. Launch Origin and choose **Tools:Fitting Function Builder** (or press **F8**) to open the **Fitting Function Builder**.
2. In the **Goal** page, select **Create a New Function** and click **Next**.
3. In the **Name and Type** page, change the setting as the following image and then click **Next**:



4. In the **Variables and Parameters** page, enter the variable and parameter names as the image below and then click **Next**:



In the **Parameters** box, use comma (",") as delimiter.


- In the **Expression Function** page, enter the equation below in **Function Body**:

$$A * \exp(R0 * k * x - km) * \sqrt{R0 + c / (x - c0)}$$

- Go to the **Constant** tab, set the value of **R0** to **2.303**.
- Give estimated initial values to the parameters according to this particular data and function.

Parameters		Constants			
Param	Unit	Meaning	Fixed	Initial Value	Significant Digits
A		?	<input type="checkbox"/>	325	System <input type="button" value="v"/>
km		?	<input type="checkbox"/>	10	System <input type="button" value="v"/>
k		?	<input type="checkbox"/>	1	System <input type="button" value="v"/>
c		?	<input type="checkbox"/>	2	System <input type="button" value="v"/>
c0		?	<input type="checkbox"/>	0.1	System <input type="button" value="v"/>

Note: You can also give different initial values each time before you actually carry out the fitting.

8. Can click the **Evaluate** button  to quick check whether the function is valid(if it is valid, an actual value will be returned for y).

Note:If you used **Origin C** as **Function Type** at the beginning, you can also compile the function at this stage to check if there is any error, this is especially useful for brackets matching.

9. Click the **Next** button three times until it goes to **Derived Parameters** page.
10. In this page, we will define the derived parameter **A0**, enter its equation in the **Derived Parameters Equations** box:




$$A0 = -A * \exp(km) * 1E-4$$


11. Click **Finish** to create this user defined fitting function. The .FDF file for it will be stored in the **User Files Folder**.




You can always modify the user defined fitting function later, either in the **Fitting Function Builder**(choose **Edit a User-defined Function** in **Goal** page), or in the **Fitting Function Organizer**.


Carry Out Curve Fitting

1. Create a new workbook.
2. Click the  button to import the **ConcentrationCurve.dat** file under *<Origin EXE Folder>\Samples\Curve Fitting* path.
3. Highlight column B and click the  button to generate a scatter plot.
4. Keep the graph activated, select **Analysis:Fitting:Nonlinear Curve Fit** to open the **NLFit** dialog.
5. In the **Function Selection** page, set **Category** as **User Defined** and then set **Function** as **MyFitFunc(User)**.
6. Click the  button to fit the data.
7. An error message returns in the **Message** tab of the lower panel, indicates the fit did not converge because of overparameterization.




- The parameters **A** and **km** have mutual dependence, so fixing either one will solve the problem. We will fix **A** this time.

- Go to the **Parameters** tab, click the  to restore the initial value setting, check the **Fixed** box of parameter **A**:



- Click the **Fit** button to carry out the fit.
- The fitted curve will be added to the original data plot,



12. A report sheet will be generated as well, in which the fitted value of all parameters(including the derived parameter A0) are reported in the parameters table:

Parameters

	Value	Standard Error	t-Value	Prob> t	Dependency
A	325	0	--	--	0
km	8.43667	0.03316	254.39421	0	0.99957
k	0.67231	0.007	96.01794	0	0.99646
c	1.97517	0.1426	13.85121	2.21627E-11	0.9992
c0	0.06017	2.74698E-4	219.03971	0	0.84502
A0	-149.92769	4.97217			

Reduced Chi-sqr = 2.61349318598E-6

COD(R²) = 0.99983847595542

Iterations Performed = 27

Total Iterations in Session = 27

Fit converged. Chi-Sqr tolerance value of 1E-9 was reached.

Some parameter values were fixed.

Standard Error was scaled with square root of reduced Chi-Sqr.

A0 are derived parameter(s).

Constants : R0=2.303



In the case of overparameterization, you can fix different parameters to get multiple fit results and then compare the fit models statistically by **Analysis:Fitting:Compare Models** tool.

4.2.2.7 Fitting One Dataset as a Function of Other Datasets

Summary

Sometimes, one may want to perform "Dataset Fitting", that is, the output may be composed of one or several datasets, like:

$$Output = A_1 * Dataset_1 + A_2 * Dataset_2$$

For example, you may want to analyze a composite spectrum to find the contributions/ratio from individual component spectra. This can be accomplished either by defining multiple independent variables or by calculating the "combination" inside the fitting function.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn

This tutorial will show you how to:

- Perform "Dataset Fitting"
- Define multiple independent variable fitting function

Steps

Import the *Composite Spectrum.dat* file from the *\Samples\Curve Fitting* folder. In this sample data, we can see that column A is the index, columns B and C are the values for the spectrum of components A and B. Column D contains values obtained after reading a composite spectrum of components A and B. By fitting column D to an equation determined by the component spectra of the pure forms of columns B and C, the coefficients for the contributions of B and C (call them c1 and c2 respectively) can be found. (Note: In this case, we supposed the independent and dependent variables have the same size. If not, interpolation is need.)

Bring up the **Fitting Function Organizer** and define a new fitting function as follow:

Function Name:	MultIndep
Function Type:	User-Defined
Independent Variables:	a, b
Dependent Variables:	ab


Parameter Names:	C1, C2
Function Form:	Origin C
Function:	$ab = C1*a + C2*b;$

Initialize both C1 and C2 to 1 in the **Parameter Initialization** edit box by entering:

C1=1;

C2=1;

Save the fitting function and close **Fitting Function Organizer**. Highlight **ONLY** Column D and bring up the **NLFit** dialog, specify the input datasets in the **Data Selection** page as follow:



Then you can click the **Fit** button to generate results.


Results

You are supposed to get these results:

	Value	Standard Error
C1	0.37169	0.00483

C2	0.66469	0.0047
-----------	---------	--------

To verify the fitted results, you can add a new column and Copy + Paste the fitted value, which comes from the fitted Y (col(C)) in the worksheet *FitNLCurve1*, into it. Then Highlight the *Composite* and the fitted data and plot a line graph to see how good the fit is:



4.2.2.8 Fitting With Multiple Independent Variables

Summary

The **Function Organizer** tool can be used to create user-defined functions with more than one independent or dependent variable. The **NLFit dialog** can then be used to fit with such functions. The preview window in the NLFit dialog is capable of plotting only one quantity versus another. However, even if the preview does not "make sense", the fitting process will correctly proceed, once proper data and parameter assignments have been made.

Note that if you wish to fit multiple independent variables with an equation of the type $y = A0 + A1 * x1 + A2 * x2 + \dots$

you can make use of the Multiple Regression tool instead of the nonlinear fitter dialog.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn

This tutorial will show you how to:

- Create a user-defined fitting function with two independent variables and one dependent variable
- Fit with that function in NLFit


Steps

1. Start with a new workbook and import the file `\Samples\Curve Fitting\Activity.dat`.
2. Select **Tools: Fitting Function Organizer** from menu (or press **F9**) to bring up the **Fitting Function Organizer** and define a new fitting function named **MultIndep** in **NewCategory** (create the category if it does not exist) as follow:


Function Name:	MultIndep
Function Type:	User-Defined
Independent Variables:	substr,inhib
Dependent Variables:	act
Parameter Names:	ki,km,vm
Function Form:	Origin C
Function:	<pre>double mix = inhib / ki; act = vm * substr / (km + (1 + mix) * substr);</pre>

3. **NOTE:** Since we are using OriginC, case must match between defined names and their use in the function definition. e.g. Substr does NOT equal substr.
4. Click Save and then OK to save the function and close the Organizer.
5. For more details about User Defined Fitting Function please refer to [User Defined Fitting Function using Origin C](#).
6. Highlight **ONLY** column C and select **Analysis: Fitting: Non-linear Curve Fit** from menu to bring up the NLFit dialog. Select the function **MultIndep** from **NewCategory** on the **Settings**:

Function Selection page. Set the input datasets in the **Data Selection** page as follow:



7. Select the **Fitted Curves** page and expand the **Fitted Curves Plot** branch. Then select **Same as Input Data** from the drop-down list next to the **X Data Type** branch.



8. Select **Parameters Tab** and set the initial values as follow:

Settings	Code	Parameters	Bounds	
Automatic Parameter Initialization is enabled.				
Param	Meaning	Fixed	Value	Error
ki	?	<input type="checkbox"/>	0.01	--
km	?	<input type="checkbox"/>	1	--
vm	?	<input type="checkbox"/>	100	--

9. Click **Fit** button to generate the fitting reports. You can see these results from the report worksheet as below:

Parameters

		Value	Standard Error
Activity	ki	0.0373	0.00233
	km	7.30567	0.71748
	vm	653.1116	22.39698

Statistics

	Activity
Number of Points	18
Degrees of Freedom	15
Reduced Chi-Sqr	155.36102
Residual Sum of Squares	2330.41531
Adj. R-Square	0.98357
Fit Status	Succeeded(100)

From the Statistics table we can know that the fitting is fairly successful.

4.2.2.9 User Defined Fitting Function using GNU Scientific Library

This article demonstrates how to use GSL function as fit function.

Minimum Origin Version Required: Origin 8.0 SR6

1. We will fit the sample Data below by the following model:

$$y = y_0 + a \int_0^x e^{\beta \cdot t} dt$$

0.1	0.10517
0.2	0.2214
0.3	0.34986
0.4	0.49182
0.5	0.64872
0.6	0.82212
0.7	1.01375
0.8	1.22554

Tutorials for Origin

0.9	1.4596
1	1.71828
1.1	2.00417
1.2	2.32012
1.3	2.6693
1.4	3.0552
1.5	3.48169
1.6	3.95303
1.7	4.47395
1.8	5.04965
1.9	5.68589
2	6.38906
2.1	7.16617
2.2	8.02501
2.3	8.97418
2.4	10.02318
2.5	11.18249
2.6	12.46374
2.7	13.87973
2.8	15.44465
2.9	17.17415
3	19.08554
3.1	21.19795
3.2	23.53253

2. Add the file `ocgsl.h` in **(User Files folder)**, before next step, make sure the gsl dlls are copied to this same location, see [Calling GNU Scientific Library](#).

`ocgsl.h`

```
#pragma dll(libgsl, header)

// this is OC special pragma,

// header keyword is to indicate libgsl.dll is in same location as this file

#define GSL_EXPORT      // for OC, this is not needed, so make it empty

// you can directly search and copy gsl function prototypes here
```

```
typedef double (* FUNC)(double x, void * params);

struct gsl_function_struct
{
    FUNC function;

    void * params;
};

typedef struct gsl_function_struct gsl_function ;

typedef struct
{
    size_t limit;

    size_t size;

    size_t nrmax;

    size_t i;

    size_t maximum_level;

    double *alist;

    double *blist;

    double *rlist;

    double *elist;

    size_t *order;
```

Tutorials for Origin

```
    size_t *level;

}

gsl_integration_workspace;

GSL_EXPORT gsl_integration_workspace *gsl_integration_workspace_alloc (const size_t
n);
GSL_EXPORT void gsl_integration_workspace_free (gsl_integration_workspace * w)
GSL_EXPORT int gsl_integration_qag (const gsl_function * f,

    double a, double b,


    double epsabs, double epsrel, size_t limit,

    int key,

    gsl_integration_workspace * workspace,

    double *result, double *abserr);
```

3. Press F9 to open the **Fitting Function Organizer** and then add a new function as follows:



4. Press the button on the right hand side of the **Function** Field to open the code builder and add the following codes and compile: **_nlfgsl_integration_qag.fit**

```
#include "..\ocgsl.h"

static double f_callback(double x, void * params)
{
    double alpha = *(double *)params;

    return exp(alpha*x);
}
```

Tutorials for Origin

```
void _nlsfgsl_integration_qag(  
  
// Fit Parameter(s):  
  
double y0, double a, double beta,  
  
// Independent Variable(s):  
  
double x,  
  
// Dependent Variable(s):  
  
double& y)  
  
{  
  
    // Beginning of editable part  
  
    double result, err, expected = -4.0;  
  
  
    // Allocates a workspace sufficient to hold 1000 double precision intervals,  
    // their integration results and error estimates  
  
    gsl_integration_workspace *ww = gsl_integration_workspace_alloc(1000);  
  
  
    gsl_function F;  
  
    F.function = f_callback;  
  
    F.params = &beta ;  
  
  
    // integral interval (0, x), within the desired absolute  
  
    // error 0 and relative error 1e-7  
  
    gsl_integration_qag(&F, 0, x, 0, 1e-7, 1000, 0, ww, &result, &err);
```



```

// frees the memory associated with the workspace w

gsl_integration_workspace_free (ww);

y = y0 + a*result;

// End of editable part
}

```

Furthermore, a more elaborate but efficient version of the fitting function is given as follows

```

//-----
//
#include <ONLSF.h>
#include "..\ocgsl.h"

static double f_callback(double x, void * params)
{
    double alpha = *(double *)params;

    return exp(alpha*x);
}

void _nlsfgsl_integration_qag(

// Fit Parameter(s):

```

Tutorials for Origin

```
double y0, double a, double beta,

// Independent Variable(s):

double x,

// Dependent Variable(s):

double& y)

{

    // Beginning of editable part

    NLFitContext *pCtxt = Project.GetNLFitContext();

    if ( pCtxt )

    {

        static vector vInteg;

        NLSFCURRINFO    stCurrInfo;

        pCtxt->GetFitCurrInfo(&stCurrInfo);

        int nCurrentIndex = stCurrInfo.nCurrDataIndex;

        BOOL bIsNewParamValues = pCtxt->IsNewParamValues();

        if ( bIsNewParamValues )

        {

            vector vx;

            pCtxt->GetIndepData(&vx);

            int nSize = vx.GetSize();
```

```

vInteg.SetSize(nSize);

// Allocates a workspace sufficient to hold 1000 double
precision intervals,

// their integration results and error estimates

gsl_integration_workspace *ww =
gsl_integration_workspace_alloc(1000);

gsl_function F;

F.function = f_callback;

F.params = &beta ;

double result, err, expected = -4.0;

for(int ii=0; ii<nSize; ++ii)
{

// integral interval (0, vx[ii]), within the
desired absolute

gsl_integration_qag(&F, 0, vx[ii], 0, 1e-7, 1000,
0, ww, &result, &err); // error 0 and relative error 1e-7

vInteg[ii] = result;

}

// frees the memory associated with the workspace w

```

Tutorials for Origin

```
        gsl_integration_workspace_free (ww);

    }

    y = y0 + a*vInteg[nCurrentIndex];

    x;

}

// End of editable part

}
```

5. Add the following initialization codes:

Parameter Init

```
//Code to be executed to initialize parameters

sort( x_y_curve );

double coeff[2];

fitpoly( x_y_curve, 1, coeff);

a = coeff[0];

y0 = coeff[1];

beta=1.0
```

6. Fit using the user-defined function **gsl_integration_qag**, here are the results:

y0 = -1.06363E-6

a = 1

beta =1

4.2.2.10 Fitting with NAG Special Function

Summary

Origin allows user to define an Origin C fitting function using NAG special functions. You can call NAG routine to evaluate the special function.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn

This tutorial will show you how to:

- Create fitting function using Fitting Function Organizer
- Create fitting function using NAG special function

Example and Steps

We will fit the following model:

$$inorm = A * exp(-td/2.0/(t - t0)) * (I0(td/2.0/(t - t0)) + I1(td/2.0/(t - t0)))$$

Here A , td and $t0$ are the model parameters we want to obtain from the data fitting. $I0$ and $I1$ are the first kind of Modified Bessel function of order 0 and order 1, respectively. For current example, we use the sample data in the end of this tutorial. The fitting procedure can be outlined into the following steps:

Press **F9** to open the **Fitting Function Organizer** and then create a new Category named **FittingWithNAGSpecialFunc**. Define a new fitting function **FittingWithBessel** in the new category as follow:

Function Name:	FittingWithBessel
Function Type:	User-Defined
Independent Variables:	t
Dependent Variables:	inorm
Parameter Names:	A,t0,td
Function Form:	Origin C
Function:	

Tutorials for Origin

Click the button (icon) beside the **Function** box to open the code builder and define and compile and save the fitting function as follows:

```
#include <origin.h>

// Add your special include files here.

// For example, if you want to fit with functions from the NAG library,

// add the header file for the NAG functions here.

#include <OC_nag8.h>

// Add code here for other Origin C functions that you want to define in this file,

// and access in your fitting function.

// You can access C functions defined in other files, if those files are loaded and
compiled

// in your workspace, and the functions have been prototyped in a header file that
you have

// included above.

// You can access NLSF object methods and properties directly in your function
code.

// You should follow C-language syntax in defining your function.

// For instance, if your parameter name is P1, you cannot use p1 in your function
code.
```

```

// When using fractions, remember that integer division such as 1/2 is equal to 0,
and not 0.5

// Use 0.5 or 1/2.0 to get the correct value.

// For more information and examples, please refer to the "User-Defined Fitting
Function"

// section of the Origin Help file.

//-----

//

void _nlsfFittingWithBessel(

// Fit Parameter(s):

double A, double t0, double td,

// Independent Variable(s):

double t,

// Dependent Variable(s):

double& inorm)

{

    // Beginning of editable part

    //inorm= A* exp(-td/2.0/(t-t0)) * ( s18aec(td/2.0/(t-
t0),NAGERR_DEFAULT)+s18afc(td/2.0/(t-t0),NAGERR_DEFAULT) );

```

Tutorials for Origin

```
static NagError fail1;

static NagError fail2;

double dtemp = td/2.0/(t-t0);

inorm= A* exp(-dtemp) * ( s18aec(dtemp,&fail1)+s18afc(dtemp,&fail2) );

if(fail1.code !=NE_NOERROR)

    printf("%s\n", fail1.message);

if(fail2.code !=NE_NOERROR)

    printf("%s\n", fail2.message);

// End of editable part

}
```

Simulate the Function

After the function body is defined, you can click the **Compile** button in **Code Builder** to check syntax errors. And then click **Return to Dialog** button to go back **Fitting Function Organizer** dialog box. Now click the **Save** button to generate the .FDF file (Function definition file).

Once you have a .FDF file, you can click the **Simulate** button to simulate a curve, this will be very helpful to evaluate the initial values. In the **simcurve** dialog, enter some proper parameter values and X range, and see what the curve looks like in the **Preview** panel.

Set the Initial Values for the Parameters

As it is a user-defined fitting function, you have to supply the initial guess values for the parameters before performing your fitting task for the data. You may do it by set them manually in the **Parameter** tab in **Nonlinear Curve Fit** dialog. For the sample data shown below, you can just set the initial values for the parameters $A = 1$, $td = 1$, $t0 = 1$. After the parameters are initialized, you can then do the fitting to obtain the fitting result, as shown to the right of the sample data.

Sample Data

Copy the below sample data and use **Import Wizard** to import the data from **Clipboard**, then do the fitting using the given initial values for the parameters: $A = 1$, $td = 1$, $t0 = 1$.

Sample Data		Results
X	Y	
2	0.7868954118	
2.080808081	0.8133022141	
2.161616162	0.8178216765	
2.242424242	0.8427866729	
2.323232323	0.8315815363	
2.404040404	0.8484657180	
2.565656566	0.8618233553	
2.646464646	0.8745962570	
2.727272727	0.8921620316	
2.808080808	0.8687399759	

Parameters			
		Value	Standard Error
"Y"	A	0.96431	0.06562
	t0	1.39545	0.40134
	td	0.53711	0.54076

Reduced Chi-sqr = 1.02442755048E-4
 COD(R²) = 0.92247024814828
 Iterations Performed = 11
 Total Iterations in Session = 11
 Fit converged - tolerance criterion satisfied.

4.2.2.11 Fitting Integral Function with parametric limit using NAG Library

Summary

Before you start delving into this tutorial, you are recommended to read the relevant tutorial in [Fitting with Integral using NAG Library](#). And as far as programming is concerned, the two tutorials are basically the same, except that here you will learn to define Origin C fitting function with fitting parameters in the integral limit, while in the previous tutorial we in fact define a fitting independent variable in the integral limit. Also note that a **different NAG integrator** is used here.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn

This tutorial will show you how to:

Tutorials for Origin

- Create a fitting function with Definite Integral using the NAG integration routine
- Create a fitting function with a parametric integral limit
- Use a log function to scale a large return value from the fitting function

Example and Steps

For example, we will fit the [sample data](#) at the bottom of this page with the following model:

$$y = \int_c^d \frac{\cosh((x_i + b^2 \cdot x^2)/(b + x))}{a + (x_i^2 + x^2)} dx_i$$


Note that we use x_i to indicate the integral independent variable while x indicates the fitting independent variable. The model parameters a , b , c , and d are fitted parameters we want to obtain from the sample data. To prepare the data, you just need to copy the sample data to an Origin Work sheet. The fitting procedure is similar to the previous tutorial:

Define Fitting Function in Fitting Function Organizer

Press **F9** to open the Fitting Function Organizer and add the User-Defined integral fitting function **nag_integration_fitting_cosh** to the Category **FittingWithIntegral**, similar to the first tutorial.

Function Name:	nag_integration_fitting_cosh
Function Type:	User-Defined
Independent Variables:	x
Dependent Variables:	y
Parameter Names:	a, b, c, d
Function Form:	Origin C
Function:	



Click the button  beside the **Function** box to open the code builder and define and compile the fitting function as follows: (**Note**: Remember to save the Function after compiling it and returning to the Function Organizer Dialog):

```
#include <origin.h>
```

```
// Add your special include files here.
```

```
// For example, if you want to fit with functions from the NAG library,  
  
// add the header file for the NAG functions here.  
  
#include <OC_nag.h>  
  
  
  
// Add code here for other Origin C functions that you want to define in this file,  
  
// and access in your fitting function.  
  
struct user  
{  
  
    double a, b, fitX; // fitX the independent variable of fitting function  
  
};  
  
static double NAG_CALL f_callback(double x, Nag_User *comm) // x is the  
independent variable of the integrand  
{  
  
    struct user *sp = (struct user *) (comm->p);  
  
    double aa, bb, fitX; // temp variable to accept the parameters in the  
Nag_User communication struct  
  
    aa = sp->a;  
  
    bb = sp->b;
```

Tutorials for Origin

```
fitX = sp->fitX;

return cosh((x*x+bb*bb*fitX*fitX)/(bb+fitX))/(aa+(x*x+fitX*fitX));
}

// You can access C functions defined in other files, if those files are loaded and
// compiled

// in your workspace, and the functions have been prototyped in a header file that
// you have

// included above.

// You can access NLSF object methods and properties directly in your function
// code.

// You should follow C-language syntax in defining your function.

// For instance, if your parameter name is P1, you cannot use p1 in your function
// code.

// When using fractions, remember that integer division such as 1/2 is equal to 0,
// and not 0.5

// Use 0.5 or 1/2.0 to get the correct value.

// For more information and examples, please refer to the "User-Defined Fitting
// Function"

// section of the Origin Help file.
```

```
//-----  
  
//  
  
void _nlsfnag_integration_fitting_cosh(  
  
// Fit Parameter(s):  
  
double a, double b, double c, double d,  
  
// Independent Variable(s):  
  
double x,  
  
// Dependent Variable(s):  
  
double& y)  
  
{  
  
    // Beginning of editable part  
  
    double epsabs = 0.00001, epsrel = 0.0000001, result, abserr;  
  
    Integer max_num_subint = 500;  
  
    // you may use epsabs and epsrel and this quantity to enhance your desired  
precision  
  
    // when not enough precision encountered  
  
  
    Nag_QuadProgress qp;  
  
    static NagError fail;
```

Tutorials for Origin

```
// the parameters parameterize the integrand can be input to the call_back
function
// through the Nag_User communication struct

Nag_User comm;

struct user s;

s.a = a;

s.b = b;

s.fitX = x;

comm.p = (Pointer)&s;

d01sjc(f_callback, c, d, epsabs, epsrel, max_num_subint, &result, &abserr,
&qp, &comm, &fail);

// you may want to exam the error by printing out error message, just
uncomment the following lines

// if (fail.code != NE_NOERROR)

// printf("%s\n", fail.message);

// For the error other than the following three errors which are due to bad
input parameters

// or allocation failure NE_INT_ARG_LT NE_BAD_PARAM NE_ALLOC_FAIL
```

```

        // You will need to free the memory allocation before calling the
integration routine again to
        // avoid memory leakage

        if (fail.code != NE_INT_ARG_LT && fail.code != NE_BAD_PARAM && fail.code !=
NE_ALLOC_FAIL)

        {

                NAG_FREE(qp.sub_int_beg_pts);

                NAG_FREE(qp.sub_int_end_pts);

                NAG_FREE(qp.sub_int_result);

                NAG_FREE(qp.sub_int_error);

        }

        y = log(result);

        // note use log of the integral result as return as the integral result is
large,

        // you are not necessary to do so

        // End of editable part
}

```

In the above code, we define the integrand as a callback function *f_callback* just outside the fitting function body *_nlsfnag_integration_fitting_cosh*. Note that we parametrize the integrand function with the variables *a*, *b* and *fitX*, and pass them into the callback function through the *Nag_User* struct. After that we perform the integration using NAG integrator *d01sjc*. Besides, you can also use other [Quadrature Routines](#) as you want. In the current example, we also use a log scale for the fitting function. (The sample data are already scaled by a log function)

Compile the code, return to the dialog and then Save the fitting function in the function Organizer and open the **Nonlinear Curve Fit** dialog in the **Analysis-Fitting** menu. You can then select this user-defined fitting function in the **Function Selection** page under **Setting** Tab.

Set the Initial Values for the Parameters

Similarly, as it is a user-defined fitting function, you have to supply the initial guess values for the parameters. You may manually set them in the **Parameter** tab in **Nonlinear Curve Fit** dialog. For current example, you can just set the initial values for the parameters $a = 1, b = 10, c = 3, d = 4$. After the parameters are initialized, you can perform the fitting to obtain the fitting result, as shown in the following.

Sample Data

Sample Data		Results
X	Y	
-5	498.19046	
-4.33333	329.43196	
-3.66667	210.28005	
-3	126.55799	
-2.33333	69.01544	
-1.66667	31.3555	
-1	9.1393	
-0.33333	-0.84496	
0.33333	-0.99914	
1	6.86736	

	Value	Standard Error
a	0.99303	0.06577
b	10	5.3108E-5
c	3.00083	0.0062
d	4.00022	9.38713E-4

4.2.2.12 Fitting with Integral using NAG Library

Summary

Origin allows user to define an Origin C fitting function which involves an integral. You can call NAG functions to perform the integration while defining the fitting function. There are built-in functions in Origin C which perform integration. For the current example, the NAG solution is recommended. It has a better performance compared to the built-in integration algorithm. Note that an **infinite NAG integrator** is used here.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn

This tutorial will show you how to:

- Create a fitting function using the Fitting Function Organizer
- Create a fitting function with a Definite Integral using a NAG integration routine
- Set up the Initial Code for the fitting function

Example and Steps

We will fit the following model:

$$y = y_0 + \int_{-\infty}^x \frac{A}{w\sqrt{\frac{\pi}{2}}} e^{-2\frac{(t-x_c)^2}{w^2}} dt$$

Here y_0 , A , x_c and w are the model parameters we want to obtain from the data fitting. The fitting procedure can be outlined into the following steps:

Define the Function


Press **F9** to open the **Fitting Function Organizer** and then create a new Category named **FittingWithIntegral**. Define a new fitting function **nag_integration_fitting** in the new category as follow:

Function Name:	nag_integration_fitting
Function Type:	User-Defined
Independent Variables:	x
Dependent Variables:	y
Parameter Names:	y0, A, xc, w
Function Form:	Origin C

Tutorials for Origin

Function:	
------------------	--



Click the  button beside the **Function** box to open the code builder then follow the steps below:

1. Scroll up to go to line

```
//add the header file for the NAG functions here.
```

2. and paste the following code below this line.

```
#include <OC_nag.h>
```

3. Go to line

```
// and access in your fitting function.
```

4. and paste the following code below.

```
struct user // parameters in the integrand
{
    double amp, center, width;
};

// Function supplied by user, return the value of the integrand at a given
x.

static double NAG_CALL f_callback(double x, Nag_User *comm)
{
    struct user *sp = (struct user *) (comm->p);
```

```

        double amp, center, width;    // temp variable to accept the
parameters in the Nag_User communication struct

        amp = sp->amp;

        center = sp->center;

        width = sp->width;

        return amp * exp( -2*(x - center)*(x - center)/width/width ) /
(width*sqrt(PI/2));
    }

```

5. Go to line

```
// Beginning of editable part.
```

6. and paste the following code below.

```

// Through the absolute accuracy epsabs, relative accuracy epsrel and
max_num_subint you can

        // control the precision of the integration you need

        // if epsrel is set negative, the absolute accuracy will be used.

        // Similarly, you can control only relative accuracy by set the
epsabs negative

        double epsabs = 0.0, epsrel = 0.0001;

        // The max number of sub-intervals needed to evaluate the function
in the integral

```

```
    // The more difficult the integrand the larger max_num_subint
should be

    // For most problems 200 to 500 is adequate and recommended

Integer max_num_subint = 200;

    // Result keeps the approximate integral value returned by the
algorithm

    // abserr is an estimate of the error which should be an upper
bound for the |I - result|

    // where I is the integral value

double result, abserr;

    // The structure of type Nag_QuadProgress,

    // it contains pointers allocated memory internally with
max_num_subint elements

Nag_QuadProgress qp;

    // The NAG error parameter (structure)

static NagError fail;

    // Parameters passed to integrand by Nag_User communication struct

    Nag_User comm;

struct user s;
```

```

        s.amp = A;

        s.center = xc;

        s.width = w;

        comm.p = (Pointer)&s;

        // Perform integration

        // There are 3 kinds of infinite boundary types you can use in Nag
infinite integrator

        // Nag_LowerSemiInfinite, Nag_UpperSemiInfinite, Nag_Infinite

        d01smc(f_callback, Nag_LowerSemiInfinite, x, epsabs, epsrel,
max_num_subint, &result, &abserr, &qp, &comm, &fail);

        // you may want to exam the error by printing out error
message, just uncomment the following lines

        // if (fail.code != NE_NOERROR)

        // printf("%s\n", fail.message);

        // For the error other than the following three errors which are
due to bad input parameters

        // or allocation failure  NE_INT_ARG_LT  NE_BAD_PARAM
NE_ALLOC_FAIL

        // You will need to free the memory allocation before calling the
integration routine again to avoid memory leakage

        if (fail.code != NE_INT_ARG_LT && fail.code != NE_BAD_PARAM &&

```

```
fail.code != NE_ALLOC_FAIL)

    {

        NAG_FREE(qp.sub_int_beg_pts);

        NAG_FREE(qp.sub_int_end_pts);

        NAG_FREE(qp.sub_int_result);

        NAG_FREE(qp.sub_int_error);

    }

    // Calculate the fitted value

    y = y0 + result;
```

7. Click **Compile** to compile the file.

In the above code, we firstly define the integrand as a callback function ***f_callback*** just outside the fitting function body ***_nlsfnag_integration_fitting***. Note that we parametrize the integrand function with the variables ***amp***, ***center*** and ***width***, and pass them into the callback function through the ***Nag_User*** struct. Inside the fitting function, we perform the integration using NAG integrator ***d01smc***. Calling NAG functions should be more efficient than writing your own routines. Using an analogous method, you can perform finite, infinite, one-dimension and multi-dimension quadrature in your fitting function. Please read the [NAG Quadrature](#) page and select a proper routine.

Set the Initial Values for the Parameters or Setup the Initial Code

As it is a user-defined fitting function, you have to supply the initial guess values for the parameters. You may do it later by setting them manually in the **Parameter** tab in **Nonlinear Curve Fit** dialog.

Simulate the Function

After entering the function body codes, you can click the **Compile** button in **Code Builder** to check syntax errors. And then click **Return to Dialog** button to go back **Fitting Function Organizer** dialog box. Now click the **Save** button to generate the .FDF file (Function definition file).

Once you have a .FDF file, you can click the **Simulate** button to simulate a curve, this will be very helpful to evaluate the initial values. In the **simcurve** dialog, enter some proper parameter values and X range, and see what the curve looks like in the **Preview** panel.

Fit the Curve

Before you start to fit the curve, it is very helpful to simulate the function first. Performing integration may take some time, if there is any mistake, you may see Origin "freeze" after you click the **Fit** button. So in the **Fitting Function Organizer** dialog, select the function we defined and click the **Simulate** button. This will bring up the **simcurve** X-Function. Enter some "guess" values and click the **Apply** button. If the simulated curve looks like your source data, you can go further to fit.

To test the fitting function:

1. Import `\Samples\Curve Fitting\Replicate Response Data.dat` to Origin.
2. Next we are going to use log scale of the data in Col(A). To do this, in the **F(x) =** column label row of column A, type in the formula `Col(A) = log(Col(A))` and hit **Enter** once to change the data.
3. Highlight column A and B and create a scatter plot, the shape is a sigmoid curve.
4. Bring up the **NLFit** dialog from **Analysis: Fitting: Nonlinear Curve Fit** menu item.
5. Select the fitting function we defined in the previous sections and go to the **Parameters** tab, initialize all parameters by 1 and fit (click **Fit** button).
6. You are supposed to see these results:

	Value	Standard Error
y0	-0.00806	0.18319
A	3.16479	0.39624
xc	-0.19393	0.10108
w	1.77252	0.33878

4.2.2.13 Fitting with Integral using LabTalk Function

Summary

Since version **Origin 8.6**, Origin introduces a new LabTalk function, **integral()**, to do one-dimensional integration. This function returns the integral value of:

$$\int_{LowerLimit}^{UpperLimit} f(t, arg1, arg2, \dots), dt$$

And the interface of the **integral()** function is defined as below:

```
integral(integrandName, LowerLimit, UpperLimit [, arg1, arg2, ...])
```

Where *integrandName* here is the function name of the integrand:

$$f(t, arg1, arg2, \dots)$$

In other word, the *integral()* function do the following things:

- Accept another function (the first argument) as the integrand.
- Perform integration on specified lower and upper limit and return the integral value.
- If need, pass the subsequent arguments (*Arg1*, *Arg2*, ...) into the integrand function.

Using this feature, we can define a fitting function with *integral()* function, and pass proper fitting parameters to the integrand, to do integration in curve fitting.

In this tutorial, we will modify the other tutorial, [calling NAG functions to do integration during fitting](#), into LabTalk form, and show you how simple and straightforward to fit an integration function.

Minimum Origin Version Required: Origin 8.6

What you will learn

This tutorial will show you how to:

- Create a fitting function using the Fitting Function Builder
- Create a fitting function with a Definite Integral using Labtalk function
- Set up the Initial Code for the fitting function

Example and Steps

The Fitting Model


The fitting model is described as below:

$$y = y_0 + \int_{-\infty}^x \frac{A}{w \sqrt{\frac{\pi}{2}}} e^{-2 \frac{(t-x_c)^2}{w^2}} dt$$

There are four parameters in the fitting function, and we need to pass three of them into the integrand, and use the independent variable as upper limit, to do integration. So you should define the integrand first, and then use the *integral()* function to perform integration inside your fitting function body.

Define the Function


1. Press **F8** to open **Fitting Function Builder** dialog. Make sure choosing **Create a New Function** option, and click **Next** to navigate to the next page.
2. In the **Name and Type** page, enter a function name, say **MyIntegGauss**. Leave the default function type as **Expression**, and then check the **Include Integration During Fitting** checkbox. This will lead you to a new page in the next step.



3. In the **Integrand** page, you can define the expression of the integrand. Currently, Origin supports one-dimensional integral only, so the integrand should have ONE integration variable. In this example, the expression of the integrand is:

$$\frac{A}{w\sqrt{\frac{\pi}{2}}} e^{-2\frac{(t-x_c)^2}{w^2}}$$


The other variables, like x_c , w , and A , are parameters of the integrand. To distinguish from fitting parameters, we named them *Arguments* here, and use the arguments name ix_c , iw , and iA instead. Later, we can pass fitting parameters into these arguments. So, the integrand definition should look like:



Note that this is a LabTalk function. To get the integration value, you must have a **RETURN** statement in the function body. And the integrand expression in this example should be:

```
return iA * exp(-2*(t-ixc)^2/iw^2) / (iw*sqrt(PI/2));
```

4. When all set, click **Next** to go to the **Variables and Parameters** page to define the variables and parameters for the fitting function as below:



5. The next **Function** page is where you define the fitting function body. Once you choose to include integration in your fitting function at the beginning of the fitting function builder wizard, there is an extra tab, **Integrand**, shown on this page. In this tab, you can map the fitting variables and parameters with elements of the integrand, including lower limit, upper limit, and integrand arguments. And in this example, we will map the variables as below:

Integrand elements	Values pass into integrand
Lower Limit	-inf
Upper Limit	x
ixc	xc

iw	w
iA	A


6. Once set up all the mappings as above table, click the **Insert** button, then well prepared *integral()* function is inserted into the **Function Body** box as:

```
integral(MyIntegrand, -inf ,x ,xc ,w ,A)
```

7. This expression means perform integration on the function, whose name is *MyIntegrand*, from negative infinite to *x*, and pass the three fitting parameters, *xc*, *w*, and *A* to the integrand.
8. By adding the constant parameter, *y0*, into the expression, the whole fitting function body should be:

```
y0 + integral(MyIntegrand, -inf, x, xc ,w ,A);
```

9. And the page may looks as below:
- 10.



11. Then active the **Parameters** tab, and give some proper initial values for each fitting parameters as:

Param	Unit	Meaning	Fixed	Initial Value	Significant Digits
y0			<input type="checkbox"/>	0	System
xc			<input type="checkbox"/>	0	System
w			<input type="checkbox"/>	2	System
A			<input type="checkbox"/>	3	System

Now, you can click **Finish** button to save this fitting function.

Fit the Curve

Copy and paste the following data into Origin worksheet:

X	Y
-1.69897	0.13136
-1.22185	0.34384
-0.92082	0.6554
-0.82391	0.73699
-0.69897	1.00157
0	1.70785
0.30103	2.31437
0.69897	2.77326
1	2.79321

Highlight the Y column, and press **Ctrl + Y** to open the **NLFit** dialog. Select the function you just defined, and click **Fit** button to perform fitting. The fitting result should be the same like using NAG function directly:

Parameters			
		Value	Standard Error
B	y0	-0.01749	0.20203
	xc	-0.21058	0.11852
	w	1.76925	0.36484
	A	3.15913	0.42476

Reduced Chi-sqr = 0.0114837622841
 COD(R^2) = 0.99334903530799
 Iterations Performed = 6
 Total Iterations in Session = 6
 Fit converged. Chi-Sqr tolerance value of 1E-9 was reached.

4.2.2.14 Fitting with Two Integrals using LabTalk Function

Summary

In some circumstance, one may want to create fitting function with multiple integrals:

$$\int_{LL1}^{UL1} f(t, \text{arg1}, \text{arg2}, \dots) dt + \int_{LL2}^{UL2} g(x, \text{arg3}, \text{arg4}, \dots) dx$$

We refer to [Fitting with Integral using LabTalk Function](#) for detailed description of parameters in the expression.

In version Origin 8.6, however, **Fitting Function Builder** just supports one integral in fitting function. Bypassing complex Origin C code, we can use **Fitting Function Organizer** to reach the goal.

In this tutorial, we will show you how to create a fitting function comprised of two integrals using function organizer. Of course, one can include more integrals as desired.

Minimum Origin Version Required: Origin 8.6

What you will learn

This tutorial will show you how to:

- Create a fitting function using the Fitting Function Organizer
- Create a fitting function with two integrals using LabTalk function

Example and Steps

The Fitting Model


The fitting model is described as below:

$$y = y_0 + \int_{-5}^x A t dt - \int_{-\infty}^x B t \exp(-t^2/w^2) dt$$


There are four parameters in the fitting function, and we need to pass three of them into the integrand, and use the independent variable as upper limit, to do integration.

Define the Function

1. Press F9 to open **Fitting Function Organizer** dialog. Add a new function by pressing **New Function** after you select a category in which you want to put your function. One can also add new category by pressing the **New Category** button.




2. Specify the function name in the **Function Name** edit box as you like. Define **Independent Variables**, **Dependent Variables** and **Parameter Names** in corresponding edit box.
3. Select the **Function Form** in the drop box. One can find explanations in the **Hints** tab at the bottom of the dialog.



- In the **Function** edit box, define your fitting function. The integrals are written in the form of LabTalk **integral** function.

```
y=integral(polyint, -5, x, a)-integral(gaussint, -inf, x, b, wc)+y0
```

- As described in [Fitting with Integral using LabTalk Function](#), x , a , b and wc are parameters passed into the integrand functions.
- Press the button at the right corner of **Parameter Settings** box to active **Parameter Settings** dialog. Set initial values as well as other constraints such as lower bounds, upper bounds for each parameter.



7. Define the two integrals in the **LabTalk Functions Definition and Initializations** box. In this case, the functions should be:

```
function double polyint(double t, double ia)
{
    return ia*t;
}


function double gaussint(t, ib, iwc)
{
    return ib *t* exp(-(t)^2/iwc^2);
}
```

8. We have successfully set our two integrals fitting function. You can set other information in corresponding box. Do not forget to **Save** your fitting function after you finish.

Fit the Curve

Copy and paste the following data into Origin worksheet:

X	Y
-3	2.47613
-2.6	2.24016
-2.2	2.01543
-1.8	1.83094
-1.5	1.85038
-1.1	2.17725
-0.9	2.44967
-0.7	2.61423
-0.5	3.02305
-0.3	3.23057
-0.1	3.37822
0.1	3.2827
0.3	3.18775
0.5	2.86194
0.7	2.69104
0.9	2.39315
1.4	2.04046
1.8	1.85287
2.2	1.85325
2.6	2.20569

Highlight the Y column, and press CTRL + Y to open the **NLFit** dialog. Select the function you just defined, and click fit button  to perform fitting.

Parameters

		Value	Standard Error
B	a	0.26191	0.03201
	b	3.5282	0.21956
	wc	1.07153	0.04832
	y0	4.57942	0.29938

Reduced Chi-sqr = 0.00376913022891
 COD(R^2) = 0.98854435477482
 Iterations Performed = 7
 Total Iterations in Session = 7
 Fit converged. Chi-Sqr tolerance value of 1E-9 was reached.

4.2.2.15 Fitting with Summation

Summary

We have showed you how to perform [fitting with an integral](#) using the [NAG Library](#), and now you'll learn how to do that without calling NAG functions. In this tutorial, we will show you how to do integration by the trapezoidal rule and include the summation procedure in the fitting function.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn


- How to include summation in your fitting function.
- Trapezoidal rule for integration.

Example and Steps

We will fit the same model as the [integral fit using NAG](#):

$$y = y_0 + \int_{-\infty}^x \frac{A}{w \sqrt{\frac{\pi}{2}}} e^{-2 \frac{(x-x_c)^2}{w^2}} dx$$

The difference is that we will perform the integration within the fitting function. Using the trapezoidal rule, we will first divide the curve into pieces and then approximate the integral area by multiple trapezoids. The precision of the result then depends on how many trapezoids will be used. Since this is a semi-infinite integration, we will set an increment (steps) and construct trapezoids from the upper integral limit, x, to the lower integral limit, negative infinity and then accumulate the area of these trapezoids. When the increment of the area is significantly small, we will stop the summation. Before doing the summation, you should guarantee that the function is **CONVERGENT**, or you should include a convergence check in your code.



Define the Function

Select **Tools:Fitting Function Organizer** or alternatively press the **F9** key to open the **Fitting Function Organizer** and then define the function as follows:

Function Name:	summation
Function Type:	User-Defined
Independent Variables:	x
Dependent Variables:	y
Parameter Names:	y0, A, xc, w
Function Form:	Origin C
Function:	

Click the button (icon) beside the **Function** box to open Code Builder. Define, compile and save the fitting function as follows:

```
#pragma warning(error : 15618)

#include <origin.h>

// Subroutine for integrand

double f(double x, double A, double xc, double w)
```

```
{  
  
    return A * exp(-2*(x-xc)*(x-xc)/w/w) / w / sqrt(PI/2);  
  
}  
  
//-----  
  
//  
  
void _nlsfsummation(  
  
// Fit Parameter(s):  
  
double y0, double A, double xc, double w,  
  
// Independent Variable(s):  
  
double x,  
  
// Dependent Variable(s):  
  
double& y)  
  
{  
  
    // Beginning of editable part  
  
    // Set the tolerance for stop integration.  
  
    double dPrecision = 1e-12;  
  
    // Initialization  
  
    double dIntegral = 0.0;  
  
    double dTrapezia = 0.0;  
  
    // Steps, or Precision.  
  
    double dStep = 0.01;
```

Tutorials for Origin

```
// Perform integrate by trapezoidal rule.

// Note that you should guarantee that the function is CONVERGENT.

do

{

    // Trapezia area.

    dTrapezia = 0.5 * ( f(x, A, xc, w) + f((x-dStep), A, xc, w) ) *
dStep;

    // Accumulate area.

    dIntegral += dTrapezia;

    x -= dStep;

}while( (dTrapezia/dIntegral) > dPrecision );

// Set y value.

y = y0 + dIntegral;

// End of editable part

}
```

Fit the Curve

We can use the same data to test the result.

1. Import *\Samples\Curve Fitting\Replicate Response Data.dat*.
2. Highlight the first column, right-click on it, and select Set Column Values from the context menu.
3. Set $Col(A) = \log(Col(A))$ in the **Set Column Values** dialog. This will make a sigmoidal curve.
4. Highlight columns A and B and create a scatter plot.
5. Then bring up the **NLFit** dialog by pressing **Ctrl + Y**. Select the fitting function we just defined and go to the **Parameters** tab, initialize all parameters to 1 and fit. You should see these results:

	Value	Standard Error
y0	-0.00806	0.18319
A	3.16479	0.39624
xc	-0.19393	0.10108
w	1.7725	0.33878

4.2.2.16 Fitting Complex Function

Summary

When fitting with a complex function, we can easily separate the complex function to two functions: one corresponding to its real part and the other corresponding to its imaginary part. With these two functions, we can define the complex fitting function with two dependent variables by **Fitting Function Organizer** and can access it in **NLFit** dialog. We will illustrate how to fit with complex function below. More details about fitting with multiple dependent or independent variable please refer to [Fitting with Multiple Independent Variables](#).

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn

This tutorial will show you how to:

- Create a user-defined complex fitting function with two dependent variables and one independent variable
- Fit with such function in NLFit

Steps

1. Select whole form below (including header line) and right click to choose **Copy** to put the data in clipboard.

Omega	Y1	Y2
0	3	0
0.01	2.88462	-0.28846

0.02	2.58621	-0.51724
0.03	2.20588	-0.66176
0.04	1.82927	-0.73171
0.05	1.5	-0.75
0.06	1.22951	-0.7377
0.07	1.01351	-0.70946
0.08	0.8427	-0.67416
0.09	0.70755	-0.63679
0.1	0.6	-0.6
0.11	0.5137	-0.56507

2. Select **Import/ Import Wizard** to open Import Wizard dialog. Then choose **Clipboard** in **Data Source** group and click **Finish** to import the data.




3. Select **Tools: Fitting Function Organizer** from menu (or press **F9**) to bring up the **Fitting Function Organizer** and define a new fitting function named **ComplexFitting** in **NewCategory** (create the category if not exist) as follow:

Function Name:	ComplexFitting
Function Type:	User-Defined
Independent Variables:	omega
Dependent Variables:	y1,y2
Parameter Names:	A,tau
Function Form:	Origin C
Function:	<pre>complex cc = A/(1+1i*omega*tau); y1 = cc.m_re; y2 = cc.m_im;</pre>

4. Note: To use the imaginary unit "i" for creating complex numbers, you need to write it as "1i" in Origin C, as in the above **Function** row. And **complex** is a class that implements a complex number data type. It contains both a Real and an Imaginary component.
5. For more details about creating user-defined fitting function, please refer to [User Defined Fitting Function using Origin C](#).
6. Highlight all the columns and select **Analysis: Fitting: Non-linear Curve Fit** from menu to bring up the NLFit dialog. Select the function **ComplexFitting** from **NewCategory** on the **Settings**:

Function Selection page. Set the input datasets in the **Data Selection** page as follow:



7. Select **Parameters Tab** and set the initial values as follows:

Param	Meaning	Fixed	Value	Error
A	?	<input type="checkbox"/>	1	--
tau	?	<input type="checkbox"/>	1	--

8. Click **Fit** to generate the fitting report sheet. You can see the results from the report worksheet as below:

Parameters

		Value	Standard Error
Y1,Y2	A	2.36712	0.15413
	tau	15.84746	1.94844

Statistics

	Y1,Y2
Number of Points	24
Degrees of Freedom	22
Reduced Chi-Sqr	0.12339
Residual Sum of Squares	2.71451
Adj. R-Square	0.92387
Fit Status	Succeeded(100)

From the Statistics table, we can see that the fitting is fairly successful.

4.2.2.17 Fitting with Convolution

Summary

When performing curve fitting to experimental data, one may encounter the need to account for instrument response in the data. One way to do this is to first perform deconvolution on the data to remove the instrument response, and then perform curve fitting as a second step. However, deconvolution is not always reliable as the results can be very sensitive to any noise present in the data. A more reliable way is to perform convolution of the fitting function with the instrument response while performing the fitting. This tutorial will demonstrate how to perform convolution while fitting.



If your data is a convolution of Gauss and Exponential functions, you can simply use built-in fitting function [GaussMod](#) in **Peak Functions** category to directly fit your data.

Minimum Origin Version Required: Origin 2016 SR0.

What you will learn

This tutorial will show you how to:

- Access fitting information during iterations.
- Perform convolution while fitting.


Example and Steps

Background

Let's start this example by importing `\Samples\Curve Fitting\FitConv.dat`.

A(X)	B(Y)	C(Y)
Sampling	Signal	Impulse
0	-0.19775	0
0.1	-0.32893	0
0.2	0.10055	0
0.3	0.09394	0
0.4	-0.1292	0
0.5	0.06346	1.48672E-6
0.6	0.19453	1.3383E-4

The source data includes sampling points, output signal, and the impulse response. This experiment assumes that the output signal was the convolution of an exponential decay function with a Gaussian response:



Now that we already have the output signal and response data, we can get the exponential decay function by fitting the signal with the below model:

$$y = y_0 + \int_{-\infty}^{+\infty} Ae^{-tx} \otimes Response, dx$$

Define the Function

Obviously, column 1 and column 2 are x and y respectively in the function. How about column 3, the impulse response? We will access this column within the fitting function, and compute the theoretical exponential curve from the sampling points. Then we can use fast Fourier transform to perform the convolution.

Press **F9** to open the **Fitting Function Organizer** and define a function like:

Function Name: FitConv
Function Type: User-Defined
Independent Variables: x
Dependent Variables: y
Parameter Names: y0, A, t
Function Form: [Origin C](#)
Function:

Click the button (icon) beside the **Function** box and write the function body in **Code Builder**:

```
#pragma warning(error : 15618)

#include <origin.h>

// Header files need to be included

#include <ONLSF.H>

#include <fft_utils.h>

//
```

```

//

void _nlsfTestConv(

// Fit Parameter(s):

double y0, double A, double t,

// Independent Variable(s):

double x,

// Dependent Variable(s):

double& y)

{

    // Beginning of editable part

    NLFitContext *pCtxt = Project.GetNLFitContext();

    Worksheet wks;

    DataRange dr;

    int c1,c2;

    dr = pCtxt->GetSourceDataRange(); //Get the source data range

    dr.GetRange(wks, c1, c2); //Get the source data worksheet

    if ( pCtxt )

    {

        // Vector for the output signal in each iteration.

        static vector vSignal;

        // If parameters were updated, we will recalculate the convolution
result.

```

```
    BOOL bIsNewParamValues = pCtxt->IsNewParamValues();

    if ( bIsNewParamValues )
    {

        // Read sampling and response data from worksheet.

        Dataset dsSampling(wks, 0);

        Dataset dsResponse(wks, 2);

        int iSize = dsSampling.GetSize();

        vector vResponse, vSample;

        vResponse = dsResponse;

        vSample = dsSampling;

        vSignal.SetSize(iSize);

        vResponse.SetSize(iSize);

        vSample.SetSize(iSize);

        // Compute the exponential decay curve

        vSignal = A * exp( -t*vSample );

        // Perform convolution

        int iRet = fft_fft_convolution(iSize, vSignal, vResponse);
```

```

        //Correct the convolution by multiplying the sampling
interval
        vSignal = (vSample[1]-vSample[0])*vSignal;

    }

    NLSFCURRINFO    stCurrInfo;

    pCtxt->GetFitCurrInfo(&stCurrInfo);

    // Get the data index for the iteration

    int nCurrentIndex = stCurrInfo.nCurrDataIndex;

    // Get the evaluated y value

    y = vSignal[nCurrentIndex] + y0;

    // For compile the function, since we haven't use x here.

    x;

}

// End of editable part
}

```

Traditionally, for a particular x , the function will return the corresponding y value. However, when convolution is involved, we need to perform the operation on the entire curve, not only for a particular data point. So, from Origin 8 SR2, we introduced the [NLFitContext class](#) to achieve some key information within the fitter. In each iteration, we use [NLFitContext](#) to monitor the fitted parameters; once they are updated, we will compute the convolution using the fast Fourier transform by the [fft_fft_convolution](#) method. The results are saved in the `vSignal` vector. Then for each x , we can get the evaluated y from `vSignal` with the current data index in `NLSFCURRINFO`.

Fit the Curve

In the fitting function body, we read the response data directly from the active worksheet. So, you should perform the fit from the worksheet.

1. Highlight column B and press **Ctrl + Y** to bring up the **Nonlinear Fitting** dialog.
2. Choose *X Data Type* from *Fitted Curves* page as **Same as Input Data**.
3. Go back to the Function Selection page to select the *FitConv* function you just defined.
4. Go to the Parameter tab to initialize the parameters as $y_0=0$, $A=10$, $t=1$.
5. Click the **Fit** button to generate the results.

If you use a fitting function similar to this tutorial, please note when you run **NLFit** in Origin, in **NLFit** dialog, choose **X Data Type** from **Fitted Curves** page as **Same as Input Data**.

4.2.2.18 Quoting Built-in Functions in Your New Function

Summary

This tutorial will show you how to reference a built-in function when creating a user-defined fitting function.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn

This tutorial will show you how to:


- Define a piecewise fitting function
- Access built-in functions in you new function
- Auto initialize the parameters

Steps

Data

Start by importing the file `\Samples\Curve Fitting\Asymmetric Gaussian.dat` into a new workbook.

Highlight column B and create a graph. The peak in the data is slightly skewed to the right. How to fit such a curve? One idea is to divide the curve into two parts - We can consider this curve to be composed of two Gaussian function as below. These two Gaussian curves share the same baseline and peak center, but differ in peak width and amplitude.



Define the Function

Press **F9** to open the **Fitting Function Organizer** and define the function as below:

Function Name:	AsymmetricGauss
Function Type:	User-Defined
Independent Variables:	x
Dependent Variables:	y
Parameter Names:	y0, xc, w1, w2, A1, A2
Function Form:	Origin C
Function:	$y = x < xc ? \text{nlf_Gauss}(x, y0, xc, w1, A1) : \text{nlf_Gauss}(x, y0, xc, w2, A2);$

Note:

For versions before **Origin 8.1**, the function body should be defined as:

```
y = x < xc ? nlfxGauss(x, y0, xc, w1, A1) : nlfxGauss(x, y0, xc, w2, A2);
x; y0; xc; w1; w2; A1; A2;
```

Listing the parameters at the end is used to avoid the "parameter not used inside the function body" error, although you already use these parameters. This is required to compile the function successfully.

When calling **nlf_FuncName** to reuse built-in functions, the syntax is:

```
nlf_FuncName( independent variable, parameter list ... )
```

where **FuncName** is the fitting function name. Besides, the old notation, **nlfxFuncName** also supported.

The *Parameter List* follows the parameter order in function definition file for the built-in function (the FDF file. You can open the FDF file in Notepad. The files are located in the \\Origin EXE Folder\FitFunc\). Note that, the function name we use is the DLL interface name. The actual name in the [General Information] section of the FDF file. Look at the *Function Source* item and the value is **fgroup.FuncName**, and use the *FuncName*. In most cases, this function name is consistent with the function name visible in the NLFit dialog. For a few few functions such as Voigt, these names are different.

For parameter initialization of this skewed gaussian function, we can simply copy the initialization code of the built-in gauss function, and make a few minor modifications:

```
xc = peak_pos(x_y_curve, &w1, &y0, &A1);  
  
w2 = w1;  
A2 = A1;
```

The final function body should be as below:

Function Name AsymmetricGauss

File Name(.FDF) C:\Documents and Settings\Administrato

Brief Description

References

Function Type User-Defined

Function Model Explicit

Independent Variables x

Dependent Variables y

Parameter Names y0,xc,w1,w2,A1,A2

Function Form Origin C

Treat All Numbers As Double

Derivatives

Function

```
y = xc < xc ? nlf_Gauss(x, y0, xc, w1, A1) : nlf_Gauss(x, y0, xc, w2, A2)
```

Peak Function

Parameter Settings

```
InitialValues = --(V)--(V)--(V)--(V)--(V)--(V)
Meanings = ?,?,?,?,?
LowerBounds = --(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)
UpperBounds = --(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)
NamingMethod = User-Defined
NumberOfSignificantDigits = 0,0,0,0,0,0
Unit = .....
Format = .....
CustomDisplay = .....

```

Enable Auto Initialization

Use OriginC

Parameter Initialization

```
xc = peak_pos(x_y_curve, &w1, &y0, &A1);
w2 = w1; A2 = A1;
```

Once compiled successfully, save the function and fit the curve. The results should be as below:

		Value	Standard Error
Amplitude 1	y0	1.80002	4.79492E-5
	xc	4.50001	3.44845E-5
	w1	1.80003	4.49861E-5
	w2	2.99998	4.87666E-5
	A1	30	0.00103
	A2	49.99962	0.00111

4.2.2.19 Fit Function with Non-constant Background

Summary

Many of the Origin built-in functions are defined as:

$$y = y_0 + \dots$$

Where y_0 can be treated as the "constant background". How about fitting a curve with a non-constant background? One option is to use the Peak Analyzer we provide. The Peak Analyzer includes multiple methods to subtract the baseline, including exponential or polynomial backgrounds. In this tutorial, we will show you how to fit such curves without using the Peak Analyzer.

Minimum Origin Version Required: Origin 8.0 SR6


What you will learn

- Review [Worksheet Query](#).
- Quote a built-in function by [nlfxFuncName](#) method.
- Auto Initialize the parameters.


Example and Steps

Prepare the Data


Let's start this tutorial by importing `\Samples\Spectroscopy\Peaks on Exponential Baseline.dat`. From the worksheet sparkline, we can see that there are two peaks in the curve. To simplify the problem, we will fit just one peak in this example.



Now bring up the [Worksheet Query dialog](#) from **Worksheet : Worksheet Query**. And we will extract data from row 1 to row 240:




So the curve we will fit should look like this:



Define the Function

As illustrated below, we can consider the source curve is the combination of an exponential decay component (the background) with a Voigt peak:



So should we write down the whole equation to define the function? Like:

$$y = y_0 + A_1 e^{-x/t_1} + A_2 \frac{2w_L \ln 2}{\pi^{3/2} w_G^2} \int_{-\infty}^{\infty} \frac{e^{-t^2}}{\left(\sqrt{\ln 2} \frac{w_L}{w_G}\right)^2 + \left(\sqrt{4 \ln 2} \frac{x-x_c}{w_G} - t\right)^2} dt$$

Well, this is a complicated equation and it includes infinite integration. Writing such an equation directly is painful. Now that we already have these two built-in functions:

ExpDec1:

$$y = y_0 + A e^{-x/t}$$

Voigt:

$$y = y_0 + A \frac{2w_L \ln 2}{\pi^{3/2} w_G^2} \int_{-\infty}^{\infty} \frac{e^{-t^2}}{\left(\sqrt{\ln 2} \frac{w_L}{w_G}\right)^2 + \left(\sqrt{4 \ln 2} \frac{x-x_c}{w_G} - t\right)^2} dt$$

we can simply use the **nfxFuncName** method to quote these two built-in functions and create a new one. Press **F9** to open the **Fitting Function Organizer** and define a function as below:

Function Name:	ExpVoigt
Function Type:	User-Defined
Independent Variables:	x
Dependent Variables:	y
Parameter Names:	y0, A1, t1, xc, A2, wG, wL

Function Form:	Origin C
Function:	$y = \text{nlf_ExpDec1}(x, y0, A1, t1) + \text{nlf_Voigt}(x, y0, xc, A2, wG, wL) - y0;$

Note:

Some of the built-in function names do not consistent with the actual DLL function name. Just like this Voigt function, it's defined in Voigt5.FDF, and if you open the FDF file by Notepad, you can see a line under [GENERAL INFORMATION] section says:

Function Source=fgroup.Voigt5

The name after "fgroup" is the actual name we should put into **nlf_*FuncName***.

Besides, for versions before **Origin 8.1 SR2**, the function body should use old *nlfxFuncName* notation and define as:

```
y = nlfxExpDec1(x, y0, A1, t1) + nlfxVoigt(x, y0, xc, A2, wG, wL)
- y0;

x; xc; A1; t1; A2; wG; wL;
```

Listing the parameters at the end is done to avoid the "parameter not used inside the function body" error, although you already use these parameters. If not, you will not compile the function successfully.

Click the  button on the right of the **Parameter Settings** and enter these parameter initial values:

y0:	0
A1:	5
t1:	50
xc:	100
A2:	50
wG:	10

wL:	10
------------	----

So the final function definition part should look like:

Function Type User-Defined

Function Model Explicit

Independent Variables x

Dependent Variables y

Parameter Names y0,A1,t1,xc,A2,wG,wL

Function Form Origin C

Treat All Numbers As Double

Derivatives

Function

```
- nlf_ExpDec1(x, y0, A1, t1) + nlf_Voigt(x, y0, xc, A2, wG, wL) - y0;
```

Peak Function

Parameter Settings


```
InitialValues = 0[V],5[V],50[V],100[V],50[V],10[V],10[V]
Meanings = ?,?,?,?,?,?
LowerBounds = --(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)
UpperBounds = --(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)--(l, Off)
NamingMethod = User-Defined
NumberOfSignificantDigits = 0,0,0,0,0,0,0
Unit = -----
Format = -----
CustomDisplay = -----
```

Auto Parameter Initialization

In the above section, we set fixed parameter initial values. If you know the possible fitted results, you can set the initial values in this way. But how about when the data is changed? Origin provides an Origin C interface to "guess" the initial values. To use the parameter initialization code, make sure to check the **Enable Auto Initialization** and **Use OriginC** checkboxes, and edit the code in Code

Builder by clicking the  icon.

(P.S: If you know the initial values very well, or you don't like coding, please skip this section.)



Now that the curve is composed by two components, we can guess the parameter values by separating these two parts, the initialization code includes:

1. Use the [get_exponent](#) function to fit the curve and get the parameter values for exponential component.
2. Remove the background -- exponential component -- from source data.
3. Approaching the peak by Gaussian peak using [peak_pos](#) function and set the initial values for peak component

So, the initialization code in Code Builder should look like this:

```
void _nlsfParamExpVoigt(
// Fit Parameter(s):
double& y0, double& A1, double& t1, double& xc, double& A2, double& wG, double& wL,
// Independent Dataset(s):
vector& x_data,
// Dependent Dataset(s):
vector& y_data,
// Curve(s):
Curve x_y_curve,
// Auxiliary error code:
```

Tutorials for Origin

```
int& nErr)

{

    // Beginning of editable part

    int nSign;

    // Evaluates the parameters' value, y0, ln(A) and R for y = y0+A*exp(R*x).

    t1 = get_exponent(x_data, y_data, &y0, &A1, &nSign);

    // Set the exponential component values for the fitting function.

    t1 = -1/t1;

    A1 = nSign*exp(A1);

    // Remove the exponential component from the curve;

    x_y_curve = x_y_curve - (y0 + A1 * exp(-x_data/t1));

    // Fit to get peak values.

    xc = peak_pos(x_y_curve, &wG, &y0, &A2);

    wL = wG;

    // End of editable part

}
```

Note:

When you check the **Enable Auto Initialization** and enter the initialization code, this code will cover the initial values in **Parameter Settings**.

Fit the Curve

No matter what kind of parameter initialization method you used, highlight column B and press **Ctrl + Y** to bring up the NLFit dialog, select the ExpVoigt function and fit. The result should be:

		Value	Standard Error
Amplitude	y0	0.04862	0.00724
	A1	5.08842	0.02599
	t1	50.67096	0.51939
	xc	102.81043	0.07241
	A2	32.91106	0.92012
	wG	9.65255	0.67731
	wL	5.7529	0.81022

4.2.2.20 Fitting with Piecewise Functions

Summary

We will show you how to define piecewise fitting function in this tutorial.
Minimum Origin Version Required: Origin 8.0 SR6


What you will learn

This tutorial will show you how to:

- Define piecewise (conditional) fitting functions.

Example and Steps

We can start this tutorial by importing the sample `\Samples\Curve Fitting\Exponential Decay.dat` data file. Highlight column D and plot a Scatter Graph. You can fit this curve using built-in functions under Growth/Sigmoidal category, however, in this tutorial, we will separate the curve into two parts by a piecewise function.




So the equation will be:

$$y = \begin{cases} a + bx + e^{-\frac{x-x_c}{t1}}, & \text{if } x < x_c \\ a + bx, & \text{if } x \geq x_c \end{cases}$$

Define the Function

Press **F9** to open the **Fitting Function Organizer** and define a function like:

Function Name:	piecewise
Function Type:	User-Defined
Independent Variables:	x
Dependent Variables:	y
Parameter Names:	xc, a, b, t1
Function Form:	Origin C
Function:	

Click the  button on the right of the **Function** edit box and define the fitting function in Code Builder using:

```
void _nlsfpiecewise(
// Fit Parameter(s):
double xc, double a, double b, double t1,
// Independent Variable(s):
double x,
// Dependent Variable(s):
double& y)
{
// Beginning of editable part
// Divide the curve by if condition.
if(x<xc) {
```

```

        y = a+b*x+exp(-(x-xc)/t1);
    } else {

        y = a+b*x;

    }

    // End of editable part
}

```

Fit the Curve

Press **Ctrl + Y** to bring up NLFit dialog with the graph window active. Select the *piecewise* function we defined and initialize the parameter values:

xc:	1
a:	1
b:	-1
t1:	0.1

Click **Fit** button to generate the results:

xc:	0.24
a:	36.76585
b:	-24.62876
t1:	0.04961

Note that this function is sensitive to *xc* and *t1*, different initial values could generate different results.

4.2.2.21 Fit Curve Through Certain Points

Summary

This tutorial shows you three methods to force a fit curve to go thru a particular point. Choice of method depends on function expression and the data point you want the fit curve to go through.

What you will learn


Tutorials for Origin


- Learn different methods to force a curve to go through a point.
- Fix fitting parameters during nonlinear fitting.
- Use general linear constraints in nonlinear fitting.
- Fit with weights.

Example and Steps


Fixing Function Parameters

This method works only when the point you want to fit through is related to a function parameter. One typical example: force the fitted line to go through the origin point, (0, 0), when fitting a straight line, $y = a + b * x$. In this particular case we know that if we let $a = 0$, the line will go through (0,0).

1. Import the data "*\Samples\Curve Fitting\Linear Fit.dat*" into an Origin worksheet.
2. Highlight one of the Y column, column D for example, and select **Analysis: Fitting: Nonlinear Curve Fit** to bring up the **NLFit** dialog.
3. Choose the **Line** function after selecting the **Polynomial** category.
4. Click the **Fitted Curves** page on **Settings** tab. Under the **X Data Type** branch, make sure the **Range** option is **Use Input Data Range + Margin**, and then enter **10** in the **Range Margin(%)** edit box. This option will lengthen the fitted curve.
5. Click the **Fit until converged** button . You can see from the **Fit Curve** tab that the curve does not go through the origin point.



- Now go to the **Parameters** tab, check the **Fixed** checkbox for parameter **A** and fix the value to **0**. Click the **Fit until converged** to fit the curve again. Now you can see the curve go through zero.



Note: You can also use the **Fix Intercept** option in the **Linear Fit** dialog to force the linear fitted line to go through the origin point.

Use Linear Constraint


This method works when the fitting function is based on a LINEAR model, such as **Line**, **Parabola**, or **Cubic**, etc.


We will show you how to force the fitted curve to go through a particular point by using linear constraint:

1. Import the data "*\Samples\Curve Fitting\Polynomial Fit.dat*" into Origin worksheet.
2. Highlight column B and press **Ctrl + Y** to bring up the **NLFit** dialog.
3. Select **Parabola** ($y = A + B * x + C * x^2$) from the **Polynomial** category. From the **Fit Curve** tab, we can see the initial value already fits the data very well.
4. Suppose we want to force the curve through (10, 100). Substitute (10, 100) to the fitting function ($y = A + B * x + C * x^2$). we then have $100 = A + 10 * B + 100 * C$. We can use this equation as a general linear constraint condition. Select the **Constraints** page on **Code** tab.

Check the **Enable Linear Constraints** checkbox, and enter the following expression into the edit box.

$$A + 10*B + 100*C = 100$$

- Click the **Fit until converged** button . We can see the fitted curve deviates from the data points, but it goes through the specified point.



Use weighting

If the parameters are some eigenvalues such as upper or lower asymptotes, and your raw data includes the points you want to fit through, you can fit the curve by assigning larger weights to these particular points. This is not an analytical solution, but you can assign larger weights to reduce the error:

- Prepare data by running the following script:

```

newbook;

string fname$ = system.path.program$;

fname$ += "Samples\Curve Fitting\Replicate Response Data.dat";

impasc fname$ options.PartImp.Partial:=1 options.PartImp.LastCol:=2;

wks.addcol();


col(a) = log(col(a)) + 5;


col(c)[1] = 100;

for(int ii = 2; ii < wks.maxrows; ii++)
{
    col(c)[ii] = 1;
}

col(c)[wks.maxrows] = 100;

```


2. First, let's see how the fitted curve looks when there is no weighting. Highlight column B and bring up NLFit dialog from **Analysis: Fitting: Nonlinear Curve Fit**. Select the **Logistic** function from **Growth/Sigmoidal** category. Then click the **Fit until converged** button . From the **Fit Curve** tab, we can see the curve does not go through any points near the top.




- Note that in the raw data worksheet, we have prepared column C and assigned large values for the first and last data points. If we use this column as weights, these two points will contribute more impact on the fitted curve and hence force the curve to go through these two points.

The screenshot shows the 'ReplicateResp - Replicate Response' worksheet. The table has columns A(X), B(Y), and C(Y). The first and last rows are highlighted with pink circles, indicating the large weight values in column C.

	A(X)	B(Y)	C(Y)
Long Name			
1	3.30103	0.13136	100
2	3.77815	0.34384	1
3	4.07918	0.6554	1
4	4.17609	0.73699	1
5	4.30103	1.00157	1
6	4.69897	1.39062	1
7	5	1.70785	1
8	5.30103	2.31437	1
9	5.69897	2.77326	1
10	6	2.79321	100

Now, activate the **Data Selection** page on the **Settings** tab. Expand the **Input Data** branch as below to expose the weighting option. Choose the **Direct Weighting** method and assign column **C** as the weighting dataset. Then click the **Fit until converged** button .



From the preview result, we can see that the fitted curve goes through the first and last data points.

4.2.2.22 Distribution Fit with the Probability Density Function and Cumulative Distribution Function

Summary

To know the location or scale parameters of a sample distribution, one can [perform distribution fit](#) on the data. However, you can also fit a probability density function or cumulative distribution function on the binned data to get these values. This tutorial shows you how to estimate these parameters by curve fitting.

Minimum Origin Version Required: Origin 2016 SR2

What you will learn

- Generating Normally Distributed Data for Fitting
- Fitting with Probability Density Function (PDF)
- Fitting with Cumulative Distribution Function (CDF)

Example and Steps

Generating Normally Distributed Data for Fitting


1. Run the following script to create sample dataset

```
newbook;

col(2) = normal(1000) * 2 + 5;
```

2. This script generates 1000 normally distributed points where $mean \approx 5$ and $\sigma \approx 2$.
3. We can first perform simple descriptive statistics on this column to see the corresponding *Moments* output.

Highlight the data column and select **Statistics: Descriptive Statistics: Statistics on Column** to open the dialog. Select **Quantities** tab, then make sure the **Mean** and **Standard Deviation** checkboxes are selected. And the click **OK** to generate report.



Descriptive Statistics			
	N total	Mean	Standard Deviation
B	1000	5.03869	2.06311

From the report worksheet, we can see the Mean and Standard Deviation are very close to the value we just set.

Fitting with Probability Density Function (PDF)

1. To fit the data with the PDF, we should calculate the binned data with **Frequency Counts** tool first. Highlight the source data column and select **Statistics: Description Statistics: Frequency Counts** from menu. This dialog will count the number of data points on specified bins.
 - Expand the **Computation Control** branch, and make sure **Bin Size** radio button is checked in **Step by** group. And then set the **Bin Size** to 0.5 .
 - Make sure the **Bin Center**, **Count** and **Cumulative Count** check boxes under **Quantities to Compute** branch are selected. Then click **OK** to count the data.

- Highlight the *Counts* column on the Frequency Counts result worksheet, select **Plot: Column/Bar/Pie: Column** to create a column graph. Now we got the histogram of the source data.
- With the graph active, select menu **Analysis: Fitting: Nonlinear Curve** menu to open the **NLFit** dialog. Then select the **Gauss** function from the **Statistics** category. Leave other options as defaults and click the **Fit** button directly to output fitting report.

Parameters						
	Value	Standard Error	t-Value	Prob> t	Dependency	
y0	-0.68078	1.57098	-0.43335	0.66834	0.74273	
xc	5.03664	0.05018	100.3801	0	5.06394E-5	
w	4.26937	0.13954	30.59591	0	0.65495	
Count	A	510.8423	20.5045	24.91367	0	0.82858
sigma	2.13468	0.06977				
FWHM	5.0268	0.1643				
Height	95.46922	2.25117				

From the fitting report, we can see that the fitted *xc* and *sigma* are close to 5 and 2.

Fitting with Cumulative Distribution Function (CDF)

- To fit the data with the CDF, we should start from the cumulative binned data. Select the **FreqCounts1** sheet from the previous section. highlight column D, *Cumulative Count*, this time. select menu **Plot: Symbol: Scatter** to plot the CDF points
- With the graph active, select menu **Analysis: Fitting: Nonlinear Curve** menu to open the **NLFit** dialog. Then select the **NormalCDF** function from the **Statistics** category. Leave other options as defaults and click the **Fit** button directly to output fitting report.

Parameters						
	Value	Standard Error	t-Value	Prob> t	Dependency	
y0	-1.03748	1.21312	-0.85522	0.40024	0.73485	
Cumulative Count	A	1002.98626	2.10846	475.69502	0	0.76168
xc	4.79432	0.00938	511.10057	0	0.50906	
w	2.09438	0.01277	163.98837	0	0.47041	

From the fitting report, we can see that the fitted *xc* and *w* are close to 5 and 2.



After you got binned data from the **Frequency Counts** tool, you can also fit the binned data with your user-defined probability density function or cumulative distribution function. [View this page for defining and fitting with a user-defined function.](#)

4.2.2.23 Fitting Integral Function with a Sharp Peak

Summary

In this tutorial, we will show you how to define an integral fitting function with a sharp peak in the integral function, and perform a fit of the data using this fitting function.

Because the integral function contains a sharp peak, the integral should be performed in three segments so that the sharp peak can be integrated in a narrow interval.

Minimum Origin Version Required: Origin 9.0 SR0

What you will learn


This tutorial will show you how to:

- Define an integral fitting function.
- Integrate a function with a sharp peak.
- Divide the integral interval into several segments.

Example and Steps

Import Data

1. Open a new workbook.
2. Copy data in [Sample Data](#) to the workbook.
3. Highlight column B, and select **Plot: Symbol: Scatter** from Origin menu. The graph should look like:



Define Fitting Function

The fitting integral function is described as follows:

$$y = \log\left(\int_0^1 \frac{1}{\sqrt{2\pi b}} e^{-\frac{(t-a)^2}{2b^2} - xt} dt\right)$$

where a and b are parameters in the fitting function.

Initial parameters are: a=1e-4, b=1e-4. Note that the integral function contains a peak whose center is about a and width is 2b. And the peak's width (2e-4) is very narrow compared with the integral interval [0,1]. To make sure it is integrated correctly at the neighborhood of the peak center, the integral interval [0,1] is divided into three segments: [0,a-5*b], [a-5*b,a+5*b], [a+5*b,1]. It is integrated in each segment, and then the three integrals are summed up.

The fitting function can be defined using the **Fitting Function Builder** tool.

1. Select **Tools: Fitting Function Builder** from Origin menu.
2. In the **Fitting Function Builder** dialog's **Goal** page, click **Next** button.
3. In the **Name and Type** page, select **User Defined** from **Select or create a Category** drop-down list, type **fitpeak** in the **Function Name** field, and select **Expression** in **Function Type** group, check **Include Integration During Fitting** check box. And click **Next** button.
4. In the **Integrand** page, type **myint** in **Integrand Name** edit box, **t** in **Integration Variable** edit box and **a, b, x** in **Arguments** edit box. Type the following script in **Integrand Function** box.

```
return 1/(sqrt(2*pi)*b)*exp(-(t-a)^2/(2*b^2)-x*t);
```

5. And click **Next** button.
6. In the **Variables and Parameters** page, type **a, b** in the **Parameters** field. Click **Next** button.
7. In the **Expression Function** page, click **Parameters** tab, and set **Initial Value** for parameters a and b to 1e-4, click **Integrand** tab, and set **Value** for **Lower Limit** and **Upper Limit** to 0 and 1, **Value** for **a, b, x** to a, b, x respectively.
8. In the **Expression Function** page, click **Insert** button. In the **Quick Check** group, type 0 in **x=** edit box, click **Evaluate** button, and it shows y=9.3e-21. This implies that the peak is not integrated correctly because y should approach 1 for x=0. Divide the integral into three segments, and type following script in **Function Body** box.

```
integral(myint, 0, a-5*b, a, b, x)+integral(myint, a-5*b, a+5*b, a, b, x)+
integral(myint, a+5*b, 1, a, b, x)
```

9. Click **Evaluate** button again, and it shows y=0.84, hence it is clear that the peak is integrated correctly this time.
10. In the **Expression Function** page, update the script in **Function Body** box as follows.


```
log(integral(myint, 0, a-5*b, a ,b ,x)+integral(myint, a-5*b, a+5*b, a ,b
,x)
+integral(myint, a+5*b, 1, a ,b ,x))
```


11. Click **Finish** button.

Fit the Curve

1. Select **Analysis: Fitting: Nonlinear Curve Fit** from Origin menu. In the **NLFit** dialog, select **Settings: Function Selection**, in the page select **User Defined** from the **Category** drop-down list and **fintheak** function from the **Function** drop-down list. **Note** that initial parameters have been set during defining the fitting function.
2. Click **Fit** button to fit the curve.

Fitting Results

The fitted curve should look like:



Fitted Parameters are shown as follows:

Parameter	Value	Standard Error
a	4.98302E-4	1.07593E-5

Tutorials for Origin

b	1.94275E-4	8.21815E-6
----------	------------	------------

The **Adj. R-Square** is 0.99799. Thus the fitting result is very good.

Sample Data

x	y
0	-0.00267
60	-0.01561
240	-0.05268
500	-0.10462
1000	-0.22092
1500	-0.31004
2000	-0.40695
3000	-0.61328
4000	-0.75884
5000	-0.9127
6000	-0.98605
7000	-1.18957
9000	-1.43831
10000	-1.41393
12000	-1.61458

15000	-1.88098
20000	-2.07792

4.2.2.24 Fitting with a Piecewise Linear Function

Summary

In this tutorial we will show you how to define a piecewise fitting function consisting of two linear segments, perform a fit of the data using this fitting function, and calculate the intersection location for two linear segments from the fitting result.

Minimum Origin Version Required: Origin 8.6 SR0


What you will learn


This tutorial will show you how to:

- Define a piecewise (conditional) fitting function.
- Auto initialize parameters.
- Calculate the intersection location of the piecewise fit lines.

Example and Steps

Import Data

1. Open a new workbook.
2. Click the **Import Single ASCII** button  to bring up the Open dialog. Browse to **\Samples\Curve Fitting** folder and select the file **Step01.dat**.
3. Right click on the **Sensor E x** column (column J), and select **Set As: X** from the context menu. Highlight **Sensor E y** column, and select **Plot: Symbol: Scatter** from Origin menu. The graph should look like:




Define Fitting Function

From the above graph, the curve consists of two segments of lines. It can be fitted with a piecewise linear function. The function can be expressed as:

$$y = \begin{cases} \frac{y_1(x_3 - x) + y_3(x - x_1)}{x_3 - x_1}, & \text{if } x < x_3 \\ \frac{y_3(x_2 - x) + y_2(x - x_3)}{x_2 - x_3}, & \text{if } x \geq x_3 \end{cases}$$

where x_1 and x_2 are x values of the curve's endpoints and they are fixed during fitting, x_3 is the x value at the intersection of two segments, and y_1, y_2, y_3 are y values at $x_i, i = 1, 2, 3$ respectively.

The fitting function can be defined using the **Fitting Function Builder** tool.

1. Select **Tools: Fitting Function Builder** from Origin menu.
2. In the **Fitting Function Builder** dialog's **Goal** page, click **Next** button.
3. In the **Name and Type** page, select **User Defined** from **Select or create a Category** drop-down list, type **pwl2s** in the **Function Name** field, and select **Origin C** in **Function Type** group. And click **Next** button.
4. In the **Variables and Parameters** page, type **x1,y1,x2,y2,x3,y3** in the **Parameters** field. Click **Next** button.
5. In the **Origin C Fitting Function** page, click the  button on the right of the **Function Body** edit box and define the fitting function in **Code Builder** as follows.

```


if( x < x3 )

    y = (y1*(x3-x)+y3*(x-x1))/(x3-x1);

else

    y = (y3*(x2-x)+y2*(x-x3))/(x2-x3);

```

6. Click **Compile** button to compile the function body. Then click **Return to Dialog** button. Click **Next** button.
7. In the **Parameter Initialization Code** page, click the  button on the right of the **Initialization Code** edit box and initialize the fitting parameters in **Code Builder** as follows.

```

int n1, n2, n3;

x_data.GetMinMax( x1, x2, &n1, &n2 );

x3 = x1 + (x2 - x1)/2;

y1 = y_data[n1];

y2 = y_data[n2];

vector vd;

vd = abs( x_data - x3 );

double xta, xtb;

vd.GetMinMax( xta, xtb, &n3 );

y3 = y_data[n3];

```

8. Click **Compile** button to compile it. Then click **Return to Dialog** button. Click **Finish** button.

Define Derived Parameters for Slopes and Intercepts

During function defined process, you can also define some additional derived Parameters such as slopes and intercepts , which are computed from the function parameter values after the fitting process ends.


1. Click **<<Back** button twice to go back to **Variables and Parameters** page, type **a1,b1,a2,b2** in the **Derived Parameters** field.
2. Click **Next** button four times to go to **Derived Parameters** page, fill in the **Meaning** column and type the equations in the **Derived Parameters Equations** area as follows, then click **Finish** button.

$$a1=(y1*x3-y3*x1)/(x3-x1);$$

$$b1=(-y1+y3)/(x3-x1);$$

$$a2=(y3*x2-y2*x3)/(x2-x3);$$

$$b2=(-y3+y2)/(x2-x3);$$



Fit the Curve

1. Select **Analysis: Fitting: Nonlinear Curve Fit** from Origin menu. In the **NLFit** dialog, select **Settings: Function Selection**, in the page select **User Defined** from the **Category** drop-down list and **pw12s** function from the **Function** drop-down list.


2. In the **NLfit** dialog, select **Parameters** tab, and fix parameters **x1**, **x2** as shown in the dialog.

NO.	Param	Meaning	Fixed	Value	Error	Dependency
1	x1	?	<input checked="" type="checkbox"/>	0.8	--	--
1	y1	?	<input type="checkbox"/>	0	--	--
1	x2	?	<input checked="" type="checkbox"/>	60	--	--
1	y2	?	<input type="checkbox"/>	0.90662	--	--
1	x3	?	<input type="checkbox"/>	30.4	--	--
1	y3	?	<input type="checkbox"/>	0.73608	--	--

3. Click **Fit** button to fit the curve.

Fitting Results

The fitted curve should look like:



Fitted Parameters are shown as follows.

Parameter	Value	Standard Error
-----------	-------	----------------

x1	0.8	0
y1	-0.0271	0.01063
x2	60	0
y2	0.95585	0.0083
x3	22.26316	0.58445
y3	0.66106	0.01197
a1	-0.05275	0.01123
b1	0.03206	8.7153E-4
a2	0.48715	0.01664
b2	0.00781	3.86455E-4

Thus the intersection point for the two segments is (22.26316, 0.66106).

Note that fitting with a piecewise linear function for more than two segments can be done in a similar way.

4.2.2.25 Fitting with an Ordinary Differential Equation

Summary

In this tutorial we will show you how to define an ordinary differential equation (**ODE**) in the **Fitting function Builder** dialog and perform a fit of the data using this fitting function.

Minimum Origin Version Required: Origin 9.1 SR0

What you will learn

This tutorial will show you how to:

- Define an ODE fitting function.
- Call NAG functions using Origin C code.
- Recalculate the ODE result only when parameters are updated.
- Interpolate on the ODE result.

Example and Steps


In this tutorial, we will use a first order ordinary differential equation as an example:


$$\frac{dy}{dx} = ay$$

$$y|_{x=x_0} = y_0$$

where **a** is a parameter in the ordinary differential equation and **y0** is the initial value for the ODE. NAG functions **d02pvc** and **d02pcc** are called using the Runge–Kutta method to solve the **ODE** problem.


Import Data

1. Open a new workbook.
2. Click the **Import Single ASCII** button  to bring up the Open dialog. Browse to the **\Samples\Curve Fitting** folder and select the file **Exponential Growth.dat**.
3. Highlight **B** column, and select **Plot: Symbol: Scatter** from Origin menu. The graph should look like:



Define Fitting Function

The fitting function can be defined using the **Fitting Function Builder** tool.

1. Select **Tools: Fitting Function Builder** from Origin menu.
2. On the **Fitting Function Builder** dialog's **Goal** page, ensure the **Create New Function** radio button is selected. Click the **Next** button.
3. On the **Name and Type** page, From the **Select or create a Category** drop-down list select **User Defined**. For **Function Name** type **FitODE**. In the **Function Type** section select the **Origin C** radio button. Click **Next**.
4. On the **Variables and Parameters** page, in the **Parameters** field type **a, y0**. Click **Next**.
5. On the **Origin C Fitting Function** page, click the  button on the right of the **Function Body** edit box and define the function in **Code Builder** as follows. Include header files for NAG and fitting:

```
#include <oc_nag.h>

#include <ONLSF.H>
```

6. Define a static function to solve ODE by calling NAG functions. Call NAG function **d02pvc** to establish ODE model and **d02pcc** to solve the model:

```
struct user // parameter in the ODE

{

    double a;

};

//Define the differentiate equation: y'=a*y

static void NAG_CALL f(Integer neq, double t, double y[], double yp[],
Nag_User *comm)

{

    neq; //Number of ordinary differential equations
```

```
t; //Independent variable

y; //Dependent variables

yp; //First derivative

struct user *sp = (struct user *) (comm->p);

double a;

a = sp->a;

yp[0] = a*y[0];
}

//Use Runge-Kutta ODE23 to solve ODE

static bool nag_ode_fit( const double a, const double y0, const double
tstart,

const double tend, const int nout, vector &vP )

{

//nout: Number of points to output

if( nout < 2 )

return false;
```

```
vP.SetSize( nout );

vP[0] = y0;

int neq = 1; //Number of ordinary differential equations

Nag_RK_method method;

double hstart, tgot, tinc;

double tol, twant;

int i, j;

vector thres(neq), ygot(neq), ymax(neq), ypgot(neq), ystart(neq);

Nag_ErrorAssess errass;

Nag_ODE_RK opt;

Nag_User comm;

struct user s;

s.a = a;

comm.p = (Pointer)&s;
```

```
ystart[0] = y0;

for (i=0; i<neq; i++)

    thres[i] = 1.0e-8;

errass = Nag_ErrorAssess_off;

hstart = 0;

method = Nag_RK_2_3;

tinc = (tend-tstart)/(nout-1);

tol = 1.0e-3;

NagError nagErr1;

//Setup ODE

d02pvc(neq, tstart, ystart, tend, tol, thres, method,

    Nag_RK_range, errass, hstart, &opt, &nagErr1);

if( nagErr1.code != NE_NOERROR )
```

```
    return false;

    for (j=1; j<nout; j++)
    {
        twant = tstart + j*tinc;

        NagError nagErr2;

        //Solve ODE

        d02pcc(neq, f, twant, &tgot, ygot, ypgot, ymax, &opt, &comm,
&nagErr2);

        if( nagErr2.code != NE_NOERROR )

            return false;

        vP[j] = ygot[0];
    }

    //Free functions for Runge-Kutta suite

    d02ppc(&opt);

    return true;
}
```

7. Define the fitting function body `_nlSFitODE`:

```
NLFitContext *pCtxt = Project.GetNLFitContext();

if ( pCtxt )

{

    static vector vX, vY;

    static int nSize;

    BOOL bIsNewParamValues = pCtxt->IsNewParamValues();

    // If parameters were updated, we will recalculate the ODE result.

    if ( bIsNewParamValues )

    {

        //Initial and final values of the independent variable

        double tstart = 0.02, tend = 2, tinc;

        int nout = 100; //Number of points

        tinc = (tend-tstart)/(nout-1);

        vX.Data( tstart, tend, tinc );

        nSize = vX.GetSize();

        if( !nag_ode_fit( a, y0, tstart, tend, nout, vY) )

            return;

    }

}
```

Tutorials for Origin

```
}  
  
//Interpolate y from fitting data's x on the ODE result.  
  
ocmath_interpolate( &x, &y, 1, vX, vY, nSize );  
  
}
```

8. Click the **Compile** button to compile the function body. To return, click **Return to Dialog** button. The **Evaluate** button on the dialog has a black figure of a running person. Clicking on it will show $y=2.6627270424371$. This implies that the function works. Click **Next**.
9. In the **Parameter Initialization Code** page, type the code in the **Initialization Code** box:

```
//Set the start y value in fitting data as the initial value of y0  
  
y0 = y_data[0];  
  
a = 1;
```

10. and click **Finish**.

Note: In order to monitor the the fitted parameters, [NLFitContext class](#) was introduced in defining fitting function to achieve some key information within the fitter

Fit the Curve


1. Highlight **B** column, then select **Analysis: Fitting: Nonlinear Curve Fit** from Origin menu. In the **NLFit** dialog, select **Settings: Function Selection**, in the page select **User Defined** from the **Category** drop-down list and **FitODE** function from the **Function** drop-down list.
2. Select **Parameters** tab, and fix **y0** as shown in the dialog.

NO.	Param	Meaning	Fixed	Value	Error	Dependency	Lower Cor
1	a	?	<input type="checkbox"/>	1	--	--	-
1	y0	?	<input checked="" type="checkbox"/>	0.77038	--	--	-

3. Click **Fit** button to fit the curve.

Fitting Results

The fitted curve should resemble the following image:



Fitted Parameters will be shown as in the following table:

Parameter	Value	Standard Error
a	1.30272	0.00858
y0	0.77038	0

Note: Fitting with more complex ODE fitting functions can also be done in a similar way.

4.2.2.26 Fitting with Convolution of Two Functions

Summary

In this tutorial, we will show you how to define a convolution of two functions, and perform a fit of the data with non-evenly spaced X using this fitting function.



If your data is a convolution of Gauss and Exponential functions, you can simply use built-in fitting function [GaussMod](#) in **Peak Functions** category to directly fit your data.

Minimum Origin Version Required: Origin 9.0 SR0


What you will learn


This tutorial will show you how to:

- Sample a function.
- Calculate a convolution of two functions.
- Define constants in the fitting function.
- Pad zeroes before the convolution.
- Interpolate the convolution result for non-evenly spaced X.
- Use a parameter to balance the speed and the precision.
- Use Y Error Bar as weight.

Example and Steps

Import Data

1. Open a new workbook.
2. Click the **Import Single ASCII** button  to bring up the Open dialog. Browse to `\Samples\Curve Fitting` folder and select the file `ConvData.dat`. Note that column A is not evenly spaced. We can use LabTalk `diff` function to verify it.
3. Right click on column C, and select **Set As: Y Error** from the short-cut menu. Highlight column B and C, and select **Plot: Symbol: Scatter** from the Origin menu. The graph should look like:



Define Fitting Function

The fitting function is a convolution of two functions. It can be described as follows:

$$y = y_0 + b_1x + \frac{b_2 A_2}{w_2 \sqrt{\pi/2}} e^{-\frac{2(x-x_{c2})^2}{w_2^2}} + (f * g)(x)$$

where

$$f(x) = \frac{s}{\pi} \cdot \frac{\tau_L x_0^2 (x_L^2 - x_0^2)}{(x - x_{c1}) \tau_L ((x - x_{c1})^2 - x_L^2)^2 + ((x - x_{c1})^2 - x_0^2)^2},$$

$$g(x) = \frac{1}{w_1 \sqrt{\pi/2}} e^{-\frac{2x^2}{w_1^2}}.$$

And x_0 , x_L , τ_L , s , y_0 , b_1 and b_2 are fitting parameters. w_1 , x_{c1} , w_2 , x_{c2} and A_2 are constants in the fitting function.

The fitting function can be defined using the **Fitting Function Builder** tool.

1. Select **Tools: Fitting Function Builder** from Origin menu.
2. In the **Fitting Function Builder** dialog's **Goal** page, click **Next**.
3. In the **Name and Type** page, select **User Defined** from **Select or create a Category** drop-down list, type **convfunc** in the **Function Name** field, and select **Origin C** in **Function Type** group. And click **Next**.
4. In the **Variables and Parameters** page, type **x0,xL,tL,s,y0,b1,b2** in the **Parameters** field, **w1,xc1,w2,xc2,A2** in the **Constants** field. Click **Next**.
5. In the **Origin C Fitting Function** page, set initial parameters as follows:

```
x0 = 3.1
xL = 6.3
tL = 0.4
s = 0.14
y0 = 1.95e-3
b1 = 2.28e-5
b2 = 0.2
```

6. Click **Constants** tab, set constants as follows:

Tutorials for Origin

```
w1 = 1.98005  
  
xc1 = -0.30372  
  
w2 = 5.76967  
  
xc2 = 3.57111  
  
A2 = 9.47765e-2
```

7. Click the  button on the right of the **Function Body** edit box and define the fitting function in **Code Builder** as follows:

8. Include header files,

```
#include <ONLSF.H>  
  
#include <fft_utils.h>
```

9. Define the function body

```
NLFitContext *pCtxt = Project.GetNLFitContext();  
  
if ( pCtxt )  
{  
  
    // Vector for the output in each iteration.  
  
    static vector vX, vY;  
  
    static int nSize;  
  
    BOOL bIsNewParamValues = pCtxt->IsNewParamValues();  
  
    // If parameters were updated, we will recalculate the convolution
```

```
result.  
  
if ( bIsNewParamValues )  
{  
  
    //Sampling Interval  
  
    double dx = 0.05;  
  
    vX.Data(-16.0, 16.0, dx);  
  
    nSize = vX.GetSize();  
  
    vector vF, vG, vTerm1, vTerm2, vDenominator, vBase, vAddBase;  
  
    double Numerator = tL * x0^2 * (xL^2 - x0^2);  
  
    vTerm1 = ( (vX - xc1) * tL * ( (vX - xc1)^2 - xL^2 ) )^2;  
  
    vTerm2 = ( (vX - xc1)^2 - x0^2 )^2;  
  
    vDenominator = vTerm1 + vTerm2;  
  
    //Function f(x)  
  
    vF = (s/pi) * Numerator / vDenominator;  
  
    //Function g(x)  
  
    vG = 1/(w1*sqrt(pi/2))*exp(-2*vX^2/w1^2);  
}
```

```

//Pad zeroes at the end of f and g before convolution

vector vA(2*nSize-1), vB(2*nSize-1);

vA.SetSubVector( vF );

vB.SetSubVector( vG );

//Perform circular convolution

int iRet = fft_fft_convolution(2*nSize-1, vA, vB);

//Truncate the beginning and the end

vY.SetSize(nSize);

vA.GetSubVector( vY, floor(nSize/2), nSize + floor(nSize/2)-1 );

//Baseline

vBase = (b1*vX + y0);

vAddBase = b2 * A2/(w2*sqrt(pi/2))*exp( -2*(vX-xc2)^2/w2^2 );

//Fitted Y

vY = dx*vY + vBase + vAddBase;

}

//Interpolate y from x for the fitting data on the convolution result.

```

```

ocmath_interpolate( &x, &y, 1, vX, vY, nSize );

}

```

10. Click **Compile** button to compile the function body. And click the **Return to Dialog** button.
11. Click **Evaluate** button, and it shows $y=0.02165$ at $x=1$. And this indicates the defined fitting function is correct. Click **Next**.
12. Click **Next**. In the **Bounds and General Linear Constraints** page, set the following bounds:

```

0 < x0 < 7

0 < xL < 10

0 < tL < 1

0 <= s <= 5

0 < b2 <= 3

```

13. Click **Finish**.


Note: In order to monitor the the fitted parameters, [NLFitContext class](#) was introduced in defining fitting function to achieve some key information within the fitter

Fit the Curve

1. Select **Analysis: Fitting: Nonlinear Curve Fit** from the Origin menu. In the **NLFit** dialog, select **Settings: Function Selection**, in the page select **User Defined** from the **Category** drop-down list and **convfunc** function from the **Function** drop-down list. Note that **Y Error Bar** is shown in the active graph, so column C is used as Y weight, and **Instrumental** weighting method is chosen by default.
2. Click the **Fit** button to fit the curve.

Fitting Results

The fitted curve should look like:



Fitted Parameters are shown as follows:

Parameter	Value	Standard Error
x0	3.1424	0.07318
xL	6.1297	0.1193
tL	0.42795	0.02972
s	0.14796	0.00423
y0	0.00216	1.76145E-4
b1	4.90363E-5	1.61195E-5
b2	0.07913	0.02855

Note that you can set a smaller value for **dx** in the fitting function body, the result may be more accurate, but at the same time it may take a longer time for fitting.

4.2.2.27 Parameter Initialization for Rational Functions

Summary

In this tutorial, we will show you how to calculate initial parameters for rational fitting functions using the multiple linear regression method, and perform a fit of the data using calculated initial parameters.

Minimum Origin Version Required: Origin 9.0 SR0

What you will learn

This tutorial will show you how to:

- Calculate initial parameters for rational fitting functions.
- Perform multiple linear regression using Origin C code.

Example and Steps

Algorithm

In this tutorial, we will use the following rational function as an example:

$$y = \frac{a + bx + cx^2}{1 + dx + ex^2}$$

where x is the independent variable, y is the dependent variable, and a , b , c , d , e are fitting parameters.

Multiplying both sides by the denominator on the right side yields:

$$y + dxy + ex^2y = a + bx + cx^2$$

and the equation can be expressed as:

$$y = a + bx + cx^2 - dxy - ex^2y$$

Substituting fitting data (x_i, y_i) $i = 1 \dots N$ into the equation gives:

$$\begin{cases} a + bx_1 + cx_1^2 - dx_1y_1 - ex_1^2y_1 = y_1 \\ a + bx_2 + cx_2^2 - dx_2y_2 - ex_2^2y_2 = y_2 \\ \vdots \\ a + bx_N + cx_N^2 - dx_Ny_N - ex_N^2y_N = y_N \end{cases}$$


Hence estimating initial parameters for a rational polynomial fitting function becomes a multiple linear regression problem with linear coefficients a , b , c , d , e .

$$\begin{bmatrix} 1 & x_1 & x_1^2 & -x_1y_1 & -x_1^2y_1 \\ 1 & x_2 & x_2^2 & -x_2y_2 & -x_2^2y_2 \\ \vdots & & & & \\ 1 & x_N & x_N^2 & -x_Ny_N & -x_N^2y_N \end{bmatrix} \begin{bmatrix} a \\ b \\ c \\ d \\ e \end{bmatrix} = \begin{bmatrix} y_1 \\ y_2 \\ \vdots \\ y_N \end{bmatrix}$$

Origin provides a function [ocmath_multiple_linear_regression](#) in Origin C for multiple linear regression, which can be called in initialization code.

Import Data

1. Open a new workbook.
2. Copy data in [Sample Data](#) to the workbook.
3. Highlight column B, and select **Plot: Symbol: Scatter** from Origin menu. The graph should look like:




Define Fitting Function and Initialize Parameters

The fitting function can be defined using the **Fitting Function Builder** tool.

1. Select **Tools: Fitting Function Builder** from Origin menu.
2. In the **Fitting Function Builder** dialog's **Goal** page, click the **Next** button.
3. In the **Name and Type** page, select **User Defined** from the **Select or create a Category** drop-down list, type **rationalfunc** in the **Function Name** field, and select **Expression** in the **Function Type** group. Click the **Next** button.
4. In the **Variables and Parameters** page, type **a, b, c, d, e** in the **Parameters** field. Click the **Next** button.
5. In the **Expression Function** page, type the following script in the **Function Body** box.

$$(a+b*x+c*x^2) / (1+d*x+e*x^2)$$

6. Click the **Evaluate** button, and it shows $y=1$ at $x=1$, hence this implies the expression is correct. Click the **Next** button.
7. In the **Parameter Initialization Code** page, click the **Open Code Builder** button  to the right of the **Initialization Code** box, and initialize fitting parameters as follows, in terms of the [algorithm](#).

```
UINT nOSizeN = x_data.GetSize(); //Number of points

UINT nVSizeM = 5; //Number of parameters

matrix mX(nOSizeN, 5);

//Construct matrix for data points of independent variables

vector vCa(nOSizeN), vCb, vCc, vCd, vCe;

vCa = 1;

mX.SetColumn( vCa, 0 );

vCb = x_data;

mX.SetColumn( vCb, 1 );

vCc = x_data^2;

mX.SetColumn( vCc, 2 );

vCd = -x_data*y_data;

mX.SetColumn( vCd, 3 );

vCe = -x_data^2*y_data;

mX.SetColumn( vCe, 4 );
```

```
//Options for multiple linear regression

LROptions stLROptions;

stLROptions.UseReducedChiSq = 1;

stLROptions.FixIntercept = 1; //Fix the intercept at 0.

FitParameter stFitParameters[ 6 ]; // should be nVSizeM+1

UINT nFitSize = nVSizeM + 1;

int nRet = ocmath_multiple_linear_regression(mX, nOSizeN, nVSizeM,
y_data,

    NULL, 0, &stLROptions, stFitParameters, nFitSize );

if( nRet == STATS_NO_ERROR )

{

    a = stFitParameters[1].Value;

    b = stFitParameters[2].Value;

    c = stFitParameters[3].Value;

    d = stFitParameters[4].Value;


    e = stFitParameters[5].Value;

}
```

8. Click the **Compile** button to compile the code. And click the **Return to Dialog** button. Click **Finish** to close the **Fitting Function Builder** dialog.

Fit the Curve


1. Select **Analysis: Fitting: Nonlinear Curve Fit** from Origin menu. In the **NLFit** dialog, select **Settings: Function Selection**, in the page select **User Defined** from the **Category** drop-down list and **rationalfunc** function from the **Function** drop-down list.
2. Click the **Parameters** tab. Initial parameters calculated from initialization code are listed in the dialog, and the fitting function curve for initial parameters is shown as follows. It seems that initial parameters from initialization code are very good.



3. Click the **Fit** button to fit the curve.

Fitting Results

The fitted curve should look like:



Fitted Parameters are shown as follows:

Parameter	Value	Standard Error
a	3.17139	0.30284
b	-1.65602	1.76748
c	0.26407	1.81764
d	3.6884	0.26362
e	5.31812	0.55265

Sample Data

x	y
-1.5	1.13173
-1.39474	0.8262

-1.28947	1.06999
-1.18421	1.37155
-1.07895	0.79569
-0.97368	2.11346
-0.86842	2.32006
-0.76316	3.9205
-0.65789	5.81904
-0.55263	7.38037
-0.44737	8.31272
-0.34211	11.39718
-0.23684	8.39808
-0.13158	4.7305
-0.02632	4.11105
0.07895	2.39105
0.18421	1.65394
0.28947	0.42953
0.39474	0.83337
0.5	1.18758

Note: You can also use this method to initialize parameters for other rational polynomial fitting functions.

4.2.2.28 Surface Fitting with Multiple Peaks

Origin provides several built-in surface fitting functions which can be used to perform fitting on 3D data. The surface fitting function is similar to the nonlinear fitting function.

Surface Fitting is only available in OriginPro.

Minimum Origin Version Required: OriginPro 9.0 SR0


What you will learn

- How to do surface fitting on matrix data.
- How to fit the surface with multiple peaks.


Steps

This tutorial is associated with the **Surface Fitting (Pro Only)** folder in the **Tutorial Data.opj** (<Origin EXE Folder>\Samples\Tutorial Data.opj).

1. With the matrix sheet active, click **Analysis** on the main menu, and then click **Nonlinear Matrix Fit...** to open the NLFit dialog. (Alternatively, you can plot the matrix as a 3D surface or contour, and then select **Nonlinear Surface Fit...** to open the same dialog.)
2. Click **Function Selection**, select **Gauss2D** from the **Function** dropdown menu.



3. Click **Advanced**, set **Number of Replicas** to **3**, and set **Peak Direction** as **Positive**.



- Click **Fit** to perform a multiple peak fit and generate a report worksheet with fitting results.

4.2.2.29 Nonlinear Multiple Variables Fitting

Summary

Origin supports fitting functions with multiple dependent or independent variables. With the nonlinear fitting function, you can define multiple variables and separate them with semicolons. Since global fitting allows you to fit only one function at a time, this is a good way to defeat that limitation.

Origin ships with three built-in functions with multiple dependent and independent variables. These functions, available in the Multiple Variables category, are actually composites consisting of two ordinary functions. The GaussianLorentz function, for example, is a combination of the Gaussian and Lorentz functions, sharing y_0 and x_c :

$$y_1 = y_0 + \frac{A_1}{w_1 \sqrt{\pi/2}} e^{-2 \frac{(x-x_c)^2}{w_1^2}}$$

$$y_2 = y_0 + \frac{2A_2}{\pi} \frac{w_2}{4(x-x_c)^2 + w_2^2}$$


This tutorial will demonstrate how to fit such multi-variable functions.

What you will learn


- Use Nonlinear Multiple Variables Fitting to fit a curve with two different functions.
- Assign data to fitting variables.

Steps


- Start with a new project or create a new workbook and import the data file `\\samples\curve fitting\Gaussian.dat`.




2. Highlight Column(A) and Column(B). In the main menu, click **Analysis**, then point to **Fitting**, and then click **Nonlinear Curve Fit**.
3. In the NLFit dialog's left panel, select **Function Selection**. In the right panel, select **Multiple Variables** in the Category dropdown menu. In the Function dropdown menu, select **GaussianLorentz**.



As you can see on the Sample Curve tab, the equations in this fitting function share the same parameters, y_0 and x_c .



4. In the NLFit dialog's left panel, select **Data Selection**. In the right panel, expand the **Range** node and assign data to the fitting variables. In this example, we have assigned column B to both y_1 and y_2 , which means that both expressions will fit the same dataset.



5. Click **Fit until converged** to fit, then **OK**. In the results sheet, compare parameters A and w, with the Gaussian and Lorentz functions sharing the same offset and peak center.

1 Nonlinear Curve Fit (GaussianLorentz) (8/22/2011 09:39:08)

Notes

Input Data

Parameters

		Value	Standard Error
Amplitude,Amplitude	y0	2.09809	0.76926
	xc	24.92185	0.09575
	A1	1075.86988	32.48958
	A2	1401.57586	52.93044
	w1	10.79511	0.31418
	w2	10.41147	0.45473

Reduced Chi-sqr = 19.6626229133
 COD(R²) = 0.97342424216416
 Iterations Performed = 7
 Total Iterations in Session = 7
 Fit converged. Chi-Sqr tolerance value of 1E-9 was reached.

Gaussian FitNL1 FitNLCurve1

4.2.2.30 Modifying Derived Parameters in Build-in Functions

Summary

Derived parameters are additional parameters computed using the fitted parameter values. You can define your own derived parameters for any built-in or user-defined fitting functions. They are not involved in the fitting process and are computed only at the end of the fitting session.

What you will learn

- How to add derived parameters in a built-in fitting function by Fitting Function Organizer.
- How to remove derived parameters in a built-in fitting function by Fitting Function Organizer.

Adding Derived Parameters


The built-in Gauss function fits the peak area with the following equation:

$$y = y_0 + \frac{A}{w\sqrt{\pi/2}} e^{-2\frac{(x-x_c)^2}{w^2}}$$

Suppose that you also want to know the peak height, which can be computed as follows:

$$h = \frac{A}{w\sqrt{\pi/2}}$$


1. Select **Tool: Fitting Function Organizer** in the menu. In the left panel of the dialog, select **Origin Basic Funcions: Gauss**.
2. Go to **Derived Parameters** section and input the $h=A/(w*\text{sqrt}(\text{PI}/2))$




Note:

- o Each derived parameter should be specified in a separate row.
 - o Derived parameters cannot be computed from other derived parameters.
3. Click on **Save** and the **OK** button.
 4. Create a new workbook and import the data file `\samples\curve fitting\Gaussian.dat`, using **File: Import: Single ASCII**.


- Highlight column A and B, then select **Analysis: Fitting: Nonlinear Curve Fit** to open the **Nonlinear Curve Fitting** dialog, and select **Gauss** from the Function drop-down list.




- Go to **Code** tab and click **Derived parameters** on the left panel. You can see the Derived Parameters listed on the right panel.



- Click **Fit** button to generate report sheets. After fitting, Origin will compute the height and include the result in the Parameters table on the fitting results worksheet.



- If you want to obtain the confidence interval for derived parameters, you can click on the green lock and select **Change Parameters** to go back to the **NLFit** dialog. Click **Advanced** option under **Settings** tab, expand **Quantities** node on the right panel and check the **LCL** and **UCL** checkboxes under **Fit Parameters** branch. Click **Fit** button to recalculate.



- Then confidence interval 95% *LCL* and 95% *UCL* are calculated for both parameters and derived parameters as below:


	Value	Standard Error	t-Value	Prob> t	95% LCL	95% UCL	Dependency
y0	5.34198	0.58341	9.15655	6.21148E-12	4.16764	6.51631	0.54074
xc	24.9069	0.08666	287.40475	0	24.73246	25.08134	1.07265E-11
w	10.16969	0.20452	49.72362	0	9.75801	10.58138	0.52123
A	984.90204	21.45075	45.91457	0	941.72392	1028.08016	0.69383
sigma	5.08485	0.10226			4.879	5.29069	
FWHM	11.9739	0.24081			11.48917	12.45862	
Height	77.27256	1.21284			74.83123	79.71389	
h	77.27256	1.21284			74.83123	79.71389	

Removing Derived Parameters

You can also remove derived parameters from result sheet. Continue with the tutorial above, follow the steps below:

1. Select **Tool: Fitting Function Organizer** in the menu to open the dialog again. In the left panel of the dialog, select **Origin Basic Functions: Gauss**.

2. Go to **Derived Parameters** section and remove expression $h=A/(w*\text{sqrt}(\pi/2))$ from that panel.



3. You may need to wait one or two seconds before the **Save** button is enabled. Click **Save** button and then **OK** button to close dialog.
4. Click on the green lock on the top left corner in result sheet *FitNL1* to change parameters and click **Fit** button again in the appeared **NLFit (Gauss)** dialog. We will see the derived parameter h has been removed from result table.

Nonlinear Curve Fit (Gauss) (8/7/2015 16:47:28)

	Value	Standard Error	t-Value	Prob> t	95% LCL	95% UCL	Dependency
y0	5.34198	0.58341	9.15655	6.21148E-12	4.16764	6.51631	0.54074
xc	24.9069	0.08666	287.40475	0	24.73246	25.08134	1.07265E-11
w	10.16969	0.20452	49.72362	0	9.75801	10.58138	0.52123
Amplitude							
A	984.90204	21.45075	45.91457	0	941.72392	1028.08016	0.69383
sigma	5.08485	0.10226			4.879	5.29069	
FWHM	11.9739	0.24081			11.48917	12.45862	
Height	77.27256	1.21284			74.83123	79.71389	

Reduced Chi-sqr = 7.81572174469
COD(R²) = 0.98986112534176
Iterations Performed = 5
Total Iterations in Session = 5
Fit converged. Chi-Sqr tolerance value of 1E-9 was reached.
sigma, FWHM, Height are derived parameter(s).

4.2.2.31 Fit Multiple Datasets by Fitting One and then Using Those Fit Parameters for Other Datasets

Summary

In some cases, you might have multiple datasets, and want to fit them using the user-defined function without parameter initial code. For increased efficiency, you can fit one and then apply the fit parameters for other datasets.

Minimum Origin Version Required: Origin 8.6

What you will learn

This tutorial will show you how to:


- Create a user-defined fitting function in Fitting Function Builder
- Perform an independent fit.
- Fit one of multiple datasets by doing 1-iteration, full-iteration.
- Apply the parameter values of one dataset to other datasets.

Steps

Create a User-Defined Function in Fitting Function Builder

The [Fitting Function Builder](#) can be used to create or edit a user-defined function. In the following section, we will define a fitting function *MyExp* with this tool.

1. Select **Tools: Fitting Function Builder...** from the main menu (or press **F8**) to open the **Fitting Function Builder**. Select the **Create a New Function** radio box.



2. Click the **Next** button to go to the **Name and Type** page. Enter *MyExp* in the **Function Name** box and select the **Origin C** radio box for the **Function Type**.

The screenshot shows the 'Fitting Function Builder - Name and Type - MyExp' dialog box. The 'Select or create a Category' dropdown is set to 'User Defined'. The 'Function Name' field contains 'MyExp', and the 'File Name(.FDF)' field contains 'MyExp.FDF'. The 'Function Model' section has 'Explicit' selected. The 'Function Type' section has 'Origin C' selected. The 'Include Integration During Fitting' checkbox is unchecked. Navigation buttons include '<< Back', 'Next >>', 'Cancel', and 'Finish'.

Fitting Function Builder - Name and Type - MyExp

Select or create a Category: User Defined (dropdown) [New]

Function Name: MyExp

File Name(.FDF): MyExp.FDF

Description: [Empty text box]

Function Model:

- Explicit
- Implicit


Function Type:

- Expression
- Equations
- Origin C
- LabTalk Script
- External DLL-based Function


Include Integration During Fitting

Buttons: [Cancel] [<< Back] [Next >>] [Finish]


3. Click the **Next** button to go to the **Variables and Parameters** page. Enter the variables and parameters as shown in the following screenshot:



4. Click the **Next** button to go to the **Origin C Fitting Function** page. Enter the function body $y=y0+a*exp(b*x)$ in the **Function Body** box. To verify the correctness of the function, click the button beside the Function box to open the Origin Code Builder.




In the **Code Builder**, click the **Compile** button to compile the function. If passed, the message *Compile Done* will show, and then you can click the **Return to Dialog** button to return to the **Fitting Function Builder**.




5. Click the **Finish** button to create this fitting function *MyExp*.

Fit Multiple Dataset with User-Defined Fitting Function


1. Import *\Samples\Curve Fitting\Exponential Decay.dat* to Origin worksheet.
2. Highlight all columns and then select **Analysis: Fitting: Non-linear Curve Fit** from the menu to open the **NLFit** dialog.
3. Select the function just defined in **Settings** tab, **Function Selection** page:




4. Switch to **Parameters** tab, enter 80, 100, -5 on the **Value** column as initial values for y_0 , a , b of the first dataset. Then select 1 from the independent fit drop-down list and iterate the first dataset until converged.




5. The parameter values are calculated and the fitting result is hinted in the bottom left corner of this dialog.



- To initialize the parameters of other datasets, apply the parameter values of the first dataset to other datasets by right-clicking the values, and then selecting **Apply Whole Set of "Value" to All Datasets** from the fly-out menu.



- Click **Fit** button to finish the fitting for all datasets.



4.2.2.32 Implicit Fitting with Three Variables

Summary

This tutorial will show you how to define an implicit fitting function with three independent variables, then perform implicit fitting with it on fitting data.

Minimum Origin Version Required: OriginPro 9.0 SR1


What you will learn

This tutorial will show you how to:


1. Define an implicit fitting function.
2. Perform implicit fitting with three independent variables.
3. Plot the fitted surface manually.

Examples and Steps

Import Data

1. Click the **Import Single ASCII** button  to bring up the Open dialog. Browse to **\Samples\Curve Fitting** folder and select the file **Ellipsoid.dat** file.
2. Highlight column C, right click on selection and choose **Set As: Z** from the context menu. Select **Plot: 3D Symbol/Bar/Vector: 3D Scatter** from Origin menu. Double click on the graph. In the

Plot Details dialog, select **Layer1** in the left panel, click **Axis** tab, set **X, Y, Z Length** as 100, 75, 50 respectively. Click the **Fit frame to layer** button in the **3D Rotation** toolbar. The graph should look like:



Define Fitting Function


The graph can be fitted with an ellipsoid. The function can be expressed as:

$$\frac{(x - x_0)^2}{a^2} + \frac{(y - y_0)^2}{b^2} + \frac{(z - z_0)^2}{c^2} = 1$$

where (x_0, y_0, z_0) is the ellipsoid's center location, **a**, **b** and **c** are semi-principal axes lengths, **x**, **y** and **z** are three independent variables for fitting data.

The fitting function can be defined using the **Fitting Function Builder** tool.

1. Select **Tools: Fitting Function Builder** from the Origin menu.
2. In the **Fitting Function Builder** dialog's **Goal** page, click **Next**.
3. In the **Name and Type** page, select **Implicit** from **Select or create a Category** drop-down list, type **Ellipsoid** in the **Function Name** field, and select **Implicit** in **Function Model** group. And click **Next**.



Note that implicit functions must be defined in **Implicit** category.

4. In the **Variables and Parameters** page, type **x, y, z** in the **Variable** field and **x0, y0, z0, a, b, c** in the **Parameter** field. Click **Next**.
5. In the **Expression Function** page, type the following script in the **Function Body** edit box.


```
(x-x0)^2/a^2+(y-y0)^2/b^2+(z-z0)^2/c^2-1
```

6. **Note** that for an implicit function $f_1(x_i, p_i) = f_2(x_i, p_i)$ where x_i ($i=1,2,..$) are independent variables, p_i ($i=1,2,..$) are parameters, it must be defined as $f = f_1(x_i, p_i) - f_2(x_i, p_i)$ in Origin where **f** is the **Estimate**.

Set initial parameters as follows in the **Parameters** tab.


```
x0=0 y0=0 z0=0 a=3 b=3 c=3
```

- In the **Quick Check** group, click **Evaluate** button, it shows $f=-0.667$ at $x=1, y=1, z=1$.



Click **Next** button, then click **Next** button again.

- In the **Bounds and General Linear Constraints** page, set lower bounds for **a, b** and **c**,




- Click **Finish** button to close the dialog.

Note that a message in **Messages Log** is shown that the implicit function is saved in the **User Files** folder.

Fit the Curve

- For implicit fitting with more than 2 independent variables, Origin only supports input data from workbooks not graphs. So we have to make the workbook for fitting data active before fitting. Select **Analysis: Fitting: Nonlinear Implicit Curve Fit** from Origin menu. In the **NLFit** dialog, select **Settings: Function Selection**, in the page select **Ellipsoid** function from the **Function** drop-down list.

2. Select **Data Selection** page, expand **Input Data: Range1**, and choose column A as X, column B as Y and column C as Z. An error message is shown at the bottom of the **Settings** panel. Following the suggestion of the error message, go to the **Fitted Curves** page and change the Data Type of X to **Fitted Point for Input Data**. The **Data Type of y** and **z** should automatically change as well.



Note that Origin doesn't support **Fit Curve** preview in the **NLFit** dialog or fitted surface in the fitted report for implicit fitting with more than two independent variables.

3. Since initial parameters have been set in **Fitting Function Builder** dialog, we can click **Fit** button to fit the curve.

Fitting Results

Switch to the fitted report. **Parameters** and **Statistics** tables are shown in the report.

Fitted Parameters are shown as follows.

Parameter	Value	Standard Error
x0	0.41073	0.01576

y0	0.32043	0.01352
z0	0.00147	0.00749
a	4.00325	0.02076
b	3.00097	0.01881
c	1.99972	0.00933

And **Adj. R-Square** is 0.99823, which means the fitted result is very good. **Note** that this result is from Origin9.0 32Bit, while in Origin9.0 64Bit the result is slightly different, and the latter is better.

In the **FitODRCurve1** worksheet, the first three columns show *XYZ* coordinates for fitted points.

Note that in the implicit fitting, *x*, *y* and *z* are all independent variables, they will all be adjusted during iterations in the fitting.

Fitted Surface

Although Origin9.0SR1 doesn't show the fitted surface in the fitted report for implicit fitting with more than two independent variables, in this example you can plot the fitted ellipsoid using **3D Parametric Function Plot** tool in Origin as follows.

1. Make the fitted report active, run following LabTalk script in the **Script Window** in order to get fitted parameter variables.

```
getnlr tr:=tt;

x0=tt.x0;

y0=tt.y0;

z0=tt.z0;

a=tt.a;

b=tt.b;

c=tt.c;
```

2. Variables **x0**, **y0**, **z0**, **a**, **b** and **c** can be used in following steps.


3. Make **Graph1** active. Select **File: New: Function Plot: 3D Parametric Function Plot** from Origin menu. In the **Create 3D Parametric Function Plot** dialog, set **u** from 0 to pi, **v** from 0 to 2*pi. And define **X ,Y** and **Z** as follows.

```
X(u,v)=x0+a*sin(u)*cos(v)

Y(u,v)=y0+b*sin(u)*sin(v)

Z(u,v)=z0+c*cos(u)
```

4. And choose **Add to Active Graph** from the drop-down list at the bottom left of the dialog.




- 5.
6. Click **OK** button to close the dialog. A 3D ellipsoid plot will be added to **Graph1**.
7. Double click on the graph. In the **Plot Details** dialog, you can customize the graph as follows. **Note** that only OpenGL of 2.1 or higher version supports 3D transparency in Origin9.0. You can

select **Tools: 3D OpenGL Settings** from Origin menu to see your OpenGL version, if your OpenGL version is lower than 2.1, you should ignore the setting for 3D transparency in Step 3.2.

1. Select **Layer1** in the left panel, click **Size/Speed** tab, clear **Worksheet data, maximum points per curve** check box in the **Speed Mode, Skip Points if needed** group. Click **Lighting** tab, choose **Directional** in the **Mode** group, and select blue color as **Ambient** color in the **Light Color** group.
2. Select the second plot in the **Layer1** branch, click **Surface** tab, set **Transparency** as 50%. Select **Fill** tab, and change **Fill piece by piece** color to white in the **Front Surface** group. Click **OK** button to close the dialog.

The graph for the fitted ellipsoid will look like:



4.2.2.33 Nonlinear fitting using Orthogonal Distance Regression

Summary

When performing non-linear curve fitting to experimental data, one may encounter the need to account for errors in both independent variables and dependent variables. In Origin, you can utilize the Orthogonal Distance Regression (ODR) to fit your data with implicit or explicit functions. This


tutorial will demonstrate how to perform non-linear curve fitting on data with both X errors and Y errors using ODR with a built in function.


Minimum Origin Version Required: Origin 9.1

What you will learn


This tutorial will show you how to use Orthogonal Distance Regression to fit nonlinear data with both X and Y errors.

Example and Steps


1. Open a new workbook.
2. Click the **Import Single ASCII** button  to bring up the Open dialog. Browse to the **\Samples\Curve Fitting** folder and select the file **ODR fitting.dat**.
3. Highlight column *XError* (long name) and right click to select **Set As: X Error** to set it as X error column.
4. Highlight column *YError* (long name) and right click to select **Set As: Y Error** to set it as Y error column.
5. Highlight all four columns and go to **Plot:Symbol:Scatter** to make a scatter plot with both X and Y error bars.
6. Go to **Analysis:Fitting:Nonlinear Curve Fit:Open dialog...** to open NLFit dialog.
7. On **Function Selection** page, select **Category** as **Polynomial**, **Function** as **Poly4** and **Iteration Algorithm** as **Orthogonal Distance Regression (Pro)**.



- Since X error and Y error columns have been specified in step 3, 4 so that when **Orthogonal Distance Regression** is selected as iteration algorithm these two columns will be automatically assigned as corresponding weight for X and Y data respectively. You can go to **Data Selection** page and expand **x** and **y** nodes under **Input Data** to see.



9. Click **Fit** button and choose **No** radio box in the appeared **Reminder Message** dialog, and click **OK** to close it, the fitting results are as shown below:



You can refer to [this page](#) for the details of the algorithm of ODR as well as Levenberg Marquardt (L-M) algorithm. Another example of using Orthogonal Distance Regression for Implicit Functions can be found [here](#).

4.3 Signal Processing

4.3.1 Signal Processing

- [FFT and IFFT](#)
- [FFT Filter](#)
- [Smoothing](#)
- [STFT \(Short-Time Fourier Transform\)](#)
- [IIR Filter](#)

- [2D FFT and Filter](#)
- [Convolution](#)
- [Wavelet](#)
- [Coherence and Correlation](#)
- [Decimation and Signal Envelope](#)
- [Rise Time](#)
- [Sound Processing](#)

4.3.2 FFT and IFFT

4.3.2.1 Summary

FFT (Fast Fourier Transform) is able to convert a signal from the time domain to the frequency domain. IFFT (Inverse FFT) converts a signal from the frequency domain to the time domain. The FFT of a non-periodic signal will cause the resulting frequency spectrum to suffer from leakage. Origin provides several windows for performing FFT to suppress leakage.

4.3.2.2 What You Will Learn


In this tutorial, you will learn how to:

1. Perform FFT on signal with different windows.
2. Recover the original signal with the spectrum.
3. Perform FFT on a graph by using the FFT gadget.


4.3.2.3 FFT Gadget

Origin's FFT gadget places a rectangle object to a signal plot, allowing you to perform FFT on the data contained in the rectangle. This is convenient for quickly observing the FFT effect on the data. The following tutorial shows how to use the FFT gadget on the signal plot.


1. Start with a new workbook, and import the data **<Origin Installation Directly>\Samples\Signal Processing\Chirp Signal.dat**.




- Highlight column B and make a line plot by clicking menu item **Plot: Line: Line**.




- With the plot active, select menu **Gadgets: FFT...** to start the FFT gadget.



- Using the default settings, click **OK** to add the rectangular Region of Interest (ROI) to the graph.



- Note that the **FFTPREVIEW** graph is created showing the FFT results for the selected data.




6. You can move the rectangle left and right to cover different portions of the data. You can also change the width of the rectangle to cover different numbers of data points. Repositioning or resizing the ROI changes the **FFTPREVIEW** graph.

4.3.2.4 **FFT**

In this example, we are going to change the window for suppressing the spectrum leakage.

1. Use the same data as the **FFT Gadget** subsection above.
2. Highlight column B, then select menu **Analysis: Signal Processing: FFT: FFT...**. This opens the **Signal Processing\FFT: fft1** dialog box.
3. In the dialog, check the **Auto Preview** box at the bottom to preview the result in the right panel. Change the **Window** to **Blackman**, but keep the remaining default settings. In the right panel, we can see that there is a sharp narrow peak spectrum for Amplitude. The **Blackman** window has suppressed the spectrum leakage very well.




4. Click **OK** to generate the resulting data and graphs.

Long Name	A(X)	B(Y)	C(Y)
Frequency	1/(sec)	Complex (a.u.)	Real (a.u.)
Comments	FFT of [ChirpSignal]"Chirp Signal"@"Amplitude"	FFT of [ChirpSignal]"Chirp Signal"@"Amplitude"	FFT of [ChirpSignal]"Chirp Signal"@"Amplitude"
F(x)=			
2	0.04883	1.35312 + 0.05927i	1.35312
3	0.09766	1.80944 - 0.13873i	1.80944
4	0.14648	2.36092 - 0.85292i	2.36092
5	0.19531	2.59074 - 2.27207i	2.59074
6	0.24414	1.81698 - 4.29756i	1.81698
7	0.29297	-0.72738 - 6.18918i	-0.72738
8	0.3418	-5.26597 - 6.2992i	-5.26597
9	0.39063	-10.37639 - 2.47017i	-10.37639
10	0.43945	-12.17611 + 6.17883i	-12.17611
11	0.48828	-5.63361 + 16.26424i	-5.63361
12	0.53711	10.26547 + 18.73255i	10.26547


4.3.2.5 IFFT

This example will show how to recover the signal from the results of doing an FFT. To do so, both settings for FFT and IFFT need to be the same, and the **Spectrum Type** needs to be **Two-sided** and **Window** needs to be set to **Rectangle**.


1. Start with your **FFT** results, above, and click on any of the green locks. Select **Change Parameters...** from the menu to open the dialog box again.




- As mentioned above, the **Window** needs to be set to **Rectangle**, and **Spectrum Type** should be **Two-sided**, so edit these two settings.



- Click **OK** and the results will be modified.
- Go to the **FFTResultData1** worksheet. We can see one column is Complex, one column is Real, and one is Imaginary. Here, we can use the Complex column (the Real column and Imaginary column also can be used). Highlight it and select the menu item **Analysis: Signal Processing: FFT: IFFT...** to open the **Signal Processing\FFT: fft1** dialog. (Note, if using Real and Imaginary columns, the first line for **Input** should be the Real column, and the **Imaginary** box should point to the Imaginary column.) Check the **Auto Preview** check box at the bottom to preview the result in the right panel.



5. Keep the default settings and click the **OK** button.
6. Now, we can make a comparison between the IFFT result (in **IFFTResultData1** worksheet) and the original signal data. As the image below shows, they are almost the same.



4.3.3 FFT Filter

4.3.3.1 Summary

Origin offers an FFT filter, which performs filtering by using Fourier transforms to analyze the frequency components in the input dataset.

There are six types of filters available in the FFT filter function: low-pass, high-pass, band-pass, band-block, threshold and low-pass parabolic. Low-pass filters block all frequency components above the cutoff frequency, allowing only the low frequency components to pass. High-pass filters work in the opposite way: they block frequency components that are below the cutoff frequency.

This tutorial will show you how to perform the low-pass and band-pass filtering using Origin's FFT filter.


4.3.3.2 What you will learn

This tutorial will show you how to:

- Perform low pass filtering.
- Perform band pass filtering.


4.3.3.3 Low-pass Filter

1. Start with an empty workbook.
2. Select **File:Import:Sound(WAV)** menu item and import the file **Origin 8 Message.wav** located at *<Origin EXE Folder>\Samples\Signal Processing*. Accept the default import settings.




3. Highlight column A(Y) and click the **Line**  button on the **2D Graph** toolbar to create a line plot.

4. This signal is a sound wave and it is already known that the high frequency components can be regarded as noise, and should be blocked. So we will use the **Low Pass** method in the **FFT Filter** tool to approximate the low frequency component for further analysis.
5. Make sure the line plot is active, then select **Analysis:Signal Processing:FFT Filters** to open the `fft_filters` dialog box.
6. Make sure the **Filter Type** is set to **Low Pass**.
7. Check the **Auto Preview** box to turn on the **Preview** panel:




The top two images show the signal in the time domain, while the bottom image shows the signal in the frequency domain after Fast Fourier Transform. The X position of the red vertical dot line indicates the cutoff frequency. By moving the vertical line horizontally, you can preview the comparison between the original signal and the filtered signal in real time, in the top part of this panel.

8. Move the vertical line to the X position of the peak amplitude (as in the image below). Note that human error may be introduced during this step, but it is acceptable since we only want to roughly filter the signal.





9. Click **OK** to apply the FFT filter to the original signal.
10. The signal after filtering will be added to the data plot of original signal. Select **Graph:Speed Mode** and turn off speed mode in this graph. The resulting graph should look like this:




11. In the resulting graph, we can see that the high frequency components are blocked by the Low Pass FFT filter.


4.3.3.4 Band-pass Filter

Tutorials for Origin

1. Start with a new workbook.
2. Click the **Import Single ASCII**  button and import the file **fftfilter3.dat** located at *<Origin EXE Folder>\Samples\Signal Processing*.
3. Highlight column B and click the **Line**  button on the **2D Graphs** toolbar to generate a line plot.




4. With the graph active, select **Analysis:Signal Processing:FFT Filters**. This opens the **fft_filters** dialog box.
5. Check the **Auto Preview** box to enable the **Preview** panel.
6. From the plot of frequency domain (the image below), we can see that this signal has components at several different frequencies> Now we are going to get the component at about 300Hz. So we will use the **Band Pass** method.



- Set the **Filter Type** to be **Band Pass**.


When **Band Pass** is chosen, there will be two vertical red lines in the preview panel, marking the Lower Cutoff Frequency and Upper Cutoff Frequency. You can similarly move these two lines and get the real time preview of filtering results in the top parts of this panel.

- Enter the values of the lower and upper cutoff frequencies according to the image below:



As long as only the desired amplitude peak stays within the cutoff frequency range, the error in filtering could be considered as acceptable even though the values of upper and lower cutoff frequencies may slightly differ for different cases.

- Click **OK** to execute filtering.
- We obtain the components at a frequency of around 300 Hz after filtering.



4.3.4 Smoothing

4.3.4.1 Summary

Smoothing is a common technique for removing noise from signals. Origin provides multiple smoothing methods, including Adjacent Averaging, Savitzky-Golay, Percentile Filter, and FFT Filter. Additionally, there is a wavelet-based tool available.

For matrix data, Origin's smoothing is performed in two ways. If the number of columns or rows is less than 32, it will expand the matrix first, then shrink it back to the original size. If greater than 31, the matrix is first shrunk, then expanded.


4.3.4.2 What You Will Learn

This tutorial will show you how to:

1. Smooth signals by several methods.
2. Smooth signals using wavelets.
3. Smooth a 3D surface.

4.3.4.3 Smoothing by Several Methods

1. Start with an empty workbook.
2. Select menu item **File: Import: Single ASCII...** to import the data **Signal with High Frequency Noise.dat** under the folder *<Origin Installation Directory>\Samples\Signal Processing* (use default settings).




3. Highlight column B in the worksheet. Then, select menu item **Analysis: Signal Processing: Smooth...** (if the tool has been used before, select **Open Dialog**) to open the **Signal Processing: smooth** dialog box.

Adjacent-Averaging

The Adjacent-Averaging method performs a broad smoothing of data.

1. Choose **Adjacent-Averaging** for **Method**. Set the **Points of Window** to **100** and **Boundary Condition** to **Periodic**. To preview the result in the right panel, check the **Auto Preview** check box.




2. Click **OK** to generate the result.

Savitzky-Golay

The Savitzky-Golay method is good for preserving the shapes of signal peaks.

1. Select column B again. On the **Analysis** menu, click **Signal Processing: Smooth:Open Dialog....**
2. In the **smooth** dialog box, set **Method** to **Savitzky-Golay**. Set **Points of Window** to **100**, **Boundary Condition** to **Periodic** and **Polynomial Order** to **3**.




3. Click **OK**.

Percentile Filter

1. Select column B again. On the **Analysis** menu, click **Signal Processing: Smooth:Open Dialog.....**


- For **Method**, choose **Percentile Filter**. Set **Points of Window** to **100**, **Boundary Condition** to **Periodic**, and for **Percentile** accept the default value of **50**.




- Click **OK** button.

FFT Filter

- Select column B again. On the **Analysis** menu, click **Signal Processing: Smooth:Open Dialog.....**
- Set **Method** to **FFT Filter**. Set **Points of Window** to **100**.




- Click **OK** to close the dialog box.
- Note that in the worksheet, there are now four added columns containing the results of your four smoothing operations. Highlight those four columns (C,D,E,F), then from the menu select **Plot: Line: Line** to make a line graph with these four datasets.




5. Comparing the results of the four methods, you can see that the Savitzky-Golay method did the best job of preserving peaks in the data, while the FFT Filter method did the poorest job of preserving peaks.

4.3.4.4 Smoothing by Wavelet


1. Start a new workbook.
2. Select menu item **File: Import: Single ASCII...** to import the data **Signal with High Frequency Noise.dat** under the folder *<Origin Installation Directory>\Samples\Signal Processing* (use the default settings).



- Highlight column B, and from the menu select **Analysis: Signal Processing: Wavelet: Smooth...** to open the **Smooth: wtsmooth** dialog box.
- In the dialog, set **Wavelet Type** to **DB6**, and **Cutoff (%)** to **98**. Check **Auto Preview** to preview the result in the right panel.




- Click **OK** to close the dialog box and generate your result.
- To see the difference between the original signal and the smoothed signal, highlight all columns in the worksheet and from the menu select **Plot: Line: Line**.



4.3.4.5 Smoothing Matrix


1. Start with a new matrix book.
2. Select menu **File: Import: Image to Matrix...** to import the image **scale.jpg** under the folder *<Origin Installation Directory>\Samples\Image Processing and Analysis* (if the *implImage* dialog box opens, simply accept the defaults and click **OK**).
3. Origin is not able to apply to perform smoothing on an image so we must convert the image to matrix data first. From the menu select **Image: Conversion: Convert to Data...** Accept the dialog box default settings and Click **OK**.
4. With the converted matrix activated, select menu **View: Image Mode** to view this matrix as image.



5. To perform smoothing, select **Analysis: Signal Processing: Smooth...** This opens the **Signal Processing: msmooth** dialog box.



6. Accept the default settings and click **OK**. To view the result, select **View: Image Mode** from the menu.



4.3.5 STFT (Short-Time Fourier Transform)

4.3.5.1 Summary

Short-Time Fourier Transform (STFT) is a time-frequency analysis technique suited to non-stationary signals. Short-Time Fourier Transforms can provide information about changes in frequency over time.


4.3.5.2 What You Will Learn

In this tutorial, you will learn how to:


1. Perform Short-Time Fourier Transform (STFT).
2. Change dialog settings to improve the time and frequency resolution.
3. Change window type to improve resolution.

4.3.5.3 Steps


1. Start with a new workbook, and import the data **<Origin Installation Directory>\Samples\Signal Processing\Chirp Signal.dat**.




- Highlight column B, and select menu **Analysis: Signal Processing: STFT...** to open the **STFT: stft** dialog box.
- In the dialog box, check **Auto Preview** at the bottom of the dialog so that you can preview your results in the right panel. Uncheck the **Auto** check box next to **Window length** and **Overlap**, then change **Window length** to 8, and **Overlap** to 7. Set **Window Type** to **Hanning** and **Option** to **Amplitude Result**.




4. Click **OK** to perform STFT with the chosen settings and obtain your results, including a matrix book with data and a color fill contour plot.




5. We can see from the above image that the time resolution is good, but the frequency is not so apparent. Click on the lock on the graph, then choose **Change Parameters...** from the menu. This reopens the STFT dialog box. Change the **Window Type** to **Rectangle** and click **OK**.




6. Now, we are better able to see resolution of both time and frequency. Please note that it is not possible to optimize for both time and frequency; the best we can do is to find the balance between them.
7. To view the result in 3D, activate the resulting matrix, then select menu **Plot: 3D Surface: Color Map Surface** to create a 3D surface of the result.
8. Double click on the 3D graph to open the **Plot Details** dialog, and go to the **Colormap/Contours** tab in the right panel. Click the **Line...** heading to open the **Contour Lines** dialog and **Hide All** lines.



9. Go to the **Mesh** tab and clear the **Enable** check box.



10. Click **OK** to finish the settings. To get a better view, rotate the graph.



4.3.6 IIR Filter

4.3.6.1 Summary

In OriginPro, it is possible to design, analyze, and implement IIR (Infinite Impulse Response) digital filters. The IIR filter supports four methods, including **Butterworth**, **Chebyshev Type I**, **Chebyshev Type II**, and **Elliptic**.

This provides users more choices in signal processing.

Minimum Origin Version Required: 9.0 SR0

4.3.6.2 What You Will Learn


This tutorial will show you:

- How to design and apply an IIR filter
- A comparison between IIR filter and FFT filter

4.3.6.3 Steps

Design and Apply IIR Filter


1. Start with a new worksheet and import the **EMG Recording.dat** file from `\Samples\Signal Processing\`.
2. Highlight column B and Select **Analysis:Signal Processing:IIR Filter** from the top menu to open the dialog.
3. Change the Response type as **High Pass**, keep the Method as **Butterworth**, uncheck the **Minimum** for Filter Order and set it as **4**. In the Frequency Specification branch, set the Cutoff Frequency(Fc) as **20**, then check the **Forward-Backward Filtering**. The dialog settings should look like the following figure, and the IIR filter is designed.









- Click **OK** to apply the created IIR filter to the input dataset.
- A new column will be added to the original data as a new column of filtered data and a new SOS Matrix worksheet.

Compare Results with FFT Filter

- Highlight column B in the original worksheet, perform FFT filter by **Analysis:Signal Processing:FFT Filters**.
- In the opened dialog, choose **High Pass** for Filter Type and set **20** as Cutoff Frequency.





- Click OK button. Column C in the EMGRecording worksheet is the filtered result of the previously designed IIR filter, highlight column B and column C to generate a line plot with the  button (Graph 1).
- Use the scale in button  to zoom the area between 12.5s and 13.3s.
- Column E in the EMGRecording worksheet is the filtered result of the FFT filter, highlight column B and column E to generate a line plot with the  button (Graph 2).
- Also use the scale in button  to zoom the area between 12.5s and 13.3s, the two graphs could be used for visualized comparison.





- Note that there are many ripples in the FFT filter result, but almost no ripples in the IIR filter result.

Ripples in FFT Filter

- Highlight column E and click on the  button to create a line plot (Graph 3).
- Activate Graph 3, choose **Gadget:FFT** and set the X Scale as From **12.664** To **13.052**.
- Click OK to bring up the preview window, in which ripples are almost pure 20.125 Hz sine.



- Now we would try to remove the ripples at 20.125 Hz by applying another high pass filter at 25 Hz, keep highlighting column E and select **Analysis:Signal Processing:FFT Filters**.
- Select **High Pass** for Filter Type and set Cutoff Frequency as **25**.
- The result is listed in Column G, highlight column G and click on the  button to create a line plot(Graph 4).
- Activate Graph 4, choose **Gadget:FFT** and set the X Scale as From **12.664** To **13.052**, in the preview window, there are still ripples, and they are shifted from 20.125 Hz to 25.157 Hz.



- Note that the ripples could not be removed by FFT filter for this dataset.

4.3.7 2D FFT and Filter

4.3.7.1 Summary

2D FFT (2-dimensional Fast Fourier Transform) can be used to analyze the frequency spectrum of 2D signal (matrix) data. Conversely, 2D IFFT (2-dimension Inverse Fast Fourier Transform) is able to reconstruct a 2D signal from a 2D frequency spectrum. OriginPro provides both for conversion between time and frequency domains in 2 dimensions, together with the 2D FFT filter to perform filtering on a 2D signal.

4.3.7.2 What You Will Learn


This tutorial will show you how to:

1. Convert image into data.
2. Perform 2D FFT on matrix data with DC shift to center.
3. Perform 2D IFFT on the 2D FFT result to recover the original matrix data.
4. Perform 2D FFT filter on matrix data.


4.3.7.3 Steps

2D FFT


1. Start with a new matrix book, and select menu item **File: Import: Image to Matrix...** to import the image **<Origin Installation Directory>\Samples\Image Processing and Analysis\cell.jpg**.




- Because Origin is not able to perform analyses on image data directly, we need to convert the image to matrix data first. So, select menu item **Image: Conversion: Convert to Data** to bring up the **Convert to Data: img2m** dialog box. Set **Type** to **byte(1)**.




- Click **OK** to finish the conversion. The result shows below. You can choose menu item **View: Data Mode** and **View: Image Mode** to convert between data mode and image mode.



4. With the converted result matrix active, select the menu item **Analysis: Signal Processing: FFT: 2D FFT...** to open the **2D FFT: fft2** dialog box. Check the **DC Shift Center** check box to shift the direct current to center. In the **Output** node, only check **Complex Matrix** and **Log Amplitude Matrix**.




- Click the **OK** button to generate the FFT results. Both the complex matrix and the log amplitude matrix are in the same matrix book. Change to image mode (**View:Image Mode**) for the log amplitude matrix. The results should look like this:



2D IFFT

1. Start with the complex matrix (FFT2_Complex1) generated in the **2D FFT** section above. Make it the active window.
2. Select the menu item **Analysis: Signal Processing: FFT: 2D IFFT...** to bring up the **2DIFFT: iff2** dialog box.
3. In the dialog box, the imaginary matrix is not needed because the **Input Matrix** is a complex matrix. Check **Undo Shift** because DC has been shifted. **Output** should have the **Real Matrix** and **Imaginary Matrix** boxes checked.



4. Click the **OK** button, and the result will be output to the same matrix book as the input complex matrix.

	1	2	3	4	5
1	169	175	177	173	174
2	166	172	175	172	173
3	159	167	172	171	172
4	150	160	168	170	171
5	141	150	161	167	170
6	132	140	150	158	164
7	125	130	138	147	155
8	122	124	130	139	148
9	121	119	121	127	134
10	127	125	124	125	126
11	125	126	125	123	123
12	121	126	128	126	125
13	122	128	132	129	127
14	119	124	128	128	126
15	116	118	122	126	126
16	120	119	122	126	126
17	113	111	120	128	127

- From the comparison shown below, the IFFT has recovered the original signal.

MBook1 :1/1	1	2	3	4
1	169	175	177	173
2	166	172	175	172
3	159	167	172	171
4	150	160	168	170
5	141	150	161	167
6	132	140	150	158
7	125	130	138	147
8	122	124	130	139
9	121	119	121	127
10	127	125	124	125
11	125	126	125	123
12	121	126	128	126
13	122	128	132	129
14	119	124	128	128

Original data

Real part of IFFT result


Imaginary part of IFFT result

2D FFT Filter


- Start with an empty matrix book and from the menu select **File: Import: Image to Matrix...** to import the image **<Origin Installation Directory>\Samples\Image Processing and Analysis\myocyte1.tif**.




2. With the imported image active, select the menu item **Image: Conversion: Convert to Data**. This opens the **Convert to Data: img2m** dialog box. Set **Type** to **byte(1)** and click **OK** to finish the conversion.



3. Activate the converted matrix and select the menu item **Analysis: Signal Processing: 2D FFT Filters....** This opens the **2D FFT Filters: fft_filter2** dialog box.
4. In the dialog box, check the **Auto Preview** check box at the bottom to view the result in the right panel. Set **Filter Type** to **Band Pass**, and set **Lower Cutoff Value** and **Upper Cutoff Value** to **0.05** and **0.25** respectively. For other controls, keep the default values.



5. Click **OK** to obtain the filtered result. As the image below shows, the background noise (the light) is removed.



4.3.8 Convolution

4.3.8.1 Summary


Convolution is commonly used in signal processing. Origin uses the convolution theorem, which involves the Fourier transform, to calculate the convolution.

4.3.8.2 What You Will Learn


With this tutorial, you will learn how to perform convolution in Origin.

4.3.8.3 Steps


1. Start with a new workbook.
2. Import the data <Origin Installation Directory>\Samples\Signal Processing\Convolution.dat.



- Highlight column B and C, and from the menu select **Analysis: Signal Processing: Convolution....** This opens the **Convolution: conv** dialog box. In the dialog, column B is labelled as Signal, and column C as Response and the Sample Interval will be set according to the input signal's associated X column.
- Expand the **Options** node and change **Convolution Type** to *Circular*, to repeat the data within range for the data outside range, but not pad with zeroes.



5. Click **OK** to obtain the result.
6. In the worksheet, highlight column B and E (press CTRL to select non-adjacent columns), then from the menu select **Plot: Line: Line** to make a graph with input signal and the output signal.



4.3.9 Wavelet

4.3.9.1 Summary

Wavelet transforms are useful for analyzing signals which exhibit sudden changes of phase and frequency, local maxima and minima, or related parameters. Wavelet transforms have become a popular tool in time-frequency analysis, especially for analysis of non-stationary signals. OriginPro provides wavelet transform tools for both continuous and discrete transforms.

4.3.9.2 What You Will Learn


This tutorial will show you how to:

1. Perform one-level discrete wavelet decomposition and reconstruct a signal from approximation coefficients and detail coefficients.
2. Apply multi-level discrete wavelet decomposition.
3. Perform continuous wavelet transform.
4. Remove noise from signals by using wavelet transform.
5. Perform 2D wavelet decomposition and reconstruction on matrix data.
6. Convert an image to matrix data.
7. Merge graph windows into one graph.


4.3.9.3 1D Wavelet Transform

Decomposition


1. Start with a new workbook, and select menu **File: Import: Single ASCII...** to import the data **<Origin Installation Directory>\Samples\Signal Processing\Chirp Signal.dat** into the worksheet.




2. Highlight column B, and select menu item **Analysis: Signal Processing: Wavelet: Decompose...** to open the **Decompose: dwt** dialog.
3. In the dialog, choose **DB6** for **Wavelet Type & Order**, and **Zero-padded** for **Extension Mode**.



4. Click **OK** to close the dialog box and output the approximation coefficients and the detail coefficients.
5. Highlight columns B, C, and D (columns C and D should contain your approximation coefficients and your detail coefficients, respectively). From the menu, select **Plot: Multi-panel: Stack...** to open the **Stack: plotstack** dialog box.
6. In this dialog, clear the **Link Layers** check box in the **Options** node. Check the **Auto Preview** check box at the bottom to see the preview graph in the right panel.



7. Click **OK** to close the dialog box and create a stack graph.




Note: To perform level 2 (3, 4, etc.) discrete wavelet decomposition, repeat steps 2 to 4 on the approximation coefficients (column C, in our example). Multi-scale wavelet decomposition (available in OriginPro) is demonstrated below.


Reconstruction

Reconstruction is the inverse operation of decomposition and this example will recover the signal from the result generated above.

1. Highlight columns C and D (your approximation coefficients and detail coefficients, from above).
2. Choose menu item **Analysis: Signal Processing: Wavelet: Reconstruction...** to bring up the **Reconstruction: idwt** dialog box.
3. To reconstruct the signal, we need to specify the same **Wavelet Type**, and **Boundary**, so set them to **DB6** and **Zero-padded**, respectively.




4. Click **OK** and the recovered signal is output to column E of the worksheet.
5. Press CTRL and select columns B and E. From the menu, choose **Plot: Line: Line** to make a graph with these two columns of data.




- We can see from the resulting graph that the original signal and the recovered signal overlay each other.

Multi-Scale Wavelet Decomposition


- Start with a new workbook, and then import the same data used in the **Decomposition** section above.
- Highlight column B and select menu item **Analysis: Signal Processing: Wavelet: Multi-Scale DWT...** to open the **Multi-Scale DWT: mdwt** dialog box.
- In the dialog, change **Extension Mode** to **Zero-padded**, and **Decomposition Level** to **3**. Click the arrow button beside **Multiple Coeff Data** and select [



- Click **OK** to obtain 3rd level discrete wavelet decomposition results. The coefficients are stored in the same worksheet as the input signal.
- Select all columns in the worksheet, then choose menu **Plot: Multi-panel: Stack...** to open the **Stack: plotstack** dialog box. Click the arrow button to the right of **Dialog Theme** and select **System Default**. Check the **Auto Preview** check box at the bottom of the dialog box to preview the graph.




6. Click **OK**. The resulting graph is shown below.




Continuous Wavelet Transform


1. Start with a new workbook with two empty columns (columns A and B) in a single worksheet.
2. Select column A and then right-click and choose **Set Column Values...** from the shortcut menu. This opens the **Set Values** dialog box. In the text box, enter `data(0, 1, 1/1023)` and click **Apply**. This fills column A with data.




3. Click the >> button to select column B. Enter $\sin(1.5/(0.25-\text{col}(A)))+\cos(0.2/(0.2-\text{col}(A)))$ and click **OK**.




4. We can make a plot to see how the data looks. With column B selected, choose **Plot: Line: Line** from the menu.




- With the worksheet active, add a new column to the worksheet by selecting **Column: Add New Columns...** from the menu. In the dialog box, accept the default value of 1 and click **OK**.



- Column C is added to the worksheet. Select it, right-click and choose **Set Column Values** from the shortcut menu. In the text box, enter `data(1, 512)` and click **OK**.




7. Select both columns B and C, then from the menu, select **Analysis: Signal Processing: Wavelet: Continuous Wavelet...** to open **Continuous Wavelet: cwt** dialog box.
8. In the dialog, set **Wavelet Type** to **MexHat**, and check **Coefficient Matrix**.




9. Click **OK** button to exit dialog.

10. The coefficients are output to a new worksheet and a matrix and a contour plot is added. Double-click on the plot to open the **Plot Details** dialog box. Select the **Colormap** tab and click on the **Fill...** heading. The **Fill** dialog box opens with color controls. Click **Load Palette**, and choose **Pumpkin Patch** from the **Select Palette** menu. Click **OK** to return to the **Plot Details** dialog box.




11. Click **OK** to change the color of the contour plot. It should now look like the graph below.




Noise Removal by Wavelet Transform


1. Start with a new workbook and from the menu, select **File: Import: Single ASCII...** Import the file **<Origin Installation Directory>\Samples\Signal Processing\Signal with Shot Noise.dat** .




- We can see from the Sparklines in the image above that there is shot noise in the signal. Highlight column B and select menu **Analysis: Signal Processing: Wavelet: Denoise...** to bring up the **Denoise: wtdenoise** dialog box.
- Check **Auto Preview** to preview your result. Set **Wavelet Type** to **DB9**, **Extension Mode** to **Zero-padded**, **Threshold Type** to **sqtwolog**, and **Thresholding Level** to **7**.



- Click **OK** to remove the shot noise from the signal. Results are output to worksheet columns C and D.



5. Highlight all columns in the worksheet, then choose menu item **Plot: Line: Line** to make a graph with the original signal and the cleaned-up signal. We see from the graph below that the shot noise has been removed.




4.3.9.4 2D Wavelet Transform

2D Wavelet Decomposition


1. Start with a new matrix book. From the menu, choose **File: Import: Image to Matrix...** and import the image, **<Origin Installation Directory>\Samples\Image Processing and Analysis\Car.bmp**.



2. To begin, we need to convert the image into data. To do this, select menu item **Image: Conversion: Convert to Data**. The **Convert to Data: img2m** opens. Set **Type** to **byte(1)**.



3. Click **OK** to obtain the converted matrix data.
4. With the converted matrix active, select menu **Analysis: Signal Processing: Wavelet: 2D Decompose...** and open the **2D Decompose: dwt2** dialog box.



- Accept the default settings and click **OK**. This performs 2D wavelet decomposition on the matrix data. A matrix book with four matrix sheets (CA, CH, CV, and CD) is generated. CA, CH, CV, and CD contain approximation coefficients, horizontal detail coefficients, vertical detail coefficients, and diagonal detail coefficients respectively. You can change the view mode to image mode by choosing **View: Image Mode** from the menu.



6. With the CA matrix sheet active, make an image plot by selecting **Plot: Image Plot** from the menu. Repeat for CH, CV, and CD matrix sheets.
7. Double click on graph of them to open the **Plot Details** dialog, in the left panel, activate **Layer1**, and then go to the **Size/Speed** tab in the right panel, and uncheck **Matrix data, maximum points per dimension**. Click **OK**. select the axes related objects (including axis, label) in the graph and press the DELETE key to delete them.

4.3.10 Coherence and Correlation

4.3.10.1 Summary

Coherence measures the degree of linear dependency of two signals by testing for similar frequency components. If two signals correspond to each other perfectly at a given frequency, the magnitude of coherence is 1. If they are totally unrelated coherence will be 0.

Correlation is another measure of the relationship between two signals. A correlation coefficient is used to evaluate similarity. If two signals have a high degree of similarity, the magnitude of the computed correlation coefficient is large. If there is little or no linear relationship between two signals, the magnitude of the coefficient is small.


4.3.10.2 What You Will Learn

This tutorial will show you how to:


1. Test coherence and find out the frequency where two signals are in the highest degree of linear dependency.
2. Perform correlation and find the lag to translate a dataset.

4.3.10.3 Coherence


1. Start with a new workbook.
2. Select the menu item **File: Import: Single ASCII...** to import the data **<Origin Installation Directory>\Samples\Signal Processing\Coherence.dat**.



3. Select column A, then right-click and select **Set As: Y** from the shortcut menu. This sets the plot designation for column A to Y.
4. Highlight the two columns and from the menu select **Analysis: Signal Processing: Coherence....** This opens the **Coherence: cohere** dialog box.
5. Change the **Window Type** to *Welch*, and click **OK**.




- Two columns of data are added to the worksheet. Highlight these two new columns and from the menu select **Plot: Line: Line** to plot coherence against frequency.




7. Select the **Data Reader** on the **Tools** toolbar to read the strongest peak in the graph. The image above shows that at a frequency of 0.25 there is a strong peak, indicating a strong correspondence between the two signals at this frequency.

4.3.10.4 1D Correlation


1. Start with a new workbook.
2. Select menu **File: Import: Single ASCII...** and import the file **<Origin Installation Directory>\Samples\Signal Processing\Correlation.dat**.




3. Select column A. Right click on it to open the shortcut menu, then choose item **Set As: Y** to set this column's plot designation to Y.
4. Highlight the two columns and from the menu select **Analysis: Signal Processing: Correlation....** This opens the **Correlation:corr1** dialog box. Accept the default settings.




5. Click **OK** to perform a correlation on the two signals.
6. The correlation result and a time lag column are output to the worksheet. Highlight column D, and from the menu select **Plot: Line: Line** to plot the result.




7. The Data Reader in the image above shows that at Time = 49, there is a strong positive peak, which means that the second dataset needs to be translated forward 49 units to align these two signals.
8. Return to the worksheet, highlight column A and B, then from the menu select **Plot: Multi-Panel: Vertical 2 Panel** to plot the two signals to two separate graph layers.



9. Double click on the top plot to open the **Plot Details** dialog box. In the left panel, select **Layer 2** (take care not to clear the check box). Go to the **Link Axes Scales** tab in the right panel and click the **Straight (1 to 1)** radio button in the **X Axis Link** group.



10. Click **OK** and both X axes now have the same scale.




11. To make the datasets movable, delete the lock by clicking on it and choosing **Recalculate Mode: None**. Click **OK** if the **Reminder Message** dialog pops up.


12. Select the top plot, then select menu **Analysis: Data Manipulation: Horizontal Translate** to add a vertical line to the layer, together with a triangle button. Click on the triangle button to open a menu and uncheck **Keep Tool after Translation**. Open the menu again, select **Translate Duplication in: New Columns** from the menu. Another two columns will be added and the source data of current curve will be copied to these two new columns.

	A(Y)	B(Y)	C(X1)	D(Y1)	E(X2)	F(Y2)
Long Name			Time	Corr Y1		
Units						
Comments				correlation of A, B	source: Correlation	source: Correlation
F(x)=						
Sparklines						
1	-0.02861	0	-80	#####	-80	0
2	0.10097	1	-79	#####	-79	1
3	0.15188	0.8	-78	#####	-78	0.8
4	-0.02864	0.6	-77	#####	-77	0.6
5	-0.09683	0.4	-76	#####	-76	0.4
6	-0.01719	0.2	-75	#####	-75	0.2
7	0.0655	0	-74	#####	-74	0
8	-0.11455	0	-73	#####	-73	0
9	-0.00732	0	-72	#####	-72	0
10	0.13931	0	-71	#####	-71	0
11	-0.17216	0	-70	#####	-70	0
12	0.1294	0	-69	#####	-69	0

13. Again, open the menu and click **Shift Curve...** to bring up the **Shift Curve** dialog box. Set **Value** to 49.



14. Click **OK** to translate the plot. This should align the two signals.



4.3.11 Decimation and Signal Envelope

4.3.11.1 Summary

Decimation is used to reduce the size of the signal sequence by merging every N samples into one. Envelope detection adds an envelope curve to the input signal. Origin's signal envelope tool computes an envelope and plots an upper envelope, a lower envelope, or both.

4.3.11.2 What You Will Learn


This tutorial will show you how to:

1. Decimate a signal to reduce the size of the input signal sequence.
2. Perform envelope detection to add the envelope curve.


4.3.11.3 Decimation

In this tutorial, we are going to perform decimation on sunspot count data. Measurements of sunspot number were collected every month for more than 200 years. We will use decimation to reduce our dataset to one sunspot count for each year.

1. Start with a new workbook, and import the data **<Origin Installation Directory>\Samples\Signal Processing\Sunspot.dat**.




2. Select column A. Right click on the column and choose **Set As: Y** to set this column's plot designation to Y. This will ensure that sunspot number is not associated with column A as X. That is because decimation needs the X column data to be strictly monotonic.
3. Select column C and from the menu choose **Analysis: Signal Processing: Decimation...**. This opens the **Decimation: decimate** dialog box.
4. In the dialog, set **Resample Factor** to **12**. Set the **Filter Type** to **Moving Average Filter**. To preview the result in the right panel, check the **Auto Preview** check box.




5. Click **OK** to output results.
6. In the worksheet, select column D (the X column generated from the result), then right-click and choose **Insert** from the shortcut menu to insert a new column. Right click again and choose **Set As: Y** to change the column's plot designation as Y.
7. Highlight the newly inserted column and right click on it and choose **Set As: X** from the context menu to change this column's plot designation to X. Right-click on the column again and choose **Set Column Values...** to bring up the **Set Values** dialog box and enter `data(1749, 1749 + 255)` into the text box and and click **OK**.



8. Select column A, then right-click to choose **Set As: X** from the shortcut menu, to set the column's plot designation back to X. The final worksheet will look similar to the one below.



9. Press CTRL and select columns C and E. From the menu, choose **Plot: Multi-Panel: Vertical 2 Panel** to make a graph. Note that the decimated line looks smoother as the image below shows.




4.3.11.4 Signal Envelope


1. Start with a new workbook.
2. Select menu item **File: Import: Single ASCII...** to import the data <Origin Installation Directory>\Samples\Signal Processing\Gaussian Envelope.dat.




3. Highlight column B and from the menu choose **Plot: Line: Line** to create a line plot.



4. With this graph active select **Analysis: Signal Processing: Envelope...** from the menu. This opens the **Envelope: envelope** dialog box.
5. In the dialog box, set **Envelope Type** to **Both Envelopes**, and **Smooth Points** to **10**. Check the **Auto Preview** box to preview the result in the right panel.



6. Click **OK** to create the graph showing upper and lower envelope curves.



4.3.12 Rise Time

4.3.12.1 Summary

In a step-like signal, rise time refers to the time required to change from a specified low value to a specified high value (or from a specified high value to a specified low value in the case of fall time). Origin's rise time tool allows you to graphically select a rectangular area tracing a rising or falling step in the signal, and from it calculate the rise time or fall time for this selected step.


4.3.12.2 What You Will Learn

With this tutorial, you will learn how to:


1. Use the Rise Time gadget tool to calculate the fall time.
2. Change the settings for fall time calculation.
3. Set the display elements on the graph.
4. Select the desired output options and output the result to worksheet.

4.3.12.3 Steps


1. Start a new workbook.
2. Select menu **File: Import: Single ASCII...** to import the data file **<Origin Installation Directory>\Samples\Signal Processing\Step Signal with Random Noise.dat**.



3. Highlight column B and make a line plot of it by selecting **Plot: Line: Line** from the menu.




4. Click the **Scale In** (🔍) button on the **Tools** toolbar, then select a range along the X axis from about 500 to 700, so that we can focus on this portion of the plot.




5. With the graph active, choose **Gadgets: Rise Time...** from the menu to launch the tool.


6. In the dialog box, click the **ROI Box** tab and set **X Scale From** to **510** and **To** to **650**. Set **Tool** to **Fall Time** and **Method** to **Histogram**.




7. Click the **Fall Range** tab and change **From (%) of Step Height** to **20** and **To (%) of Step Height** to **80**.




8. Click the **Quantities** tab, check only three check boxes: **Dataset Name(name)**, **Fall Range(dVref)** and **Fall Time(dT)**.




9. Click the **Output To** tab, clear **Script Window** and check **Append to Worksheet**.



10. Click the **Display on Graph** tab, expand the **Indicator** branch, and change **Edge Color** to **Blue**. Check **Fall Range**.




11. Click **OK** to add the rectangular region-of-interest (ROI) to the graph.




12. As the above image shows, the two red horizontal lines delineate the upper level and lower level. The vertical distance between the two blue lines is the fall range, shown by the two indicator points on the line plot. At the top of the rectangle, the fall time and fall range are reported.


- Click on the triangle button in the upper-right corner of the ROI to open a menu and select **Fix ROI Position**, so that the yellow ROI rectangle is locked in place.



- Open the menu again and click **New Output** to output the results. Open the menu again and choose **Go to Report Worksheet**.



15. The report worksheet is activated and we can see that the three parameters that we chose on the **Quantities** tab are reported.



	A	B	C
Long Name	Dataset Name(name)	Fall Range(dVref)	Fall Time(dT)
Units			
Comments			
1	[StepSignalwit]"Step ...	1.30755	0.69596
2			
3			
4			
5			
6			
7			
8			
9			

4.3.13 Sound Processing

4.3.13.1 Summary

Origin features some useful signal processing tools, such as smoothing, FFT filtering, and spectral analysis tools like the Fast Fourier Transform (FFT) . These can be useful for performing sound analysis. This tutorial will remove a specific noise from an audio signal (.WAV file) based on the spectral range of the noise.

Minimum Origin Version Required: Origin 9 SR0

4.3.13.2 What You Will Learn

1. Import a sound file (.WAV) into Origin.
2. How to view sampling interval information.
3. How to use FFT gadget to check the frequency spectra of a signal.
4. Perform FFT filter on the audio signal.
5. Export a filtered signal as a .WAV file.


4.3.13.3 Steps

In this tutorial, we will use "Origin8 Message.wav" and "Dial Tone.wav" which can be found under the subfolder "\\Samples\\Signal Processing\\" of the Origin installation folder.


Play the sound file "Origin 8 Message.wav" and you will hear a dial tone noise in the background. The 2nd file is a recording of the dial tone.

1. Start Origin, and create a new project with an empty worksheet in a workbook.


2. Select menu **File: Import: Sound (WAV)...** to open the **Sound** dialog. (Hint: if this menu item is not shown, select menu **File: Import: Customize...** to open the **Import Menu Customization** dialog to add it.) Navigate to the "\\Samples\Signal Processing\" folder and double click "Origin 8 Message.wav" and "Dial Tone.wav" to add them to the import list. Make sure **Show Options Dialog** is checked and click **OK**.



3. In the **Import and Export: impWav** dialog, click the triangle button to the right of **Dialog Theme**, and select *System Default* from the context menu. Then expand **Import Options** node, change **Multi-File (except 1st) Import Mode** to *Start New Sheets*.




4. Click **OK** to import the two sound files into two




worksheets:

5. In each worksheet, we can see the **Sampling Interval** has the same value of $2.26757E-5$ (second). Click the *i* icon in the top left corner of the column and the **Column additional**



information dialog pops up with the sampling interval information. Click **OK** to close this dialog.




6. With **Dial Tone** worksheet activated, highlight column A, and select menu **Plot: Line: Line** to make a line plot.




7. Using this graph, select menu **Gadgets: FFT...** to open the **Data Exploration: addtool_curve_fft** dialog. Using the default settings, click **OK** button to perform an FFT of the data and create the **FFTPREVIEW** graph with the results.



8. Uncheck the **Log Scale** checkbox on the **FFTPREVIEW** graph, and then select menu **Graph: Rescale to Show All** to rescale the graph. We can see that the distribution of frequency is mainly under 2000 Hertz with the largest peaks being under 500 Hertz.



9. Activate the worksheet **Origin 8 Message** and highlight column A. Select menu **Analysis: Signal Processing: FFT Filters** to open the **Signal Processing: fft_filters** dialog. In the dialog, change **Recalculate** to *None*, select **High Pass** for **Filter Type**, uncheck the **Auto** checkbox for **Cutoff Frequency** and change value to 500. Clear **Keep DC Offset** checkbox. We can auto preview the result by ticking the **Auto Preview** checkbox at the bottom, and the result will be shown in the right panel, which can be shown or hidden by using the button in the bottom right corner of the left panel.




Note: If **Recalculate** is not *None*, the results need to be copied to new columns without the recalculate lock for changing the **Data Type**, see step 11 below.


10. Click **OK** to generate the results. We can see that the filtered result is in floating point format. In order to create a new WAV file, we need to convert this to an integer format.

	A(Y)	B(Y)	C(X1)	D(Y1)
Long Name	Origin 8 Message		Filtered X1	Filtered Y1
Units				
Comments				500 Hz High Pass fft filter of "Origin 8 Message"
Sampling Interval	2.26757E-5 (second)			
Sparklines				
1	126		0	60.05184
2	112		2.26757E-5	41.48331
3	120		4.53515E-5	45.0095
4	112		6.80272E-5	32.64136
5	122		9.07029E-5	38.38947
6	134		1.13379E-4	46.26404
7	130		1.36054E-4	38.27481
8	144		1.5873E-4	48.43108
9	106		1.81406E-4	6.74163

11. Highlight column D (the filtered result column), and then choose **Properties...** item from the right-click context menu, to open the **Column Properties** dialog. In this dialog, expand **Options** node, set **Format** to *Numeric*, then change **Data Type** to *Short(2)*. Click **OK** to apply these settings to column D and close this dialog.



12. Keeping column D highlighted, select menu **File: Export: Sound (WAV)...**. In the open dialog, enter a file name (such as *Origin 8 Message_filtered.wav*) and save to a familiar location. Make sure the **Show Options Dialog** checkbox is ticked.
13. Click **Save** button and the **Import and Export: expWAV** dialog pops up. Clear the **Auto** checkbox for **Column**, and change it to 4.



Note: The **Column** is specified for the Y column, and Origin will find its sampling interval if exists or its associated X column. If no X column or the X column is not even spacing, there will be error messages.

14. Click **OK** to export column D as a wave file. Now you can play this wave file and hear that the dial tone has been removed. Note that information with the same spectra as the dial tone is also removed.

4.4 Peak Analysis

4.4.1 Create and Subtract Baseline with Peak Analyzer

4.4.1.1 Summary

In OriginPro, the **Peak Analyzer** is capable of creating and subtracting baseline. There are various ways for baseline creation. You can generate baseline anchor points automatically or manually and then connect them with interpolation or fit them with a function.

Minimum Origin Version Required: 2016 SR0


4.4.1.2 What you will learn

- How to create baseline with 2nd Derivative method
- How to create baseline with Asymmetric Least Squares (ALS) Method (Pro)
- How to subtract a baseline from the spectrum

4.4.1.3 Steps


Create baseline with 2nd Derivative method

1. Start a **New Workbook** and import the `<Origin EXE Folder>\Samples\Spectroscopy\Baseline.dat`. Highlight the second column. In the main menu, select **Analysis: Peaks and Baseline: Peak Analyzer** to open the dialog of the **Peak Analyzer**.
2. In the first page (the **Goal** page) of the **Peak Analyzer**, select **Create Baseline** as **Goal**. Click **Next** to go to the **Baseline Mode** page.




- Next we are going to create a user defined baseline for this spectrum by defining anchor points. On the **Baseline Mode** page, select **User defined** from the **Baseline Mode** dropdown list. Check on **Snap to Spectrum** to make sure when you add or move a baseline anchor point, it will be pulled back onto the spectrum.
- The first two methods in **Anchor Points Finding** are the most commonly used, and they can find anchor points automatically based on the derivative of the spectrum. If the baseline is approximately constant, **1st Derivative and 2nd Derivative** is more powerful, otherwise, we should use **2nd Derivative**. In this example, the baseline is more curly, so we use **2nd Derivative** method for locating anchor points.

For other methods in **Anchor Points Finding** and related smoothing parameters, you can refer to the link: [Baseline Mode Page](#).



- Now click the **Find** button in the **Baseline Anchor Points** group. You can preview the anchor points in preview window.



- Click **Next** to go to the **Create Baseline** page, select **Interpolation** in the **Connect by** drop-down list. In **Interpolation** method group, select **Spline** from the drop-down list. You can preview the spectrum in preview window, and then click **Finish** to get the baseline data.

Connect by Interpolation

Snap to Spectrum

Baseline Anchor Points Add Modify/Del


Number of Baseline Points 1501 Same as Input Data

Interpolation Method

Line


Spline

BSpline




Create baseline with ALS Method (Pro)

1. Start from the **Baseline Mode** page, and select the **Asymmetric Least Squares Smoothing Baseline** (ALS) as the baseline method. The ALS baseline can be tuned easily with a few parameters without pre-selecting any anchor points.





2. Click **Next** go to **Asymmetric Least Squares Smoothing Baseline** page, adjust the parameters to make the baseline optimal, then click **Finish** button to output the results table and graph.



Subtract Baseline from a Spectrum

1. If you want to subtract baseline, select **Subtract Baseline** as the **Goal** at start page.
2. After you created a baseline, click **Next** button to go to **Subtract Baseline** page.
3. Click **Subtract** button for previewing the subtracted data. The baseline data and subtracted spectrum will be outputted after clicking **Finish** button. The figures below displayed the **Subtract Baseline** page and the preview of the subtracted spectrum.



4.4.2 Use Script to Search for Baseline Anchor Points in Peak Analyzer

4.4.2.1 Summary

In OriginPro, the **Peak Analyzer** is capable of creating and subtracting baseline. You can create a baseline by finding baseline anchor points first and then connect those anchor points either by interpolation or by fitting. To search for those baseline anchor points, you can either use built-in methods or define the search method on your own using LabTalk scripts.


4.4.2.2 What you will learn

- How to create baseline with user-defined scripts
- How to integrate peaks from user-defined baseline

4.4.2.3 Steps

Create baseline with User-Defined Scripts

1. Start a **New Workbook** and import the *<Origin EXE Folder>\Samples\Spectroscopy\Chromatography\Liquid chromatogram.dat*. Highlight the second column. In the main menu, select **Analysis: Peaks and Baseline: Peak Analyzer** to open the dialog of the **Peak Analyzer**.
2. Make sure **Goal** is selected as **Integrate Peaks** and click **Next** button to go to **Baseline Mode** page.
3. Select **Baseline Mode** as **User Defined** and continue to select **Anchor Points Finding Method** under **Baseline Anchor Points** node as **Use Script to Search**.
4. Enter *apt_x* and *apt_y* in **X=** and **Y=** edit boxes, respectively. Then paste the scripts shown below into **Before Formula Script** box. Click **Find** button will run the scripts and the detected baseline anchor points will display on the preview window.



```
Dataset dspos;
```

```
pkfind iy:=(dsx, dsy) dir:=p npts:=5 value:=200 ocenter:=dspos; // Find major peak positions
```

```
int npk=dspos.GetSize(); // Get major peak numbers
```

```
// Create datasets to store anchor points
```

```
int nn = dsx.GetSize(); // Get source X size
```

```
dataset apt_x, apt_y; // Create datasets to store anchor points
```

```
apt_x.SetSize(npk+1); // Set anchor points number
```

```
apt_y.SetSize(npk+1);
```

```
apt_x[1] = dsx[1]; // Set 1st data point as 1st anchor point
```

```

apt_y[1] = dsy[1];

apt_x[npk+1] = dsx[nn]; // Set last data point as last anchor point

apt_y[npk+1] = dsy[nn];

for (ii=1; ii<=npk; ii++)

{

int  istart = dspos[ii]; // Get row index of ii-th peak

int  iend = dspos[ii+1]; // Get row index of the next peak

range rtemp = [??]!dsy[$(istart):$(iend)]; // Declare the range and point to the
loose dataset

limit rtemp; // Get stats of the subrange

int  ind = limit.imin; // Get min Y row index

apt_y[ii+1]=limit.ymin; // Get min Y between two peaks as anchor point

apt_x[ii+1]=dsx[ind];

};

```

The script will firstly find all major peak positions and then treat the minimum between every two adjacent peaks as one baseline anchor point, then add the first and last data points as two baseline anchor points.

Note: You can still uncheck **Enable Auto Find** checkbox and then use **Add** or **Modify/Del** to add or remove baseline anchor points.

5. Click **Next** button to go to **Create Baseline** page, make sure **Connect by** is selected as **Interpolation** and the **Interpolation Method** is **Line**. Then click **Finish** to obtain integration areas for each peak.

4.4.3 Batch Peak Analysis Using Theme with Script Before Each Process

4.4.3.1 Summary

Origin can perform batch peak analysis of multiple datasets using an [Analysis Theme](#). You can choose to pre-process the peak data, e.g., exclude unwanted datasets, before actually input it for peak analysis using script specified before each process.

Minimum Origin Version Required: 2016 SR0

4.4.3.2 What Will You Learn


This tutorial will show you how to:

- Save analysis settings as a theme for batch peak analysis
- Writing script before each process to pre-process data
- Batch peak analysis using an analysis theme

4.4.3.3 Steps

Save Analysis Settings as a Theme

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open **Tutorial Data.opj** and browse to the **Script Before Process in Batch PA** folder in **Project Explorer (PE)**.
2. With the project open, browse to the folder *Script Before Process in Batch PA*.
3. Click on worksheet **Data1** in workbook with title **Sample - Spectrum and Noise Mixed** to activate source data sheet.
4. Highlight column *B* and go to menu **Analysis: Peaks and Baseline: Peak Analyzer** to open dialog. Select **Fit Peaks(Pro)** as **Goal**.
5. Click **Next** button, select **None(Y=0)** as **Baseline Mode**. Click **Next** button twice to go to **Fit Peaks(Pro)** page, expand **Configure Graph** subnode under **Result** node and set **Create Report Graph** to **<None>** to turn off generating report graph, which can speed up the analysis process.
6. Now click the  button next to the **Dialog Theme** control and select **Save as ...** to open **Theme Save as...** dialog. In the **Theme Name** edit box, enter *MyPeakAnalysis* and click **OK** button to save it.
7. Click **Finish Button** to perform the analysis and output results.

Prepare Script for Pre-processing Peak Data

The **Batch Peak Analysis Using Theme** dialog provides three edit boxes to allow running script before each process, after each process and at the end of all processes. In this section we will mainly show how to write script before each process to pre-process the peak data.

1. Activate worksheet **Data1** again, we can see from the sparkline of each dataset that some of peak data are very noisy, e.g., column *C*, *E*, *F*, and we want to exclude such noisy dataset if it reaches certain noise level.
2. The way used to identify whether data is noisy in this tutorial follows the routine below:

- Filter raw data with a high-pass FFT filter to obtain the high-frequency noise from the data.
- Find the standard deviation(SD) of the noise and the corresponding raw data.
- Set a criteria that if the ratio of the square of SD of the noise over the square of SD of the raw data is over 30%, it will be regarded as noisy data and will be excluded for batch analysis.

3. Follow the routine above, the script for pre-excluding noisy data is as following:

```
dataset dr;

fft_filters iy=_ry filter:=high oy:=dr; // Perform high-pass fft filter to obtain
noise

stats dr;

double nSD = stats.sd; // Calculate SD of noise

stats _ry;

double sSD = stats.sd; // Calculate SD of raw data

if(nSD^2/sSD^2>0.3) // Set noise identification criteria

    _skip=1;


else

    _skip=0;
```

where *_ry* refers to current y data, *_skip* determines whether to skip current dataset.

Batch Analyze Datasets Using Analysis Theme

1. Activate worksheet **Data1**, highlight all columns in the sheet and go to menu **Analysis: Peaks and Baseline: Batch Peak Analysis Using Theme...** to open dialog.
2. Select *MyPeakAnalysis* from **Theme** drop-down list, **Peak Properties(Pro)** from **Result Sheet** drop-down list.
3. To output results to a specified sheet, you can enter the range syntax in **Output Sheet** edit box. Suppose we want to export to *MyResults* sheet in *MySummary* book, you can input *[MySummary]MyResults!* in the edit box.
4. Input the script we wrote in section above into **Script Before Each Process** under **Script** node.



5. Click **OK** button to perform batch peak analysis and you will see noisy datasets are excluded in **MyResults** sheets.

	A(Y)	B(Y)	C	D(Y)	E(Y)	F(Y)	G(Y)	H(Y)	I(Y)	J(Y)
Long Name	Dataset	Peak Index	Peak Type	Area Fit	Area FIT	Area FitTP	Center Max	Center Grv	Max Height	FWHM
1	[Sample]Data1!(A,B)	1	Gaussian	62.965	62.96315	26.83319	1.00146	1.00146	111.9851	0.5282
2	[Sample]Data1!(A,B)	2	Gaussian	#####	#####	52.29279	3.99952	3.99952	#####	0.7740
3	[Sample]Data1!(A,B)	3	Gaussian	48.98016	48.98016	20.87402	6.99981	6.99981	#####	0.2484
4	[Sample]Data1!(A,D)	1	Gaussian	66.69304	66.69304	11.37578	1.2	1.2	#####	0.2873
5	[Sample]Data1!(A,D)	2	Gaussian	#####	#####	30.09453	3.8	3.8	#####	0.3611
6	[Sample]Data1!(A,D)	3	Gaussian	#####	#####	38.35519	6.3	6.3	#####	0.1950
7	[Sample]Data1!(A,D)	4	Gaussian	#####	#####	20.1744	8.8	8.8	#####	0.1950
8	[Sample]Data1!(A,G)	1	Gaussian	93.24854	93.24854	30.21961	1.8	1.8	#####	0.7235
9	[Sample]Data1!(A,G)	2	Gaussian	#####	#####	39.84866	5	5	#####	0.6582
10	[Sample]Data1!(A,G)	3	Gaussian	92.36032	92.36026	29.93173	8	8	89.14607	0.9730
11	[Sample]Data1!(A,H)	1	Gaussian	#####	#####	45.4566	2.49826	2.49826	#####	0.5965
12	[Sample]Data1!(A,H)	2	Gaussian	#####	#####	54.5434	7.50242	7.50242	#####	0.9573

4.4.4 Combine Quick Peaks Gadget with Peak Analyzer

4.4.4.1 Summary

The Quick Peaks gadget provides an intuitive way to carry out peak analysis, and Peak Analyzer provides further options for peak finding, fitting, etc. You can first use Quick Peaks gadget to find peaks and then use the Peak Analyzer to analyze the peaks. You can save the whole analysis as a theme in the Peak Analyzer for future use and/or batch processing.

Minimum Origin Version Required: OriginPro 9.0 SR0


4.4.4.2 What You Will Learn

This tutorial will show you how to:


- Use the Quick Peaks gadget to find peaks.
- Open the Peak Analyzer from Quick Peaks gadget.
- Further analyze the peaks found in Quick Peaks gadget using the Peak Analyzer.

4.4.4.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open **Tutorial Data.opj** and browse to the **Quick Peaks Gadget** folder in **Project Explorer (PE)**.
2. Highlight all columns in the **Nitrate** worksheet and click the  button on **2D Graph** toolbar to generate a line graph.
3. Activate the generated graph window and select **Gadgets:Quick Peaks**.


4. In the **ROI box** tab, change the **From** and **To** values of X scale to **34.75** and **35** respectively, select the **Fixed(Prevent moving by ROI)** check box.




5. In the **Baseline** tab, select the **Full Plot Range** radio button for **Range**.




- In the **Find Peak** tab, change the **Method** for **Peak Filtering** to **By Number**, and set the **Number of Peaks** as **3**, select **Blue** as the color of the **Peak Label**.





- In the **Output to** tab, change the **Result Worksheet Name** to **[QkPeak]%C_Result2**.



8. In the **Quantities** tab, you can decide which quantities to output. Leave only the check boxes for **Peak ID**, **Peak X**, **Peak Y**, **Height**, **Peak Area** and **FWHM** checked, and clear the other check boxes. Click **OK** to add the gadget to the plot.





9. Click the triangle button  to the right of the ROI box and select **New Output** to generate the report worksheet.
10. Bring up the context menu again to select **Go to Report Worksheet** to open the result worksheet.




	A	B	C(X)	D(Y)	E(Y)	F(Y)	G(Y)
Long Name	Dataset Name	Peak ID	Peak X	Peak Y	Height	Peak Area	FWHM
Units							
Comments					Peak Height from Baseline		
1	[Nitrite]Nitrite!(Time,Voltage)	Peak 1	34.801	339.64548	142.39745	0.59145	0.00321
2	[Nitrite]Nitrite!(Time,Voltage)	Peak 2	34.8695	341.8306	143.77188	0.63798	0.0036
3	[Nitrite]Nitrite!(Time,Voltage)	Peak 3	34.9358	338.89009	139.8831	0.61917	0.00371

11. Now we are going to open the Peak Analyzer to carry out peak fitting. Bring up the context menu and choose **Switch to Peak Analyzer**.



12. The Peak Analyzer is opened, the **Fit Peaks** goal is already selected, the baseline mode and peak finding method follow the settings in the Quick Peaks gadget.
13. Go to the **Fit Peaks** page directly and click the **Fit** button to fit the three found peaks with default Gaussian function.
14. Click the  button and select **Save As** in the context menu to save this analysis as a theme with the name **MyQuickPeaks**.



15. In the Peak Analyzer, click the **Finish** button to generate the peak fitting results.

Notes: The theme can be used in the batch peak analysis. Select **Analysis:Peaks and Baseline:Batch Peak Analysis using Theme** to open the **paMultiY** dialog. The batch peak analysis is very useful when you have multiple data files that are similar. You can refer to [this example](#) for more details.

4.4.5 Peak Finding

4.4.5.1 Peak Finding

- [Picking and Marking Peaks](#)

4.4.5.2 Picking and Marking Peaks

Summary

The Peak Analyzer provides several methods to pick peaks automatically. Also, user can opt to add/delete/modify the peaks manually.

Labels are added to the peak centers after they are found or added, to show user the positions of the current peaks.

Minimum Origin Version Required: Origin 8.0 SR6

What you will learn


- How to use and customize the auto peak finding in the Peak analyzer
- How to customize the labels for the peak centers

Steps

1. Start a new workbook and import the file <Origin Program Folder>\Samples\Spectroscopy\HiddenPeaks.dat.
2. Highlight the second column.
3. Create a line plot by selecting **Plot: Line: Line**.
4. With the graph active, select **Analysis: Peaks and Baseline: Peak Analyzer** to open the dialog of the Peak Analyzer.
5. In the first page (the **Start** page), select the **Find Peaks** radio button in the **Goal** group. Then click the **Next** button to go to the next page.




6. In the **Baseline Mode** page, select **None(Y=0)** for **Baseline Mode**.




Click the **Next** button to go to the **Find Peaks** page.

7. In the **find Peaks** page:


1. Expand the **Peak Finding Settings** branch. Make sure that **Local Maximum** is selected for **Method**. Then click the **Find** button. Only five peaks are detected.



2. Change **Method** to **2nd Derivative (Search Hidden Peaks)**. Click the **Find** button again. This time, seven peaks are detected.



3. Click **Finish** to complete the analysis. We will get this final graph:



4.4.6 Peak Integration

4.4.6.1 Peak Integration

- [Integrating Peaks](#)

4.4.6.2 Integrating Peaks

Summary

Use the Peak Analyzer to integrate peaks and find their areas.

Minimum Origin Version Required: Origin 8.0 SR6


What you will learn

- How to pick an existing dataset as baseline
- How to subtract a baseline from the spectrum data
- How to calculate peak areas with the Peak Analyzer

Steps


1. Start a new workbook and import the file *\\Samples\Spectroscopy\Peaks with Base.DAT*.

2. Highlight the second column.




3. In the main menu, click **Analysis**, then point to **Peaks and Baseline**, and then click **Peak Analyzer**.

4. In the first page (the **Goal** page) of the **Peak Analyzer**, select **Integrate Peaks** in the **Goal** group. Click **Next** to go to the **Baseline Mode** page.




5. On the **Baseline Mode** page, select **Use Existing Dataset** from the **Baseline Mode** dropdown list. Click the **triangular button** to the right of the Dataset dropdown menu, and then select **[PeakswithBase]\"Peaks with Base\"!C\"Base\"** on the fly-out menu. Click **Next** to go to the

Baseline Treatment page of the Peak Analyzer.




6. Select the **Auto Subtract Baseline** check box. Click the **Integrate Peaks** page icon in the upper panel (or click **Next** twice to go to the Integrate Peaks page). In the preview graph, you will see

two numbered yellow rectangles representing two peaks found with the default settings.




7. For **Integration Window Width**, select **Adjust on Preview Graph**. On the graph, click inside the rectangle marked with 1. A pair of "handles" appears on either side of the yellow integration window. Drag these handles to adjust the range for which integration will be performed. Click

inside the rectangle marked with **2** and adjust the integration range for the second peak.



- In the **Integrate Peaks** page of the Peak Analyzer, make sure all the desired quantities to compute have been selected in the **Quantities** group. For example, if you want to calculate the peak centroid for each peak, select the **Peak Centroid** check box. If you don't want to output the percent areas, clear the **Percent Area** check box. When you are done, click **Finish** to perform the analysis.



The result is in a worksheet named *Integration_Result1*.

	Index	Area	Row Index	Beginning X	Ending X	FWHM	Center	Height	Centroid
1	1	26.62295	93	77	119	13.16915	103	1.87906	102.12429
2	2	-27.62137	267	249	293	13.28994	277	-1.9043	275.88972
3									

If the Area check box was selected in the Quantities group, peak area data appears in the Area column of the result worksheet.

4.4.7 Peak Fitting

4.4.7.1 Peak Fitting

- [Peak Fitting with Baseline](#)
- [Peak Fitting with Preset Peak Parameters](#)
- [Setting the Fix, Share Status or Bounds for Multiple Peak Parameters Simultaneously](#)

4.4.7.2 Peak Fitting with Baseline

Summary

In OriginPro, the **Peak Analyzer** is capable of performing multiple peak fitting with several baseline subtraction options.

There are various ways to create a baseline for your spectrum data. You can select a few anchor points and then fit them with a function. The fitting of the baseline can be done along with the peak fitting.


Minimum Origin Version Required: OriginPro 8.0 SR6

What You Will Learn

- How to perform fitting of peaks
- How to fit the baseline

Steps

1. Start a new worksheet and import the file <Origin Program Folder>\Samples\Spectroscopy\Peaks on Exponential Baseline.dat.
2. Highlight the second column in the worksheet.




The screenshot shows a software window titled "PeaksonExpone - Peaks on Exponential Baseline.dat". The window displays a worksheet with two columns: "A(X)" and "B(Y)". The "B(Y)" column is highlighted. A sparkline plot is visible in the background, showing a peak at approximately X=10. The data points are as follows:

	A(X)	B(Y)
Long Name	Channel	Amplitude
Units		
Comments		
F(x)		
Sparklines		
1	10	4.24
2	11	4.16
3	12	4.09
4	13	4.02
5	14	3.95
6	15	3.89
7	16	3.81
8	17	3.74


3. Select **Analysis: Peaks and Baseline: Peak Analyzer** from the main menu to open the **Peak Analyzer**.

4. Select the **Fit Peaks** radio button in the **Goal** group on the first page. Click **Next** to go to the **Baseline Mode** page.




5. In the **Baseline Mode** page, select **User Defined** from the **Baseline Mode** drop-down list. Click the **Find** button in the **Baseline Anchor Points** group. Eight anchor points should be found.

Then click **Next** to go to the **Create Baseline** page.




6. In the **Create Baseline** page, select **Fitting** with the **Connect By** drop-down list. In the **Fitting** group, select **ExpDec2** from the **Function** drop-down list. Click **Next** to go to the **Baseline**


Treatment page.



7. In the **Baseline Treatment** page, select the **Fit Baseline with Peaks** check box. Click **Next** to go to the **Find Peaks** page.




- In the **Find Peaks** page, click the **Find** button to search peaks. Two peaks should be found. Then click **Next** to go to the **Fit Peaks** page.



- In the **Fit Peaks** page, click the **Fit Control** button to open the **Peak Fit Parameters** dialog.

10. In the **Peak Fit Parameters** dialog, make sure that both peak types are Gaussian. Click the **Fit Until Converge** button. When the fitting is done, click **OK** to close the dialog.



11. Back in the **Fit Peaks** page, click **Finish** to complete the analysis. See the results in the source workbook and the graph report.

4.4.7.3 Peak Fitting with Preset Peak Parameters

Summary

In some cases, you may want to perform peak fitting with preset peak parameters. For example, you may have many datasets with fixed numbers of peaks and the centers of these peaks do not vary from dataset to dataset. What you are interested in is mainly other parameters of the peaks, for example, heights. Using the theme feature of the Peak Analyzer, you may carry out peak fitting with fixed peak parameters easily.

Minimum Origin Version Required: OriginPro 2016 SR0

What You Will Learn


1. How to save Peak Analyzer settings in a theme and reuse them
2. How to fix peak parameters

Steps


Save a theme with peak positions and peak parameters

1. Start a new worksheet and import the file <Origin Program Folder>\Samples\Spectroscopy\HiddenPeaks.dat.

2. Highlight the second column and select **Analysis: Peaks and Baseline: Peak Analyzer** from the Origin menu to open the **Peak Analyzer**.



3. On the first page, select the **Fit Peaks** radio button in the **Goal** group. Click **Next** to go to the **Baseline Mode** page.




4. In the **Baseline Mode** page, select **None (Y=0)** with the **Baseline Mode** drop-down list. Click **Next** to go to the **Find Peaks** page.




5. In the **Find Peaks** page:

- a. Clear the **Enable Auto Find** check box, because we want to find the peaks manually. Click the **Peaks Info** button to open the **Peak Info** dialog.




- b. In the **Peak Info** dialog, click the **Add** button seven times to add 7 peaks. Enter the peak centers and heights as follows:



Click **OK** to return to the Peak Analyzer.

- c. Click **Next** to go to the **Fit Peaks** page.
6. In the **Fit Peaks** page:
 - a. Click **Fit Control** to open the **Peak Fit Parameters** dialog.
 - b. In the **Peak Fit Parameters** dialog, click the **Fix or release all peak centers** button. Then click the **Fit Until Converge** button. When the fitting is done, click **OK** to return to the **Peak Analyzer** dialog.



- c. Click the right-sided triangle button to the right of **Dialog Theme** in the upper panel. Select **Save As** from the short-cut menu. The **Theme Save as** dialog opens.

- d. In the **Theme Save as** dialog, enter **MyFitting** after **Theme Name**. Clear and select the check boxes as the screenshot below:




Click **OK** to save the theme. This should bring you back to the **Peak Analyzer** dialog.

- e. Click the **Finish** button in the **Peak Analyzer** to complete the analysis.

Reuse the theme

1. Start another new workbook and import the file <Origin Program Folder>\Samples\Spectroscopy\HiddenPeaks.dat.

2. Highlight the second column
3. Select **Analysis: Peaks and Baseline: Peak Analyzer** from the Origin menu to open the **Peak Analyzer** dialog.
4. On the first page of the **Peak Analyzer**, click the right-sided triangle button to the right of **Dialog Theme**. From the short-cut menu, pick **MyFitting**.



5. Click **Next** to check if the settings in every step are correct. Note that in the **Find Peaks** page, you can see the peak centers and heights are same as last time.
6. When you reach the last page, click the **Fit Control** button to open the **Peak Fit Parameters** dialog. Make sure that all peak centers are fixed and the values are the same as last time. Click **OK** to return to the **Peak Analyzer**.
7. Click **Finish** to complete the analysis. Check the results to see whether they are the same as the results we got last time.

4.4.7.4 Setting the Fix, Share Status or Bounds for Multiple Peak Parameters Simultaneously

Summary

When performing peak analysis, one often wants to fix parameter values, or share parameters between multiple peaks, or specify bounds. If your data has a few peaks, you can simply perform these settings for each peak. But if your data has many, it may be time consuming to set individually. To make the process more efficient, the **Peak Analyzer** offers context menus which can allow you to set the fix, share status or bounds for multiple peak parameters simultaneously. For more details about these settings, please refer to the Origin Help File.


Minimum Origin Version Required: OriginPro 8.0 SR6

What You Will Learn


- How to set share status of multiple peak parameters simultaneously.
- How to set upper bounds and upper bound values to multiple peak parameters simultaneously.

Steps


1. Start a new workbook and import the file *<Origin Program Folder>\Samples\Spectroscopy\Positive & Negative Peaks.dat*.
2. Highlight the second column and select **Analysis: Peaks and Baseline: Peak Analyzer** to open the **Peak Analyzer** dialog. In the first page (the **Start** page), select the **Fit Peaks** radio button in the **Goal** group. Then press the **Next** button to go to the next page.
3. In the **Baseline Mode** page, select **Constant** with the **Baseline Mode** drop-down list and choose **Mean** in the **Constant** group. Then click **Fit Peaks** in the wizard map to directly go to the **Fit Peaks** page.




4. In the **Fit Peaks** page:
 1. click **Fit Control** button to open the **Peak Fit Parameters** dialog. In the lower left corner of the dialog, set the fitting function to **Voigt**.
 2. Make sure the **Parameters** tab is active and then select **1** in the **Share** column of the **wG_1** row. Then right click on it and select **Apply Same "Share" to All wG**. Then you will find that all the parameters with the **wG** prefix are shared in the same group.




- Then select **2** in the **Share** column of the **wL_1** row. Then right click on it and select **Apply Same "Share" to All wL**. Then you will find that all the parameters with the **wL** prefix are shared in the same group. After this, the **Parameters** tab should look like below:



4. Activate the **Bounds** tab. Double-click in the cell in the first **Gaussian width** row and the second **< or <=** column. And you will find **<=** is shown in this cell (the **<** will be shown if you double-click in the cell for one more time). Then type **5** into the **Upper Bounds** column in the same row.
5. Then right click on it and select **Apply Same "Bounds" to All wG**.



After this, the **Bounds** tab should look like:



- Click the **Fit Until Converged** button. When the fitting is done, click **OK** to close the dialog.
- Back in the **Fit Peaks** page, click **Finish** to complete the analysis. See the results in the source workbook and the graph report.

4.5 Data Manipulation

4.5.1 Setting Column Values

- [Setting Column Values](#)

4.5.1.1 Setting Column Values

Summary

Origin provides several ways to fill a worksheet column with values. Use **Auto Fill** or script commands to fill a series of values. Use the **Set Values** dialog box to define a mathematical formula to generate or transform a data set. Refer to values in other columns from the same sheet or from

other sheets and books. Select from a large collection of built-in functions to compute values. Create variables from metadata stored in worksheets or column headers, and use these variables in your column formula.

This tutorial will show you how to compute column values by:


- Filling a Column with an Arithmetic Series
- Using Built-in Functions
- Using Other Columns
- Using Cell Values
- Using Variables from Workbook Metadata

Filling a Column with Arithmetic Series

Origin provides multiple methods to fill a column with arithmetic series.


Using Auto Fill

1. Enter a few starting values in cells.




	A(X)	B(Y)
Long Name		
Units		
Comments		
F(x)		
1	1	1
2	3	
3		
4		
5		
6		
7		
8		
9		
10		

2. Select the two cells.
3. Move the mouse to the bottom right-hand corner of the second cell. The cursor will change to display "+".



4. Drag the mouse toward the bottom of the column. The column will be filled with 1, 3, 5, 7,




Note that a row can also be auto filled by dragging towards the right. To repeatedly copy values instead of generating new values, hold down the CTRL key and drag the mouse toward the bottom of the column.

Using Filling A Set of Numbers

1. Right click on the column B and select **Fill Column with: A Set of Numbers** from the context menu to bring up the **PatternN** dialog
2. Enter 23 in the *To* edit box. Enter 2 in the *Increment* edit box

3. After you click the **OK** button, Column B will be filled with values: 1, 3, 5, 7,, 23

Using Data List

1. Click the **Add New Columns** button  on the Standard toolbar to add a new column C.
2. Type the following script in the Command window.

```
col(C) = {1:2:23};
```

3. Column C will be filled with values: 1, 3, 5, 7,, 23






`{v1:vstep:vn}` produces the same result as the function `data(v1,vn,vstep)`.

Using Built-in Functions


1. Create a new workbook. Import Step Signal with Random Noise.dat from the **\Samples\Signal Processing** folder.

We are going to calculate the moving average of column B, that is, calculating the adjacent average value at each point of column B.


2. Click the **Add New Columns** button  on the Standard toolbar to add a new column C. Highlight this column and right-click, and then click **Set Column Values...** to open the **Set Values** dialog.
3. In **Set Values** dialog, click the **Search and Insert Functions** button  to search for keyword *adjacent average*.




4. Double click function name **Movavg(vd,back,forward)** to insert it into dialog and close the dialog.



5. Highlight the characters **vd**. In the **wcol(1)** menu, point to **wcol(2)**, replace **back** with **0** and replace **forward** with **2**. Your formula should look like this:



- Click **OK**. The last column will fill with the moving average from column B.



When referring to another column in the same worksheet, you can use index, short name, or long name to identify the column.


Using Other Columns

We will show you how to use other columns in the Set Values dialog.

- Create a new workbook. Import US Metropolitan Area Population.dat from the **\Samples\Data Manipulation** folder.
- Add a new column to the worksheet (right-click to the right of the last column in the worksheet and select **Add New Column** from the context menu). Change the Long Name of the column to *Population/Sq. Mi.*
- Highlight this column and right-click on it. Select **Set Column Values** to bring up the dialog. Click the Col(A) menu and choose **Col("Population"):A** and then enter the / character. Click the Col(A) menu again and choose **Col("Sq. Mi.):B**. The formula should look like:
Col("Population")/Col("Sq. Mi.")
- Click OK and the column will get computed using data from the other two columns.


Using Columns from Other Sheets

The **Set Values** dialog provides an **Variable** menu to easily insert range variables that point to columns in other books/sheets, which can then be used to compute column values for the current column.

1. Open the project **Samples\Data Manipulation\Setting Column Values.OPJ** and switch to the **Columns from Other Sheets** subfolder.
2. Right-click on the worksheet tab labelled **Sample** and select **Duplicate Without Data**. Rename (by double-clicking on the current name) the new sheet as: **Corrected Sample**.
3. Now you will fill these three columns with data based on formulas that reference columns in the other sheets. Highlight the first column and right-click on it to select **Set Columns Values** to open the dialog. Select **Variables: Add Range Variables by selection** to open the **Select from Worksheet** dialog. With this dialog, you could select a column from worksheet and insert it as a range variable to the **Before Formula Script** panel.
4. When the **Select from Worksheet** dialog is open, activate the **Sample** sheet, highlight column A to select and click the  button to confirm selection and click **OK** in the appeared **Insert Mode** dialog box.
5. "range r1 = Sample!Col(A);" will be automatically inserted into the **Before Formula Scripts** panel. Please rename it as:

```
range rTime = Sample!Col(A);
```

6. **Note:** There will also be an alternative script which uses index in expression. This script is commented and will not be executed.
7. Then enter **rTime** in the **Column Formula** and click the **OK** button to generate data for the first column and close the dialog



8. Highlight column B and column C and right-click on them, select **Set Multiple Column Values** to open the dialog. Then select **Variables: Add Range Variable by Selection** and insert two range variables one by one(column B in the **Sample** and **Reference** sheet) to the **Before Formula Script** panel similarly as the previous steps. Rename them as:

```
range rSample = Sample!Col(B);
```

9. and

```
range rRef = Reference!Col(B);
```

10. Now we will edit the range variables in the **Before Formula Scripts** panel and use another expression to get the same results. Remove the column names **Col(B)** of the two range variables and select **Variables: Predefined Variables: wcol(_ThisNumCol)** in both lines so it looks as follows:


```
range rSample = Sample!wcol(_ThisColNum);
```

11.

```
range rRef = Reference!wcol(_ThisColNum);
```

12. Then input the following expression into the **Column Formula**:

```
rSample - (rSample[1] - rRef[1])
```



13.

14. Click the **OK** button to generate data for the column B and column C of the **Corrected Sample** worksheet.

	A(X)	B(Y)	C(Y)
Long Nam	Time	Transducer 1	Transducer 2
Units	sec	mV	mV
Sparklines			
F(x)	rTime	rSample - (rSample[1] - rRef[1])	
1	0	20.41	8.23
2	1	19.99	8.17
3	2	20.54	8.17
4	3	20.84	8.21
5	4	20.47	8.16
6	5	21.13	8.16
7	6	20.41	8.05
8	7	20.25	8.11
9	8	20.02	7.96
10	9	20.15	7.95
11	10	20.62	7.98



1. You reference a particular cell value with square brackets, so [1] in the formula above means the first element.
2. You can select **Formula: Save** and **Formula: Load** in the **Set Column Values** dialog to save your formulas and reload it into other columns to generate new data.

Using Cell Values

Values contained in specific worksheet cells can be referenced and used to compute the formula for setting column values. This provides an easy way to use worksheet cells as control cells for updating values in a column.

1. Open the project **\Samples\Data Manipulation\Setting Column Values.opj** and switch to the **Cells in a Worksheet** subfolder in Project Explorer.
2. Right-click on column C and select the **Set Column Values...** context menu to bring up the Set Values dialog.
3. Use the **Variables: Add Range Variable by Selection** menu item to open the **Select from Worksheet** dialog. Then select column G(Value) in this worksheet, click . Click **OK** for the appeared **Insert Mode** dialog to add its expression to the **Before Formula Scripts** panel.
4. In the **Before Formula Scripts** panel, change the name of the range variable to be **rControl** and add these additional lines so that the script looks like below

```

range rControl = Col(G);

//range r1 = Col(7);

int nOrder = rControl[2];


int nPoints = rControl[3];

differentiate -se iy:=(1,2) order:=1 smooth:=1 poly:=nOrder npts:=nPoints

oy:=(1,3);

```

5. The script calls the **differentiate** X-Function and passes the cell values from column G as arguments for polynomial order and number of points, which controls the Savitzky-Golay smoothing performed during the differentiation.
6. The **Set Values** dialog then should be as following:



7. Click **OK** to close the dialog and see the results in column C. Now you can try to change the values in column G, to change the output.

Note: Allowed values of polynomial order are 1 to 9.




The graph shown in the worksheet was first created and then embedded into the worksheet by merging a group of cells.

Using Variables from Workbook Metadata

Metadata stored in the workbook, such as variables saved when importing data using the Import Wizard, can be referenced and used for computing column values.

1. Open or continue working with **\Samples\Data Manipulation\Setting Column Values.OPJ**, and switch to the **Worksheet Metadata** subfolder from the Project Explorer window.
2. Select column A and right-click to select the **Insert** menu option. A new column is inserted to the left of column A.
3. Select the first column (this newly inserted column) and right-click on it. Then select the **Set Column Values** menu item to open the Set Values dialog.
4. Select the **Variables: Add Info Variable** menu item to open the **Insert Variables** dialog. Select **Numeric int** from the **Variable Type** drop-down list. Expand the **USER.VARIABLES** node and click to highlight **NUMBEROFPOINTS** row with **Value** as **3800**. Press the **Insert** button to insert this variable into the **Before Formula Scripts** panel.



5. Next, set **Variable Type** to **Numeric double**. Hold the **Shift** key down to select both **StartFrequencyKHz** and **StepFrequencyKHz**, and then press **Insert** to insert these two variables. Press the **Close** button to close the dialog.
6. In the upper **Column Formula** panel, input $\{d1:d2:d1+(n1-1)*d2\}$ and then press the OK button to generate data and close the dialog. The column will be filled with frequency values.
7. Highlight the first and second columns, right-click on them and select **Set As: XYY** to change the plotting designations to X and Y. After you change the long name of the first column to **Frequency**, the worksheet should look like:

	C1(X)	A(Y)	B(Y)
Long Name	Frequency	Real	Imaginary
Sparklines			
F(x)=	{d1:d2:d1+(n1-1)*d2}		
1	500	6.35	-4.39
2	500.25	5.98	-4.27
3	500.5	5.86	-3.91
4	500.75	6.23	-3.66
5	501	6.47	-3.42
6	501.25	6.47	-3.3
7	501.5	6.71	-2.69
8	501.75	6.1	-3.05
9	502	5.74	-2.32
10	502.25	6.23	-2.2
11	502.5	6.1	-1.71
12	502.75	5.86	-2.08
13	503	5.74	-2.08
14	503.25	5.37	-2.2
15	503.5	6.1	-1.92

4.5.2 Worksheet Data Operations

- [Worksheet Query](#)
- [Data Reduction](#)
- [Data Filter](#)
- [Lock Filter with Analysis](#)

4.5.2.1 Worksheet Query

Summary

This tutorial will show you how to use the **Worksheet Query** dialog.

Minimum Origin Version Required: Origin 8.5.1 SR0


What you will learn

This tutorial will show you how to:

- Extract numeric and time data
- Use an alias in an extraction condition
- Use LabTalk functions in an extraction condition

Dialog overview

Start with a new workbook and import the file `\Samples\Statistics\body.dat`, click the menu item **Worksheet: Worksheet Query** to open the dialog as follows:



Basically, there are two main panels in the **Worksheet Query** dialog. The left panel lists all the columns in the active worksheet, you can right-click and select some column properties you want to see, such as *Format*, *1st Value*, etc.


Note the **Extract** column in this panel, only data selected in the Extract checkbox will be extracted.

The right panel is where you set and test extract conditions. For example, you can select the column you want to use in the extract condition, and then click the **=>** button to move it into the **Select Column Variable for If Test** group.

Set the conditions


Extract Numerical Data

When there are available columns in the **Select Column Variable for If Test** group, the **Condition** edit box becomes editable for you to set conditions. For example, select *height* and *weight* to the group. Origin will automatically set an alias for each column. You can click into the **Alias** cell and rename the alias:




These alias can be used directly in the extract condition. Let's keep the default alias, *h* and *w* in this example.

The buttons on the right side of **Condition** edit box can be help to establish extract conditions. For example, to extract data that is no less than 160cm, highlight the column on **Select Column Variable for If Test** and click **Add...** button and build the first condition as follow:



Click **OK** to close the dialog. When there are multiple conditions, you can also combine these conditions by logical operation using **AND**, **OR**, **NOT** buttons. Now click **AND** button and then highlight *w* on **Select Column Variable for If Test** group and click **Add...** button again, this time, we are looking for weight no greater than 50kg:



When the condition is done, click **All Rows** button to select all rows, then click the **Test -- select if true** button and Origin will return 5 found records. Of course, if you familiar to logical operation syntax, you can type the condition on the edit box directly:

```
h>=160 AND w<=50
```

Accept other default settings and click the **OK** button. A new workbook is created with these 5 records.

Extract Strings

When extracting strings, you need to enclose the string by double quotation marks ". For example, select the *gender* column into the **Select Column Variables for If Test** group. Using the alias *g*, you can extract all female data by:

```
g == "F"
```

Extract Time Data

[Date and Time](#) data are internally saved as numeric values in Origin. Date is the integer part of the numeric value, while Time is the fractional part. In Origin, you can use the *int()* and *frac()* functions to return the integer and fractional part of a number, and use the *Date(MM/DD/YY)* and *Time(HH:mm:ss)* functions to transfer string to time data. We can combine these functions to extract time data.

For example, using data from [Import Time Data](#) tutorial, you can extract data within time period 10:00 ~ 11:00 by:

```
frac(B) > Time(10:00:00) AND frac(B) < Time(11:00:00)
```

You can see Origin found 120 records. Similarly, if you want to extract *Date* data, you can try some condition like:

```
int(A) > Date(01/24/2004)
```

4.5.2.2 Data Reduction

Summary

Worksheet datasets can be reduced in size using various tools. Origin offers six tools which can be used for data reduction, including the [Data Filter](#), [Worksheet Query](#) and four data reduction x-functions, which reduce the number of data rows by different methods.

Minimum Origin Version Required: 2015 SR0


What You Will Learn


In this tutorial, you will learn how to:

- Reduce XY data to evenly spaced X
- Reduce Duplicate X Data for XY dataset
- Reduce XY data by Group
- Reduce worksheet rows


Steps

Reduce to Evenly Spaced X


1. Create a new workbook and click the  button to import the file **Signal with High Frequency Noise.dat** under <Origin EXE folder>\Samples\Signal Processing path.
2. Highlight column B and select **Analysis:Data Manipulation:Reduce to Evenly Spaced X** to open the **reduce_ex** dialog. Edit the settings so that they match the following.




- Click **OK**. A new column (column C) is added to the worksheet. This column contains its own sampling interval information. Right click on its column header and select **Show X Column**. In the **Show X Column: colshowx** dialog box, click **OK** to generate an X column using the sampling interval. You can see that the original XY dataset has been reduced by generating a new, larger sampling interval.




- Highlight column B and C (hold down the **Ctrl** key for multiple selection), and click the button to generate a line plot for original (Black) and reduced (Red) data.
- You can see from the plot that the data size is considerably reduced:



Reduce Duplicate X

1. Create a new workbook and click the  button to open the **Import Wizard**. Select the data files **Step01.dat**, **Step02.dat** and **Step03.dat** under the file path <Origin EXE Folder>\Samples\Curve Fitting\. Change the **Import Mode** to **Start New Rows** and make sure the default import filter **step** is applied. Click **Finish** to import these data files.
2. Highlight column A and B, select **Analysis:Data Manipulation:Reduce Duplicate X Data** to open the **reducedup** dialog. Duplicate the settings as depicted below:




3. Click **OK** to apply settings and in the results sheet **Sheet2**, we can see that for each X value, 3 duplicates are found. In the reduced dataset, the Y values for each duplicated X have been replaced by the sum of the Y values.


	A(X1)	B(Y1)	C(X2)	D(Y2)
Long Name	ReduceDu	ReduceDupY1	DupX1	DupXCount1
Units				
Comments		Duplicates replaced with Sum of "conc17"		
F(x)=				
1	0	0	0	3
2	1.6	-0.01038	1.6	3
3	3.2	0.00635	3.2	3
4	4.8	-0.01886	4.8	3
5	6.4	-0.00427	6.4	3
6	8	0.02093	8	3
7	9.6	0.065	9.6	3
8	11.2	0.00214	11.2	3
9	12.8	0.06268	12.8	3
10	14.4	0.06262	14.4	3
11	16	0.10034	16	3
12	17.6	0.06281	17.6	3
13	19.2	0.11499	19.2	3
14	20.8	0.1214	20.8	3
15	22.4	0.12543	22.4	3
16	24	0.13385	24	3
17	25.6	0.18195	25.6	3
18	27.2	0.17139	27.2	3
19	28.8	0.138	28.8	3

Reduce/Combine Duplicate Rows

- Go to *Sheet1* of the previous section, highlight column A and select **Worksheet:Remove/Combine Duplicated Rows...** to open the **wdeldup** dialog. Select **Average** from **Merge Duplications by** drop-down list, and click the right-sided triangle button on the **Output Worksheet** row to select **<new>:New Sheet** and check the **Output Counts** box and click **OK**.



2. Entire worksheet rows are reduced into the average values of merged rows which are determined by duplications in the selected column. A new column **Counts** is added to the end of the result worksheet *wdeldup* and it reports the number of duplicates found for each X value.





	M(X7)	N(Y7)	O(X8)	P(Y8)	Q(Y8)
Long Name	conc23	conc23	conc24	conc24	Counts
Units					
Comments	Sensor G x	Sensor G y	Sensor H x	Sensor H y	
F(x)=					
1	1.2	0	1.4	0	3
2	2.8	0.11737	3	0.17448	3
3	4.4	0.27997	4.6	0.41884	3
4	6	0.40171	6.2	0.57955	3
5	7.6	0.51925	7.8	0.68073	3
6	9.2	0.63123	9.4	0.76457	3
7	10.8	0.69611	11	0.81905	3
8	12.4	0.75454	12.6	0.8929	3
9	14	0.82426	14.2	0.88688	3
10	15.6	0.84269	15.8	0.93241	3
11	17.2	0.86731	17.4	0.9457	3
12	18.8	0.90261	19	1.00258	3
13	20.4	0.93424	20.6	0.98714	3
14	22	0.94843	22.2	1.03746	3
15	23.6	0.95477	23.8	1.0414	3
16	25.2	0.98433	25.4	1.03587	3
17	26.8	0.98297	27	1.05837	3
18	28.4	0.99487	28.6	1.07505	3
19	30	1.01113	30.2	1.08614	3
20	31.6	1.03864	31.8	1.07638	3
21	33.2	1.04718	33.4	1.10826	3
22	34.8	1.03794	35	1.11607	3
23	36.4	1.04631	36.6	1.12785	3
24	38	1.07383	38.2	1.14673	3
25	39.6	1.06616	39.8	1.13881	3
26	41.2	1.07251	41.4	1.14844	3




The tool **Reduce Duplicate X** works for XY dataset only, while the tool **Remove/Combine Duplicate Rows** works for an entire worksheet.

You can also remove duplicate XY data from an XYZ dataset by using the [Statistics on Columns](#) tool, please refer to this [Quick Help](#).


Reduce by Group

1. Open a new workbook, then click the  button to import the **Magnetization.dat** file under <Origin EXE folder>\Samples\Data Manipulation path.
2. Highlight columns A and B and click the  button to generate a line plot.


3. Activate this graph and select **Analysis:Data Manipulation:Reduce by Group** to open the **reducexy** dialog. Edit your settings as below:




4. Click **OK** to reduce the data. The reduced XY dataset will be added as two new columns at the end of original worksheet:



5. The reduced XY dataset is added as a new data plot to the original graph:



Reduce Worksheet Rows

1. Open a new workbook, then Click the  button to import the file **Nitrite.dat** (path is <Origin EXE folder>\Samples\Spectroscopy). There are 6392 data points in this file.

	A(X)	B(Y)
Long Name	Time	Voltage
Units		
Comments		
F(x)=		
Sparklines		
6383	0.3544	1.7
6384	0.3544	1.8
6385	0.3544	1.5
6386	0.35441	1.9
6387	0.35441	1.1
6388	0.35441	1.9
6389	0.35442	1.7
6390	0.35442	1.4
6391	0.35442	1.5
6392	0.35442	1.8
6393		
6394		
6395		
6396		
6397		

- Highlight both columns in the Nitrite worksheet and select **Worksheet:Reduce Rows** to open the **wreducerows** dialog, and edit the settings to match the image below:

Data Manipulation\Worksheet: wreducerows

Dialog Theme

Description Reduce worksheet rows by deletion or mergence

Recalculate

Input

Reduce Method

Delete Rows

Skip Rows


Starting Row to Delete


Output


OK Cancel

Note: You can select the arrow button right to the **Output** select box and choose **<new>:New Column(s)** to make the selection.


- When you click **OK**, only the first of every 10 rows is kept. Ninety percent of data points are discarded. Remaining data points are output to new columns:



- Select the entire worksheet and click the  button to generate line plots for original (Black) and reduced (Red) data:



5. Note that peak heights were changed with data reduction. To maintain data plot shape, we should keep more data points. Click the green lock on Graph 1 and choose **Change Parameters** to open the **wreducerows** dialog again. Change the value of **Delete Rows** to **3** and click **OK**.
6. This time 25% of data points were kept, better preserving the shape of the original data plot.



4.5.2.3 Data Filter

Summary

The **Data Filter** is a column-based tool to reduce rows of worksheet data, and consequently also hide the undesired rows for relevant data analysis and graphing. Three data formats are supported: numeric, text and date/time.




Minimum Origin Version Required: Origin 2015 SR0


What you will learn

This tutorial will show you how to:


- Use the data filter to reduce worksheet data
- Auto update the graphs and analysis results when apply a column filter
- Add a floating graph to a worksheet.


Steps


1. Create a new workbook by clicking the **New Workbook** button . Then click the **Import Single ASCII** button  to import the **automobile.dat** file in the <Origin Folder>\Samples\Statistics\ path. Both buttons are located in the **Standard** toolbar.
2. Highlight column C(Power), right click and choose **Set As:X** in the context menu to set this column as X.
3. Highlight column C and G (hold **Ctrl** key when clicking), click the  button on the **2D Graph** toolbar to generate a scatter plot from these two columns.
4. Activate the generated graph and select **Analysis:Fitting:Linear Fit** from menu item to open the **Linear Fit** dialog. In this dialog, set **Recalculate** to **Auto** to ensure auto update of the analysis result, accept other settings as default and click **OK** to carry out the analysis.






5. A fitted curve and a result table will be added to the graph, activate the graph again and double click on the X axis to open the **Axis** dialog, Select the **Horizontal** icon in the **Scale** tab, choose **Auto** for **Rescale**. Do the same for the Y axis (**Vertical** icon) and also set its rescale mode to **Auto**. Click **OK** to apply the settings and close the dialog.





6. Go back to the original worksheet **automobile**, click the **Add New Columns** button  seven times to add seven new empty columns to the end of the worksheet to work as background later.
7. Right click in the gray area of the worksheet and select **Add Graph...** in the context menu to open the **Graph Browser**, in this dialog, select the previously generated graph in the left panel and click **OK** to add this graph as a floating chart to the worksheet. Resize and move the floating chart for clearer view.




8. Highlight column A and B and click the **Add/Remove Data Filter** button  on the **Worksheet Data** toolbar to add empty data filters to both columns.
9. Click the **Filter** icon  on the column header of column B, clear the check boxes before *Buick, Chrysler, GMC, Kia, Lincoln, Mercedes, Saab, Volvo* to hide all rows with these entries, to leave only the Japanese makers. Click **OK** to apply the filter. The worksheet data, graph and analysis result will all be auto updated accordingly.



10. Click the **Filter** icon  on the column header of column A and select **Between**, note that the data type of column A is numeric by default from importing. Accept default setting of the **Between** dialog and click **OK**. A data filter is applied to this column.
11. Again click the **Filter** icon  on column A and this time choose **Custom Filter** in the context menu to customize the filter, change the **Condition** as **x.between(1996,2000)** to set the **From** and **To** value respectively, click the **Test** button and in the original worksheet, only the rows meet this testing condition will be highlighted, this works as a preview of the data reduction.

Notes: In order to view the whole worksheet at this stage, you can minimize the **Custom Filter** dialog, then scroll up and down the worksheet freely. You can later restore the dialog for further settings.

12. Click the **OK** button to apply the new filtering condition and the data, graphs and analysis results are updated and the graph is also auto rescaled.



4.5.2.4 Lock Filter with Analysis

Summary

Generally, when graphing or analysis is done on data with a filter, changes in the filter condition of the source worksheet trigger recalculation for the analysis results and graph.

However for [Copy Columns](#) and [Pivot Table](#), in the Recalculate lock icon context menu, there are [three worksheet filter options](#). These are used to control whether the results will be affected by further filter changes.

Minimum Origin Version Required: Origin 9.1 SR0


What you will learn


- How to copy columns to a new sheet or new workbook
- How to lock a Data Filter condition on copied columns
- How to push back the Data Filter condition to the source worksheet


Steps

1. Import the Origin sample data *automobile.dat* which is located in **<Origin Program Folder>\Samples\Statistics**.


- Highlight the **Make** column, then right-click and select **Filter: Add or Remove Filter** in the context menu or select the **Filter** button from the **Worksheet** toolbar.



- To show only the **Honda** data, click on the filter icon  that appears on the top left of the column's first cell. Choose **Select All** to clear all the options. Select **Honda**. Click the **OK** button.




- To copy columns to a different sheet, hold down the CTRL key and select the **Make, Power** and **Engine Displacement** columns. Next, right-click and select the **Copy Columns to...** in the context menu.
- In the **colcopy** dialog, select **Auto** in the **Recalculate** drop-down list. Make sure the **Destination Columns** is set to a new worksheet in the same workbook. A new sheet with the copied columns will be created.



- Click and drag the sheet tab of the copied worksheet to blank Origin workspace. This will create a new workbook to hold the copied data so the copied data and original data can now be compared side by side.
- Click on the green Recalculate lock icon on the top left of the first cells' in the columns of this copied sheet. Select **Worksheet Filters: Lock** in the context menu. The filter conditions will be

saved into the operation.



8. In the source worksheet, add Data Filter to **Power** column, and click on the filter icon to select **Greater Than....** In the **Simple Number Filter** dialog, set **Value** to 100, and click **OK**. The filter will show only the **Power** data above 100 in the original workbook but since the filter was locked in the copied workbook the data in it will no longer update.
9. The filter conditions on the original workbook were changed and in order to set them back to the way they are in the copied workbook, use **Push Back**. In the copied sheet, click on the green lock in column(A) and select **Worksheet Filters: Push Back** from the context menu. This will result in the data filter condition in the original workbook being pushed back so that the filter condition set on **Power** no longer applies.



The lock filters options are just available in the new result sheet. If copy column to the same worksheet, the options are not shown in the Recalculate lock icon's context menu.

4.5.3 Pivot Table

4.5.3.1 Summary

The Pivot Table provides a quick way to summarize your data, and to analyze, compare, and detect relationships in your data. This tool can sort, count, sum, or compute minimum, maximum, or mean of data stored in a worksheet.

Minimum Origin Version Required: Origin 2015 SR0

4.5.3.2 What you will learn


- How to summarize data by a Pivot Table.
- How to sort output by row or column totals in Pivot Table.
- How to combine small values in columns or rows, and custom extra value.

4.5.3.3 Import Data from Database

1. Before creating a pivot table, we should can import data from database. Suppose we have already set up a database named *AdventureWorks2008R2* on a server machine - *myServer* - running SQL Server, with user name as "accounting", and password as "mydatabase".
2. To connect the database, we use a connection string:


```
Provider=SQLOLEDB.1;Password=mydatabase;Persist Security Info=True;
User ID=accounting;Initial Catalog=AdventureWorks2008R2;Data
Source=myServer
```

3. Activate an empty worksheet and open SQL Editor by clicking the **Open SQL Editor** button on the **Database Access** toolbar.



4. Select menu item **Edit Connection String...** from SQL Editor's **File** menu, in the open dialog, put the connection string (see step 1 above) to the text box. And then you can click the **Test** button to test if the connection is fine. If fine, click the **OK** button to connection to the database.

Tutorials for Origin



5. In the right text box, put the following SQL statements.

```
SELECT

DatePart (yyyy, SOH.OrderDate) AS YEAR,

CR.Name As CustomerCountry,

    Pr.Name As ProductName,

    Pr.Color As ProductColor,

    PC.Name As ProductCategory,

    PS.Name As ProductSubcategory,

    SOH.OrderDate As OrderDate,

    SOD.OrderQty As OrderAmount,

    SOD.LineTotal As TotalCost

FROM Person.CountryRegion AS CR

INNER JOIN Person.StateProvince AS SP

ON SP.CountryRegionCode = CR.CountryRegionCode

INNER JOIN Person.Address AS A

ON A.StateProvinceID = SP.StateProvinceID
```

```
INNER JOIN Person.BusinessEntityAddress AS BEA

ON BEA.AddressID = A.AddressID

INNER JOIN Person.Person AS P

ON P.BusinessEntityID = BEA.BusinessEntityID

INNER JOIN Sales.PersonCreditCard AS PCC

ON PCC.BusinessEntityID = P.BusinessEntityID

INNER JOIN Sales.SalesOrderHeader AS SOH

ON SOH.CreditCardID = PCC.CreditCardID

INNER JOIN Sales.SalesOrderDetail AS SOD

ON SOD.SalesOrderID = SOH.SalesOrderID

INNER JOIN Production.Product AS Pr

ON Pr.ProductID = SOD.ProductID

INNER JOIN Production.ProductSubcategory AS PS

ON PS.ProductSubcategoryID = Pr.ProductSubcategoryID

INNER JOIN Production.ProductCategory AS PC

ON PC.ProductCategoryID = PS.ProductCategoryID

--WHERE SOH.OrderDate BETWEEN '1/1/2005' AND '12/31/2008'
```

6. Select menu **File: Save to Active Worksheet** to save these settings to the worksheet, and then select menu **Query: Import** to import the data into worksheet, and then close SQL Editor. We can see the imported data form the image below.

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)
Long Name	YEAR	CustomerCountry	ProductName	ProductColor	ProductCategory	ProductSubcategory
Units						
Comments						
F(x)=						
1	2005	Canada	Road-150 Red, 62	Red	Bikes	Road Bikes
2	2005	France	Mountain-100 Silver, 44	Silver	Bikes	Mountain Bikes
3	2005	United States	Mountain-100 Silver, 44	Silver	Bikes	Mountain Bikes
4	2005	United States	Road-650 Black, 62	Black	Bikes	Road Bikes
5	2005	Australia	Mountain-100 Silver, 44	Silver	Bikes	Mountain Bikes
6	2005	United States	Road-150 Red, 44	Red	Bikes	Road Bikes
7	2005	Australia	Road-150 Red, 62	Red	Bikes	Road Bikes
8	2005	Australia	Mountain-100 Black, 48	Black	Bikes	Mountain Bikes
9	2005	Australia	Mountain-100 Silver, 38	Silver	Bikes	Mountain Bikes
10	2005	United States	Road-150 Red, 48	Red	Bikes	Road Bikes
11	2005	United States	Road-150 Red, 48	Red	Bikes	Road Bikes
12	2005	United Kingdom	Road-650 Red, 52	Red	Bikes	Road Bikes

7. Click **Close** to close the dialog.

4.5.3.4 Create a Pivot Table

The imported dataset is a total cost summary of three product categories(Bikes,Accessories, Clothing) in six different countries by year. Suppose now you want to create a pivot table to see the yearly *Sum of Total Cost* of different product category. Follow the steps below to create the pivot table.

1. Activate the Sheet1, select **Worksheet: Pivot Table** from the main menu to open the dialog. And specify the following settings in the dialog:
 - o For **Pivot Table Row Source**, click the triangle button to add column A.
 - o For **Pivot Table Column Source**, click the triangle button to add column E.
 - o Select **Sum** with the **Summarize by** drop-down list. Then select column I for **Pivot Table Data Source**.
 - o Expanding **Options** branch, check **Total for Rows** and **Total for Columns** check boxes, and select **Row Label Ascending** from the **Sort Output Rows** drop-down list.

Recalculate Manual

Pivot Table Row Source [Book1]Sheet1!A:YEAR

Pivot Table Column Source [Book1]Sheet1!E:ProductCategory

Pivot Table Data Source [Book1]Sheet1!TotalCost

Summarize by Sum

Combine Smaller Values
Combine Direction None

Options

Totals for Rows

Sort Output Rows Row Labels Ascending

Totals for Columns

Sort Output Columns Column Labels Ascending

Normalize by Column Totals None

Show Zeros when Empty

Row Source Extra Values

Column Source Extra Values


2. Click the **OK** button to create the pivot table. The table should like this:

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	YEAR	Sum of TotalCost			
Units					
Comments		Accessories	Bikes	Clothing	Total_YEAR
F(x)=					
UserParam1					
1	2005	0	3.11421E6	0	3.11421E6
2	2006	0	6.26258E6	0	6.26258E6
3	2007	281089.1	8.96743E6	132728.69	9.38125E6
4	2008	391752.38	8.79936E6	192688.76	9.3838E6
5	Total_ProductCategory	672841.48	2.71436E7	325417.45	2.81418E7
6					
7					


4.5.3.5 Combine Small Values

In this section, we will show you how to present those categories with the percentage of the summarized value (Count/Sum/Mean/Min/Max) accounts for that of grand total exceeding a threshold percent, and combine small value categories into a default **Others** category.

1. Based on the above example, click on the lock icon in the **Pivot1** worksheet, and select **Change Parameters** to open the dialog again.



2. Specify the following settings in the dialog:
 - o Expanding **Combine Smaller Values** branch, select **Column** in the **Combine Direction** drop-down list,
 - o Select **By Percent of Grand Total** in **Mode** drop-down list.
 - o Enter **30** in **Percent** textbox and **Other Smaller Items** in the **Column Label** textbox.
 - o Expanding **Options** branch, uncheck the boxes of **Totals for Rows** and **Totals for Columns**



- Click **OK** button. The pivot table shows the summarization of data by **Sum**. And only Category *Bikes* has the percent of grand total exceeding the threshold percent 30 %, other smaller categories has been reduced into Category **Other Smaller Items**.


	A(X)	B(Y)	C(Y)
Long Name	YEAR	Sum of TotalCost	
Units			
Comments		Bikes	Other Small
F(x)=			
UserParam1			
1	2005	3.11421E6	0
2	2006	6.26258E6	0
3	2007	8.96743E6	413817.79
4	2008	8.79936E6	584441.14
5			
6			

4.5.3.6 Extra Categories Source

In this section, we will show you how to present those categories that are missing in the source data sheet with ' **Column Source Extra Value**. This is useful when you want to ensure all needed categories will be presented in the result pivot table that might be used for later plotting.

Suppose we want to know the *Sum of Total Cost* of different product categories before *Year 2007*. Follow the steps below to create the pivot table.

- To filter the years before 2007, we use the data filter. Go to Sheet 1 and select **Col A**. Click button in the main menu bar. Click again the filter icon on **Col A** and select **Less Than**. Customize the pop-out filter dialog as follow, then click OK to close the dialog.




- Click on the lock icon in the **Pivot1** worksheet, and select **Recalculate**. As shown in the following pivot table, only *Bikes* is presented here, because other two product categories do not has any

cost data record in Year 2005 and 2006.

	A(X)	B(Y)
Long Name	YEAR	Sum of Total
Units		
Comments		Bikes
F(x)=		
UserParam1		
1	2005	3.11421E6
2	2006	6.26258E6
3		
4		
5		


3. Back to **Pivot1** worksheet, select col(b) and then click **Plot: Column/Bar/Pie: Column** to plot a column graph(*Graph1*).
4. Next we want to add two missing categories back into the pivot table. Click on the lock icon in the **Pivot1** worksheet, and select **Change Parameter**.Customize the dialog as follow, click OK to close the dialog. The pivot table would look as follow.



The pivot table would look as follow.

Long Name	YEAR	Sum of TotalCost			
Units					
Comments		Accessories	Bikes	Clothing	Other Smaller Items
F(x)=					
UserParam1					
Filter	Less than 2007				
1	2005	0	3.11421E6	0	0
2	2006	0	6.26258E6	0	0
3	2007	281089.1	8.96743E6	#####	0
4	2008	391752.38	8.79936E6	#####	0
5					
6					
7					
8					

- Back to **Pivot1** worksheet again. Click again the filter icon on **Col A** and select **Clear Filter** from the pop-up menu to remove the filter. Then select all columns to plot a column graph(*Graph2*). The graph would show the missing categories.
- Back to **Pivot1** worksheet again, right click the grey area and select **Add Graph** to add Graph2 onto the **Pivot1** worksheet




Year filtering can also be obtained in **Database**. In this case, you can **customize the favorable time period by rewriting this script:**

```
--WHERE SOH.OrderDate BETWEEN '1/1/2005' AND '12/31/2008'
```

4.5.3.7 Create analysis template

In this section we will show you how to create analysis template for the pivot table, reimport data from database and reuse the analysis template to create pivot table for new data.

1. Activate the Book1, click **File: Save Workbook as template** and save it as *SumTotalCost.ogw*.
2. Open a new OPJ file and then click **File: Open** to open *SumTotalCost.ogw*.
3. To change the data source as *AdventureWorks2008* in database,
 - Activate Sheet1 and open SQL Editor by clicking the **Open SQL Editor** button .
 - Click **File: Edit Connection String** then type the following string in the open dialog, click **Test** then click OK to connect the database.


```
Provider=SQLOLEDB.1;Password=mydatabase;Persist Security Info=True;  
  
User ID=accounting;Initial Catalog=AdventureWorks2008;Data Source=myServer
```


- Back to the **SQL Editor** dialog, On the right panel, rewrite the last script as

```
--WHERE SOH.OrderDate BETWEEN '1/1/2001' AND '12/31/2004'
```

- Select menu File: Save to Active Worksheet to save these settings to the worksheet, and then select menu Query: Import to import the data into worksheet, and then close SQL Editor. We can see the imported data form the image below.

Long Name	A(X) YEAR	B(Y) CustomerCountry	C(Y) ProductName	D(Y) ProductColor	E(Y) ProductC
Units					
Comments					
F(x)=					
Filter					
1	2001	Canada	Road-150 Red, 62	Red	Bikes
2	2001	France	Mountain-100 Silver, 44	Silver	Bikes
3	2001	United States	Mountain-100 Silver, 44	Silver	Bikes
4	2001	United States	Road-650 Black, 62	Black	Bikes
5	2001	Australia	Mountain-100 Silver, 44	Silver	Bikes
6	2001	United States	Road-150 Red, 44	Red	Bikes
7	2001	Australia	Road-150 Red, 62	Red	Bikes
8	2001	Australia	Mountain-100 Black, 48	Black	Bikes
9	2001	Australia	Mountain-100 Silver, 38	Silver	Bikes
10	2001	United States	Road-150 Red, 48	Red	Bikes
11	2001	United States	Road-150 Red, 48	Red	Bikes

4. To update the pivot table, go to Sheet 'Pivot1', click the yellow lock and select **Recalculate**. The pivot table would be updated according to new data.
5. To update the embedded graph,
 - o double click the embedded graph and a floating chart would pop up.
 - o Select the graph and click **Rescale** button to refresh . The floating chart would be updated too.
 - o click the arrow button at the upper right corner of the floating chart to put it back to the worksheet. The worksheet would look as follow.



4.5.4 Categorical Values Ordering and Sharing

4.5.4.1 Summary

Categorical values are used to store categories information in a column. In Origin, you have the capacity to manually add, remove, order categories in a column and the categorical information stored in the column will be carried over to result sheet during analysis. You can easily save categories into a text file and share across columns or worksheets.

Minimum Origin Version Required: Origin 2015 SR0


4.5.4.2 What you will learn





- How to manipulate categorical values
- How to order categorical map
- How to share categorical values


4.5.4.3 Manipulate Categorical Values

1. To import the Origin sample data, select **File: Import: Excel(XLS, XLSX, XLSM...)** from the Origin menu. Browse to **<Origin Program Folder>\Samples\Statistics** and select *HouseholdCareSamples.xls*. Click the **Add File(s)** button. Make sure that the **Show Options Dialog:** check box is selected. Click the **OK** button to open the **impMSEExcel** dialog.
2. Specify the following settings in the **impMSEExcel** dialog:
 - Under **File Info**, expand the **HouseholdCareSamples.xls** branch. Unselect **File Sheet(s)**, then check the check boxes next to **HQ Family Mart** and **TX Trust-Mart**.
 - In the **Header Lines** branch, select **1** in **Number of Subheader Lines** drop-down list and then **1** for **Long Names**. Check **Apply Header to All Sheets** box.
 - Click **OK** to import the data into Origin.
3. On the **HQ Family Mart** worksheet, highlight column *Category* (long name) and right click to select **Set As Categorical**. Double click on the **Unsorted** on **Categories** label row to bring up **Categories** dialog.
4. Now we want to only keep **Household Clean, Kitchen Clean, Dishwashing Liquid, Laundry Powder** and **Fabric Conditioner** five categories and order them as listed. To do so, first check **Customize Categories (Add, Delete, Set Arbitrary Order)** box, hold Ctrl key to select unwanted


categorical values and use **Remove** button  to remove them.



5. Then use **Move To Top** button , **Move Up** button , **Move Down** button  and **Move To Bottom**  button to reorder them as shown below:




6. Then click **Save >** button and select **Save As** to bring up **Categories Save as** dialog. Enter *HouseholdCare Category* as **Name** and click **OK** to save the categorical values in a text file under displayed **Save Path** for sharing later.




7. Click **OK** to close **Categories** dialog box.
8. Next we want to know the total number of items in each of the five categories specified in step 4 and make a column plot of results. To do so, highlight column *Number* (long name) and go to **Statistics: Descriptive Statistics: Statistics on Columns: Open Dialog...** to bring up **Statistics on Columns** dialog, click right-sided triangle icon on **Group** row to select **E(Y):Category** as grouping column and click **OK** to close the dialog. In the prompt dialog, click **OK**.

9. Switch to *DescStatsQuantities1* flat sheet, select column *N total* (long name) and go to **Plot: 2D: Bar: Column** to create the column plot.
10. Double click on the X axis tick labels to bring up **Tick Labels** page on **Axis** dialog, go to **Format** tab and select *45* from **Rotate (deg.)** drop-down list and click **OK** to close the dialog.
11. Double click on the graph to bring up **Plot Details** dialog, expand **Layer1** node to go to its subnode. In the Pattern tab, expand the **Color** drop-down list in the **Fill** group, select **By Points** tab, and choose the color **Black** under **Increment from** list to set it as the starting color. Click **OK** to close dialog.



12. Right click on the page and select **Fit Page To Layers...** and click **OK** in the appeared dialog to bring the X axis label into page. Delete the legend, use **Text** tool to add *HQ Family Mart* as graph title. Move X axis title and added graph title to proper positions, and the column plot looks like the


following:




4.5.4.4 Share Categorical Values

1. Continue from the section above, now we want to share the categories saved earlier with second worksheet *TX Trust-Mart*. To do so, activate *TX Trust-Mart* sheet and highlight column *Category* (long name) and right click to select **Set As Categorical**.
2. Double click on the *Unsorted* on **Categories** label row to bring up **Categories** dialog, check **Customize Categories (Add, Delete, Set Arbitrary Order)** box and click **Load >** button on the

right and select appeared *HouseholdCare Category* file.



- Follow steps 7-12 in above section and add text *TX Trust-Mart* instead of *HQ Family Mart* in step 12, we will obtain a column plot from *TX Trust Mart* source sheet as following:



4.6 Analysis Templates

- [Creating and Using Analysis Templates](#)
- [Creating Analysis Templates using Set Column Value](#)
- [Creating a Custom Report Sheet](#)

4.6.1 Creating and Using Analysis Templates

4.6.1.1 Summary

Routine tasks can be simplified by creating an Analysis Template. Such templates can contain multiple analysis results and also custom report sheets. A new instance of the template can then be

opened at any time and source data can be changed to update all analysis results and custom reports.


Minimum Origin Version Required: Origin 2015 SR0

4.6.1.2 What you will learn

- How to create an analysis template (OGW)
- How to re-use an analysis template with new data

4.6.1.3 Steps

Importing Data


1. Start with a new workbook.
2. Click the **Import Single ASCII** button  on the **Standard** toolbar to open the ASCII dialog box. Browse to the <Origin EXE folder>\Samples\Curve Fitting\ folder and select the file **Sensor01.dat**. Make sure that **Show Options Dialog** is selected and click the **Open** button. This will open a dialog for specifying import settings.
3. In the **impASC** dialog, expand the **(Re)Naming Worksheet and Workbook** node and clear the **Rename Sheet with (Partial) Filename** box.
4. Click the arrow button next to **Dialog Theme**, and select **Save to <Sheet>** in the fly-out menu. This will save your import settings to the worksheet.
5. Click **OK** to import the file to **Sheet1**.
6. Right click the worksheet tab and rename this worksheet as **Data**.


Performing Analysis

1. Highlight column B and use the **Analysis: Fitting: Linear Fit** menu item to open the **Linear Fit** dialog box.
2. Set **Recalculate** to **Auto**, accept other default settings and click **OK** to perform a linear fit.
3. A hierarchical report sheet will be added to the book, with result tables and embedded graphs.
4. Go to the **FitLinear1** report sheet and double-click to open the graph under the **Fitted Curves Plot** tree node. This graph contains the data plot and fitted curve.
5. Click the menu item **View:Show:Frame** to show the graph frame.
6. Double click on the data plot to open the **Plot Details** dialog box. In the left panel, select **FitLine** to open the **Page Properties** dialog box. Go to the **Legends/Titles** tab and clear the **Indicate Active Dataset** check box, then press **OK** to close the dialog.
7. Select **Format: Axes: Y Axis...** in the main menu to open the **Axis** dialog box. Verify that the **Type** under **Major Ticks** node is set to **By Increment** and set the **Value** to **5**. Use Shift/Ctrl key

to select both **Horizontal** and **Vertical** icons on the left panel and change the **Rescale** mode to **Auto** for both X and Y axes. Click **Apply** to apply settings and choose **OK** to close the dialog.

8. Manually move the legend object to a suitable position so all text is visible. The final graph should look like the image below:




9. Put this graph back into the result sheet by clicking on the restore button  at the top right of the title bar.

Saving an Analysis Template

1. Activate the workbook and select **File: Save Workbook as Analysis Template**.
2. Browse to the desired location and enter a file name, for example **MySensorData**, and press the **Save** button.
3. Now the file **MySensorData.OGW** is saved as an Analysis Template. This template can be re-used in the future to carry out similar analyses.

Re-using the Analysis Template

1. Start a new project, then select the menu item **File: Recent Books**. From the fly-out menu options, select the Analysis Template **MySensorData.ogw** that was saved earlier.

2. Make the **Data** worksheet active, and click the **Import Single ASCII** button . Browse to the file **Sensor02.dat** under the *<Origin EXE Folder>\Samples\Curve Fitting* path and import the file.

Note: You can also locate the **Sensor02.dat** file in your local drive, drag and drop it into this **Data** sheet to import.

3. Since the **Recalculate** mode was set to **Auto**, the linear analysis will be performed automatically for the new data.
4. Go to the **FitLinear1** worksheet and under the **Fitted Curves Plot** node, double-click to open the graph and view the updated results.



The Analysis Template can be used in the batch processing of similar data, see [this tutorial](#) for details.

4.6.2 Creating Analysis Templates using Set Column Value

4.6.2.1 Summary

This tutorial will demonstrate how to add a column, set up **Before Formula Script** and have that script run whenever data changes in other columns. This technique can be used to create an **Analysis Template** for repeated analysis of similar data.

Minimum Origin Version Required: Origin 8.0 SR6

4.6.2.2 What you will learn

- How to use Set Column Values to create an analysis template
- How to select rows via the *Go to* function

4.6.2.3 Steps

1. Import the data from *\Samples\Statistics\automobile.dat* into a newly created workbook, as below. In this example, we will extract data, according to the *Make* column, into different worksheets.

	A(Y)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	Year	Make	Power	0~60 mph	Weight
Units			kw	sec	kg
Comments					
1	1992	Buick	132	14	2238
2	1992	Acura	154	12	2324
3	1992	GMC	158	13	1531
4	1992	Chrysler	132	10	2088
5	1992	Kia	121	12	1202
6	1992	Suzuki	106	10	1417
7	1992	Volvo	95	14	1661
8	1992	Mercedes	132	14	2208
9	1992	Acura	128	13	1412
10	1992	Isuzu	124	17	1518

2. Add an empty column to the worksheet and bring up the **Set Column Values** dialog of the column. In the **Before Formula Script** box, enter the script below.

```
// Data range on which to perform discrete frequency count

range makeCol = !col(make);

// Worksheet to be extracted

range sourceWks = !;

// Clear worksheets

int sheetNum = page.nlayers;

int colNum = wks.ncols - 1;

if (sheetNum>1)

{

    for (jj=2; jj<=sheetNum; jj++)
```



```
    {  
  
        layer -d 2;  
  
    }  
  
}  
  
// Tree variable to hold discfreqs outputs  
  
tree tr;  
  
// Perform discrete frequency count  
  
discfreqs irng:=makeCol rd:=tr;  
  
// String array to get result from tree  
  
StringArray sa;  
  
sa.append(tr.FreqCount1.Data1);  
  
if( sa.GetSize() != NANUM )  
  
{  
  
    // Loop to extract data  
  
    for (ii=1; ii<=sa.GetSize(); ii++)  
  
    {  
  
        string sn$ = sa.GetAt(ii)$;  
  
        // Extract condition string  
  
        string cond$ = "makeCol$ = " + sn$;
```

```

// Create worksheet with different Make name

newsheet name:=sn$ cols:=colNum outname:=on$ active:=0;

// Extract data

wxt test:=cond$ iw:=sourceWks c2:=colNum ow:=on$;

}

}

```

3. This script will first perform a discrete frequency count on the *Make* column to get distinct values for *Make*. It will then create a new worksheet for each brand and extract data into these sheets.



- 4.
5. Make sure the recalculate mode is set to **Auto** and click **OK**. The data will be separated into different worksheets. Then the empty column (H) with a green lock icon indicates that this procedure can be updated automatically.

	E(Y)	F(Y)	G(Y)	H(Y)
Long Name	Weight	Gas Mileage	Engine Displacement	
Units	kg	mpg	cc	
Comments				
1	2238	11	5736.5	
2	2324	11	5212	
3	1531	10	5900.4	
4	2088	12	6277.4	
5	1202	12	5736.5	
6	1417	14	5736.5	
7	1661	13	5031.7	
8	2208	12	5736.5	
9	1412	12	5736.5	
10	1518	13	5900.4	

6. There are 18 makes of cars in the source data, so 18 new worksheets were created. Now we can check whether auto-update works.

Go to the **Honda** tab. Notice that there are 19 rows.

7. Switch to the first sheet. Scroll down and delete the last row.

	A(Y)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)	G(Y)	H(Y)
Long Name	Year	Make	Power	0~60 mph	Weight	Gas Milea	Engine Di	
Units			kw	sec	kg	mpg	cc	
Comments								
Sparklines								
338	2004	Infiniti	38	12	867	35	1491.5	
339	2004	Isuzu	49	15	848	36	1589.8	
340	2004	Honda	52	10	1210	25	1458.7	
341								
342								
343								
344								
345								
346								
347								

Then auto-update will be triggered. Go to the **Honda** tab. You will see there are only 18 rows.

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)	G(Y)
Long Name	Year	Make	Power	0~60 mph	Weight	Gas Mileag	Engine Dis
Units			kw	sec	kg	mpg	cc
Comments							
Sparklines							
13	1999	Honda	70	18	1067	24	2196.3
14	2000	Honda	44	13	1210	24	1606.2
15	2001	Honda	64	17	746	27	1589.8
16	2001	Honda	66	14	1847	26	2474.9
17	2002	Honda	51	17	1240	29	1475.1
18	2003	Honda	38	19	1024	31	1245.6
19							
20							
21							
22							
23							

4.6.3 Creating a Custom Report Sheet

4.6.3.1 Summary

Worksheets in Origin can be customized by merging cells and coalescing various objects such as graphs, external images, links to variables and tables/cells in other sheets, into a custom report.

This tutorial will show you how to add a custom report to an existing analysis template. You can then import new data, recalculate results, and export or print the custom report.

Note: This tutorial suggests that you can drag-and-drop data files onto Origin. If you do so, [please do not run Origin as administrator](#).

Minimum Origin Version Required: Origin 9.0 SR0

4.6.3.2 What you will learn


- How to create a custom report sheet
- How to save a custom report as part of an Analysis Template (OGW) and re-use it with new data

4.6.3.3 Steps

Note: Please complete the previous tutorial named "[Creating and Using Analysis Templates](#)" in which an analysis template named **MySensorData.OGW** is created.


Importing Data


- Using the **File:Open** menu item, set the **Files of type** drop-down to **Workbooks (*.ogw)**, then navigate to and open the Analysis Template **MySensorData.OGW**. This analysis template was saved with a linear fit analysis for column B of the first worksheet, and a customized embedded graph with the data and the linear fit line (note that templates do not contain data, so at this point, you see no data and no results).

- Make the **Data** worksheet active, and click the **Import Single ASCII** button  to directly import the file **Sensor01.dat** under *<Origin EXE Folder>\Samples\Curve Fitting* path.


Note: You can also locate the **Sensor01.dat** file in your local drive, drag and drop it into this **Data** sheet to import.

Creating a Custom Report Sheet

- Right-click on the **Data** worksheet and select **Add** to add a new worksheet. Rename this worksheet as **Custom Report**.
- Activate the **Custom Report** sheet and choose **Format:Worksheet** (or hit **F4**) to open the **Worksheet Properties** dialog. Go to the **Size** tab and under the **Size** node, set **Row Number** as **20** and **Column Number** as **9**. Then go to the **Miscellaneous** tab and check the **Auto Add Rows** check box. Click **OK** to apply these settings and close the dialog.
- In the worksheet, click and drag on the row headers for **Long Name**, **Unit**, **Comments** and **F(x)=** to select these four rows. Then right click and select **Delete** from the context menu. This removes the three rows from the worksheet.
- Highlight the range of the cells in the first three rows for all columns and click the **Merge Cells** button  located in the **Styles** toolbar to merge the cells. Enter the text **Sensor Data Analysis Report** in this merged cell.
- In the 5th row, merge the cells in columns G and H. Repeat for the 6th row. In row 5, column F, enter the text **File Name:** In row 6, column F, enter the text **File Date:**.
- Right click the merged (column G and H) cells in row 5 and choose **Insert Variables** from the context menu. Make sure the dialog settings look like those in the image below and insert the **FILENAME** variable into this cell.




7. Right click the merged (column G and H) cells in row 6 and choose **Insert Variables** from the context menu. Insert the **FILEDATE** variable following the settings in the image below:




8. Right click on the cell containing the date information and choose **Format Cells** from the context menu. Change the **Format** drop-down to **Date** and click **OK**.
9. Go to the **FitLinear1** worksheet and locate the **Parameters** table. Click the triangle button next to it and choose **Copy Table** from the fly-out menu.
10. Go to the **Custom Report** sheet and select the 9th row in column E. Right click and choose **Paste Link**. Clear the pasted text **Sensor Output** in column E by pressing the **Delete** key.
11. In the 13th row, merge the cells in columns G and H. Do the same in the 14th row.
12. Return to the **FitLinear1** sheet and in the **Statistics** table, select the two data cells for **Pearson's r** and **Adj. R-Square**. Right click and choose **Copy** to copy only these two cells.
13. Go to the **Custom Report** sheet and select the merged cell in the 13th row, then right-click and choose **Paste Link**. The two merged cells are filled with corresponding values. Enter the text **Pearson's r** and **Adj. R-Square** in the cells to the left of these pasted values.
14. In the 8th row, merge the three cells in columns F, G and H. Do the same in rows 12 and 20. Enter the text **Fit Parameters**, **Fit Statistics** and **Report Date: \$(@D, D1)** in rows 8, 12 and 20, respectively.

15. Right click on the merged cells in row 20 and choose **Set Data Style:Rich Text** from the context menu. By enabling rich text, the string **\$(@D,D1)** will display as the actual system date.
16. Hold the CTRL key and select all cells with numeric values, then right-click and choose **Format Cells** in context menu, then choose **Set Decimal Places=** from the **Digits** drop-down menu, and enter **3** as **Decimal Number**, and press OK.
17. Using buttons in the **Style** and **Format** toolbars, change cell borders, font sizes, styles and colors to customize the report as in the image below. You may also need to manually adjust the width of some columns to ensure that all text is displayed.



18. Go to the **FitLinear1** sheet and double-click on the graph under **Fitted Curves Plot** to open the embedded graph. Right click on the graph's title bar and choose **Duplicate** from the context menu to duplicate the graph window (Graph1). Double click on the axis of duplicated graph to bring up **Axis** dialog. Go to **Scale** tab under both **X Axis** and **Y Axis** and choose **Auto** from the **Rescale** drop-down list. Then close the original embedded graph window.
19. Return to the **Custom Report** worksheet, right click on the gray area of this worksheet and select **Add Graph** from context menu. In the **Graph Browser**, select **Graph1** which was created by duplicating the embedded graph. Click **OK** to add this graph to this worksheet as a floating chart.


20. You can manually resize and move this floating chart using its anchor points and position it anywhere in the worksheet.
21. Go to **Format:Worksheet** (or press **F4**) to open the **Worksheet Properties** dialog. In the **View** tab, under the **Show Grid Lines** node, clear the check boxes next to **Column Grid** and **Row Grid**. On the **Format** tab, make sure **Apply To** is set to **Data**, and select **Show Missing as Blank** to show missing values as blank instead of displaying the "--" characters. Press **OK** to close this dialog.
22. Select **File:Print Preview** to preview the custom report. It should look similar to the image below:



Saving the Analysis Template

1. Activate the workbook and select **File:Save Workbook as Analysis Template**.
2. Browse to a desired file path and enter the file name **SensorDataReport** and click **Save**.
3. You can use this **SensorDataReport.OGW** as an Analysis Template for future analyses of similar data, and the custom report will also be included in the workbook.

Re-using the Analysis Template

1. Start a new project and then select the menu item **File: Recent Books** and from the fly-out options select the Analysis Template **SensorDataReport.ogw** which was saved earlier.
2. Make the **Data** worksheet active, and click the **Import Single ASCII** button  to directly import the file **Sensor02.dat** under *<Origin EXE Folder>\Samples\Curve Fitting* path.

Note: You can also locate the **Sensor02.dat** file in your local drive, drag and drop it into this **Data** sheet to import.

3. The linear fit results and the custom report are automatically generated using the newly imported data.

4.7 Analysis Themes

4.7.1 Summary

In Origin 8, analysis procedures can be controlled by Themes. Themes are actually XML files which save settings in the analysis dialog. For example, after performing the analysis, there will now be a <Last Used> theme for this dialog which has saved the most recently used settings. You can assign a proper name for the theme and use it in the future.

For this tutorial, the Statistics on Columns dialog will be used to demonstrate how to create and use an analysis theme. This analysis provides descriptive statistics about the data such as mean, standard deviation, minimum, maximum, and more. For visualization, a histogram or box chart can also be created in the Analysis Result Sheet.

Minimum Origin Version Required: Origin 8.0 SR6

4.7.2 What you will learn

This tutorial will show you how to:


- Perform simple descriptive statistics
- Create an Analysis Theme
- Use the theme

4.7.3 Steps

4.7.3.1 Save the analysis procedure as Theme

1. Start with a new workbook and import the file `\Samples\Statistics\automobile.dat`.
2. Highlight column C and use the menu item **Statistics: Descriptive Statistics: Statistics on Columns** to open the dialog.
3. Select **Quantities** tab, then expand the **Moments** tree node, and check the *N Total*, *Mean*, *Standard Deviation*, *SE of Mean* and *Sum* box.
4. Expand the **Plots** tree node, and check the *Histograms* and *Box Charts* check boxes. You will then get the corresponding histogram as well as box chart graphs.

5. Your selections in this analysis dialog can be saved as your theme, so that you may easily repeat the procedure. Click the arrow to the right of Dialog Theme and choose **Save as...** ...



... to bring up this dialog:



6. Type a proper theme name, such as "MyTheme" and click **OK**.
7. Click the **OK** button in the **Statistics on Columns** dialog. Results are reported to a new worksheet named DescStatsOnCols1.

Descriptive Statistics

	N total	Mean	Standard Deviation	SE of mean	Sum
Power	340	79.85	28.07561	1.52261	27149




You can save a customized dialog theme as default, so it will be used every time you open the dialog of analysis operation. To do this, choose **Save as <Default>** to save the current dialog theme as the default setting of this dialog. It is also possible to delete the default theme and roll back to system default, to do this, choose **Delete** from the fly-out menu.


4.7.3.2 Repeat the analysis procedure by Theme

Once you save a theme, there are many ways to use it. For example, you can highlight column E and perform the same statistical analyses on it.


- Open the **Statistics on Columns** dialog from the **Most Recently Used** items at the bottom of the **Statistics** menu. Most of the menu accessible dialogs can be opened from MRU menus.



When you open the dialog from MRU, the default theme is <Last Used>. To use the **MyTheme** theme, select *MyTheme* from the **Dialog Theme** shortcut menu. The settings from that theme will then be displayed in the dialog. Click the **OK** button to do the analysis.



- Another way to apply the analysis theme is to use the cascaded menu item. Once you use an analysis dialog for the first time after installation, or save a theme for a dialog, there will be one more menu level added. You can choose the *MyTheme* menu.



When selecting, *Open Dialog...*, the dialog will open to the <Factory Default> theme. To change the settings of your theme, you can select your theme name from the **Dialog Theme** shortcut menu inside the dialog, make changes, and resave the theme. Alternatively, to open a dialog with a saved theme without performing the analysis, hold down the *shift* key while selecting the theme from the menu. This will bring up the dialog with your theme applied so you can make changes as needed.

4.8 Batch Processing

- [Batch Processing Multiple Files using Analysis Template](#)
- [Batch Processing Multiple Datasets using Analysis Template](#)
- [Batch Processing with Summary Report in External Excel File](#)
- [Batch Processing with Word Template for Reporting](#)
- [Batch Processing Grouped Datasets Using Analysis Template with Multi-Data Sheets](#)

4.8.1 Batch Processing Multiple Files using Analysis Template

4.8.1.1 Summary

Origin can perform batch analysis of multiple files or datasets, using an Analysis Template. This tutorial will focus on batch analysis of files.

4.8.1.2 What You Will Learn

This tutorial will show you how to:



- Perform batch processing with multiple data files using an analysis template

4.8.1.3 Steps


Adding a Result Sheet with Quantities to Summarize for Each File


Note: First follow the steps in the previous tutorial "[Creating a Custom Report Sheet](#)" and create the Analysis Template **SensorDataReport.ogw**.

1. Start with a new project.
2. Use **File:Open** to open the **SensorDataReport.ogw** created from the previous tutorial "[Creating a Custom Report Sheet](#)".

3. Make the **Data** worksheet active, click the **Import Single ASCII** button , browse to the folder <Origin EXE Folder>\Samples\Curve Fitting\ and import the file **Sensor01.dat** .
4. Go to the **FitLinear1** sheet, find the **Summary** table, click the triangle button next to it and choose **Create Copy As New Sheet** from fly-out menu. The table contents are copied to a new sheet named **Summary**.
5. Go to **Summary**, delete the first column (highlight, right-click and choose **Delete** from the fly-out menu) and click the  button to add a new column to this worksheet (this new column will be column A).
6. Go to the **FitLinear1** sheet and in the **Statistics** table, click on the cell with text **Pearson's r**, then right-click and choose **Copy**. Go back to **Summary**, right-click the cell in column A, **Parameters** row, and select **Paste Link** to paste the parameter label.
7. Go back to the **FitLinear1** sheet and this time, right click on the cell with the value of Pearson's r and select **Copy**. In **Summary** right-click in the row 1 cell of column A and select **Paste Link** to paste the value as a link.
8. Copy the contents in the **Long Name** cell of column F and **Paste Link** in the **Long Name** cell of column A.
9. Rename **Summary** as **Result**, then use **File:Save Workbook As Analysis Template** menu to save this modified analysis template as **BatchSensorData.ogw**.

Performing Batch Processing with Multiple Data Files

1. Start with a new project.
2. Click on the **Batch Processing** button .
3. For **Batch Processing Mode** select the **Load Analysis Template** button.
4. In the **Analysis Template** drop-down, select the **BatchSensorData.ogw** file we saved earlier (you may need to click the button to the right of the list and browse to the saved file).
5. Select **Import From Files** in the **Data Source** drop-down list.
6. Click on the **Browse** button in the **File List** section and select the **Sensor01.dat**, **Sensor02.dat** and **Sensor03.dat** from the <Origin EXE Folder>\Samples\Curve Fitting folder.
7. Click **Add File(s)**, then click **OK**.
8. Select **File Name** as **Dataset Identifier**.
9. Make sure the **Data Sheet** drop-down is set as **Data**.
10. Make sure the **Result Sheet** drop-down is set as **Result**.
11. Make sure that **Delete Intermediate Workbook** is cleared.



12. Click **OK**. All three data files will be analyzed, and a workbook including the custom report will be created for each file (from the Main Menu, choose **Window:Cascade** to see all windows). Also, a **Summary** workbook is generated. This workbook contains summarized analysis results from the three **Result** sheets in the analysis template.

	A(Y)	B(Y)	C(y/Er±)	D(Y)	E(y/Er±)	F(Y)	G(Y)
Long Name	Dataset	Intercept	Intercept	Slope	Slope	Statistics	Statistics
Parameters		Value	Standard Error	Value	Standard Error	Adj. R-Square	Pearson's r
1	Sensor01.dat	0.11883	0.50426	1.44803	0.07839	0.9471	0.97462
2	Sensor02.dat	-0.85811	0.36326	2.62654	0.05647	0.99129	0.99587
3	Sensor03.dat	0.4598	0.43614	4.43734	0.0678	0.99558	0.99791
4							
5							
6							
7							

4.8.2 Batch Processing Multiple Datasets using Analysis Template

4.8.2.1 Summary

Origin can perform batch analysis of multiple files or datasets, using an Analysis Template. This tutorial will focus on batch analysis of datasets.

4.8.2.2 What You Will Learn



This tutorial will show you how to:


- Perform batch processing with multiple datasets using an analysis template

4.8.2.3 Steps

Note: First follow the steps in the previous tutorial "[Batch Processing Multiple Files using Analysis Template](#)" and create the Analysis Template **BatchSensorData.ogw**.


Prepare Datasets for Batch Processing

1. Start with a new workbook.
2. Click the **Import Wizard** button  on the **Standard** toolbar to open the **Import Wizard** dialog box.
3. Click the browser button  to the right of the **File** box. Browse to the <Origin EXE folder>\Samples\Curve Fitting\ folder, select the files **sensor01.dat**, **sensor02.dat** and **sensor03.dat**, and add them to the lower panel of the file dialog. Click **OK** to return to the **Import Wizard** dialog.
4. Note that the **Import Filter for Current Data Type** drop-down changes to show **Origin Folder: ASCII**. Change **Import Mode** to **Start New Columns**.
5. Click **Next** to navigate to the **File Name Options** page.
6. Select the **file name to column comments** box to fill the *Comment* of each column with the imported file name. Clear the **Include path when appending file name** box. Click **Finish** to import the data.



7. Select to highlight all the six columns of the worksheet, then right click and select **Set As: XY XY** from the shortcut menu. You will have a worksheet with three pairs of XY columns.

Performing Batch Processing with Multiple Columns

1. Make the worksheet with the three pairs of XY columns active.
2. Highlight columns **A(X1)** through **F(Y3)**.
3. Select **File: Batch Processing** from the menu or click the **Batch Processing** button .
4. Select the **Load Analysis Template** check box for the **Batch Processing Mode**.
5. In the **Analysis Template** drop-down, select the **BatchSensorData.ogw** file we saved earlier.
6. Select **Use Existing XY Datasets** from the **Data Source** drop-down list.
7. Select **Comments** for the **Dataset Identifier**.
8. Make sure the **Data Sheet** drop-down is set to **Data**.
9. Make sure the **Result Sheet** drop-down is set to **Result**.
10. Make sure **Delete Intermediate Workbook** is cleared.



- Click **OK**. All three pairs of XY columns will be analyzed, and a workbook including the custom report will be created for each file. Also a **Summary** workbook will be generated, displaying the summarized analysis results based on the **Result** sheet in the template.

	A(Y)	B(Y)	C(yEr±)	D(Y)	E(yEr±)	F(Y)	G(Y)
Long Name	Dataset	Intercept	Intercept	Slope	Slope	Statistics	Statistics
Parameters		Value	Standard Error	Value	Standard Error	Adj. R-Square	Pearson's r
1	Sensor01.dat	0.11883	0.50426	1.44803	0.07839	0.9471	0.97462
2	Sensor02.dat	-0.85811	0.36326	2.62654	0.05647	0.99129	0.99587
3	Sensor03.dat	0.4598	0.43614	4.43734	0.0678	0.99558	0.99791
4							
5							
6							
7							

4.8.3 Batch Processing with Summary Report in External Excel File

4.8.3.1 Summary


This tutorial is associated with the Sample Origin Project: **\Samples\Batch Processing\Batch Processing with Summary Report in External Excel File.OPJ**

Minimum Origin Version Required: Origin 8.1 SR2

4.8.3.2 What you will learn

- How to perform batch processing of multiple data files
- How to send results to an external Excel file and save that file

4.8.3.3 Steps

1. Make the 'Raw Data' Worksheet in the 'Book1' Workbook active.
2. Select **File : Batch Processing...** from the menu or click the **Batch Processing** button  on the Standard Toolbar.
3. Select the **Repeatedly Import into Active Analysis Template Window** radio.
4. Set **Data Source** as **Import From Files**.
5. Check the **Use Import Setting in Workbook** check box.
6. Click the ... browse button next to **File List**.
7. Select **All Files (*.*)** in Files of Type and browse to Origin's \Samples\Batch Processing folder.
8. Select all 10 .csv files in the folder, click **Add File(s)** then click **OK**.
9. **Dataset Identifier** should be set to **None**.
10. **Data Sheet(s)** should be set to 'Raw Data'. Note: 'Raw Data' is the first sheet of 'Analysis Template', it will be renamed as the file name of last import file by default if this template has already been used and re-saved.
11. **Result Sheet** should be set to 'My Results'.
12. Click the button to the right of the "Output Sheet" edit box. *This will minimize the main dialog.* Then click on the title bar of the Excel book (Book2), and press the button to the right of the scrolled up dialog to expand it again.
13. Expand the Options branch and check the **Clear Output Sheet on Start** check box and enter **7** as the **Starting Row of Output Sheet**.
14. Check the **Append Label Rows** check box.
15. Click OK

4.8.4 Batch Processing with Word Template for Reporting

4.8.4.1 Summary

Origin can perform batch analysis of multiple files and output cell-linked analysis results to an external Word template for reporting.

Minimum Origin Version Required: Origin 2016 SR0

4.8.4.2 What you will learn

This tutorial will show you how to:

- Add bookmarks from a Word template to a specific Analysis Template
- Link analysis results to bookmarked cells in Word template and adjust the sizes of graphs to be exported
- Sending one time results to Word template for reporting
- Perform batch analysis of multiple files and export results to Word/PDF files

4.8.4.3 Steps

In this tutorial we will use a built-in Word template *Sensor Analysis Report.dotx* which is located at <Origin EXE folder>\Samples\Batch Processing\ folder. To view the bookmark labels on the Word template, with the file open go to **File: Options** to open **Word Options** dialog. Then select **Advanced** on the left panel and scroll down to section **Show document content** on the right panel and check **Show bookmarks** checkbox there.

Document1 - Word

FILE HOME INSERT DESIGN PAGE LAYOUT REFERENCES

Paste Font Paragraph Styles Editing

Clipboard

OriginLab

20+ years serving the scientific and engineering community

One Revolution Plaza, Suite 303

Northampton, MA 01060

USA

Sensor Data Analysis Report

File Name: [FileName]

File Date: [FileDate]



Summary Table		
Intercept	[InterceptValue]	± [InterceptError]
Slope	[SlopeValue]	± [SlopeError]
Adj. R-Square	[RSquare]	


[FittedGraph] [ResidualPic]

Fitted Curve Plot Residual Plot

PAGE 1 OF 1 47 WORDS 70%


Add Bookmarks to Analysis Template


1. Go to menu **File: Open** and browse to <Origin EXE folder>\Samples\Batch Processing\ folder, select file **Sensor Analysis.ogw** to open it.
2. Activate worksheet *Data*, click button  and browse to <Origin EXE folder>\Samples\Curve Fitting\ folder and select file **Sensor01.dat** to import data for analysis.
3. Go to menu **File: Add Word Bookmarks to Analysis Template...** to open dialog. Click the browser button  to the right of the **Word template** box and browse to <Origin EXE folder>\Samples\Batch Processing\ folder to select **Sensor Analysis Report.dotx**.
4. Click to select all bookmark entries in **Bookmarks** list under **Select Bookmarks** node and click **OK** button to add those bookmark entries to active analysis template.



Link Analysis Results to Word Template

1. Right click cell next to *FileName* bookmark in *Links* column (**Long Name**) and select **Insert Variable**.
2. In appeared dialog, click **Info** tab and select **FILENAME** under **SYSTEM.IMPORT** treenode. Click **Insert** button to insert it.
3. Do the same to insert info variable for bookmark **FileDate**. To make it display as normal date, right click that cell and select **Format Cells**.
4. Select **Date** from **Format** drop-down list and click **OK** button to close dialog.

5. For graph bookmark *FittedGraph*, right click the cell in *Links* column (**Long Name**) in newly generated worksheet **Bookmarks** to select **Insert Graph** to open dialog. In appeared dialog, click the browser button  to the right of the **Graphs** box to open **Graph Browser** dialog. Check **Show Embedded Graph** checkbox on the bottom left to make embedded graphs available in panel on the left. Click to select desired graph and add it to panel on the right. Click **OK** to insert graph to **Bookmarks** worksheet.



Then input graph width for instance 250, in unit of points in *GraphWidth* (**Long Name**) column to adjust the size of graph exported to Word report.

6. Do the same to insert graph for bookmark *ResidualPlot*.
7. For bookmarks related to parameter values, you can copy and paste values as link from report sheet. To do it, click report sheet *Linear Fit of Data B "Sensor Output"* and locate the **Parameters** table. Click the corresponding data cell and right click to select **Copy**. Return to **Bookmarks** sheet, right click desired cell in *Links* column and select **Paste Link** to build the connection between bookmarks in Word template and values in report sheet.
8. Repeat this "Copy and Paste Link" operation to fill in the rest of bookmark links. When done, select menu **File: Save Workbook as Analysis Template...** to save the analysis template as **Sensor Analysis Template.ogw** .

	A(X)	B(Y)	C(Y)
Long Name	Bookmarks	Links	GraphWidth
Comments		1. For meta data, right click and select "Insert Variables". 2. For analysis results, copy from the report sheet, and then paste link. 3. For graph, right click and select "Insert Graph", or copy from the report sheet and then paste link.	If the link is a graph, specify the width to be set in the export word report for this graph, by unit of points(72 point=1 inch).
Word Template		C:\Program Files\OriginLab\Origin2016\Samples\Batch Processing\Sensor Analysis Report.dotx	
1	FileName	Sensor01.dat	
2	FileDate	12/11/2015	
3	FittedGraph		250
4	ResidualPlot		250
5	InterceptValue	0.11883	
6	InterceptError	0.50426	
7	SlopeValue	1.44803	
8	SlopeError	0.07839	
9	RSquare	0.9471	



You can follow the steps in the previous tutorial "[Creating a Custom Report Sheet](#)" to learn how to copy and paste results as link to desired cell.

Sending One Time Results to Word Template to Create Word Report



Sometimes we may just want to analyze one data file and quickly create one Word report. Continue from the example above, suppose we have all results linked to Word bookmarks as shown in *Bookmarks* worksheet, to create an one time Word report for active sheet you can simply click Export


to Word button on the top left corner to create it.

You can further specify where to output the Word report in appeared **Export Path** dialog.

Batch Process and Export Results to Word/PDF Files


1. Start with a new project.
2. Click on the **Batch Processing** button .
3. Make sure **Load Analysis Template** is selected as **Batch Processing Mode**. In the **Analysis Template** drop-down, select the **Sensor Analysis Template.ogw** file we created earlier (you may need to click the button to the right of the list and browse to the created file).
4. Select **PDF** from **Export to** drop-down list to export report as PDF file.
5. Click the browser button to the right of the **Word template** box and browse to <Origin EXE folder>\Samples\Batch Processing\ folder to select **Sensor Analysis Report.dotx**.

6. Optionally you can click browser button  on the right of **Export Path** to specify another path for export.
7. Click on the **Browse** button  in the **File List** section and select the **Sensor01.dat**, **Sensor02.dat** and **Sensor03.dat** from the <Origin EXE Folder>\Samples\Curve Fitting folder.
8. Click **Add File(s)**, then click **OK**.
9. Select **File Name** as **Dataset Identifier**.
10. Make sure the **Data Sheet** drop-down is set as **Data**.
11. Make sure the **Result Sheet** drop-down is set as **Result**.
12. Make sure that **Delete Intermediate Workbook** is cleared.



The location of exported PDF files was outputted to **Message Log**.

A sample of exported PDF version report is as following:



4.8.5 Batch Processing Grouped Datasets Using Analysis Template with Multi-Data Sheets

4.8.5.1 Summary

Origin can perform batch analysis on grouped datasets using an analysis template with multiple data sheets.

Minimum Origin Version Required: 2016 SR0

4.8.5.2 What you will learn

This tutorial will show you how to:

- Create a multi-data sheets analysis template
- Perform batch analysis on grouped datasets using analysis template

4.8.5.3 How the Analysis Template Works

The reference multi-data sheets analysis template **Multi-Data Sheets Analysis.ogw** that we are going to make is located in <Origin EXE Folder>\Samples\Batch Processing folder. This analysis template will process 10 CSV files located in <Origin EXE Folder>\Samples\Batch Processing folder in group of 5. Every 5 data files will be imported into the sequential data sheets in the analysis template and a non-linear fit will be conducted to obtain the peak area and its standard error of each curve. Eventually we will perform linear fit to peak area versus temperature data extracted from file name and output the results.

4.8.5.4 Steps

Create Multi-Data Sheets Analysis Template

Import CSV Files into Sequential Data Sheets

1. Create a new workbook. Go to menu **File: Import: Comma Delimited (CSV)...** to open **CSV** dialog.
2. Browse to <Origin EXE Folder>\Samples\Batch Processing folder and select the first five data files, make sure **Files of type:** is selected as *.csv, then click **Add Files(s)** and **OK** button to open **Comma Delimited(CSV): impCSV** dialog.
3. Expand **Import Options: Header Lines** node, select **Number of Subheader Lines** as 2, **Long Name** as 1 and **Units** as 2. Click **OK** to finish import.

Perform Nonlinear Fit to Obtain Peak Area

4. Highlight column 2 in sheet *T275k*, hold Ctrl + Y or go to menu **Analysis: Fitting: Nonlinear Curve Fit** to open **NLFit** dialog.
5. Select **Gauss** as **Function** in **Origin Basic Functions** category.
6. Click **Fit** button to perform the fitting. Click **OK** in the prompt to close it.
7. Repeat steps 4, 5, 6 for data *T285k*, *T295K*, *T305K*, *T315K* to obtain peak areas for all five peaks.

Prepare Data for Linear Fit

8. Right click sheet tab *FitNLCurve5* and select **Add** to add a worksheet. Double click on the name and input *TempData* as sheet name.
9. Hold Ctrl+D to open **Add New Columns** dialog and input 2 in the edit box to add 2 extra columns. Click **OK** button to close dialog.
10. Set the **Long Name** of the 4 columns as *Data File*, *Temperature*, *Area Value*, *Area Error*, respectively.
11. Right click the first data cell in column *Data File* and select **Insert Variable** to open dialog. Right click the node of workbook *T315K* on the right panel and check **Show Sheet Level** item to show sheets under it. Then click *T275K* sheet on the right panel and click **Label** tab on the left panel. Click property **Name** to highlight that row and click **Insert** button to insert sheet name into this cell.
12. Repeat this step for other four sheets to add the sheet name to column *Data File*.
13. Next we want to extract the temperature number from sheet name in first column, to do so highlight column *Temperature* and right click to select **Set Column Values...** Input formula below in the edit box to extract the middle 3 numbers from file name and click **OK** to close dialog and apply.

```
Value (mid (col ("Data File"), 2, 3) $)
```

14. Go to sheet *FitNL1* and highlight the two value cells under area **A** section in *Summary'* node. Right click to select **Copy** to copy the data. Then go to *TempData* sheet and paste link the data in the first row in column *Area Value* and *Area Error*. Repeat this step for other four data files.

15. Set the designation of column *Temperature* as **X**, column *Area Error* as **Y Error**.

Perform Linear Fit and Create Result Sheet

16. Highlight column *Area Value* and *Area Error* and go to menu **Analysis: Fitting: Linear Fit** to open dialog, select **Recalculate** mode as **Auto**, click **OK** to perform linear fitting and close the dialog. Click **OK** in appeared prompt to close it.

17. Right click sheet tab *FitLinearCurve1* and select **Add** to add a new sheet and name it as *Results*.

18. Hold Ctrl + D to open **Add New Columns** dialog and input 3 in edit box to add 3 new columns.

19. Set the **Long Name** of the 5 columns as *Intercept Value*, *Intercept Error*, *Slope Value*, *Slope Error* and *Adj. R-Square*, respectively.

20. Go to sheet *FitLinear1*, copy the 5 value cells under **Summary** node and go back to *Results* sheet and click the first cell in first data row to paste as link.


21. Go to menu **File: Save Workbook As Analysis Template...** to save it as an analysis template and name it as *Multi-Data Sheets Analysis*.

Batch Analyze Files in Groups


In <Origin EXE Folder>\Samples\Batch Processing folder, we have 10 CSV data files. Suppose now we want to group the files as two groups and re-order them as: group 1 as *T365K*, *T345K*, *T325K*, *T305K*, *T285K*; group 2 as *T355K*, *T335K*, *T315K*, *T295K*, *T275K*. After we will process those two grouped files using the analysis template we created in section above.

1. Go to menu **File: Batch Processing...** to open dialog, click the more options button next to **Analysis Template** edit box to browse to analysis template **Multi-Data Sheets Analysis.ogw**.

2. Click the more options button next to **File List** edit box to bring up **Open** dialog. Firstly drag and drop CSV files one by one to re-order them as shown below and click **Add File(s)** button to add the files to list. Click **OK** button to exit dialog.



3. Select **File Name** as **Dataset Identifier**, **Results** sheet as **Result Sheet** and uncheck **Delete Intermediate Workbook**.



4. Click **OK** button to start processing. The results will be outputted to **Summary** workbook as shown below:

	A(Y)	B(X)	C(Y)	D(Y)	E(Y)	F(Y)
Long Name	Dataset	Intercept Value	Intercept Error	Slope Value	Slope Error	Adj. R-Square
Units						
Comments						
F(x)=						
1	T365K.csv, T345K.csv, T325K.csv, T305K.csv, T285K.csv	13815.20722	7263.08994	141.51071	22.90197	0.90286
2	T355K.csv, T335K.csv, T315K.csv, T295K.csv, T275K.csv	5799.63634	5098.28296	167.08504	16.51348	0.96204
3						
4						
5						

5 Statistics

5.1 Descriptive Statistics

- [Descriptive Statistics](#)
- [Cross Tabulation](#)
- [2D Binning](#)
- [Distribution Fit](#)
- [Partial Correlation Coefficient](#)

5.1.1 Descriptive Statistics

5.1.1.1 Summary

Origin provides comprehensive Descriptive Statistics support including basic statistics (mean, median, variance, etc.), frequency counts, and correlation coefficients of your data sets. In addition to strong plotting features, Origin's statistical tools help you summarize and analyze your data.

This tutorial will show you how to:

- Use the **Statistics on Column** dialog to calculate descriptive statistics for grouped data.
- Copy statistical results to a new worksheet for further processing.
- Sort worksheet data by the attribute values in a designated column.
- Analyze data sets with the **Correlation Coefficient** Tool.


Minimum Origin Version Required: Origin 2015 SR0

5.1.1.2 Finding Frequency Information for Groups

We will use the **Discrete Frequency** tool to quickly obtain frequency information for groups of data.

1. Open a new workbook. From the Menu Bar select **File: Import: SingleASCII: Statistics|automobile.dat**.
2. Highlight the first two columns in the **automobile** worksheet. From the Menu Bar, select **Statistics: Descriptive Statistics: Discrete Frequency: Open Dialog**. Change the **Recalculate** mode to **Auto**. To make operation in the source data worksheet [Controlling the](#)

[Categorical Values section](#) working, change the **Sort Data By** to **Categorical Order**. Then click **OK**.





3. The resultant worksheet **DiscretFreq1** displays data and its counts for automobile Year and Make, respectively.




In spite of the fact that there are locks on the columns, the worksheet can be rearranged by highlighting the desired column, going to the Menu Bar, selecting **Worksheet:Sort Worksheet**, and selecting **Ascending**, **Descending**, or **Custom** from there.



5.1.1.3 Calculating Descriptive Statistics on Grouped Data

Basic statistical treatments can be performed on the data in individual columns using the **Statistics on Columns** tool.


1. Return to the **automobile** worksheet. From the Menu Bar, select **Statistics: Descriptive Statistics: Statistics on Columns: Open Dialog...**
2. In the **Statistics on Columns** dialog box, in the **Input** tab, expand **Range 1** and click the interactive button  to the right of **Data Range**. Return to the worksheet, select column **C** and drag to column **G**. Click the interactive button again to restore the dialog box. In the dialog box, after adjusting **Input Data**, **Range 1** and **Grouping Range**, click the context menu button  and select **B(Y): Make**. Change the **Recalculate** mode to **Auto**.



3. In the **Output** tab, in the **Graph** group, check the **Arrange Plots of Same Type in One Graph** box. Also, in the **Plots** tab, check the **Box Charts** check box.



- Click **OK** to get the results in a report sheet.






In order to modify an individual box plot, open it with a double-click. When the modification is complete, click the **Close** button in the top right corner of the plot. The modified box plot will then be restored to the report sheet.

5.1.1.4 Using Statistical Results for Further Operations


It is possible to perform further data analysis and to plot the statistical results.

For example, to obtain average attribute values (i.e. horsepower, 0-60 mph time, weight, mileage) by Vehicle Make from 1992 to 2004, perform the following:

- Return to the **automobile - automobile.dat** workbook, and open the **DescStatsQuantities1** worksheet. Highlight the **D(Y2)** and the **E(yEr±)** columns, go to the Menu Bar and select **Worksheet: Unstack Columns: Open Dialog...**
- In the **wunstackcol** dialog box, change the **Recalculate** mode to **Auto**, select **Group Columns** and click the context menu button  and select **A(X1) Data**.
- Expand **Options** and check the **Include Other Columns** box. On **Other Columns**, click the context menu button  and select **A2:(X) Make**. Set **Matching Longest Group** as Extract Rule for Other Columns Values, expand **Output Settings**, and from **Put Grouping Info. to**, select **Long Name**. Click **OK**.




4. To see the results, open worksheet **UnstackCols1**, highlight the worksheet, and from the Menu Bar, select **Plot: Multi-Panel: Stack**.
5. In the **Plotting:plotstack** dialog box, set **Plot Type** to **Scatter**. Click **OK**.
6. Now we are going to rotate the tick labels at top X axis for clarification. Double click on the top X axis tick labels to open the **Axis** dialog, and set the following in **Top** icon. Click **OK**.



Rotate the Tick Labels for bottom in the same way.

7. The report sheet and the graph will appear as shown below:




5.1.1.5 Analyzing the Relationship Between Different Indicators

Use a correlation coefficient to explore the relationship between columns of the automobile data. Next, construct scatter plots with confidence ellipses to obtain graphical representations of the correlations.

1. In the **automobile - automobile.dat** workbook, open the **automobile** worksheet, and highlight the last five columns.

- From the Menu Bar, select **Statistics: Descriptive Statistics: Correlation Coefficient: Open Dialog....** In the corrcoeff dialog box, expand **Correlation Types** and check the **Pearson** box.
- Expand **Plots** and check the **Add Confidence Ellipse** box. The **Scatter Plot** check box will be automatically selected. Click **OK**.
- The **ScatterMatrix1** and **CorrCoeff1** worksheets should appear as below; demonstrating the high positive correlation between **Engine Displacement** and **Power**, and the high negative correlation between **Gas Mileage** and **Engine Displacement**.




5.1.1.6 Controlling the Categorical Values

- In the following steps, we want to customized the order of values shown in the graph but not change the source data. Right click Column **B** in workbook, select **Set As Categorical** in the context menu, double click the **Categories** cell of the column, "Unsorted", to open the **Categories** dialog.


	A(X)	B(Y)	C(Y)	D(Y)
Long Name	Year	Make	Power	0~60 mph
Units			kw	sec
Comments				
F(x)=				
Sparklines				
Categories		Unsorted		
1	1992	Buick	132	14
2	1992	Acura	154	12

- Uncheck **<auto>** checkbox, use     to adjust position of each item to follow the image below, in this way we can sort the items by country of the manufacturers, which is U.S.->Japanese/Korea->Europe. Click **OK** to close the dialog.






- You can go to the report sheet created in section above. Because **Auto** mode is used for recalculation, the report sheet of **Discrete Frequencies** and **Statistics on Columns**,

including the box charts, are updated automatically with the specified order of the Categorical data.



4. The results of **Unstacked Columns** and the stacked graph are updated automatically as well.



Note: If the operation hasn't been auto-updated, you can also manually trigger the operations by clicking the **Recalculate** button  in the **Standard** toolbar. The button will turn green  after recalculation is done

5.1.2 Cross Tabulation

5.1.2.1 Summary

Cross tabulation is particularly useful for analyzing categorical data. In these analyses, a contingency table is used to display the frequency distribution of two or more variables. Analyses based on the table can determine whether there is a significant relationship between variables, and assess the strength of the relationship between the variables.

Minimum Origin Version Required: Origin 2016 SR0

5.1.2.2 What you will learn

This tutorial will show you:





1. How to perform the Cross Tabulation.
2. How to interpret the results.


5.1.2.3 User Story

Our data are from the **Montana Economic Outlook Poll** conducted in May 1992, with accompanying demographics for 209 out of 418 poll respondents. We have data on seven variables: **Age**(under 35, 35-54, 55 and over), **Sex**(male, female), **Financial Status**(worse, same, or better than a year ago), etc. With the data, we want to learn:

1. The frequency distribution of financial status in three different age groups, and whether male and female differ in the distribution.
2. Whether there is significant relationship between "Financial status" and "Age" for male and female groups.
3. The strength of the relationship.

5.1.2.4 Preparing Data for Analysis

1. Open a new project or a new workbook. Import the data file
\\Samples\Statistics\MontanacOutlookPoll.dat
2. We begin by sorting the categorical values.
 - On the **MontanacOutlookPoll** worksheet, highlight column **B** and right click to select **Set As Categorical**. Double-click on **Unsorted** in the Categories label row to open the **Categories** dialog box. Check **Customize Categories (Add, Delete, Set Arbitrary Order)** box. Then use the Move To Top , Move Up , Move Down  and Move To Bottom buttons  to reorder categories as "under 35", "35-54" and "55 and over":




- Repeat the same steps for column **C** so that the categorical mapping is **<Female, Male>**
- Repeat the same steps for column **G** so that the categorical mapping is **<Better, Same, Worse>**




To exclude missing values from analysis, we should [set the columns as categorical](#). Otherwise the missing values will be kept as numeric values.

5.1.2.5 Performing Cross Tabulation


1. Open the Cross Tabulation dialog by choosing the menu item **Statistics: Descriptive Statistics: Cross Tabulation**.
2. Click on the **Input** tab. The data is in raw data mode, so select column **B**, **G** and **C** for **Row**, **Column** and **Layer**, respectively.




- Click on the **Statistics** tab, uncheck the **Expected Counts**, **Residuals**, **Standardized Residuals** and **Adjusted Residuals** and accept all the other default settings.



- On the **Tests** tab, select the **Chi-Square Test** check box. Expand the **Measures of Association** branch, and then select the **Contingency Coefficients**, **Phi**, and **Cramer's V** boxes (for measuring nominal association).



5. Click on the **Output** tab and select the **Mosaic Plot** check box. Accept the other default settings and click **OK**.




5.1.2.6 Interpreting The Results

Go to sheet **Crosstab1**

Frequency Distribution


We can get frequency distribution information from the **Mosaic Plot** and the **Contingency Table**. The area of each rectangle in the **Mosaic Plot** is proportional to the percentage of the Y variable for each level of the X variable, so we can visually compare the frequency distribution of "Financial status" and "Age" for female, male and total. From the **Contingency Table** we can get more specific information. Combining the **Mosaic Plot** with **Contingency Table**, we learn:

1. There is a major difference between young and old women's views.
 - A majority of young women, 59.5%, feel they have better financial status. A majority of old women, 58.3% think their financial status remains the same.
 - Fewer young women, 11.9%, think their wealth status remains the same, while fewer old women, 11.1% think that they are better off financially.




		"Financial Status"				
		Better	Same	Worse	Total	
"Age"	Under 35	Count	25	5	12	42
		Row%	59.52381	11.90476	28.57143	100
		Col%	64.10256	15.15152	41.37931	41.58416
		Total%	24.75248	4.9505	11.89119	41.58416
	35-54	Count	10	7	6	23
		Row%	43.47826	30.43478	26.08696	100
		Col%	25.64103	21.21212	20.68966	22.77228
		Total%	9.90099	6.93069	5.94059	22.77228
	55 and over	Count	4	21	11	36
		Row%	11.11111	58.33333	30.55556	100
		Col%	10.25641	63.63636	37.93103	35.64356
		Total%	3.9604	20.79208	10.89109	35.64356
Total	Count	39	33	29	101	
	Row%	38.61386	32.67327	28.71287	100	
	Col%	100	100	100	100	
	Total%	38.61386	32.67327	28.71287	100	

2. Compared to women, men's feeling for financial status shows another interesting pattern:
 - Men show no significant difference in financial status between age groups.
 - Men at peak-age are a little more likely to be confident of their financial status.



3. Regardless the sex of respondents, there are some trends by age:
 - Younger people are more likely to be confident of their financial status
 - Older people are more likely to feel that their financial status did not change.



		"Financial Status"					
		Better	Same	Worse	Total		
"Age"	Under 35	Count	34	16	21	71	
		Row%	47.88732	22.53521	29.57746	100	
		Col%	47.88732	21.05263	35	34.29952	
		Total%	16.42512	7.72947	10.14493	34.29952	
	35-54	Count	26	23	17	66	
		Row%	39.39394	34.84848	25.75758	100	
		Col%	36.61972	30.26316	28.33333	31.88406	
		Total%	12.56039	11.11111	8.21256	31.88406	
	55 and over	Count	11	37	22	70	
		Row%	15.71429	52.85714	31.42857	100	
		Col%	15.49296	48.68421	36.66667	33.81643	
		Total%	5.31401	17.8744	10.62802	33.81643	
Total	Count	71	76	60	207		
	Row%	34.29952	36.71498	28.98551	100		
	Col%	100	100	100	100		
	Total%	34.29952	36.71498	28.98551	100		

Detecting Relationships Between Age and Financial Status

The **Chi-Square Tests** Table show test results for the independence of row and column variables. If the **Prob>ChiSq** is less than 0.05, this means the row and column variables, in this case age and financial status, are significantly related. Note the conclusions in the footnotes beneath the table. We conclude that:

- Women of different ages differ in financial status.
- In contrast, there is no evidence to show an association between men's age and their financial status.
- Regardless sex, people of different ages usually differ in financial status.

Chi-Square Tests T

		ChiSquare	df	Prob > ChiSq
Sex = Female	Pearson Chi-Square	24.88134	4	5.31505E-5
	Likelihood Ratio	27.39901	4	1.65075E-5
Sex = Male	Pearson Chi-Square	2.61078	4	0.62491
	Likelihood Ratio	2.68512	4	0.61182
Sex = Total	Pearson Chi-Square	20.67931	4	3.66559E-4
	Likelihood Ratio	22.06371	4	1.94652E-4

Sex = Female:
According to Pearson Chi-Square test:
At the 0.05 level, there is significantly evidence of association between two variables.

Sex = Male:
According to Pearson Chi-Square test:
At the 0.05 level, there is NOT significantly evidence of association between two variables.

Sex = Total:
According to Pearson Chi-Square test:
At the 0.05 level, there is significantly evidence of association between two variables.

Assessing the Strength of the Relationship

The **Measures of Association** table helps in assessing the strength of the relationship between "Financial status" and "Age". As this is a 3*3 table(three levels for Age and three levels for Financial status), we can choose a **Contingency Coefficient** to compare across layers. (See the [introduction page](#) for the difference of the three statistics). From the table we can see

- Women's financial status shows a stronger association with age than is the case with men. (0.444 v.s. 0.155)

Measures of Associ


		Value
Sex = Female	Phi	0.49634
	Cramer's V	0.35096
	Contingency Coefficient	0.44459
Sex = Male	Phi	0.15694
	Cramer's V	0.11097
	Contingency Coefficient	0.15504
Sex = Total	Phi	0.31607
	Cramer's V	0.2235
	Contingency Coefficient	0.30137

Cramer's V, Contingency Coefficients: Values range from 0 to 1. A larger value indicates the stronger association of two variables. Gamma, Kendall, Somer's D: Values range from -1 to 1. A positive value means one ordinal variable increases with the other. Lambda, Uncertainty Coefficient: Values range from 0 to 1. A larger value indicates better prediction of Y by X.

5.1.3 2D Binning

5.1.3.1 Summary

The 2D Frequency Count/Binning operation counts the frequencies for data with two variables. A 3D bar graph and/or an image plot of the results can be generated, giving a graphic representation of data distribution.




Minimum Origin Version Required: Origin 2015 SR0

5.1.3.2 What you will learn



- How to count the frequencies for data with two variables.
- How to plot 2D binning into 3D Histogram.

5.1.3.3 Steps



1. Select File: Open Sample *Projects: Analysis: Statistic page: 2D Frequency Count/Binning*, Activate the 3D Histogram.dat book.
2. Highlight column A and column B, select menu **Statistics: Descriptive Statistics: 2D Frequency Counts/Binning** to bring up the **TwoDBinning** dialog.
3. Specify the following settings in the dialog box:
 - Uncheck the **Auto** checkbox, set the **Bin Size** for X to 40.
 - Set the **Bin Size** for Y to 15.



- Check on **Output Matrix** checkbox in the end of the dialog and check on **3D Bars** for **Matrix Plot**.

Output Worksheet  

Subtotal Count for Each Binned Y

Output Matrix  

Matrix Plots

3D Bars

Image Plot

4. Click the **OK** button, then you will get the following outputs:


- o **Worksheet**

A(X)	B(Y)	C(Y)	D(Y)
Bin Ends of "Tensile Strength"	Count	Count	Count
	120 - 135	135 - 150	150 - 165
	135	150	165
840	0	0	1
880	0	0	1
920	1	0	3
960	0	0	7
1000	0	2	4
1040	1	3	9
1080	0	2	3

- o **Matrix**


	1	2	3	4
1	0	0	1	0
2	0	0	0	0
3	1	1	3	7
4	0	0	2	17
5	0	3	14	32
6	0	1	11	42
7	0	0	10	37
8	0	0	10	17
9	0	0	1	6

- o **3D Histogram**



5.1.3.4 Further Customizations


4. Double click the 3D Histogram to go to the **Plot Details** dialog, go to the **Colormap** tab, click the **Fill** button to open the **Fill** tab, specifies the **Fill** tab follows the graph below



Click **OK** to close the **Fill** tab, and click **OK** in **Plot Details** to close the dialog.

5. Double click the Axis to open the **Axis** dialog and go to **Scale** tab, specifies the **Scale** for XYZ axis follows the graphs below:

- Change the scale for X axis in X icon form 820 to 1220 with *Major Ticks* value 40.



- Change the scale for Y axis in Y icon form 127.5 to 277.5 with *Major Ticks* value 15.
 - Change the scale for Z axis in Z icon form 0 to 100 with *Major Ticks* value 20.
6. Change title for X, Y, Z axis in **Title** tab into *Tensile Strength*, *Brinell Hardness* and *Number of Tests*, respectively. Click **OK** to apply the setting and close the dialog.

5.1.4 Distribution Fit

5.1.4.1 Summary

Knowing the distribution model of the data helps you to continue with the right analysis. or make estimation of your data. The **Distribution Fit** tool helps users to examine the distribution of their data, and estimate parameters for the distribution.

5.1.4.2 What you will learn

This tutorial will show you:

- How to carry out distribution fit for practical data with Origin
- How to interpret the generated results

5.1.4.3 User Story

A house builder is trying to decide how many new houses he should build in the next year based on past sales of houses in the surrounding area. He would like to know the following:

- If he is going to build 80 new houses, what is the probability that all of them will be sold?
- The builder believes that he can make a profit if there is at least a 60% probability that he will sell all of his houses. How many houses should he build?

To solve this problem, The house builder needs to:


- Perform a distribution fit to sample data (houses sold in the surrounding area)
- Select the best fitting distribution
- Calculate the probability using the cumulative distribution function of the selected distribution
- If the probability is more than 60%, reconsider the schedule.

5.1.4.4 Choosing Distributions

1. Start with a new project or a new workbook. Import the data file:

\\Samples\Statistics\HouseSold.dat

2. Highlight Column B, select **Plot: Statistics: Histogram** from Origin menu




3. Consider the facts as below to choose the distributions:


- The data are taken on integer values only so we can consider to fit both continuous and discrete distributions. (If there are floating point numbers, only continuous distributions can be considered). However, as usually continuous distributions provide better fit than discrete distributions we want to choose from continuous distributions.
- Value of new house sold are positive values, we don't need to consider the normal distribution, which can take on negative values
- Look at the histogram, the data is clustered around a value, we don't need to consider the exponential distribution, which is for data extremely asymmetric

5.1.4.5 Performing Distribution Fit


1. Return to the **HouseSold** worksheet and highlight the column B. From the Menu Bar, select the **Statistics: Descriptive Statistics: Distribution Fit** menu
2. In the dialog that opens, in the **Distributions** tab, clear **Normal** and select the following three distributions based on the conclusions in the [Choosing Distributions](#) section
 - **LogNormal**
 - **Weibull**
 - **Gamma**



3. In the **Plots** tab, select **Probability Plot**



4. In the **Goodness of Fit** tab, check all three methods. Click **OK** to apply the settings and close dialog.




5.1.4.6 Comparing and Selecting Fitting Models

We can compare and select a fitting model based on the following results of distribution fit:

- **Probability (P-P) Plot**

The closer all the scatter points are to the reference line, the better the distribution is for the dataset. From the Probability Plot, both lognormal and gamma distribution can be considered as good models for the data.



- **Goodness of Fit Tests table**

Look at the P-values in table, if the p-value is less than 0.05, it means we reject the distribution at the 0.05 level. P-value of lognormal and gamma are larger than 0.05, then from the **Goodness of Fit Tests**, we can see that both lognormal and gamma are good models for the data.

Goodness-of-Fit Tests

	Distribution	Goodness of Fit tests	Statistics	P-value	Decision at level(5%)
New House Sold	Lognormal	K-S test	0.03457	0.45539	Can't reject Lognormal
		K-S modified test	0.03295	0.0998	Can't reject Lognormal
		A-D test	0.68316	0.07408	Can't reject Lognormal
	Weibull	K-S modified test	0.06783	<=0.01	Reject Weibull
		A-D test	4.90331	<0.01	Reject Weibull
	Gamma	K-S test	0.02828	0.74285	Can't reject Gamma
		K-S modified test	0.02797	>0.25	Can't reject Gamma
		A-D test	0.54291	0.18207	Can't reject Gamma

From the **Probability (P-P) Plot** and **Goodness of Fit Tests** table, we can draw a conclusion that lognormal and gamma are both good choices. Here we choose the lognormal as an example for further analysis.

5.1.4.7 Making Estimations

Once the best distribution model is found, we can use the CDF and INV functions to calculate these probabilities:

- If he is going to build 80 new houses, what is the probability that all of them will be sold?
- How many houses should be built if he hopes to have a 60% chance of selling all of the houses?

1. To answer the first question, open the **Command Window** or the **Script Window** from the **Windows** menu, and type commands as below

```
logncdf(80, 3.94262, 0.35614) =
```

2. where 3.94262 is mu and 0.35614 is sigma, obtained from the **Parameter Estimates** table in the Report Sheet.

Parameter Estimates

	Distribution	Parameter	Estimate	Lower 95%	Upper 95%
New House Sold	Lognormal	Location mu	3.94262	3.91452	3.97072
		Scale sigma	0.35614	0.33679	0.37661
	Weibull	Scale alpha	61.47763	59.76193	63.24259
		Shape beta	2.95464	2.78884	3.1303
	Gamma	Shape alpha	8.18942	7.34083	9.13611
		Scale theta	6.69975	5.98501	7.49985

- 3.
4. You will get

```
logncdf(80, 3.94262, 0.35614) = 0.89136185728793
```

5. We can conclude that if the house builder builds 80 new houses, there is an 89% probability that he will NOT sell all of those houses.

1. To answer the second question, run the script below in the **Command Window** or the **Script Window**

```
logninv(1-0.6, 3.94262, 0.35614) =
```

2. You will get

```
logninv(1-0.6, 3.94262, 0.35614) = 47.105650533425
```

3. We can conclude that the house builder is more likely to make a profit if he builds 47 new houses.



We choose the lognormal model in [Choosing Distribution section](#) so we use logncdf and logninv for the estimation. If we choose gamma, we can use [gamcdf](#) and [gaminv](#) for the estimation, which will result in a similar conclusion.

Notes: There are also other descriptive statistics and graphs in results of **Distribution Fit** which help you to take a quick look of your data

- **Descriptive Statistics** table
- **Quantiles** table
- **Histogram**
- **Box Chart**
- **CDF** (Cumulative Distribution Function Plot)

5.1.5 Partial Correlation Coefficient

5.1.5.1 Summary

The Partial Correlation Coefficient is a tool for measuring the the linear relationship between two random variables, after excluding the effects of one or more control variables.

5.1.5.2 What you will learn

This tutorial will show you:


- How to carry out partial correlation in Origin, using a practical example.
- How to interpret the generated results.

5.1.5.3 User Story

We have some public data from the World Bank that includes 11 indicators (health expenditure, GDP, population, etc.) by country, for years 2000 to 2010. We want to study the relationship between internet use, mobile phone use and health expenditures in the United States.

5.1.5.4 Detect Relationship with Pearson's R

1. Choose menu **File: Open Sample OPJ: Statistics Improvements in Origin 2016** to open the OPJ.
2. Click the Project Explorer tab and browse to the folder *Partial Correlation Coefficient*.
3. Activate **Sheet1** with source data. We have already applied a data filter to get data for the United States between 2000 and 2010.
4. First we will use the **Correlation Coefficient** tool to visually detect the relationship between **Mobile phone subscribers, Total internet users, Health expenditures per capita** and the **GDP per capita**.
 1. Press the **Ctrl** key and highlight **Col(E), Col(U1), Col(H)** and **Col(S)**.
 2. From the menu, select **Statistics: Descriptive Statistics: Correlation Coefficient**.
 3. In the opened dialog, select the **Scatter plots** and **Add Confidence Ellipse** check boxes under the **Plots** branch. Clear the **Show Significance in Result Table** check box and select the **Flag Significant Correlations** check box.



5. From the Pearson's correlation coefficient and the scatter matrix, we can see:

4.

Tutorials for Origin

- The scatter data are fairly linear.
- The shape of confidence ellipses is narrow.
- All Pearson's correlation coefficients are flagged in red.
- Each Pearson's correlation coefficient is larger than 0.9.


It appears that there is a strong relationship between **Mobile phone subscribers**, **Total internet users**, **Health expenditures per capita** and **GDP per capita**.



5.1.5.5 Revealing the Real Relationship with Partial Correlation Coefficients

Though it appears that **Mobile phone subscribers**, **Total internet user** and **Health expenditure per capita** are strongly related, we know that **GDP per capita** also affects these three indicators. We want to measure the real relationship of the three indicators after excluding the effect of **GDP per capita**.

1. Activate the sheet with source data. Press the **Ctrl** key and highlight **Col(E)**, **Col(U1)** and **Col(H)**.
2. Choose menu **Statistics: Descriptive Statistics: Partial Correlation Coefficient**.
3. In the opened dialog, the three highlighted columns are automatically selected as **Variables**.
4. We want to remove the effect of **GDP per capita**, so we choose **Col(S)** as **Controlling Variables**. Select the **Flag Significant Correlations** check box.



5. Go to sheet **PCorr1**. It contains the partial correlation coefficients after excluding the effect of **GDP per capita**. We can see:
 - Only **Mobile phone subscribers** and **Health expenditures per capita** are significantly related (The Partial Corr value is marked as red). But the real relationship is not as strong as the **Pearson's r** seemed to show previously. (Partial Corr = 0.87307 v.s. Pearson's Corr = 0.99157).
 - The Partial correlation coefficient for **Mobile phone subscribers** and **Total internet users** decreased to be 0.26178. They are not significant related.
 - There is no evidence to show **Total internet users** and **Health expenditures per capita** are related (Partial Corr = 0.07615), while previously, we obtained a Pearson's r = 0.96685.

	Business: Mobile phone subscribers	total internet user	Health: Health expenditure per capita (current US\$)
Partial Correlations	Partial Correlations	Partial Correlations	Partial Correlations
Business: Mobile phone subscribers	1	0.26178	0.87307
total internet user	0.26178	1	0.07615
Health: Health expenditure per capita (current US\$)	0.87307	0.07615	1

5.1.5.6 Conclusion

Why such different results? Looking at the Pearson's r value of **GDP per capita** between the other three indicators, we can see **GDP per capita** influenced the three indicators. Even though there is no relationship between **Total internet users** and **Health expenditures per capita**, **Total internet users** and **Mobile phone subscribers**, the "false relationship" is still shown by the Pearson's r because of the effect of **GDP per capita**. Partial Correlation Coefficients are useful for examining the true relationship between two factors by eliminating the effects of correlated control variables. The statistic is useful for experiments where various interrelated phenomena are to be studied.

5.2 Hypothesis Tests

5.2.1 Summary

Hypothesis tests are frequently used to measure the quality of sample parameters or to test whether estimations for two samples on a given parameter are equal .

With parametric methods,assumptions are made about the underlying distribution from where the sample populations are selected. Usually, it requires that the data are independently sampled from a normal distribution.

5.2.2 What you will learn

This tutorial will show you:

- How to carry out hypothesis tests for practical data with Origin
- How to interpret the generated results

5.2.3 Steps

5.2.3.1 Hypothesis Tests in Origin

Data Type	Goal	Method
One Sample	Compare the mean with a given value	One-Sample t-Test
	Compare the variance with a given value	One-Sample Test for Variance
Two Samples	Test whether the means are equal	Two-Sample t-Test
	Test whether the variance are equal	Two Sample Test for Variances
Paired Samples	Test whether the means are equal	Pair-Sample t-Test


5.2.3.2 One-Sample t-Test


Perform One-Sample t-Test using Raw data

Suppose a manufacturer produces high-quality screw nuts that must equal 21 millimeters in diameter. The quality control department randomly drew 120 nuts from the finished products, measured the diameters for each and stored the results in Diameters.dat file.They want to determine whether the mean diameter of the nuts is equal to 21 or not. Historically, the distribution of the measured diameters is known to be approximately normal, but the standard deviation of the population is unknown. Hence they may use the One-Sample t-Test in Origin following the steps below:

1. Start with a new workbook and import the file `\Samples\Statistics\diameter.dat`.

2. Open the **One-Sample t-Test** dialog by using the menu item **Statistics:Hypothesis Testing:One-Sample t-Test**.
3. Click the **Input** tab, set **Input Data Form** to **Raw**.
4. Click the arrow button to the right of **Input** and select *A(X):diameter*.
5. Click the **t-Test for Mean** tab and set **Test Mean** to 21; Make sure that **Alternate Hypothesis** is set to *Mean <> 21* (two-sided test), check **Confidence Interval(s)** and set **Confidence Level(s) in %** to 95.





6. Note that by default the test procedure provides descriptive statistics of the variable and the hypothesis test results. Additionally, it is possible to produce a histogram of the data and a confidence interval for the mean.
7. Click the **OK** button to finish the analysis and generate results.

The Descriptive Statistics table shows the sample size, mean, standard deviation, and standard error for the variable. The sample mean, 21.00459, is comparatively little bigger than the hypothesis mean 21, and the standard error of the mean(SEM) is 0.00156.

Descriptive Statistics

	N	Mean	SD	SEM
"diameter"	100	21.005	0.0156	0.00156

From the t-Test table, the t statistic (2.9437) and the associated p-value (0.00404) provide evidence that the average diameter of screw nuts is significantly different with 21 at the $\alpha = 0.05$ level.

Test Statistics

	t Statistic	DF	Prob> t
"diameter"	2.9437	99	0.00404

Null Hypothesis: Mean = 21
 Alternative Hypothesis: Mean <> 21
 "diameter": At the 0.05 level, the population mean is significantly different from the test mean (21).

The confidence interval indicates that it is 95% confident that the true mean of the variable lies within the interval [21.0015, 21.00769].


Confidence Intervals for Mean

	Conf. Levels in %	Lower Limits	Upper Limits
"diameter"	95	21.0015	21.00769

Perform One-Sample t-Test using Summarized data

To perform a One-Sample t-Test using summarized data, we need to change the **Input Data From** in **Input** tab into **Summarized data**.

Assume we have measured 70 nuts this time, so the sample size will be 70. After a further calculation, we have got 20.95 for the mean, and 0.218 for the standard deviation. So we enter the mean, standard deviation and sample size into the **Input** Box below:



Then, we set 21 as the **Test Mean** in **t-Test for Mean** tab, click **OK** to execute.

We get the summary table shown below, the results indicate that the population mean is NOT significantly different from the test mean in this study.

Test Statistics

	t Statistic	DF	Prob> t
Summarized Data	-1.91895	69	0.05913

Null Hypothesis: Mean = 21
 Alternative Hypothesis: Mean <> 21
 At the 0.05 level, the population mean is NOT significantly different from the test mean (21).

5.2.3.3 Pair-sample t-Test

Perform Pair-sample t-Test using Raw data


Suppose you want to compare abrasion resistance between two kinds of tires. You randomly draw from each type of tires respectively and group them into 8 pairs. Make sure each pair consists of two

types of tires. Next, equip the paired tires on 8 planes to run the abrasion test and measure the abrasion data to do paired-sample t-test.

1. Start with a new workbook and import the file `\Samples\Statistics\labrasion_raw.dat`.
2. Open the **Pair-sample t-Test** dialog by using the menu item **Statistics:Hypothesis Testing:Pair-sample t-Test**.
3. On the **Input** tab, set column *tireA* as **1st Data Range** and column *tireB* as **2nd Data Range**.
4. Click the **t-Test for Mean** tab and enter 0 to be **Test Mean**.

Descriptive Statistics

	N	Mean	SD	SEM
"diameter"	100	21.005	0.0156	0.00156



5. Accept other settings as default and click the **OK** button to generate results.

Descriptive Statistics

		N	Mean	SD	SEM	Median
"tireA"		8	6145	1366.49709	483.12968	5760
"tireB"		8	5825	1097.46461	388.01233	5420
	Difference	8	320	319.68735	113.02655	320
	Overall	16	5985	1208.63008	302.15752	5600

Test Statistics

	t Statistic	DF	Prob> t
	2.83119	7	0.02536

Null Hypothesis: mean1-mean2 = 0
 Alternative Hypothesis: mean1-mean2 <> 0
 At the 0.05 level, the difference of the population means is significantly different from the test difference(0).


From the t-Test table, the t statistic (2.83119) and the associated p-value (0.02536) indicate that the difference between the two means is significant, that is to say, the two types of tires have different abrasion resistance.

Perform Pair-sample t-Test using Summarized data

Perform Pair-Sample t-Test using Summarized data

To perform a Pair-Sample t-Test using summarized data, we need to change the Input Data From in Input tab into Summarized data.

Assume 16 samples has been tested this time, so the sample size will be 16. After a further calculation, we have got 305 for the mean paired difference, and 310 for the standard deviation for the difference between paired data points (please refer to Algorithms: [Pair Sample T-Test](#)). So we enter the mean difference, standard deviation and sample size into the Input Box below:



Since our data yielded a p-value of 0.0013, which is less than our 0.05 a-level, we can reject the null hypothesis.

Test Statistics			
	t Statistic	DF	Prob> t
Summarized Data	3.93548	15	0.00132

Null Hypothesis: mean1-mean2 = 0
 Alternative Hypothesis: mean1-mean2 <> 0
 At the 0.05 level, the difference of the population means is significantly different from the test difference(0).

This study indicates the difference between the two means is significant, thus, the two types of tires have different abrasion resistance.


5.2.3.4 Two-Sample independent t-Test

Perform Two-Sample t-Test using Raw data

A physician is evaluating the effect of two kinds of soporifics. To test the effectiveness of these two medicines, 20 insomniacs patients are randomly selected. Half took medicine A and the other half took medicine B, The extended sleeping time were recorded after each patient took the medicine. The result is saved as the time_raw.dat file.

To determine whether the two medicine have different effect on patients, we could carry out a two-sample independent t-test with the following steps:

1. Start with a new workbook and import the file **\\Samples\Statistics\time_raw.dat**.
2. Open the **Two-Sample t-Test** dialog by using the menu item **Statistics:Hypothesis Testing:Two-Sample t-Test**.
3. On the **Input** tab, select **Raw** for the **Input Data Form**; set *medicineA* as **1st Data Range** and *medicineB* as the **2nd Data Range**.



- Accept other settings as default and click the **OK** button to generate results.

The t-Test procedure automatically provides two tests of the mean difference. One is based on the assumption that the variances of two samples are equal and the other is not. In this example, both tests indicate that there is no significant evidence for a difference in cure effects between medicine A and medicine B. (p-values are 0.0738 and 0.074, both greater than the significance level 0.05.)

t-Test Statistics


	t Statistic	DF	Prob> t
Equal Variance Assumed	1.89811	18	0.07384
Equal Variance NOT Assumed (Welch Correction)	1.89811	17.8248	0.074

Null Hypothesis: mean1-mean2 = 0
 Alternative Hypothesis: mean1-mean2 <> 0
 At 0.05 level, when equal variance is assumed, Mean1 - Mean2 is NOT significantly different from 0
 At 0.05 level, when equal variance is NOT assumed, Mean1 - Mean2 is NOT significantly different from 0


Perform Two-Sample t-Test using Summarized data

To perform a Two-Sample t-Test using summarized data, we need to change the **Input Data Form** in **Input** tab into **Summarized data**.

Assume 50 patients has been tested this time, so the sample size will be 50. After a further calculation, we have got 2.33 for the 1st mean, and 1.858 for the 1st standard deviation, and 1.28 for the 2nd mean, and 1.671 for the 2nd standard deviation. So we enter the mean, standard deviation and sample size into the Input Box below.



We can also check on the Confidence Intervals (Levels in 95%) in **t-Test for mean** tab, to calculate the difference between test groups. Click **OK** to execute.



Since our data yielded a p-value of 0.0037, which is less than our 0.05 α -level, we can reject the null hypothesis. This study indicates that the mean extended sleeping of two patients groups are not the same. In fact, we can conclude that 1st soporific has a stronger effect on patients.

The Confidence Intervals show that we can be 95% confident that the mean time difference between two groups is 0.3487~1.7513

t-Test Statistics			
	t Statistic	DF	Prob> t
Equal Variance Assumed	2.97118	98	0.00373
Equal Variance NOT Assumed (Welch Correction)	2.97118	96.91755	0.00374

Null Hypothesis: mean1-mean2 = 0
 Alternative Hypothesis: mean1-mean2 \neq 0
 At 0.05 level, when equal variance is assumed, Mean1 - Mean2 is significantly different from 0
 At 0.05 level, when equal variance is NOT assumed, Mean1 - Mean2 is significantly different from 0


Confidence Intervals for Mean			
Conf. Levels in %	Lower Limits	Upper Limits	
95	0.3487	1.7513	



Note that both equal variance and unequal variance assumptions are supported. To determine whether the two samples have equal variances, we may select from top menu **Statistics:Hypothesis Testing:Two-Sample Test for Variance** to use the two-sample test for variance for testing

5.2.3.5 Two-Sample Test for Variance

1. Continue with a new workbook and import the file \Samples\Statistics\time_raw.dat.
2. Open the **Two-Sample Test for Variance** dialog by using the menu item **Statistics:Hypothesis Testing:Two-Sample Test for Variance**.
3. Select "Raw" for the **Input Data Form**; set column A and column B as the first and second data range respectively.



- Accept other settings as default and click the **OK** button to generate results.

Descriptive Statistics				
	N	Mean	SD	Variance
"medicineA"	10	2.35	1.97611	3.905
"medicineB"	10	0.75	1.78901	3.20056

F Statistics				
	F	Numer. DF	Denom. DF	Prob > F
	1.2201	9	9	0.77181

Null Hypothesis: Variance1/Variance2 = 1
 Alternative Hypothesis: Variance1/Variance2 <> 1
 At the 0.05 level, the two population variances are NOT significantly different.

According to result , $P_value=0.77181 > 0.05$, therefore ,it fail to reject null hypothesis, so two population variances are not signification difference.

5.3 ANOVA

- [One Way ANOVA](#)

- [One-Way Repeated Measures ANOVA](#)
- [Two Way ANOVA](#)
- [Two Way Repeated Measures ANOVA](#)
- [Two-Way Mixed-Design ANOVA](#)
- [Three-Way ANOVA](#)

5.3.1 One Way ANOVA

5.3.1.1 Summary

Statistics has two modes of data input; indexed and raw. When a statistical analysis is performed, there is usually no need to use an entire data set; Origin provides several methods of data selection. For example, the interactive **Regional Data Selector** button can be used in the graphical selection of data, or the **Column Browser** dialog can be employed to make the selection.

In this tutorial, you will learn how to use the two methods of data input so that the Analysis of Variance (ANOVA) statistical test can be performed.

ANOVA is a parametric method for means comparison of several groups, and it is also an extension of two independent sample t-tests. ANOVA is more powerful than multiple t-tests since it controls the chance to commit type I error better when the number of groups is relatively large. For example, when comparing the means among 5 groups using a t-test, ten multiples of the t-test, each with a significant level of 0.05, are performed, resulting in an overall chance to commit type I error of $1-(1-0.05)^{10}=0.599$. Under the same circumstances, the chance to commit type I error in ANOVA is 0.05. ANOVA requires normality and equal variance. If these requirements are not met, non-parametric analysis should be used.

Minimum Origin Version Required: Origin 2016 SR0

5.3.1.2 What You Will Learn

This tutorial will show you how to:

- Use different input data modes in the statistical analysis dialog
- Do normality tests
- Perform one-way ANOVA

5.3.1.3 Steps

Origin can perform ANOVA from an indexed data mode, or from a raw data mode.

When an indexed data mode is used, the data needs to be organized in a factor column and a data column.

	A(1)	B(1)
Long Name	plant	nitrogen
Comments	Factor	Data
1	PLANT3	18.15473
2	PLANT3	12.90409
3	PLANT2	18.61197
4	PLANT1	17.7111
5	PLANT4	11.81661
6	PLANT3	11.68327
7	PLANT2	23.43165
8	PLANT2	14.01454

When a raw data mode is used, the data needs to be organized with different levels in different columns.


	A(1)	B(1)	C(1)	D(1)
Long Name	Plant1	Plant2	Plant3	Plant4
Comments	Level1	Level2	Level3	Level4
1	17.7111	18.61197	18.15473	11.81661
2	32.15046	23.43165	12.90409	2.39438
3	17.70871	14.01454	11.68327	1.09914
4	28.07729	12.17685	23.52293	16.00756
5	7.83567	4.86902	16.00594	13.85077
6	2.06008	18.93963	3.04056	9.22245
7	22.81923	29.92086	14.29516	14.86523

Indexed Data Mode


Nitrogen content, in milligrams, has been recorded for 4 kinds of plants. We are interested to know whether different plants have significantly different nitrogen content. As a result, we will use the index data mode in One-Way ANOVA analysis.

1. Start with a new workbook. From the Menu Bar, click **File:Import:Single ASCII...**, browse to the *Samples\Statistics* folder and double click on **nitrogen.txt**. In the **Import and Export:impASC** dialog box, click the **OK** button.
2. Next, we perform a normality test on each group of data to determine whether it follows a normal distribution. Highlight the first column of the workbook and from the Menu Bar, select **Worksheet: Sort Worksheet: Ascending**.
3. From the Menu Bar, select **Statistics: Descriptive Statistics: Normality Test: Open Dialog**. In the **Normality Test** dialog, in the **Input** tab, expand **Input Data** and **Range 1**. Press the triangle

button at the right of **Data Range** and select **B(Y): nitrogen**, then press the triangle button at the right of **Group** and select **A(X): plant**. Click **OK**.




- With the **nitrogen** worksheet active, go to the Menu Bar and open **Statistics: ANOVA: One-Way ANOVA...**. In the **ANOVAOneWay** dialog box, in the **Input** tab, set **Input Data** to **Indexed**. Pressing the triangle button at the right of **Factor**, select **A(X): plant** and pressing the triangle button at the right of **Data**, select **B(Y): nitrogen**.



- In the **Means Comparison** tab, check the **Tukey** check box; In the **Tests for Equal Variance** tab, check the **Levene** check box; In **Power Analysis** tab, select **Actual Power** check box; In the

Plots tab, check the **Means Plot[SE as Error]** and the **Means Comparison Plot** check boxes. Click **OK**.



Result Interpretations

- On the ANOVA1Way1 report sheet, you will see a **Homogeneity of Variance Test** node. If results are not visible, click to expand the node. Because the p-value is greater than 0.05, the four groups are considered to have equal variance.

Levene's Test(Absolute Deviations)

	DF	Sum of Squares	Mean Square	F Value	Prob>F
Model	3	18.06843	6.02281	0.34578	0.79229
Error	76	1323.76846	17.41801		

At the 0.05 level, the population variances are not significantly different.

- The ANOVA table (Overall ANOVA) reports a p-value that is smaller than 0.05, hence at least two of the four groups have significantly different means.

Overall ANOVA

	DF	Sum of Squares	Mean Square	F Value	Prob>F
Model	3	1996.36652	665.45551	12.86214	6.99338E-7
Error	76	3932.05317	51.73754		
Total	79	5928.41969			


Null Hypothesis: The means of all levels are equal.
 Alternative Hypothesis: The means of one or more levels are different.
 At the 0.05 level, the population means are significantly different.

- Expanding the results of "Means Comparisons" reveals further information regarding relationships between groups.


Tukey Test

	MeanDiff	SEM	q Value	Prob	Alpha	Sig	LCL	UCL
PLANT2 PLANT1	2.26308	2.27459	1.40706	0.75274	0.05	0	-3.71181	8.23796
PLANT3 PLANT1	-2.46538	2.27459	1.53284	0.70039	0.05	0	-8.44027	3.5095
PLANT3 PLANT2	-4.72846	2.27459	2.93989	0.16935	0.05	0	-10.70334	1.24643
PLANT4 PLANT1	-10.93833	2.27459	6.80085	4.38499E-5	0.05	1	-16.91322	-4.96345
PLANT4 PLANT2	-13.20141	2.27459	8.20791	8.24355E-7	0.05	1	-19.1763	-7.22653
PLANT4 PLANT3	-8.47295	2.27459	5.26801	0.00207	0.05	1	-14.44784	-2.49807

- Here we see that the mean of PLANT4 differs significantly from the other three groups. Looking at the **Means Plot** and **Means Comparison Plot**, we can see that PLANT4 has the smallest mean and is significantly different from the other three groups.



Means Comparison using Tukey Test



- In the "Powers" table, **Actual Power**=0.99976, that is, the chance of a Type II error occurring is almost equal to zero.

Powers			
	Alpha	Sample Size	Power
Actual Power	0.05	80	0.99976

Raw Data Mode

1. Start with a new workbook. From the Menu Bar, click **File:Import:Single ASCII...**, and double click on **nitrogen_raw.txt**. In the **Import and Export:impASC** dialog box, click **OK**.
2. Highlight all columns, and from the Menu Bar, click **Statistics : ANOVA : One-Way ANOVA**. In the **ANOVAOneWay** dialog, in the **Input** tab, set **Input Data** to **Raw**, and click **OK**.
3. Repeat the examination of analysis results and you will see that we reach the same conclusions as we did when using **Indexed data mode**.

	A(X)	B(Y)	C(Y)	D(Y)
Long Name	Plant1	Plant2	Plant3	Plant4
Units				
Comments				
F(x)=				
Sparklines				
1	17.7111	18.61197	18.15473	11.81661
2	32.15046	23.43165	12.90409	2.39438
3	17.70871	14.01454	11.68327	1.09914
4	28.07729	12.17685	23.52293	16.00756
5	7.83567	4.86902	16.00594	13.85077
6	2.06008	18.93963	3.04056	9.22245
7	22.81923	29.92086	14.29516	14.86523
8	6.22726	22.32084	26.2977	8.1437
9	12.25362	20.46398	27.19654	0.89452



If the **Level Name** is set to **Auto**, it will follow the column long name of the selected data.

5.3.2 One-Way Repeated Measures ANOVA

5.3.2.1 Summary

One-way repeated measures ANOVA is similar to one-way ANOVA, but deals with a dependent variable subjected to repeated measurements. In this situation, the independence assumption of general one-way ANOVA is not tenable, since there is probably a correlation between levels of the repeated factor.

Similar to one-way ANOVA, one-way repeated measures ANOVA can be employed to test whether the means are equal or not. These means include the mean of different measurements and the mean of different subjects. The results will be shown in the table named *Test of Within-Subjects Effect* and *Test of Between-Subjects Effect* respectively. Note that the repeated measures ANOVA in Origin requires balanced sample data, that is, equal sample size at each level.

Minimum Origin Version Required: Origin 8.6 Pro SR0

5.3.2.2 What you will learn

This tutorial will show you how to:


- Input indexed data into the statistical analysis dialog.
- Perform One-way Repeated Measures ANOVA.
- Interpret results of a One-way Repeated Measures ANOVA analysis.


5.3.2.3 Steps

Origin can perform **One-Way Repeated Measures ANOVA** in both indexed and raw data mode. For **One-Way Repeated Measures ANOVA**, if the indexed mode is used, data should be organized into three columns: **Factor**, **data**, and **Subject**. When the Raw data mode is used, the different levels should be in different columns.


Indexed data mode

The data contains measurements for 3 different doses on 20 subjects, and we are interested in whether different doses on subjects have different effects. To test this, we will perform a One-Way Repeated Measures ANOVA using the indexed data mode.


1. Click the **Import Single ASCII** button  to import the file **One Way_RM_ANOVA_indexed.dat** in the `\Samples\Statistics\ANOVA` folder.
2. Select **Statistics: ANOVA: One-Way Repeated Measures ANOVA** to open the dialog. In the **Input** tab of this dialog, select **Indexed** from the **Input Data** drop-down list and set column **B(dose)**, **C(Data)**, and **A(Subject)** as the **Factor**, **Data**, and **Subject** respectively.



3. Go to **Means Comparison** tab, select the check box after **Bonferroni** to enable the Bonferroni test.



4. Select the **Means Plot(SE as Error)** and **Means comparison Plot** check boxes in the **Plots** tab.



5. Click the **OK** button to perform the analysis.

Results Interpretation

Go to the worksheet **ANOVAOneWayRM1**, where the analysis results are listed.

You can refer to this [help file](#) for details of interpreting results of repeated measures ANOVA.

Multivariate Tests

		Value	F	Num df	DF	Prob>F
dose	Pillai's Trace	0.17777	3.02689	2	28	0.06455
	Wilks' Lambda	0.82223	3.02689	2	28	0.06455
	Hotelling's Trace	0.21621	3.02689	2	28	0.06455
	Roy's Largest Root	0.21621	3.02689	2	28	0.06455

Origin prints out MANOVA automatically alongside repeated measures to detect repeated-measures effects. Note that the four different methods (Pillai's trace, Wilks' lambda, Hotelling's trace, and Roy's largest root) generate identical F statistics and probabilities, **P=0.06455**, so the means under three levels condition are not statistically different. Compare with the following report in repeated measures ANOVA, we can see that the conclusion is conservative.

Mauchly's Test of Sphericity

	Mauchly's W	Approx. Chi-Square	DF	Prob>ChiSq	Greenhouse-Geisser Epsilon	Huynh-Feldt Epsilon	Lower-bound Epsilon
dose	0.94397	1.61448	2	0.44609	0.94694	1	0.5

This table shows the results of the Mauchly's Test of Sphericity. From the test results we can see that Sphericity holds. We are interested in the value of **Prob > ChiSq**, which is the significance level of the Mauchly's Test, we can see from this example that the significance level (0.44609) is greater than 0.05. Therefore, the assumption of Sphericity has not been violated.

Tests of Within-Subjects Effects

		Sum of Squares	DF	Mean Square	F	Prob>F
dose	Sphericity Assumed	0.4473	2	0.22365	3.43018	0.03908
	Greenhouse-Geisser	0.4473	1.89389	0.23618	3.43018	0.04187
	Huynh-Feldt	0.4473	2	0.22365	3.43018	0.03908
	Lower-bound	0.4473	1	0.4473	3.43018	0.0422
Error(dose)	Sphericity Assumed	3.78162	58	0.0652		
	Greenhouse-Geisser	3.78162	54.92273	0.06885		
	Huynh-Feldt	3.78162	58	0.0652		
	Lower-bound	3.78162	29	0.1304		

P < 0.05

From this table we are able to get the F value for the factor in addition to its associated significance level and effect size. As our data follow the assumption of Sphericity, we can conclude that when using an ANOVA with repeated measures with **Sphericity Assumed**, the means under three levels condition are statistically different ($P = 0.03908 < 0.05$). In other words, dose is a significant factor.

Descriptive Statistics

	Mean	Std. Error	95.00% LCL	95.00% UCL
10	1.1312	0.06875	0.99059	1.27181
20	0.95877	0.05324	0.84988	1.06765
30	1.03693	0.06119	0.91178	1.16207


Pairwise Comparison

Bonferroni Test


	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
10 20	0	0.17243	0.06593	58	2.61543	0.03402	0.05	1	0.00989	0.33498
10 30	1	0.09427	0.06593	58	1.42989	0.47434	0.05	0	-0.06827	0.25681
20 30	2	-0.07816	0.06593	58	1.18554	0.72192	0.05	0	-0.2407	0.08438

The results presented in the previous table showed that there is an overall significant difference among the means but we do not know where those differences came from. This table shows the results of the Bonferroni test, which allows us to learn which specific means are different. In this case, the means of dose=10 and dose=20 have a significant difference ($P = 0.03402 < 0.05$ and Sig Flag = 1).

From the two plots below, we can also easily come to the same conclusion.



Means Comparison using Bonferroni Test



5.3.3 Two Way ANOVA

5.3.3.1 Summary

In some cases, we want to examine the relationship between two factors (categorical variables) and a continuous outcome variable. The effects on the outcome of the change in one factor may depend on the level of the other factor, so we need to consider the interactions between two factors. Two way ANOVA is an appropriate method to analyze the main effects of and interactions between two factors.

Minimum Origin Version Required: Origin 2016 SR0

5.3.3.2 What you will learn

This tutorial will show you how to:

- Perform Two-way ANOVA
- Interpret results from Two-Way ANOVA
- Make the Interaction Plot


5.3.3.3 Steps

Researchers are interested in the effects of sex and dietary group on systolic blood pressure (SBP). The "dietary group" factor includes three groups: strict vegetarians (SV) who eat no animal products of any kind; lacto vegetarians (LV) who eat dairy products but no other animal products; and "normal" (NOR) subjects who eat a standard American diet. Sex and dietary group may be independent or they may interact with each other. One approach to solve this problem is to construct a two-way ANOVA model predicting mean SBP level.


Indexed data mode

Perform Two Way ANOVA

1. Start with a new workbook and import the file `\Samples\Statistics\SBP_Index.dat`.
2. Open the **Two-Way ANOVA** dialog by choosing the menu item **Statistics: ANOVA: Two-Way ANOVA**, then in the **Input** tab, set the **Input Data** mode as **Indexed**.
3. Also in the **Input** tab, select column A,B and C for **Factor A**, **Factor B** and **Data**, respectively. Check the **Interactions** box.



- In the **Descriptive statistics** tab, check all boxes.
- In the **Means Comparison** tab, set **Significance Level** to 0.05, and check the box beside **Tukey** to select this test as the means comparison method.



- Click the **OK** button to perform Two-Way ANOVA.

Interpreting Results

Overall ANOVA

	DF	Sum of Squares	Mean Square	F Value	P Value
Sex	1	1594.39725	1594.39725	17.64529	4.05551E-5
Dietary	2	1137.86004	568.93002	6.29638	0.00224
Interaction	2	245.48621	122.7431	1.3584	0.2595
Model	5	2794.86329	558.97266	6.18618	2.40633E-5
Error	194	17529.50212	90.35826	--	--
Corrected Total	199	20324.36541	--	--	--

At the 0.05 level, the population means of **Sex** are **significantly** different.
 At the 0.05 level, the population means of **Dietary** are **significantly** different.
 At the 0.05 level, the interaction between **Sex** and **Dietary** is **not significant**.

From the "Overall ANOVA" table in the Two-Way ANOVA result sheet, we can see that **Dietary** and **Sex** are both significant factors, but the interaction between them is not significant. So we can say that the main effects of both **Dietary** groups and **Sex** are significant, yet the effect on the outcome of the change in **Dietary** doesn't depend on the level of **Sex**.

The Interaction Plot


To further detect interaction, we can make an "Interaction Plot" using the following steps.

1. Right-click on the title of the "Interaction" table and select **Create Copy as a new sheet** from the context menu.

Interaction		N	Mean	SD	SEM	Variance	Missing	NonMissing
Male	SV	30	117.24744	10.63207	1.94114	113.04092	0	30
	LV	25	119.01081	8.49339	1.69868	72.13771	0	25
	Nor	45	120.76882	8.82486	1.31553	77.87808	0	45
Female	SV	25	110.93646	10.37779	2.07556	107.69851	0	25
	LV	30	110.85397	9.57768	1.74864	91.7319	0	30
	Nor	45	117.78078	9.35218	1.39414	87.4633	0	45


2. Go to the new sheet and right-click on column B and select **Set As Categorical** from the fly-out menu.
3. Select the first three cells in column D and then press the **Ctrl** key and select the other cells in column D.

A(X1)	B(X2)	C(Y2)	D(Y2)	E(yEr±)	F(yEr±)	G(Y2)	H(Y2)	I(Y2)
		N	Mean	SD	SEM	Variance	Missing	NonMissin
Male	SV	30	117.24744	10.63207	1.94114	113.04092	0	30
Male	LV	25	119.01081	8.49339	1.69868	72.13771	0	25
Male	Nor	45	120.76882	8.82486	1.31553	77.87808	0	45
Female	SV	25	110.93646	10.37779	2.07556	107.69851	0	25
Female	LV	30	110.85397	9.57768	1.74864	91.7319	0	30
Female	Nor	45	117.78078	9.35218	1.39414	87.4633	0	45

4. Click the  button on the **2D Graphs** toolbar to create a graph.
5. Right-click on the graph legend and select **Properties** from the context menu. In the **Object Properties** dialog box, edit the text as shown below. Click the **OK** button to close the dialog box and update the legend. We now have an **Interaction Plot** which can show the interaction between two factors.

\l(1) Male


\l(2) Female




The data plots in the chart above suggest only a weak interaction between **Sex** and **Dietary**, so we should recalculate the effects of the two factors without interaction.

Recalculate

1. Click on the green lock in the **ANOVA2Way1** result sheet, and select **Change Parameters** to open the dialog again.



2. In the **Input** tab in the open dialog, clear the **interactions** box and click the **OK** button.



We can see that the **Dietary** and **Sex** are significant factors from the "Overall ANOVA" table. The mean of *Nor* is significantly greater than that of *LV* and *SV* for factor **Dietary**. The mean of *Male* is significantly greater than that of *Female*, from the "Dietary" table.

Overall ANOVA

	DF	Sum of Squares	Mean Square	F Value	P Value
Sex	1	1405.79986	1405.79986	15.50138	1.14502E-4
Dietary	2	1154.79872	577.39936	6.36683	0.00209
Model	3	2549.37708	849.79236	9.37043	8.11226E-6
Error	196	17774.98833	90.68872	--	--
Corrected Total	199	20324.36541	--	--	--

At the 0.05 level, the population means of **Sex** are **significantly** different.

At the 0.05 level, the population means of **Dietary** are **significantly** different.

Tukey Test


		MeanDiff	SEM	q Value	Prob	Alpha	Sig	LCL	UCL
Sex									
Female	Male	-5.28125	1.34676	5.54574	1.21684E-4	0.05	1	-7.93726	-2.62524
Dietary									
LV	SV	0.18281	1.81598	0.14237	0.99443	0.05	0	-4.1059	4.47152
Nor	SV	4.89599	1.62989	4.24812	0.00843	0.05	1	1.04675	8.74522
Nor	LV	4.71318	1.62989	4.0895	0.01182	0.05	1	0.86394	8.56241

Sig equals 1 indicates that the difference of the means is significant at the 0.05 level.

Sig equals 0 indicates that the difference of the means is not significant at the 0.05 level.

Raw Data Mode

1. Start with a new workbook and import the file `\Samples\Statistics\SBP_Raw.dat`
2. Highlight all columns and select menu item **Statistics : ANOVA : Two-Way ANOVA** to bring up the **ANOVATwoWay** dialog box. In the **Input** tab, choose **Raw** as the **Input Data** mode.
3. Also in the **Input** tab, set **Number of levels** of **Factor A** as 2 and type **Sex**, **Male** and **Female** for **Name**, **Level1 Name** and **Level2 Name** in **Factor A** branch, respectively.
4. Also in the **Input** tab, set **Number of levels** of **Factor B** as 3, and type **Dietary Group**, **SV**, **LV** and **Nor** for **Name**, **Level1 Name**, **Level2 Name** and **Level3 Name** in **Factor A** branch, respectively.



5. In the **Means Comparison** tab, set **Significance Level** to 0.05, and check the box beside **Tukey** to use it as the means comparison method.
6. Click the **OK** button to perform Two-Way ANOVA.

5.3.4 Two Way Repeated Measures ANOVA

5.3.4.1 Summary

For Two-Way Repeated Measures ANOVA, "Two-way" means that there are two factors in the experiment, for example, different treatments and different conditions. "Repeated-measures" means that the same subject received more than one treatment and/or more than one condition. Similar to two-way ANOVA, two-way repeated measures ANOVA can be employed to test for significant differences between the factor level means within a factor and for interactions between factors. Using a standard ANOVA in this case is not appropriate because it fails to model the correlation between the repeated measures, and the data violates the ANOVA assumption of independence. Two-Way Repeated Measures ANOVA designs can be two repeated measures factors, or one repeated measures factor and one non-repeated factor. If any repeated factor is present, then the repeated measures ANOVA should be used.

In the following example, the two factors are the repeated measures factors.

Minimum Origin Version Required: Origin 8.6 Pro SR0

5.3.4.2 What you will learn

This tutorial will show you how to:


- Input raw data in the statistical analysis dialog.
- Perform Two-Way Repeated Measures ANOVA.
- Interpret results of a Two-Way Repeated Measures ANOVA

5.3.4.3 Steps

Origin can perform **Two Way Repeated Measures ANOVA** in both indexed and raw data mode. For Two-Way repeated measures ANOVA, if the indexed mode is used, data should be organized into four columns: Factor A, Factor B, Data, and Subject. When the Raw data mode is used, the different factors and levels should be in different columns.

In this example, we are interested in whether different drugs and doses have different effects on subject. We will perform the **Two-Way Repeated Measures ANOVA** to determine whether the drug type and dosage have significant effect on a subject. If there is significant difference, we will perform **pairwise comparison** to determine of which level the effects are different.


Raw data mode

1. Click the **Import Single ASCII** button  to import the file **Two-Way_RM_ANOVA_raw.dat** in the *Samples\Statistics\ANOVA* folder.
2. Select **Statistics: ANOVA: Two-Way Repeated Measures ANOVA** to open the dialog.
3. In **Input** tab, select **Raw** from the **Input Data** drop-down list.
4. In this example, there are two factors. Set 3 and 2 for Number of Levels in **Factor A** and **Factor B** drop-down list to specify levels of the factor. Set **Name** to **drug** and **dose** respectively.


Notes: **Factor A** and **Factor B** are set as repeated measures factor by default (The **Repeated** check box under **Factor** is checked). If one factor is a non-repeated measures factor, just uncheck the **Repeated** check box.

5. Now under the **Data** branch, there are three subgroups. In the **drug Level1** subgroup, select column **d1d1** as the **dose Level1** input data range.
6. Similarly, select **d1d2**, **d2d1**, **d2d2**, **d3d1**, and **d3d2** for the next 5 input data range.


7. Check the **Interactions** check box to calculate interaction effects.



- In the **Descriptive Statistics** tab, select all check boxes to compute the mean, standard error, and 95% confidence interval of all the levels of the factors as well as interactions.



- In the **Means Comparison** tab, select the **Bonferroni** check box to enable the Bonferroni test.



- Click the **OK** button to perform the analysis.

Results Interpretation

Go to the worksheet **ANOVATwoWayRM1**, where the analysis results are listed. You can refer to this [help file](#) for details of interpreting results of repeated measures ANOVA.

⇒ *Multivariate Tests* ▼

		Value	F	Num df	DF	Prob>F
drug	Pillai's Trace	0.133	1.99423	2	26	0.1564
	Wilks' Lambda	0.867	1.99423	2	26	0.1564
	Hotelling's Trace	0.1534	1.99423	2	26	0.1564
	Roy's Largest Root	0.1534	1.99423	2	26	0.1564
dose	Pillai's Trace	0.19986	6.74428	1	27	0.01504
	Wilks' Lambda	0.80014	6.74428	1	27	0.01504
	Hotelling's Trace	0.24979	6.74428	1	27	0.01504
	Roy's Largest Root	0.24979	6.74428	1	27	0.01504
drug * dose	Pillai's Trace	0.27164	4.8482	2	26	0.01624
	Wilks' Lambda	0.72836	4.8482	2	26	0.01624
	Hotelling's Trace	0.37294	4.8482	2	26	0.01624
	Roy's Largest Root	0.37294	4.8482	2	26	0.01624

Origin uses a multivariate analysis to detect repeated-measures effects. In this example, four different methods (Pillai's trace, Wilks' lambda, Hotelling's trace, and Roy's largest root) generate identical F statistics and probabilities. For **drugs**, P_value=0.1564, so we can conclude that the effect of **drugs** did not reach conventional levels of statistical significance. Similarly, we can also conclude that **dose** and **drugs* dose** are significant.

Mauchly's Test of Sphericity

	Mauchly's W	Approx. Chi-Square	DF	Prob>ChiSq	Greenhouse-Geisser Epsilon	Huynh-Feldt Epsilon	Lower-bound Epsilon
drug	0.84441	4.39712	2	0.11096	0.86536	0.9193	0.5
dose	0	0	0	0	1	1	1
drug * dose	0.47007	19.62694	2	5.47097E-5	0.65362	0.6734	0.5

Warning: No Sphericity test performed due to insufficient degrees of freedom.

This table shows the results of Mauchly's Test of Sphericity and evaluation of epsilon. From the column **Prob>ChiSq**, we can learn that the significance level of **drugs** is greater than 0.05 (P_value=0.11096), and the value of **drugs*dose** is smaller than 0.05. For **drugs*dose**, the assumption of sphericity has been violated. Note that **Greenhouse-Geisser Epsilon**=0.65362, which is smaller than 0.75, so we will proceed with the test by using **Greenhouse-Geisser** correction.

Tests of Within-Subjects Effects

		Sum of Squares	DF	Mean Square	F	Prob>F
drug	Sphericity Assumed	0.06038	2	0.03019	2.88316	0.06461
	Greenhouse-Geisser	0.06038	1.73071	0.03489	2.88316	0.07313
	Huynh-Feldt	0.06038	1.8386	0.03284	2.88316	0.0696
	Lower-bound	0.06038	1	0.06038	2.88316	0.10101
Error(drug)	Sphericity Assumed	0.56546	54	0.01047		
	Greenhouse-Geisser	0.56546	46.72928	0.0121		
	Huynh-Feldt	0.56546	49.64207	0.01139		
	Lower-bound	0.56546	27	0.02094		
dose	Sphericity Assumed	0.03982	1	0.03982	6.74428	0.01504
	Greenhouse-Geisser	0.03982	1	0.03982	6.74428	0.01504
	Huynh-Feldt	0.03982	1	0.03982	6.74428	0.01504
	Lower-bound	0.03982	1	0.03982	6.74428	0.01504
Error(dose)	Sphericity Assumed	0.15942	27	0.0059		
	Greenhouse-Geisser	0.15942	27	0.0059		
	Huynh-Feldt	0.15942	27	0.0059		
	Lower-bound	0.15942	27	0.0059		
drug * dose	Sphericity Assumed	0.13506	2	0.06753	4.84575	0.0116
	Greenhouse-Geisser	0.13506	1.30725	0.10332	4.84575	0.02564
	Huynh-Feldt	0.13506	1.3468	0.10028	4.84575	0.0245
	Lower-bound	0.13506	1	0.13506	4.84575	0.03644
Error(drug * dose)	Sphericity Assumed	0.75256	54	0.01394		
	Greenhouse-Geisser	0.75256	35.29564	0.02132		
	Huynh-Feldt	0.75256	36.36348	0.0207		
	Lower-bound	0.75256	27	0.02787		

From this table we are able to find out the F value for the factor, its associated significance level and the effect size. For **drug**, the p_value is 0.06461 in the **prob>F** column, so **drugs** have no significant effect on subjects, while **dose** have (p_value=0.01504). For interaction **drugs*dose**, we can still proceed with the test by using the **Greenhouse-Geisser** correction and conclude that interaction **drugs*dose** have significant effect (p_value = 0.02564).

drug

Descriptive Statistics

	Mean	Std. Error	95.00% LCL	95.00% UCL
drug Level1	1.0833	0.03709	1.00719	1.15941
drug Level2	1.05375	0.03436	0.98324	1.12426
drug Level3	1.0375	0.03383	0.9681	1.1069

Painwise Comparison

Bonferroni Test

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
drug Level1 drug Level2	0	0.02955	0.01977	54	1.49462	0.4225	0.05	0	-0.0193	0.0784
drug Level1 drug Level3	1	0.0458	0.01977	54	2.31657	0.07305	0.05	0	-0.00305	0.09465
drug Level2 drug Level3	2	0.01625	0.01977	54	0.82195	1	0.05	0	-0.0326	0.0651

Sig equals 1 indicates that the difference of the means is significant at the 0.05 level.
 Sig equals 0 indicates that the difference of the means is not significant at the 0.05 level.
 Sig equals -1 indicates that the difference of the means is not tested.

In general, Bonferroni tests are recommended to determine which specific means differed and determine whether or not the Sphericity assumption is violated. The Bonferroni correction relies on a general probability inequality and therefore isn't dependent on specific ANOVA assumptions. This table presents the results of the Bonferroni test, we can conclude that the means are not significant different ($P > 0.05$ and sig Flag=0). Of course, we do not need to perform **pairwise comparison** because drugs have no significant effect.

dose

Descriptive Statistics

	Mean	Std. Error	95.00% LCL	95.00% UCL
dose Level1	1.07358	0.03494	1.00188	1.14527
dose Level2	1.04279	0.03267	0.97575	1.10982

Painwise Comparison

Bonferroni Test

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
dose Level1 dose Level2	0	0.03079	0.01614	27	1.90751	0.06714	0.05	0	-0.00233	0.06391

Sig equals 1 indicates that the difference of the means is significant at the 0.05 level.
 Sig equals 0 indicates that the difference of the means is not significant at the 0.05 level.
 Sig equals -1 indicates that the difference of the means is not tested.

In this table, we can conclude that means of different dose are not significantly different ($p_value = 0.06714$ and sig Flag = 0).

Painwise Comparison

Bonferroni Test

dose within drug = drug Level1

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
dose Level1 dose Level2	0	0.1063	0.02796	54	3.80208	0.0055	0.05	1	0.02043	0.19218

dose within drug = drug Level2

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
dose Level1 dose Level2	0	-0.03036	0.02796	54	1.08577	1	0.05	0	-0.11623	0.05552

dose within drug = drug Level3

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
dose Level1 dose Level2	0	0.01643	0.02796	54	0.58759	1	0.05	0	-0.06944	0.1023

drug within dose = dose Level1

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
drug Level1 drug Level2	0	0.09788	0.02796	54	3.50078	0.01408	0.05	1	0.01201	0.18375
drug Level1 drug Level3	1	0.09074	0.02796	54	3.24531	0.03025	0.05	1	0.00486	0.17661
drug Level2 drug Level3	2	-0.00714	0.02796	54	0.25548	1	0.05	0	-0.09302	0.07873

drug within dose = dose Level2

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95.00% LCL	95.00% UCL
drug Level1 drug Level2	0	-0.03878	0.02796	54	1.38707	1	0.05	0	-0.12465	0.04709
drug Level1 drug Level3	1	8.61787E-4	0.02796	54	0.03082	1	0.05	0	-0.08501	0.08674
drug Level2 drug Level3	2	0.03964	0.02796	54	1.41789	1	0.05	0	-0.04623	0.12552

In this table, we can conclude that dose1 is significantly larger than dose2 within drug1, and drug1 is significantly larger than drug2 and drug3 within dose1.

5.3.5 Two-Way Mixed-Design ANOVA

5.3.5.1 Summary

The two-way mixed-design ANOVA is also known as two way split-plot design (SPANOVA). It is ANOVA with one repeated-measures factor and one between-groups factor.

Minimum Origin Version Required: Origin 2016 SR0

5.3.5.2 What you will learn

This tutorial will show you how to:

- Perform the two-way mixed design ANOVA.
- Interpret results of the two-way mixed design ANOVA

5.3.5.3 User Story

A researcher wants to know whether a treatment can help people lose weight. 48 participants(24 male) take part in the study. The researcher record their weights every three months during the treatment program.

5.3.5.4 Preparing Analysis Data

To perform two-way mixed-design ANOVA, the data can be arranged as below


Subject	Between-Groups Factor		Repeated Measure Factor		
	Gender		weight1	weight2	weight3
19	male		67.4	68.2	70.2
20	male		88.5	90.1	78.4
21	male		69	70.3	70.6
22	male		75.9	70.5	71.6
23	male		88	80.9	82.6
24	male		100.1	96.2	90.3
25	female		69.3	55.1	60.3
26	female		76.05	47.6	50.05
27	female		108.5	72.3	58.5
28	female		85.5	76.9	55.5
29	female		61.5	68.7	51.5
30	female		76.7	75.9	66.7
31	female		66.3	60.5	60.0

Notes: Data can also be arranged in index mode for two-way mixed-design ANOVA. Refer to the sample data, \Samples\Statistics\ANOVA\two-way rm ANOVA1_indexed.dat, for index mode of data of this tutorial.


5.3.5.5 Performing Two-Way Mixed-Design ANOVA

Tutorials for Origin


1. Open a new project or a new workbook. Import the data file `\Samples\Statistics\ANOVA\two-way rm ANOVA1_raw.dat`
2. Select **Statistics: ANOVA: Two-Way Repeated Measures ANOVA...** from Origin menu
3. In the opened dialog, choose the **Input** tab,
 - o Set **Input Data** as **Raw**
 - o Expand **Factor A** branch, change the **Name** as **Weight** and set **Number of Levels** = 3. Expand **Factor B** branch, change the **Name** as **Gender** and unselect **Repeat** check box
 - o In the **Data** branch, set column **C, D** and **E** to be **Weight Level1, Weight Level2** and **Weight Level3**, respectively, and set column **B** as **Gender**
 - o Select **Interactions** check box



4. Choose the **Descriptive Statistics** tab. select all check boxes



5. Choose the **Means Comparison** tab, select **Bonferroni** check box.



6. Click **OK** button to perform the analysis

5.3.5.6 Interpreting the Results

Go to the worksheet **ANOVATwoWayRM1**, where the analysis results are listed.

You can refer to this [interpreting results help page](#) for details of interpreting results of repeated measures ANOVA. .

1. From the **Mauchly's Test of Sphericity** table, we can see **Prob>ChiSq**(0.01258) < 0.05. So the repeated measure variable, **Weight**, violates the Sphericity assumption. We should consider the **Greenhouse-Geisser** correction ect. While the Epsilon is larger than 0.75, we will look at the Huynh and Feldt correction in step 2 below

	Mauchly's W	Approx. Chi-Square	DF	Prob>ChiSq	Greenhouse-Geisser Epsilon	Huynh-Feldt Epsilon	Lower-bound Epsilon
Weight	0.82327	8.75143	2	0.01258	0.84981	0.89821	0.5

2. From the **Tests of Within-Subject Effects** table, we can see
 - o For **Weight**, the p_valeur is about 0 in the **Prob>F** column, It indicates that the weight is a significant effect, that is, the weights change over time.
 - o While the interaction, **Weight*Gender**, is not significant different(p_value = 0.14025), we can conclude that there is not a significant interaction effect, **Weight*Gender**

Tests of Within-Subjects Effects

		Sum of Squares	DF	Mean Square	F	Prob>F
Weight	Sphericity Assumed	6328.11622	2	3164.05811	43	2.16215E-13
	Greenhouse-Geisser	6328.11622	1.69962	3723.25578	43	9.9634E-12
	Huynh-Feldt	6328.11622	1.79641	3522.64301	40.71343	2.89727E-12
	Lower-bound	6328.11622	1	6328.11622	40.71343	7.76453E-8
Weight * Gender	Sphericity Assumed	318.3098	2	159.1549	2.04792	0.13484
	Greenhouse-Geisser	318.3098	1.69962	187.28303	2.04792	0.14282
	Huynh-Feldt	318.3098	1.79641	177.19204	2.04792	0.14025
	Lower-bound	318.3098	1	318.3098	2.04792	0.15917
Error(Weight)	Sphericity Assumed	7149.81058	92	777.15337		
	Greenhouse-Geisser	7149.81058	78.18247	914.50686		
	Huynh-Feldt	7149.81058	82.63493	86.52286		
	Lower-bound	7149.81058	46	155.43066		

- We can further study how the weights change over time during the treatment. Expand the **Weight** branch. From the tables we can see

 - From the **Descriptive Statistics** table we can see that the weights are decreasing
 - In the **Pairwise Comparison** table, the **1** in the **Sig Flag** column indicates the pair of group is significant different. We can draw conclusion that the weights are significantly decreasing

Weight

Descriptive Statistics

	Mean	Std. Error	95% LCL	95% UCL
Weight Level1	83.28479	2.20515	78.84606	87.72352
Weight Level2	74.66625	1.59795	71.44974	77.88276
Weight Level3	67.05729	1.23317	64.57505	69.53953

Pairwise Comparison

Bonferroni Test

	Index	Mean Difference	Std. Error	DF	t value	Prob> t	Alpha	Sig Flag	95% LCL	95% UCL	
Weight Level1	Weight Level2	0	8.61854	1.79948	92	4.78945	1.91332E-5	0.05	1	4.23043	13.00666
Weight Level1	Weight Level3	1	16.2275	1.79948	92	9.01787	7.98371E-14	0.05	1	11.83939	20.61561
Weight Level2	Weight Level3	2	7.60896	1.79948	92	4.22841	1.66392E-4	0.05	1	3.22084	11.99707

Sig equals 1 indicates that the difference of the means is significant at the 0.05 level.
 Sig equals 0 indicates that the difference of the means is not significant at the 0.05 level.
 Sig equals -1 indicates that the difference of the means is not tested.

- From the **Tests for Between-Subjects Effects** table, we can see **Gender** is a significant effect, that is, Female and Male can be significant different.

Tests of Between-Subjects Effects

	Sum of Squares	DF	Mean Square	F	Prob>F
Intercept	810060.00111	1	810060.00111	2961.43253	2.07173E-43
Gender	8857.94694	1	8857.94694	32.38305	8.40281E-7
Error	12582.68074	46	273.53654		

- Look at the **Gender** branch to see the details.

 - There are only two levels for Gender and we already know they are significant different, so we don't need to look at the **Pairwise Comparison** table

- From the **Descriptive Statistics** table we can see that average weight of men is more than women.

	Mean	Std. Error	95% LCL	95% UCL
male	82.84583	1.94913	78.92243	86.76923
female	67.15972	1.94913	63.23632	71.08312

Notes: As there is no serious violation of sphericity assumption, we can ignore the **Multivariate Tests** table. See more details from the [interpreting results help page](#).

5.3.6 Three-Way ANOVA

5.3.6.1 Summary

Three-way ANOVA tests for main effects, and interaction effects between all combinations of three factors, on a dependent variable.

Minimum Origin Version Required: Origin 2016 SR0

5.3.6.2 What you will learn

1. How to carry out three-way ANOVA for practical data with Origin
2. How to interpret the generated results


5.3.6.3 User Story

We have some public data from the World Bank. It includes three factors: Region(Asia/Europe/Africa, etc.), Developing Index (Developing/Developed Country) and Year (2000/2005/2010). We want to understand how these three factors affect the number of internet users and whether there are any significant differences between the groups.


5.3.6.4 Performing Three-Way ANOVA

1. Choose menu **File: Open Sample OPJ: Statistics Improvements in Origin 2016** to open the OPJ
2. With the opened OPJ, browse to the folder *Three Way ANOVA*
3. Click on worksheet **Sheet1** containing the source data.
4. Click **Statistics: ANOVA: Three-Way ANOVA**

- In the **Input** tab of the opened dialog, set **Input Data** as **Indexed**. Then expand the **Input Data** branch, select column C,D, B and E for **Factor A,Factor B, Factor C** and **Data**, respectively



- In the **Model** tab, make sure all boxes are selected. This determines that a full factorial model will be used for the three-way ANOVA.



- Click **OK** to apply all setting and close the dialog.
- Go to sheet **ANOVA3Way1**. The **Overall ANOVA** table includes ANOVA test results for the main effects and the interactions. If the **P Value** is less than 0.05, this means the levels in the corresponding factor are significantly different. Note the conclusions in the footnotes beneath the table.

Overall ANOVA					
	DF	Sum of Squares	Mean Square	F Value	P Value
Developing Index	1	23652.65024	23652.65024	132.61578	0
Year	2	15248.13748	7624.06874	42.74666	0
Region	5	15055.32285	3011.06457	16.88245	1.77636E-15
Developing Index*Year	2	511.16006	255.58003	1.43299	0.23954
Developing Index*Region	5	9230.53132	1846.10626	10.35076	1.78556E-9
Year*Region	10	5342.29117	534.22912	2.99532	0.0011
Developing Index*Year*Region	10	896.73603	89.6736	0.50278	0.88834
Model	35	241745.07507	6907.00214	38.72621	0
Error	516	92031.03363	178.35472	0	0
Corrected Total	551	333776.1087	0	0	0


At the 0.05 level, the population means of **Developing Index** are significantly different.
 At the 0.05 level, the population means of **Year** are significantly different.
 At the 0.05 level, the population means of **Region** are significantly different.
 At the 0.05 level, the population means of **Developing Index*Year** are not significantly different.
 At the 0.05 level, the population means of **Developing Index*Region** are significantly different.
 At the 0.05 level, the population means of **Year*Region** are significantly different.
 At the 0.05 level, the population means of **Developing Index*Year*Region** are not significantly different.

From the **Overall ANOVA** table above we can see the two-way interaction of factors **Developing Index*Year** is not significant (p-value = 0.23954). The three-way interaction of factors **Region*Developing Index*Year**, is not significant. (p-value = 0.88834).


5.3.6.5 Examining Significant Interactions

In the following, we are going to further examine factors showing a significant interaction.


1. Click the green lock in the sheet **ANOVA3Way1** and choose **Change Parameters** from the context menu



2. In the **Model** tab, clear the **Effect A*B** and **Effect A*B*C** check boxes, where interactions between factors could not be detected.



3. In the **Means Comparison** tab, select the **Bonferroni** check box. Bonferroni is the most commonly used post-hoc test. It controls the overall Type I error.
4. In the **Mean Plot** tab, select all available check boxes. (**Effect A*B** and **Effect A*B*C** are disabled because they are not included in the model.)



5. Click **OK** to apply all setting and close the dialog.

5.3.6.6 Interpreting Results

The results in the sheet **ANOVA3Way1** are updated using the new calculation parameters.

Overall ANOVA

Overall ANOVA

	DF	Sum of Squares	Mean Square	F Value	P Value
Developing Index	1	24445.97236	24445.97236	138.04613	0
Year	2	44473.73843	22236.86921	125.57135	0
Region	5	15019.51175	3003.90235	16.963	1.44329E-15
Developing Index*Region	5	9809.01069	1961.80214	11.07827	3.65762E-10
Year*Region	10	20038.12871	2003.81287	11.31551	0
Model	23	240274.94891	10446.73691	58.99261	0
Error	528	93501.15979	177.08553	0	0
Corrected Total	551	333776.1087	0	0	0


At the 0.05 level, the population means of **Developing Index** are **significantly different**.
 At the 0.05 level, the population means of **Year** are **significantly different**.
 At the 0.05 level, the population means of **Region** are **significantly different**.
 At the 0.05 level, the population means of **Developing Index*Region** are **significantly different**.
 At the 0.05 level, the population means of **Year*Region** are **significantly different**.

From the table we can see all remaining effects are significantly different. We can use the **Means Comparisons** results and **Means Plots** to further detect differences between each group.

Means Comparison and Means Plot of the Three Main Effects


Expanding the branch **ANOVA: Means Comparison: Bonferroni Test**, you can see the means comparison table for each effect. It is useful, along with the **Means Plot** at the bottom of the result sheet, for pairwise comparisons between members of a group.

Comparison between Developing and Developed Country




From the result above we can see the number of internet users of developing countries is much fewer than the developed countries.

Comparison between Years



From the result above we can see the number of internet users greatly increased between 2000 and 2010.

Comparison between Regions




The results above tell us:



- Internet users in Africa are significantly fewer than other continents.
- Internet users in the Middle East are significantly fewer than Europe and the Americas.
- There is no significant difference between other pairs of continents.

Comparing Same Level Between Different Groups


We can compare the sample level between different groups with **Mean Comparison** results of the interactions. In the following we will show how to use a data filter to quickly view the results we are interested in.

1. In the sheet **ANOVA3Way1**, expand the branch **ANOVA: Means Comparison: Bonferroni Test**.
2. Click the triangle button next to **Interactions** and choose **Create Copy as New Sheet** from the context menu.



3. Go to the generated sheet **Interactions**. Now we are going to compare developing and developed countries in different regions by applying a data filter in the results.
 1. Highlight column C, click the **Add/Remove Data Filter** button  to add a data filter to the column.
 2. Click the **Filter** icon  on the column header, choose **Custom Filter**.
 3. Select the **Advanced** check box in the bottom-right corner of the open dialog. Add following script in the **Condition** box.

```
col (c) $==$col (f) $
```



4.

4. From the results below we can see:

3.

- The internet users in the developed and developing countries are not significantly different in Africa and Middle East.
- The internet users in the developed countries are significant higher than the developing countries on the following four continents.

1. Asia


2. Europe

3. The Americas

4. Oceania

	A(Y)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)	G(Y)	H(Y)Er?	I(Y)	J(Y)	K(Y)	L(Y)	M(Y)	N(Y)
Long Name	Developing Index	Year	Region	Developing Index	Year	Region	MeanDiff	SEM	T Value	Prob.	Alpha	Sig	LCL	UCL
Filter			col(c)\$==col(f)\$											
6	Developing Country	--	Asia	Developed Country	--	Asia	-42.92764	7.63444	-5.6229	2.01079E-6	0.05	1	-68.79032	-17.06497
17	Developing Country	--	Europe	Developed Country	--	Europe	-22.4491	2.31388	-9.70192	0	0.05	1	-30.28769	-14.61051
27	Developing Country	--	Africa	Developed Country	--	Africa	-3.25806	7.58844	-0.42935	1	0.05	0	-28.96493	22.4488
36	Developing Country	--	The Americas	Developed Country	--	The Americas	-46.60039	4.53941	-10.26573	0	0.05	1	-61.97825	-31.22253
44	Developing Country	--	Oceania	Developed Country	--	Oceania	-55.64037	6.35642	-8.75342	0	0.05	1	-77.17358	-34.10716
51	Developing Country	--	Middle East	Developed Country	--	Middle East	-16.60325	7.83002	-2.12046	1	0.05	0	-43.12847	9.92197
72		2000	Asia		2005	Asia	-8.27063	3.25534	-2.54054	1	0.05	0	-20.04479	3.50353

1 in the Sig column means the pair of levels are significant different, while 0 means no significant different



5.4 Nonparametric Tests

- [Non-parametric Statistics Overview](#)

5.4.1 Non-parametric Statistics Overview

5.4.1.1 Summary

Nonparametric tests are used when you don't know whether your data are normally distributed, or when you have confirmed that your data are not normally distributed.

Minimum Origin Version Required: Origin 8.0 SR6

5.4.1.2 What you will learn

This tutorial will show you:

- An introduction on non-parametric tests in Origin
- How to run the non-parametric tests for different practical situations
- How to calculate correlation coefficient in non-parametric statistics

5.4.1.3 Introduction: Nonparametric Tests in Origin

Nonparametric tests do not require the assumption of normality. They are commonly used in the following situations:

- Small sample size.
- Categorical/Binary/Ordinal data.

- Normal distribution cannot be assumed.

		Nonparametric	Parametric
		<i>Data from any distribution</i>	<i>Data from normal distribution</i>
		<i>Small Samples</i>	<i>Large Samples</i>
One Sample		Wilcoxon Signed Rank Test	One Sample T-Test
Two Samples	Independent Samples	<ul style="list-style-type: none"> • Mann-Whitney test • Kolmogorov-Smirnov test 	Two Sample T-Test
	Paired Samples	<ul style="list-style-type: none"> • Wilcoxon signed rank Test • Sign Test 	Paired Sample T-Test
Multiple Samples	Independent Samples	<ul style="list-style-type: none"> • Kruskal-Wallis ANOVA • Mood's Median Test 	One Way ANOVA
	Related Samples	Friedman ANOVA	One Way Repeated Measure ANOVA

5.4.1.4 Examples

One Sample Independent Tests


The One-Sample Wilcoxon Signed Rank test is designed to examine the population median relative to a specified value. You may choose a one- or two-tailed test. The Wilcoxon signed rank test hypotheses are H_0 : median = hypothesized median versus H_1 : median \neq hypothesized median. In this example, a quality engineer in a production shop is interested in whether median (or average) of the weight of product is equal to 166. So select 10 product at random and measured their weight . The data measured as following:

151.5 152.4 153.2 156.3 179.1 180.2 160.5 180.8 149.2 188.0

The engineer perform **Normality Test** to determine if the distribution of the data is normal distribution

1. Open a new worksheet and input the above data in col(A). Select **Statistics: Descriptive Statistics: Normality Test...** to open the **Normality Test** dialog.

2. Select A(X) as **Data range**.



3. Click the **OK** button to generate results.


Shapiro-Wilk

	DF	Statistic	p-value	Decision at level(5%)
B	10	0.83472	0.03814	Reject normality

B: At the 0.05 level, the data was not significantly drawn from a normally distributed population.

According to result, P-value=0.03814, the distribution of the data is not normal distribution at the 0.05 level. So, perform One-Sample Wilcoxon Signed Rank test:

1. Select **Statistics: Nonparametric Tests: One-sample Wilcoxon Signed Rank Test...** to open the dialog.
2. Set column A as **Data Range**.
3. Input **166** in **Test Median** text box.



4. Click the **OK** button to generate results

Descriptive Statistics

	N	Min	Q1	Median	Q3	Max
A	10	149.2	152.175	158.4	180.35	188

Test Statistics

	W	Z	Exact Prob > W	Asymp. Prob > W
A	28	0	1	1

Null Hypothesis: Median = 166
 Alternative Hypothesis: Median <> 166
 A: At the 0.05 level, the population median is NOT significantly different from the test median (166).


According to the result, it fails to reject null hypothesis at the 0.05 level and concludes that the median is equal to 166.

Two Sample Independent Tests

Origin provides two tests for non-parametric statistics of two sample independent system: the **Mann-Whitney Test** and **Two Sample Kolmogorov-Smirnov Test**.

This following example shows the practical use of **Mann-Whitney Test**. The abrasions(in mg) are measured for two types of tires(A and B), 8 experiments were carried out for each tire type. The data is indexed and stored in abrasion_indexed.dat file.

1. Import the abrasion_indexed.dat file from \Samples\Statistics\
2. Select **Statistics: Nonparametric Tests: Mann-Whitney Test** to open the dialog.
3. Keep **Input Data Form** as **Index**
4. Set column A as **Group Range**, set column B as **Data Range**.
5. Select the **Exact P Value** check box.



6. Click the **OK** button to generate results, which should be in the **MannWhitney1** sheet

Test Statistics

	U	Z	Exact Prob> U	Asymp. Prob> U
	34.5	0.2102	0.82191	0.83351

Null Hypothesis: $F(x) = G(y)$
 Alternative Hypothesis: $F(x) \neq G(y)$
 At the 0.05 level, the two distributions are NOT significantly different.

- **U**: The **U** statistic can be simply calculated from the rank of two groups. It is the number of times a score in the 2nd group is larger than a score in the 1st group.
- **Z**: The approximate Normal test statistic. It provides an excellent approximation as the sample size grows.
- **Exact Prob**: The exact p-value, only available when **Exact P Value** is selected in the dialog. However, it could be very CPU-time consuming for large sample size.
- **Asymp.Prob**: The asymptotic p-value calculated from the approximate Normal test statistic, **Z**

Non-parametric Measures of Correlation


Correlation coefficient is used as a measure of relationship between two variables. It is possible to calculate the correlation coefficient for non-parametric statistics.

Origin provides two non-parametric methods to measure the correlations between variables:

- **Spearman**: common substitution of Pearson correlation coefficient, Spearman's coefficient can be used when both dependent (variable and independent variable are ordinal numeric, or when one variable is a ordinal numeric and the other is a continuous variable. However, it can also be appropriate to use Spearman's correlation when both variables are continuous.
- **Kendall**: Used with ordinal variables for assessing agreement among raters

The following example shows how to calculate correlation coefficient for non-parametric situations.

1. Import the abrasion_raw.dat file from **Samples\Statistics**;
2. Highlight Column A and column B. Select **Statistics:Descriptive Statistics:Correlation Coefficient** to open the corrcoef dialog;
3. Check **Spearman** and uncheck **Pearson**;



- Click the **OK** button to generate the results, in the **CorrCoef1** sheet.

From the value of **Spearman Corr.**, it can be concluded that the abrasion between tire A and tire B are strongly related.

Spearman Correlations


		tireA	tireB
"tireA"	Spearman Corr.	1	0.90476
	Sig.	--	0.00201
"tireB"	Spearman Corr.	0.90476	1
	Sig.	0.00201	--

2-tailed test of significance is used

Paired Sample wilcoxon Signed Rank Tests

We will compare the two medians of *tire A* and *tire B* in above example.

1. Continue with the abrasion_raw.dat file from **Samples\Statistics**;
2. Select **Statistics: Nonparametric Tests: Paired Sample wilcoxon Signed Rank Tests** to open the dialog;
3. Select Column A as **1st Range Data** and column B as **2nd range Data**;



4. Click the **OK** button to generate the results.

Descriptive Statistics						
	N	Min	Q1	Median	Q3	Max
"tireA"	8	4870	4980	5760	7330	8650
"tireB"	8	4900	4950	5420	6687.5	7930

Ranks				
		N	Mean Rank	Sum Rank
"tireB"- "tireA"	Positive Ranks	2	1.5	3
	Negative Ranks	6	5.5	33

Test Statistics				
	W	Z	Exact Prob> W	Asymp. Prob> W
	33	2.0329	0.03906	0.04206

Null Hypothesis: $F(x) = G(y)$
 Alternative Hypothesis: $F(x) \neq G(y)$
 At the 0.05 level, the two distributions are significantly different.

We can conclude that two medians are significantly different. Obviously, median of group A is larger than that of group B.


Multiple Independent Samples Test


In this example, the gas mileage of four car makers are measured. Several experiments are carried out for each car makers. The results are listed in the sample data table.

GMC/mpg	Infinity/mpg	Saab/mpg	Kia/mpg
26.1	32.2	24.5	28.4
28.4	34.3	23.5	34.2
24.3	29.5	26.4	29.5
26.2	35.6	27.1	32.2
27.8	32.5	29.9	
30.6	30.2		
28.1			

To evaluate whether the gas mileage of the four car makers are equal, and which one is the most efficient, Kruskal-Wallis ANOVA is chosen as the nonparametric test method.

1. Create a new workbook in Origin, copy the sample data and paste into it;

2. Select **Statistics:Nonparametric Tests:Kruskal-Wallis ANOVA** to open the kwanova dialog;
3. Specify Raw as **Input Data Form**;
4. Click the **triangle button**  next to **Input**, and select **All Columns** in the context menu;



5. Click the **OK** button to generate results, the results are stored in a new worksheet **KWANOVA1**.

From the p-value we can conclude that gas mileage of the four car makers are significant different.

Test Statistics


Chi-Square	DF	Prob>Chi-Square
12.59645	3	0.0056

Null Hypothesis: The samples come from the same population.
 Alternative Hypothesis: The samples come from different populations.
 : At the 0.05 level, the populations are significantly different.

Multiple Related Samples Test

Ophthalmologists are investigating whether laser He-Ne therapy works for children. They have data from 2 groups, 6-10 Years Old and 11-16 Years Old. Each data set contains study of 5 persons' naked-eye eyesight difference after 3 period of therapy. The results are stored in the eyesight.dat. Due to the small sample size, non-parametric statistics would be needed in analysis, following the steps below:

1. Import the eyesight.dat file from **\Samples\Statistics**;
2. Select **Statistics:Nonparametric Tests:Friedman ANOVA** to open the friedman dialog;
3. Select Column A as **Data Range**, Column C as **Factor Range**, and Column D as **Subject Range**;



4. Click the **OK** button to generate results.


The p-value of χ_{66010}^2 is 0.0067379, which is less than 0.05. The populations are significantly different, indicating that the therapy are effective for the age group 6-10.

Test Statistics

Chi-Square	DF	Prob>Chi-Square
10	2	0.00674

Null Hypothesis: The samples come from the same population.
 Alternative Hypothesis: The samples come from different populations.
 At the 0.05 level, the populations are significantly different

In a similar way, choose column B as **Data Range** and the rest setting of **Input** are the same with Step 3 previously.



Check the result, we can see that p-value of χ^2_{16} is 0.02599, less than 0.05 or 0.10. So we can also conclude that eyesight of 11-16 years old kids is better after 3 period of therapy.

Test Statistics

	Chi-Square	DF	Prob>Chi-Square
	7.3	2	0.02599

Null Hypothesis: The samples come from the same population.
 Alternative Hypothesis: The samples come from different populations.
 At the 0.05 level, the populations are significantly different

And we can see that $\chi^2_{6-10} > \chi^2_{11-16}$, that means, laser He-Ne therapy works better on 6-10 years old kids. The earlier children are to be involved in therapy, the more their eyesight can be improved.

5.5 Survival Analysis

- [Kaplan-Meier Estimator](#)
- [COX Model Estimator](#)
- [Weibull Fit](#)

5.5.1 Kaplan-Meier Estimator

5.5.1.1 Summary

Survival analysis is the study of the time until a certain event, such as a death or failure in treatment. It also called event history analysis in social science, or reliability analysis in engineering.

Survival function, $S(t)$, can describes the survival rate at time t . And $S(t)=1-F(t)$, where $F(t)$ is the cumulative distribution function of the failure times. While The hazard function $h(t)$ (also known as the failure rate, hazard rate, or force of mortality) is the ratio of the probability density function $P(t)$ of $F(t)$ to the survival function $S(t)$.

The Kaplan-Meier also called product-limit estimator provides an estimate of $S(t)$ and $h(t)$ from a sample of failure times which may be progressively right-censored.

Minimum Origin Version Required: Origin 8.0 SR6

5.5.1.2 What you will learn


This tutorial will show you how to:


- Perform Kaplan-Meier Estimator
- How to interpret the results

5.5.1.3 Steps


Running Kaplan-Meier Estimator

Scientist is looking for a better medicine for cancer resistance. After exposing some rats to a carcinogen DMBA, they apply different medicine to different groups of rats and record their survival status for first 60 hours. In the 1st group, 15 rats survived after being exposed, on which Medicine 1 is applied. Note that on the 30th hours, 1 rat is dead but not for carcinoma. In the 2nd group, 15 rats survived with drug 2 applied. Note that on the 14th hour, the 15th hour and the 25th hour, 1 rat die but not because of carcinoma. And the records of two groups rats are sorted in the file **/Samples/Statistics/SurvivedRats.dat**. Note that in Status, 0 = dead but not because of carcinoma, 1 = dead because of carcinoma, 2 = alive.


1. Click the Import Single ASCII button  to import the file **/Samples/ Statistics/ SurvivedRats.dat**
2. Analyze the dataset using the Kaplan-Meier Estimate tool. Use the menu item **Statistics: Survival Analysis: Kaplan-Meier Estimator** to open the dialog.
3. Set column **A**, **B** and **C** as **Time Range**, **Censor Range** and **Grouping Range** respectively in the **Input** tab.
4. Set 0 and 2 as **Censored Value(s)**




- In the **Survival Table** tab, select the **Event and censor values Summary** , **Survival Estimates**, **Quartile Estimates** and **Mean Estimates** check boxes.



- Select **Survival** , **One Minus survival** and **Hazard** check box in the **Survival Plots** tab.



7. Select the **Log-Rank** check box in the **Equality Test** tab.



8. Click the **OK** button.

Interpreting the Results

Go to worksheet **KaplanMeier1** for the analysis report :

1. From the "summary of event and censored values" table, we can see that **Censored=3** and **Percent Censored =0.2** for drug 1 group and **Censored=9** and **Percent Censored=0.6** for drug 2 group.

Summary of Event and Censored Values

	Total	Events	Censored	Percent Censored
drug1	15	12	3	0.2
drug2	15	6	9	0.6

Censored Value(s): 0,2

- "Kaplan-Meier Survival Estimates " tables display a descriptive procedure for examining the distribution of time-to-event variables. We also can compare the distribution by levels of a factor variable. **Quartile Estimates** and **Means Estimates** table Provides the estimates and confidence interval of quartile and mean.

Survival Analysis of Time (drug1)

Kaplan-Meier Survival Estimates

Time	Status	Cumulative Survival	Standard Error	Cumulative Event	Number Remaining
14		0.93333	0.06441	1	14
15	--		--	2	13
15		0.8	0.10328	3	12
17	--		--	4	11
17		0.66667	0.12172	5	10
20		0.6	0.12649	6	9
21		0.53333	0.12881	7	8
23		0.46667	0.12881	8	7
30 +	--		--	8	6
32		0.38889	0.1287	9	5
38		0.31111	0.12426	10	4
42		0.23333	0.11499	11	3
58		0.15556	0.09955	12	2
60 +	--		--	12	1
60 +	--		--	12	0

Observations with status as + are censored ones.

Quartile Estimates

Percent	Estimate	95% LCL	95% UCL
25	17	15	23
50	23	17	42
75	42	23	58

Mean Estimate

Estimate	Std.Error	95% LCL	95% UCL
32.02222	4.53441	23.13494	40.9095

Estimation is underestimated because the largest observation is censored.

Survival Analysis of Time (drug2)

Kaplan-Meier Survival Estimates

Time	Status	Cumulative Survival	Standard Error	Cumulative Event	Number Remaining
14	+	--	--	0	14
15	+	--	--	0	13
17		0.92308	0.07391	1	12
23		0.84615	0.10007	2	11
25	+	--	--	2	10
28		--	--	3	9
28		0.67692	0.13366	4	8
36		0.59231	0.14122	5	7
60		0.50769	0.14418	6	6
60	+	--	--	6	5
60	+	--	--	6	4
60	+	--	--	6	3
60	+	--	--	6	2
60	+	--	--	6	1
60	+	--	--	6	0

Observations with status as + are censored ones.

Quartile Estimates


Percent Failures	Estimate	95% LCL	95% UCL
25	28	23	60
50	--	--	--
75	--	--	--

Mean Estimate


Estimate	Std.Error	95% LCL	95% UCL
46.4	5.26463	36.08152	56.71848

Estimation is underestimated because the largest observation is censored.


- The survival curves give a visual representation of the life tables. A plot of the Kaplan-Meier estimate of the survival function is a series of horizontal steps of declining magnitude. In the plot, the survival curve declines more rapidly, the survival rate is smaller. This Survival function plot shows proportion of individuals surviving at each hour for drug 1 group and drug2 group and the survival curve of drug1 always declines more rapidly, so we can conclude that drug 2 is one better medicine for cancer resistance.



4. From one minus survival function, we can get the same conclusion as Survival function plot.



5. Hazard rate is the instantaneous probability of the given event occurring at any point in time. It can be plotted against time on the X axis, forming a graph of the hazard rate over time. And hazard function is the equation that describe this plotted line. From the graph, we can get the hazard rate of drug 1 group is greater than drug 2 group. So we can conclude that drug 2 is one better medicine for cancer resistance.



6. For overall tests of the equality of survival times across groups, Origin provides three methods:
- Log rank: Tests equality of survival functions by weighting all time points the same.
 - Breslow: Tests equality of survival functions by weighting all time points by the number of cases at risk at each time point.
 - Tarone-Ware: Tests equality of survival functions by weighting all time points by the square root of the number of cases at risk at each time point.

Test of Equality over Groups

	Chi-Square	df	Prob>Chi-Square
Log Rank	4.73554	1	0.02955
Breslow	4.91804	1	0.02658
Tarone-Ware	4.89582	1	0.02692

Since the significance values of the tests are all smaller than 0.05, there is statistically significant difference between two treatments(drug1 and drug2) in survival time.

5.5.2 COX Model Estimator

5.5.2.1 Summary

The Cox Model Estimation, also called the proportional hazard model is a classical semi-parameter method in survival analysis. A Cox model provides an estimate of the effect on survival for variables and the hazard of death for an individual. Using Cox regression analysis, we will obtain an equation for the hazard as a function of several variables. A positive regression coefficient for an explanatory variable means that the hazard is higher with higher values of that variable. While for negative regression coefficient for an explanatory variable, the hazard is lower with higher values of that variable.

The proportional hazards assumption: Observations should be independent, and the hazard ratio should be constant across time; that is, the proportionality of hazards from one case to another should not vary over time.


Minimum Origin Version Required: Origin 8.0 SR6


5.5.2.2 What you will learn

This tutorial will show you how to:

- Perform COX Model Estimator
- How to interpreting the results

5.5.2.3 Perform COX Model Estimator

1. Click the Import Single ASCII button  to import **phm_Cox.dat** located in the **\Samples \Statistics** subfolder.
2. Select **Statistics: Survival Analysis: Cox Model Estimator** to open the dialog.
3. Put the **A(X):month** column into **Time Range**. Similarly, put the **B(Y):status** column into **Censor Range**.
4. Click the interactive data selection button and choose the **Charlson** and **tKt_v** column into the Covariate Range edit box.
5. Select **0** as the censoring value from censoring value(s) drop-down list.
6. Check **Survival** and **Hazard** box in Survival Plots group.
7. Click the **OK** button to perform the Cox Model Estimator analysis.



5.5.2.4 Interpreting the Results

Go to worksheet **CoxPHM1** for the analysis report.

1. From the "Summary of event and censored values" table, we can see that **censored** =112 and **percent Censored** =0.8.

Summary of Event and Censored Values

Total	Events	Censored	Percent Censored
140	28	112	0.8

Censored Value(s): 0

- The following table displays the result of test whether the model is significant or not. Note that the null hypothesis is $\beta_1 = \beta_2 = 0$. In this example, $\text{Pr} > \text{ChiSq} = 4\text{E}(-4) < 0.05$, therefore, we reject the null hypothesis, that is, exist one $\beta_i \neq 0$ ($i=1,2$) at least.

Analysis of -2 Log Likelihood Estimates

-2 Log Likelihood	Chi-Square	DF	Pr > ChiSq
239.8598	15.5649	2	4E-4


Iteration limit was reached without convergence.
Validity of the model fit is questionable.

- In the "Analysis of parameter Estimates" table, the coefficient estimates of charlson is 0.2876 and $\text{Pr} > \text{ChiSq} = 5\text{E}-4 < 0.05$, so $\beta_1 = 0.287$ and charlson is significant variable. Hazard ratio, can be interpreted as the predicted change in the hazard for a unit increase in the predictor. For variable charlson, **Hazard ratio**=1.333, means that the hazard become 1.333 times when charlson increment one unit. Similarly, **tKt_v** is significant variable. The coefficient estimates of **tKt_v** $\beta_2 = -0.837$ and hazard ratio=0.433. we can know the hazard function: $h(t,x) = h_0(t) \cdot \exp(0.2876 \cdot \text{charlson} - 0.837 \cdot \text{tKt}_v)$


Analysis of parameter estimates

	DF	Estimate	Standard Error	Chi-Square	Pr > ChiSq	Hazard Ratio
"charlson"	1	0.2876	0.0827	12.0856	5E-4	1.3333
"tKt_v"	1	-0.837	0.3445	5.9032	0.0151	0.433

- Survival function plot shows proportion of individuals surviving at each hour and is a visual display of the model-predicted. The horizontal axis shows the time to event. The vertical axis shows the probability of survival.



- Hazard function plot display the instantaneous probability of the given event occurring at any point in time.



5.5.3 Weibull Fit

5.5.3.1 Summary

Weibull fit is a kind of parameter method to analyze the relationship between the survival function and failure time. After analysis, we can get parameter estimates, which can determine survival function and hazard function of Weibull distribution .

Weibull distribution:

$$f(x) = \frac{c}{\sigma} \left(\frac{x - \theta}{\sigma}\right)^{c-1} \exp\left(-\left(\frac{x - \theta}{\sigma}\right)^c\right) \text{ where } x > \theta, \text{ for } c, \sigma > 0$$

Survival function:

$$S(x) = \exp\left(-\left(\frac{x - \theta}{\sigma}\right)^c\right)$$

Hazard function:

$$h(x) = \frac{c}{\sigma} \left(\frac{x - \theta}{\sigma}\right)^{c-1}$$

where c is the shape parameter, σ is the scale parameter, and θ is the location parameter. If $c > 1$ the hazard increases , if $c = 1$ the hazard is constant(exponential model), if $c < 1$ the hazard decreases.


Minimum Origin Version Required: Origin 9.1 SR0


5.5.3.2 What you will learn

This tutorial will show you how to:

- Perform Weibull Fit
- How to explain analysis report

5.5.3.3 Perform Weibull Fit

1. Click the Import Single ASCII button  to import **weibull fit.dat** located in the \Samples \Statistics subfolder.
2. Select **Statistics: Survival Analysis: weibull fit** to open the dialog.
3. Put the **A(X)** column into **Time Range**. Similarly, put the **B(Y)** column into **Censor Range**.
4. Select **0** as the censoring value form censoring value(s) drop-down list.
5. Click the **OK** button to perform the Weibull fit analysis.



5.5.3.4 Interpreting the Result

Go to worksheet **WeibullFit1** for the analysis report.

- From the "summary of event and censored values" table , we can see that **censored** =19 and **percent Censored** =0.2111.

Summary of Event and Censored Values

Total	Events	Censored	Percent Censored
90	71	19	0.21111

Censored Value(s): 0

- From the Analysis of parameter estimates, we can get all parameter estimates for Weibull distribution.

Intercept= θ =4.1959, Weibull Scale= σ =66.4153, Weibull Shape= c =2.0204, Scale =0.495 (scale= $1/c$).

Analysis of parameter estimates

	DF	Estimate	Standard Error	95% LCL	95% UCL
Intercept	1	4.1959	0.0588	4.0806	4.3112
Scale	1	0.495	0.0481	0.4091	0.5988
Weibull Scale	1	66.4153	3.9077	59.1815	74.5333
Weibull Shape	1	2.0204	0.1963	1.67	2.4443

*Log-Likelihood=-87.087474880717

$c > 1$, so we can conclude that the hazard increases as time. Furthermore, we can get the survival function and hazard function:

$$S(x) = \exp\left(-\left(\frac{x - 4.1959}{66.4153}\right)^{2.0204}\right)$$

$$h(x) = \frac{2.0204}{66.4153} \left(\frac{x - 4.1959}{66.4153}\right)^{1.0204}$$

5.6 Multivariate Analysis

- [Principal Component Analysis](#)
- [Cluster Analysis](#)
- [Discriminant Analysis](#)
- [Partial Least Squares](#)

5.6.1 Principal Component Analysis

5.6.1.1 Summary

Principal Component Analysis is useful for reducing and interpreting large multivariate data sets with underlying linear structures, and for discovering previously unsuspected relationships.

We will start with data measuring protein consumption in twenty-five European countries for nine food groups. Using Principal Component Analysis, we will examine the relationship between protein sources and these European countries.

Minimum Origin Version Required: Origin 8.6 SR0


5.6.1.2 Selecting Principal Methods


To determine the number of principal components to be retained, we should first run Principal Component Analysis and then proceed based on its result:


1. Open a new project or a new workbook. Import the data file **\samples\Statistics\Protein Consumption in Europe.dat**
2. Select the entire worksheet and then select **Statistics: Multivariate Analysis: Principal Component Analysis**.
3. Accept the default settings in the open dialog box and click **OK**.
4. Select sheet **PCA Report**.
5. In the **Eigenvalues of the Correlation Matrix** table, we can see that the first four principal components explain 86% of the variance and the remaining components each contribute 5% or less. We will keep four main components.

	Eigenvalue	Percentage of Variance	Cumulative
1	4.00644	44.52%	44.52%
2	1.635	18.17%	62.68%
3	1.12792	12.53%	75.22%
4	0.95466	10.61%	85.82%
5	0.46384	5.15%	90.98%
6	0.32513	3.61%	94.59%
7	0.27161	3.02%	97.61%
8	0.11629	1.29%	98.90%
9	0.09911	1.10%	100.00%

6. A scree plot can be a useful visual aid for determining the appropriate number of principal components. The number of components depends on the "elbow" point at which the remaining eigenvalues are relatively small and all about the same size. This point is not very evident in the scree plot, but we can still say the fourth point is our "elbow" point.



- Click the lock icon  in the results tree and select **Change Parameters** in the context menu. In the **Settings** tab, set **Number of Components to Extract** to **4**. Do not close the dialog; in the next steps, we will retrieve component diagrams.



5.6.1.3 Request Principal Component Plots

In the **Plots** tab of the dialog, users can choose whether they want to create a scree plot or a component diagram.

- **Scree Plot**

The **scree plot** is a useful visual aid for determining an appropriate number of principal components.

- **Component Plot**

Component plots show the component score of each observation or component loading of each variable for a pair of principal components. In the **Select Principal Components to Plot** group, users can specify which pair of components to plot. The component plots include:

- **Loading Plot**

The **loading plot** is a plot of the relationship between the original variables and the subspace dimension. It is used to interpret relationships between variables.


- **Score Plot**

The **score plot** is a projection of data onto subspace. It is used to interpret relationships between observations.

- **BiPlot**

The **biplot** shows both the loadings and the scores for two selected components in parallel.

1. In the dialog that was opened in the preceding steps, select the **Plots** tab. Make sure **Scree Plot**, **Loading Plot**, and **Biplot** are selected.
2. The first two components are usually responsible for the bulk of the variance. This is why we are going to plot the component plot in the space of the first two principal components. In the **Select Principal Components to Plot** group, set **Principal Component for X Axis** to **1**, and set **Principal Component for Y Axis** to **2**. Click **OK**.



5.6.1.4 Interpreting The Results

1. In the **Correlation Matrix**, we can see that the variables are highly correlated. Many values are greater than **0.3**. Principal Component Analysis is an appropriate tool for removing the collinearity.

Correlation Matrix

	Red Meat	White Meat	Eggs	Milk	Fish	Cereals	Starch	Nuts	Fruits & Vegetables
Red Meat	1	0.153	0.58561	0.50293	0.06096	-0.49988	0.13543	-0.34945	-0.07422
White Meat	0.153	1	0.62041	0.28148	-0.23401	-0.4138	0.31377	-0.63496	-0.06132
Eggs	0.58561	0.62041	1	0.57553	0.06557	-0.71244	0.45223	-0.55978	-0.04552
Milk	0.50293	0.28148	0.57553	1	0.13788	-0.59274	0.22241	-0.62109	-0.40836
Fish	0.06096	-0.23401	0.06557	0.13788	1	-0.52423	0.40385	-0.14715	0.26614
Cereals	-0.49988	-0.4138	-0.71244	-0.59274	-0.52423	1	-0.53326	0.651	0.04655
Starch	0.13543	0.31377	0.45223	0.22241	0.40385	-0.53326	1	-0.47431	0.08441
Nuts	-0.34945	-0.63496	-0.55978	-0.62109	-0.14715	0.651	-0.47431	1	0.37497
Fruits & Vegetables	-0.07422	-0.06132	-0.04552	-0.40836	0.26614	0.04655	0.08441	0.37497	1

2. The main component variables are defined as linear combinations of the original variables.

The **Extracted Eigenvectors** table provides coefficients for equations.

Extracted Eigenvectors				
	Coefficients of PC1	Coefficients of PC2	Coefficients of PC3	Coefficients of PC4
Red Meat	0.30261	-0.05625	-0.29758	0.64648
White Meat	0.31056	-0.23685	0.6239	-0.03699
Eggs	0.42668	-0.03534	0.18153	0.31316
Milk	0.37773	-0.18459	-0.38566	-0.00332
Fish	0.13565	0.64682	-0.32127	-0.21596
Cereals	-0.43774	-0.23349	0.09592	-0.0062
Starch	0.29725	0.35283	0.24298	-0.33668
Nuts	-0.42033	0.14331	-0.05439	0.33029
Fruits & Vegetables	-0.11042	0.53619	0.40756	0.46206


$$PC1 = 0.30261 * RedMeat + 0.31056 * WhiteMeat + 0.42668 * Eggs + 0.37773 * Milk + 0.13565 * Fish - 0.43774 * Cereals + 0.29725 * Starch - 0.42033 * Nuts - 0.11042 * FruitsVegetables$$


$$PC2 = -0.05625 * RedMeat - 0.23685 * WhiteMeat - 0.03534 * Eggs - 0.18459 * Milk + 0.64682 * Fish - 0.23349 * Cereals + 0.35283 * Starch + 0.14331 * Nuts + 0.53619 * FruitsVegetables$$


$$PC3 = -0.29758 * RedMeat + 0.6239 * WhiteMeat + 0.18153 * Eggs - 0.38566 * Milk - 0.32127 * Fish + 0.09592 * Cereals + 0.24298 * Starch - 0.05439 * Nuts + 0.40756 * FruitsVegetables$$

$$PC4 = 0.64648 * RedMeat - 0.03699 * WhiteMeat + 0.31316 * Eggs - 0.00332 * Milk - 0.21596 * Fish - 0.0062 * Cereals - 0.33668 * Starch + 0.33029 * Nuts + 0.46206 * FruitsVegetables$$

3. The **Loading Plot** reveals the relationships between variables in the space of the first two components. In the loading plot, we can see that Red Meat, Eggs, Milk, and White Meat have similar heavy loadings for principal component 1. Fish, fruit, and vegetables, however, have similar heavy loadings for principal component 2.




4. The **biplot** shows both the loadings and the score for two selected components in parallel. It can reveal the projection of an observation on the subspace with the score points. It can also find the ratio of observations and variables in the subspace of the first two components. (Note: Double-click the graph to open and customize.)
5. Use the Data Reader tool  to open the Data Info window and examine the plot in greater detail. We can see that Spain and Portugal's protein sources differ from those of other European countries. Spain and Portugal rely on fruits and vegetables, while eastern European countries such as Albania, Bulgaria, Yugoslavia, and Romania prefer cereals and nuts.




To display country information in the **Data Info** window, as in the image above:


1. Right-click the **Data Info** window and select **Preferences...**
2. In the **Rows** tab, move **Country** from the left panel to the right. Click **OK**.



To create an arbitrary 3D loading plot, such as PC1-PC2-PC4 or PC1-PC3-PC5 loading plot:

1. Click the lock icon  in the results tree and select **Change Parameters** in the context menu. In the **Settings** tab, set **Number of Components to Extract** as needed. For example, if you want to do a PC1-PC2-PC4 loading plot, **Number of Components to Extract** should be set as **4**. Click **OK** to close the dialog.
2. The **Extracted Eigenvectors** table now has 4 columns. To duplicate the sheet *PCA Plot Data1*, select the sheet *PCA Plot Data1* and right click to select **Duplicate**. Then rename the new sheet as sheet *PCA Plot Data2*.
3. Suppose you want to plot a PC1-PC2-PC4 loading plot. Activate the sheet *PCA Plot Data2*, Highlight **Col (E)** and right click to insert a column ahead of **Col (E)**. Insert a column ahead of **Col (G)**. Highlight two new columns and right click to select **Set as: Z**.
4. Rename the long name of **Col (H1)** and **Col (I1)** as **Principal Component 4**. Set the all the **Eigenvalue** of **Col (H1)** as **0**.
5. Go to sheet *PCA1*, copy the **Coefficients of PC4** in the **Extracted Eigenvectors** table and paste it into **Col (I1)** of sheet *PCA Plot Data2*.
6. Highlight **Col (C)** to **Col (I1)** and select **Plot: 3D Symbol/Bar/Vector: 3D Vector XYZ XYZ**.
7. You can also customize the Plot by changing vector color and adding label. Double click to enter **Plot Detail** dialog and then go to **Original** level. Select **3D Vector** tab, change **Color** as **Blue** and **Width** as **4**; Go to **Label** tab and customize **Label From: Col(G)**, **Position: Right**, **Size: 20** and **Attach to:**

Arrow Head. Click **OK** to close the dialog. The 3D loading plot will be created as follow.



5.6.2 Cluster Analysis

5.6.2.1 Summary

We will perform cluster analysis for the mean temperatures of US cities over a 3-year-period.


The starting point is a hierarchical cluster analysis with randomly selected data in order to find the best method for clustering. K-means analysis, a quick cluster method, is then performed on the entire original dataset.

Minimum Origin Version Required: Origin 8.6 SR0


5.6.2.2 Hierarchical Cluster Analysis

1. Start with a new project or a new workbook. Import the data file **\\Samples\Graphing\US Mean Temperature.dat**.
2. Highlight Column D through Column O.
3. Select **Statistics: Multivariate Analysis: Hierarchical Cluster Analysis**.


4. Select **Input** tab, click the **triangle button** next to **Variables**, and then click **Select Columns...** in the context menu.




5. In the lower panel of the Column Browser dialog, click the ... button. Set the data range from **1** to **100**. Click **OK**.





6. In the dialog, go to **Settings** tab, make sure **Cluster** is set to **Observations**, and **Number of Clusters** is **1**. Select **Furthest Neighbor** for **Cluster Method** and then click **OK**.




7. Go to the **Cluster 1** sheet. Based on the resulting dendrogram, we choose to cluster data into 5 groups.




8. Click the lock icon in the dendrogram or the result tree, and then click **Change Parameters** in the context menu.
9. Set **Number of Clusters** to **5** in the **Settings** tab and then select the **Cluster Center** check box in the **Quantities** tab. Click **OK**.




10. In the resulting dendrogram, we can clearly see how observations are clustered. (Note, you can double-click to open and customize the dendrogram.)




11. Due to the large number of observations, tick labels overlap in this dendrogram. Use the




Scale In  tool to select an area to magnify.




5.6.2.3 Analyzing Original Data with K-Means Cluster


1. Right-click on **Cluster Center** and select **Create Copy as New Sheet** in the context menu. We are going to use the newly created **Cluster Center** as the **Initial Cluster Centers** in our k-means cluster analysis.



2. Go back to the worksheet with the source data (US Mean Temperature), and highlight col(D) through col(O). Select **Statistics: Multivariate Analysis: K-Means Cluster Analysis**.
3. Select the **Specify Initial Cluster Centers** check box in the **Options** tab. Click the **interactive button**  next to **Initial Cluster Centers**. The dialog will "roll up".
4. Go to **Cluster Center** and highlight Col(D) through Col(O). Click the button on the rolled-up dialog to restore the dialog.
5. In the **Plot** tab, select **Group Graph**. Click the **interactive button**  next to **X Range**. The dialog will "roll up". Go back to the source worksheet **US Mean Temperature**, and highlight **Col(B):Longitude**. Click the button in the rolled up dialog to restore.
6. Click the **triangle button**  next to **Y Range**, and then select **C(Y), Latitude**. Click **OK**.



7. Activate the worksheet **K-Means Plot Data1**. Observe that data has been clustered into 5 groups corresponding to the latitudes of the cities.



5.6.3 Discriminant Analysis


5.6.3.1 Summary


The Iris flower data set, or Fisher's Iris dataset, is a multivariate dataset introduced by Sir Ronald Aylmer Fisher in 1936. This dataset is often used for illustrative purposes in many classification systems. The dataset consists of fifty samples from each of three species of Irises (iris setosa, iris virginica, and iris versicolor). Four characteristics, the length and width of sepal and petal, are measured in centimeters for each sample. We can use discriminant analysis to identify the species based on these four characteristics.

We will use a random sample of 120 rows of data to create a discriminant analysis model, and then use the remaining 30 rows to verify the accuracy of the model.


Minimum Origin Version Required: Origin 8.6 SR0

5.6.3.2 Discriminant Analysis

1. Open a new project or a new workbook. Import the data file **\Samples\Statistics\Fisher's Iris Data.dat**
2. Highlight columns A through D. and then select **Statistics: Multivariate Analysis: Discriminant Analysis** to open the **Discriminant Analysis** dialog, **Input Data** tab. Columns A ~ D are automatically added as **Training Data**.
3. Click the **triangle button**  next to **Group for Training Data** and select **E(Y):Species** in the context menu



4. Click the **Quantities** tab and select the **Discriminant Function Coefficients** check box. Expand the **Canonical Discriminant Analysis** branch and select the **Canonical Coefficients** check box. Accept all other default settings and click **OK**



5.6.3.3 Interpreting Results

Click on the **Discriminant Analysis Report** tab.

Canonical Discriminant Analysis

The **Canonical Discriminant Analysis** branch is used to create the discriminant functions for the model.

1. Using the **Unstandardized Canonical Coefficient** table we can construct the canonical discriminant functions.

Unstandardized Canonical Coefficients

	Canonical Variable 1	Canonical Variable 2
Constant	-2.10511	-6.66147
Sepal Length	-0.82938	0.0241
Sepal Width	-1.53447	2.16452
Petal Length	2.20121	-0.93192
Petal Width	2.81046	2.83919

$$D1 = -2.10511 - 0.82938 * SL - 1.53447 * SW + 2.20121 * PL + 2.81046 * PW$$

$$D2 = -6.66147 + 0.0241 * SL + 2.16452 * SW - 0.93192 * PL + 2.83919 * PW$$

where SL = Sepal Length, SW = Sepal Width, PL = Petal Length, PW = Petal Width

- The Eigenvalues table reveals the importance of the above canonical discriminant functions. The first function can explain 99.12% of the variance, and the second can explain the remaining 0.88%.

Eigenvalues

	Eigenvalue	Percentage of Variance	Cumulative	Canonical Correlation
1	32.19193	99.12%	99.12%	0.98482
2	0.28539	0.88%	100.00%	0.4712

- The Wilk's Lambda Test table shows that the discriminant functions significantly explain the membership of the group. We can see that both values in the **Sig** column are smaller than 0.05. Both values should therefore be included in the discriminant analysis.

Wilks' Lambda Test

	Wilks' Lambda	Chi-square	df	Sig.
1 to 2	0.02344	546.1153	8	8.87078E-113
2 to 2	0.77797	36.52966	3	5.78605E-8

At the 0.05 level, the dimensionality is significantly 2.

Classification

- The **Classification Summary for Training Data** table can be used to evaluate the discriminant model. From the table we can see that the classification in the groups **setosa** is 100% correct. For **versicolor**, only two observations are mistakenly classified as virginica, and for **virginica**, only one is mistakenly classified. The error rate is only 2.00%. This model is good.

Classification Summary for Training Data

Classification Count

	Predicted Group			
	setosa	versicolor	virginica	Total
setosa	50	0	0	50
	100.00%	0.00%	0.00%	100.00%
versicolor	0	48	2	50
	0.00%	96.00%	4.00%	100.00%
virginica	0	1	49	50
	0.00%	2.00%	98.00%	100.00%
Total	50	49	51	150
	33.33%	32.67%	34.00%	100.00%

Error Rate

	setosa	versicolor	virginica	Total
Prior	0.33333	0.33333	0.33333	
Rate	0.00%	4.00%	2.00%	2.00%

Error rate for classification of training data is 2.00%.

- You can further switch to the **Training Result1** sheet to see which observation is mistakenly classified. In the sheet we can see the post probabilities calculated from the discriminant model and which group the observation is assigned to.

Fisher's IrisD - Fisher's Iris Data.dat

	A(Y)	B(Y)	C(Y)	D(Y)
Long Name	Allocated to Group	Post Probabilities		
Units				
Comments	Classification			
F(x)=				
UserParam1		setosa	versicolor	virginica
79	versicolor	3.77353E-23	0.99252	0.00748
80	versicolor	9.55534E-12	1	1.91062E-8
81	versicolor	1.02211E-17	1	3.00775E-6
82	versicolor	9.64807E-16	1	3.2667E-7
83	versicolor	1.6164E-16	1	3.77844E-6
84	virginica*	4.24195E-32	0.14339	0.85661
85	versicolor	1.72451E-24	0.96356	0.03644
86	versicolor	1.34475E-20	0.99404	0.00596
87	versicolor	3.30487E-21	0.99822	0.00178
88	versicolor	2.03457E-23	0.99946	5.4431E-4
89	versicolor	5.80699E-18	0.99995	5.1371E-5
90	versicolor	5.98119E-21	0.99982	1.81687E-4
91	versicolor	5.87861E-23	0.99939	6.1442E-4
92	versicolor	5.39901E-22	0.99809	0.00191
93	versicolor	3.55951E-18	0.99999	1.12857E-5
94	versicolor	2.10415E-14	1	1.13502E-7

Fisher's Iris Data | Discrim1 | Training Result1 | Canonical

- For the 84-th observation, we can see the post probabilities(virginica) 0.85661 is the maximum value. i.e. the 84-th observation will be assigned to the group **virginica** (at 85.7% probability).
- But in source data, the 84-th observation is in group **versicolor**. So this observation is mistakenly classified by the model.

5.6.3.4 Model Validation

Model validation can be used to ensure the stability of the discriminant analysis classifiers

There are two methods to do the model validation

- **Cross-validation:**

In cross-validation, each training data is treated as the test data, exclude it from training data to judge which group it should be classified as, and then verify whether the classification is correct or not.

- **Subset Validation:**

Usually we will randomly divide the set of observations into subsets, the first of which is used for the estimation of discriminant model (training set) and the second is for testing the reliability of the results (test set).

Preparing Data for Analysis

We are going to sort the data in random order, and then use the first 120 rows of data as training data and the last 30 as test data.

1. Go back to sheet **Fisher's Iris Data**
2. Add a new column and fill the column with **Normal Random Numbers**.
3. Select the newly added column. Right-click and select **Sort Worksheet: Ascending** from the shortcut menu.


Notes: Origin will generate different random data each time, and different data will result in different results.

In order to get the same results as shown in this tutorial, you could open the *Tutorial Data.opj* under the **Samples** folder, browse in the **Project Explorer** and navigate to the **Discriminant Analysis (Pro Only)** subfolder, then use the data from column (F) in the **Fisher's Iris Data** worksheet, which is a previously generated dataset of random numbers.


Run Discriminant Analysis





1. Select columns A through D.


2. Select **Statistics: Multivariate Analysis: Discriminant Analysis** to open the **Discriminant Analysis** dialog.
3. To set the first 120 rows of columns A through D as **Training Data**, click the **triangle button** next to **Training Data**, and then select **Select Columns** in the context menu.




4. In the **Column Browser** dialog, click the ... button in the lower panel. Set data range from **1** to **120**. Click **OK**.



5. To set first 120 rows of Col(E) as **Group for Training Data**, click the **triangle button**  next to **Group for Training Data** and select **E(Y): Species** in the context menu. Then click the **Group for Training Data triangle button**  again, select **Select Columns** in the context menu, and set range from **1** to **120** with column browser. Click **OK**.
6. Select **Predict Membership of Test Data** check box. Click the **Test Data** interactive button . The dialog will "roll up". Select columns A through D in the worksheet. Click the button in the rolled up dialog to restore the dialog. Then click the **triangle button**  to open **Column Browser** by selecting **Select Columns** in the context menu. Click ... button in lower panel, and set range from **121** through **150**.



7. Click the **Settings** tab and select the **Cross Validation** check box. Click **OK**.



Cross-validation

Go to sheet **Discriminant Analysis Report1**. The **Cross-validation Summary for Training Data** table provides prediction error rate by classifying each case while leaving it out from the model calculations. However, this method is still more "optimistic" than subset validation.

[-] *Cross-validation Summary for Training Data* ▾

[-] *Classification Count* ▾

	Predicted Group			
	setosa	virginica	versicolor	Total
setosa	44	0	0	44
	100.00%	0.00%	0.00%	100.00%
virginica	0	36	2	38
	0.00%	94.74%	5.26%	100.00%
versicolor	0	2	36	38
	0.00%	5.26%	94.74%	100.00%
Total	44	38	38	120
	36.67%	31.67%	31.67%	100.00%

[-] *Error Rate* ▾

	setosa	virginica	versicolor	Total
Prior	0.33333	0.33333	0.33333	
Rate	0.00%	5.26%	5.26%	3.51%

Error rate for Cross-validation of training data is 3.51%.


Subset Validation

1. The **Classification Summary for Test Data** provide information that how the test data are classified.

[-] *Classification Summary for Test Data* ▾

	setosa	virginica	versicolor	Total
Count	6	12	12	30
Percent	20.00%	40.00%	40.00%	100.00%

2. On the worksheet **Fisher's Iris Data**, copy the last 30 rows (121 through 150) of **Col(E): Species**.
3. On the worksheet **Test Result**, add one column, **Col(E)**, to the worksheet. Paste the copied values in the new column.
4. Add a new column, **Col(F)** to the worksheet, right click on it and select Set Column Values in the context menu. In the opened dialog, type **Compare(col(A),col(E))** in the pop-up dialog and click OK.



5. None of 30 values is 0, it means the error rate the testing data is 0. Our discriminant model is pretty good.

5.6.3.5 Adjusting Prior Probabilities

Discriminant analysis assumes that prior probabilities of group membership are identifiable. If group population size is unequal, prior probabilities may differ. We can use **Proportional to group size** for the **Prior Probabilities** option in this case.


1. Go to sheet **Discrim2**, **Prior** row of the **Error Rate** table under **Classification Summary for Training Data** branch indicate the prior probabilities for membership in groups. It is assumed that a case is equally likely to be one of the three groups. Adjusting the prior probabilities according to the group size can improve the overall classification rate.

Error Rate ▼

	setosa	virginica	versicolor	Total
Prior	0.33333	0.33333	0.33333	
Rate	0.00%	2.63%	5.26%	2.63%

Error rate for classification of training data is 2.63%.

2. Click on the  button and select **Change Parameter** from the context menu. Select **Proportional to group size** for **Prior Probabilities** radio box. Click **OK** button.



3. We can see the classification error rate is 2.50%, it is better than 2.63%, error rate with equal prior probabilities.

Prior Probabilities = Proportional to group

[-] Error Rate ▾

	setosa	virginica	versicolor	Total
Prior	0.36667	0.31667	0.31667	
Rate	0.00%	2.63%	5.26%	2.50%

Prior Probabilities = Equal

[-] Error Rate ▾

	setosa	virginica	versicolor	Total
Prior	0.33333	0.33333	0.33333	
Rate	0.00%	2.63%	5.26%	2.63%

5.6.4 Partial Least Squares

5.6.4.1 Summary

Partial least squares (PLS) is a method for constructing predictive models when there are many highly collinear factors.

This tutorial will start with the spectral data of some samples to determine the amounts of three compounds present. The data includes:


Tutorials for Origin


- Data of the spectra emission intensities at different wavelength (v1 - v43)
- Amount of the three compounds in the sample (comp1, comp2, comp3)


This tutorial will establish a model to predict the amount of the three compounds from v1 - v43

Minimum Origin Version Required: Origin 2016 SR0

5.6.4.2 Partial Least Squares Regression


1. Start with a new project or a new workbook. Import the data file:
\\Samples\Statistics\MixtureSpectra.dat
2. Highlight Column("v1") through Column("v43").
3. Select **Statistics: Multivariate Analysis: Partial Least Squares**. This opens the pls dialog box to the **Input Data** tab.
4. The highlighted columns are automatically added as independent variables. Click the **triangle button**  next to **Independent Variables**, and click **Select Columns...** in the context menu.
5. Ensure the lower panel is expanded by clicking the button with two arrows in the bottom right of the **Column Browser** dialog.
6. In the lower panel click the ... button. A **Range** dialog box will open. Clear the **Entire Column(s)** box and set the data range from **1** to **20**. Click **OK**, then click **OK** to close the Column Browser.



7. Click the interactive button  to the right of **Dependent Variables**. Return to the worksheet, select column("comp1") and drag to column("comp3"). Click the interactive button again to restore the dialog box.




8. Since v1 to v43 are absorbance, there is no need to standardize them. Click on the **Settings** tab, set **Method** to SVD and clear the **Scale Variables** check box.
9. Select the **Cross Validation** check box. It helps find the optimal number of factors in the model.



10. Click the **Plots** tab and expand the **Component Plot** branch. Select the following check boxes and click the **OK** button.

- **Variable Importance Plot**
- **X Loadings Plot**
- **Y Loadings Plot**
- **X Scores Plot**
- **Y Scores Plot**
- **Diagnostics Plots**



5.6.4.3 Developing the Model


In the workbook, select the tab for the **PLS1** sheet:

1. The **Cross Validation** table shows the optimum number of factors to extract. PRESS is the predicted residual sum of squares of the model. The model with minimum Root Mean PRESS has the optimal number of factors:


Factors	Root Mean PRESS
0	0.1678
1	0.08999
2	0.03165
3	0.03096
4	0.02836
5	0.02895
6	0.02996
7	0.03051
8	0.03028
9	0.03021
10	0.03151
11	0.03279
12	0.03312
13	0.03397
14	0.03428
15	0.03459

Minimum root mean PRESS: 0.02836
Optimal number of factors: 4.


2. The Diagnostics Plots are residual plots of Y and X, which can be used to judge the quality of the model. Overall we can say that the fitted model is good because:
 - o Layer 1 - The **Predicted values-Actual values** graph indicates that the model fits well for the first component.
 - o Layer 2 - In the **Predicted values-Residual** graph, residuals are randomly distributed around zero. This indicates that there is no drift in the process.
 - o Layer 4 - The P-P plot of residual can be used to check whether the variance is normally distributed. The result falls almost in a line, which means the variance is normally distributed.



3. A summary of importance of v1~v43 is given by the VIP plot. If the variable has small regression coefficients and low VIP values, we can consider excluding it in the model. For example
 - o VIP values of v41 ~ v43 in the plot below are low:




- Coefficients of v41 ~ v43 are also small in the three coefficients below:




4. However, as in step 2, it appears that the model fits well so it is also acceptable to keep these less important variables.

5.6.4.4 Interpreting the Results


1. The **Variance Explained** table shows the proportion of variance explained by each factor. In the example, Factor 1 explains 71.36% variance for the X effect and 75.6% variance for the Y effect. Factor 2 explains 23.99% variance for the X effect and 22.14% for the Y effect. The **Variance Explained Plot** indicates that more attention should be paid to the first two factors as these two explained more than 95% variance for X and Y effects.




2. The Loading Plot reveals the relationships between X and Y variables in the space of the first two factors.
 - From the Y loading plot we can see that the three compounds have different loading on Factor 1 and Factor 2.



- From the X loading plot it is apparent that v26 ~ v38 have similar heavy loadings for Factor 2, and v17, v18, v19, v23 and v24 have similar light loadings for factor 1 and factor 2.






Notes: To examine the plot in detail, you can double-click to open the graph containing the

loading plot and [zoom in](#) it with the **Scale In** tool 

5.6.4.5 Using the Model to Predict

After the model is established, we can predict the amounts of the three compounds in new samples from their spectra emission intensities at different wavelengths:

1. Click the green lock on the PLS1 sheet and select **Change Parameter** from the context menu.
2. In the dialog that opens, click on the **Input** tab and select the **Predict Responses** check box.
3. Click the interactive button  to the right of **Independent Variables for Prediction**. Return to the workbook, select the **MixtureSpectra** sheet. Select column("v1") to column("v43"). Click the interactive button again to restore the dialog box.
4. Click the triangle button  next to **Independent Variables for Prediction**, and then click **Select Columns...** in the context menu.
5. In the lower panel of the **Column Browser** dialog, click the ... button. Deselect the **Entire Column(s)** box and set the data range from **21** to **25**. Click **OK** to close the **Range** dialog and **Column Browser** dialog..



6. Click the **OK** button to apply the settings and close the dialog.
7. The **PLSResults1** sheet will now contain the predicted amounts of the three compounds in the five new samples:

The screenshot shows a software window titled 'MixtureSpectr - MixtureSpectra.dat *'. It displays a table with columns for 'A(X1)', 'B(Y1)', 'C(Y1)', and 'D(Y1)', and rows for 'Long Name', 'Units', 'Comments', 'F(x)=', and numbered rows 1 through 10. The data is as follows:

	A(X1)	B(Y1)	C(Y1)	D(Y1)	
Long Name	Observations	comp1	comp2	comp3	lr
Units					
Comments	Predicted Responses for Test Data				
F(x)=					
1	21	0.03112	0.60104	0.35266	ln
2	22	0.45822	0.22111	0.2981	v1
3	23	0.23019	0.43717	0.30898	v2
4	24	0.33108	0.23231	0.40731	v3
5	25	0.37709	0.38007	0.21355	v4
6					v5
7					v6
8					v7
9					v8
10					v9

The bottom of the window shows a navigation bar with 'MixtureSpectra', 'PLS1', and 'PLSResults1'.

5.7 Power and Sample Size

5.7.1 Summary

Power and sample size analysis is useful in design of experiments. Insufficient data translates into a lack of power to reject a false null hypothesis and collecting too much data is a waste of time and resources. Therefore, it is essential to determine the sample size requirements prior to conducting an experiment. The power of the experiment can be computed for a given sample size, and required sample sizes can be computed for given power values.

Minimum Origin Version Required: Origin 8.0 SR6

5.7.2 What you will learn

This tutorial will show you how to calculate sample size or estimate power value to design experiments, using some practical examples.

5.7.3 (PSS)One-Sample t-Test

Background:

A sociologist wants to determine whether the average infant mortality rate in the United States is equal to 8. In experiment design, the difference of rate cannot vary more than 0.5. And it is already known that the standard deviation should be 2.1 from pilot studies.

Question:

What would the sample size be, in order to estimate the average infant mortality rate at a confidence level of 95% ($\alpha=0.05$) for power values of 0.7, 0.8 and 0.9?

Steps in Origin:

1. Activate an empty worksheet, select **Statistics: Power and Sample Size: (PSS) One-sample t-test**;
2. In the **PSS_tTest1** dialog box, choose the following settings and click **OK**.



Origin Output:

A result sheet will be generated, listing the calculated sample size for hypothetical powers.

☐ *Sample Size(s) for Hypothetical Power(s)* ▾

Alpha	Power	Sample Size
0.05	0.7	111
0.05	0.8	141
0.05	0.9	188

Null Mean = 8; Alternate Mean = 8.5; SD = 2.1; 2-Sided Test

Result Interpretation:

According to results, when designing his experiment the sociologist should conduct a survey of 111 samples for a power value of 0.7; 141 samples for power value of 0.8; and 188 samples for power value of 0.9.

5.7.4 (PSS)Two-Sample t-Test

Background:

A doctor's office participates in two local insurance plans, Healthwise and Medicare. The purpose is to compare the mean time (in days) until reimbursement of claims for the two plans. Historical data shows that for the Healthwise plan, the average time is 32 days and the standard deviation is 7.5 days. For the Medicare plan, the average reimbursement time is 42 days and the standard deviation is 3.5 days.

Question:

If 10 claims from each plan were selected and the corresponding reimbursement times were recorded, what is the power to detect the difference in mean reimbursement times between the 2 plans by 5% or more?


Steps in Origin:

1. Compute the pooled standard deviation as:

$$\sqrt{((5 - 1) * 7.5^2 + (5 - 1) * 3.5^2) / (5 + 5 - 2)} = 5.85235$$

*Note that this value will be used as the standard deviation later for the power calculation.

2. Sample size of 1st group and 2nd group should be 10 (20 samples total).
3. Activate an empty worksheet and select **Statistics: Power and Sample Size: (PSS) Two-Sample t-Test**,
4. In the **PSS_tTest2** dialog box, choose the following settings and click **OK**.



Origin Output:

A result sheet will be generated, showing the calculated power.

Power(s) for Hypothetical Sample Size(s)

Alpha	Sample Size	Power
0.05	10	0.95054

Group1 Mean = 32; Group2 Mean = 42; SD = 5.85235; 2-Sided Test

Interpretation of Results:

We can conclude that the doctor's office has a 0.95054:1 (or 95%) chance of detecting a difference if it collects 10 claims for each plan. The chance that you will fail to reject the null hypothesis and incorrectly conclude that the two means are not different is 4.946% (1 - 0.95054).

5.7.5 (PSS) Paired-Sample t-Test

Background:

Two machines of the same type are used to measure the depth of an amorphous silicon (a-Si) thin film. To determine if there is a difference in the two machines measurements, an engineer plans a study to compare the depth measurements made by the two machines.

In a previous study on depth of the a-Si thin film, the standard deviation of the difference was found to be 2µm. In addition, it is known that the difference in measurement by the two machines should not exceed 0.5µm, and the average depth measured by Machine #1 is 5000µm.

Question:

How many samples must be taken at a confidence level of 99% to obtain power values of 0.8, 0.9 and 0.95?

Steps in Origin:

From the information above, it is concluded that the mean of the 1st group is 5000 μm and the mean of the 2nd group is 5000.5 μm .

1. Activate an empty worksheet and select **Statistics: Power and Sample Size: (PSS) Paired t-Test**
2. In the **PSS_tTestPair** dialog box, set controls as in the following image and click **OK**.



Origin Output:

A result sheet will be generated, listing the required sample size at different power values.

Sample Size(s) for Hypothetical Power(s)

Alpha	Power	Sample Size
0.01	0.8	191
0.01	0.9	242
0.01	0.95	289

Group1 Mean = 5000; Group2 Mean = 5000.5; SD = 2; 2-Sided Test

Interpretation of Results:

We conclude that the engineer has an 80% chance of detecting a difference if 191 thin film samples are measured; a 90% chance if 242 thin film samples are measured; and a 95% chance if 289 thin film samples are measured by each machine.

5.7.6 (PSS)One-Way ANOVA

Background:


Researchers are interested in whether different plants have different nitrogen contents. They planned to record nitrogen contents in milligrams for 4 species of plants (80 observations per species). Previous research suggests that the square root of MSE (Mean Squared Error) is 60 and the CSS (corrected sum of squares) of the means is 400.

Question:

Is the plan feasible? (i.e. will the calculated power be acceptable?)

Steps in Origin:

1. The sample size for each group is 80.
2. Activate an empty worksheet and select **Statistics: Power and Sample Size: (PSS)One Way ANOVA**
3. In the **PSS_ANOVA1** dialog box, choose the following settings and click **OK**.



Origin Output:

A result sheet is generated, and the power value is calculated from the known condition.

Power(s) for Hypothetical Sample Size(s) 

Alpha	Sample Size	Power
0.05	80	0.6993

Treatments = 4; CSS of Means = 400; SD = 60

Interpretation of Results:

It appears that the original research plan is deficient. There is only a 69% chance of detecting a difference from each group. To get more reliable results, researchers must collect more samples per species of plant.

5.8 ROC curve

5.8.1 Summary

The Receiver Operating Characteristic (ROC) analysis curve is mainly used for diagnostic studies in Clinical Chemistry, Pharmacology, and Physiology. It has been widely accepted as the standard method used for describing and comparing the accuracy of diagnostic tests.

Please refer to the [Origin help file](#) for details on how to use the ROC curve.

5.8.2 What you will learn


This tutorial will show you how to:

- Carry out ROC curve analysis.
- Interpret the analysis of results.


5.8.3 Steps

In this example, we perform a study to determine whether serum sodium can help to diagnose Rocky Mountain Spotted Fever (RMSF).

The data is retrieved from people with or without RMSF, the sodium level for each person is measured by 2 screening techniques. ROC curve analysis is carried out for data from both methods, used to check the relationship between serum sodium and RMSF, and helped to judge which diagnostic method is better.

1. Click the **Import Single ASCII** button  to import the **sodium.dat** file into Origin, the file is under the `\Samples\Statistics` folder.
2. Select **Statistics: ROC Curve...** to open the ROC curve dialog.
3. Under the **Input Data** branch, select column **B(Method1)** and **C(Method2)** for **Data**, and column **A(Sickness)** for **State**, respectively.

4. Set **RMSF** as **Positive State Value** and select the **Positive v.s. Low** button for Test Direction under the Computation Control branch.
5. Accept all other default settings and click the **OK** button to carry out the analysis.




Results Interpretation: Go to worksheet ROC Curve1, where the analysis results are listed.

Area Under the Curve

	Area	Std. Error	Asymptotic Prob	95% LCL	95% UCL
Method1	0.88862	0.04577	2.48984E-6	0.79892	0.97833
Method2	0.79407	0.06344	3.66257E-4	0.66972	0.91842

From the table, we can see that the **Asymptotic Prob** of both methods are much smaller than 0.05, hence we can conclude that both methods are effective.

In ROC analysis, the closer the area is to 1.0, the better the test is, while the closer the area is to 0.5, the worse the test is. In this analysis, the area of method 1 and method 2 are 0.88862 and 0.79407, respectively. Both these results are much larger than 0.5. However, the area of method 1 is closer to 1.0, so we can conclude that method 1 is better than method 2.



In addition, we can examine the shape of ROC curve, which is also included in the report sheet. Since method 1 appears to have greater sensitivity than method 2, we can roughly conclude that method 1 is better than method 2.

6 Graphing


6.1 Plotting

- [3D Bar with Labels](#)
- [Creating a Graph](#)
- [Basic 2D Plotting](#)
- [Basic 3D Plotting](#)
- [Plot from User Defined Graph Template](#)
- [Adding a Data Plot to Existing Graph](#)
- [Smart Peak Labels with Leader Line](#)
- [Error Bars with Fill Area](#)
- [Mark out a segment of plot with different plot style](#)
- [Overview of Customization](#)
- [Plotting Overlapping Data and Setting Transparency](#)
- [Plotting using Plot Setup](#)

6.1.1 3D Bar with Labels

6.1.1.1 Summary

This tutorial will show you how to create the following graph:



Minimum Origin Version Required: 2015 SR0

6.1.1.2 What You will learn

This tutorial will demonstrate how to:

- Create and customize a flat Color Fill surface.
- Use Plot Setup to add a 3D bar plot to the original graph.
- Add and customize labels on the 3D bars.

6.1.1.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Creating a Flat Color Fill Surface from a Matrix


Open Tutorial Data.opj and browse to the folder *3D Bar with Labels*.

1. Activate the Matrix *MBook1B*.

- From the Origin menu select **Plot: 3D Surface: Color Fill Surface** to create a 3D plot that will have **Speed Mode** turned on:




- On the Origin menu, click **Format: Layer Properties**.
- On the **Size/Speed** tab, clear **Matrix data, maximum points per dimension**. This turns off **Speed Mode** allowing for full display of the dataset. Click **Apply**.




- Expand **Layer1** and select the plot under it.


- To flatten the plot of the US, click on the **Surface** tab and enable the **Flat** option.



- On the **Fill** tab, click the **Contour fill from matrix** radio button to set the colors according to the matrix information. Deselect the **Fill back surface** check box as well.
- Next click the **Colormap/Contours** tab to set the matrix colors and click **Level...**
- In the **Set levels** dialog that opens, select the **#Major Levels** radio button and set it to **2**. Set the **Total # of Levels** to **2** and click **OK** to close the dialog.




- Click on each color level under the **Fill...** heading to open the **Fill** dialog and choose the color. Set the three colors to **Black**, **Gray** and a customized blue with an RGB of **0, 64, 128** as shown below:




11. On the **Mesh** tab, clear the Enable box and click **OK** to close the dialog box.

12. The graph will resemble the image below:



Adding and Customizing 3D bars and labels

1. With the graph active select **Graph: Plot Setup** on the Origin menu. This opens the **Plot Setup** dialog box.
2. In the upper-left corner set **Available Data** to **Worksheets in Folder**. This will make the data in *Book2B* available for plotting on the same graph.
3. Select *Book2B*, set **Plot Type** to **3D - Bars**. In the middle panel set X, Y and Z as columns A1, G1 and D, respectively. Click **Add** to add the plot to the current layer:



Click **OK** to exit the dialog box.



In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking and expand **Available Data** panel by clicking again. Please refer to [Plotting using Plot Setup](#) for more information.


- To customize the 3-D bars, double-click on them to open the **Plot Details** dialog box. On the **Pattern** tab, set the border color to **Wine** and the fill color to **Red**. On the **Outline** tab set the **Width (in %)** to **10**. Click **Apply**
- Next, select the **Label** tab and check the **Enable** box.
- Set the **Label Form** as **Col(B):"City"** so that labels display the city name located in Col(B) of the worksheet.


7. Set the **Position** in **Z** as **Top Outside** with an Offset of **10** and set the **Orientation** in the **YZ** plane. Set the other controls as shown below and click **OK** to close dialog.

8. At this point the labels will not show as the axes scale is too small for them to be in the graph range. Double-click the vertical axis (Z Axis) and go to the **Scale** tab, set **From** to 0 and , **To** to 8000000. Click **OK** to exit.

9. Double-click on the graph again and in the **Plot Details** dialog box, select the **Graph1** option in the left panel. On the **Display** tab set the **Color** to **LT Gray**. Click **OK** to close dialog.
10. Double-click the Z axis title and change it to **Population (Million)**.

11. The final graph should resemble the one shown below:




12. Since this is a 3D OpenGL Graph, use the  **Rotate Tool** button on the **Tools** toolbar or hold down the **R** key and use the mouse, to rotate. You can also click the graph and select the



button to enter rotation mode as shown below, or use the controls in the **3D Rotation**

toolbar:



6.1.2 Creating a Graph

6.1.2.1 Summary

Origin provides templates library. You can create and modify templates by your own and add to the collection. Creating a graph in Origin is as simple as selecting the desired data and then selecting a template from a menu or from the graphing toolbars. The **Plot Setup** dialog offers more flexibility in creating plots, such as plotting data from multiple books or sheets.


Starting with Origin 2016, a more powerful "cloneable" template has been added. These templates are designed for "smart plotting", meaning you can clone a graph with a complicated layer hierarchy or with source data that cannot be specified by simple selection. See [this tutorial on plotting from user-defined graph templates](#) to learn how to save and use both standard and cloneable templates.


This tutorial will show you how to:

- Select data in a worksheet and quickly create a plot
- Change X/Y input of the data plot with context menu
- Add data to or remove it from an existing graph
- Use Plot Setup to plot data from multiple sheets
- Plot groups of plots by label

Minimum Origin Version Required: Origin 2016 SR0

6.1.2.2 Create a Plot Quickly by Selecting Data

1. Click the **Import Multiple ASCII** button  to open the dialog for import multiple ASCII, select the files **S15-125-03.dat**, **S21-235-07.dat** and **S32-014-04.dat** from `\Samples\Import and Export\` and click **Add File(s)** to add three files to the lower panel.
2. Make sure **Show Options Dialog** is checked, click the **File Name** column header to sort the files, click **OK**.
3. In the **Import and Export: impASC** dialog Change **Import Options: Import Mode** to **Start New Sheets**. Expand the **(Re)Naming Worksheet and Workbook** node and change settings so that only the sheet gets renamed.




4. Click **OK**. The imported results should appear as below:

4	0.04	39.6	112.5	100.6
5	0.05	40.5	113.1	101.7
6	0.06			101.3
7	0.07			100.4
8	0.08			101.1
9	0.09	39.3	115.4	101

File name as worksheet name

5. Make the third worksheet, S32-014-4, active. To create a three layer graph, highlight the three Y columns, Delta Temperature, Magnetic Field, and Position, and then select **Plot:**


Multi-Y: 3Ys Y-YY. Note: There is no need to highlight the Time column, as Origin will automatically plot the Y columns against the associated X column in the worksheet.




6.1.2.3 Change X/Y Data of the Plot

Use the same worksheet from the previous example.


1. Highlight column B and click the **Line** button  to generate a line plot.




- Right click on the data plot and point to the **Change Y** context menu, then select column C (Magnetic Field) in the fly-out.



- You may see a reminder message about rescaling the graph to show all data. Choose **Yes** and click **OK** so that the updated plot will be auto-rescaled.



4. The plot will update as shown below:





With this context menu, you can change the X or Y data of the current plot to be another column. This column will be any column other than the current X or Y data column from the same worksheet, regardless of column designation.


Note: You can also use the **Layer Contents** or **Plot Setup** dialog to change the input data.

6.1.2.4 Add Data to an Existing Graph and Update Legend


By Drag and Drop

1. Go back to the book with the three sheets of data from the above example.
2. Highlight the **Delta Temperature** column (Column B) from the first sheet and then select **Plot: Line: Line** to create a line plot.
3. Go back to the workbook. For each of the remaining two sheets, select the **Delta Temperature** column and position the cursor at the edge of the column until you see the cursor change to








- Then you can drag-and-drop the column into the graph page. Another curve will be added to the current layer.





- After adding the other curves, right click on the layer icon **1** and select **Plot Setup** from the context menu.




- The **Plot Setup** dialog opens with the bottom panel visible. (Note: The **Plot List** panel is the only one you need, but if you wish, you can click the  button to expand and show the other two panels of the dialog.) Hold the **Shift** key while selecting all three data plot entries, and then right-click and select **Group**. Click **OK** to close the dialog.



In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

- Grouping the plots allows for quick creation of presentation-ready graphs, because each selection in the group is assigned a differentiating set of plot attributes (line color = black, red, green; symbol shape = square, circle, triangle; etc...).
- Select **Graph: Legend: Update Legend...** to open the *legendupdate* X-Function dialog. Set the **Auto Legend Translation Mode** to *Custom*. Enter @WS for **Legend Custom Format**. Click **OK** and the legend will now contain the worksheet name for each data plot.






The default plot type of the drag and drop plot is **Current**, which is the same as the current active plot. However you could change the default option. To do this, click **Tools: Options** and go to the **Graph** tab, and change the setting of **Drag and drop plot** drop-down menu.


By Layer Contents Dialog


The **Layer Contents** dialog box is useful primarily for adding or removing data plots from the graph layer. Starting with Origin 2016, you can switch layers without closing the dialog box, making it easier to add plots to, or remove plots from, a multi-layer graph. To demonstrate, we will return to the 3-layer graph that we created in the first exercise in this tutorial:





In the first exercise, we plotted data from sheet S32-014-04. In this exercise, we will swap the data from sheet S32-014-04 with data from sheet S21-235-07.

1. Right-click on the layer **1** icon in the upper-left corner of the graph window and choose **Layer Contents**.
2. In the dialog box that opens, click the drop-down list in the upper-left corner and select **Worksheets in Folder**.
3. Right-click on the left-panel headings and select **Sheet** (if not already displaying) so that you can see which worksheets contain which workbook datasets, then click on the Sheet heading to sort datasets by sheet name.




- In the right-hand panel of Layer Contents, select **Delta Temperature** from sheet S32-014-04 and click the **Remove Plot** button  to remove the plot from graph layer 1.




- In the left-hand panel, select **Delta Temperature** from sheet S21-235-07 and click the **Add Plot** button , then click **Apply** to add the new plot to layer 1. You have now swapped one dataset for another.
- Click the **Layer(1)** button at the top of the dialog and choose **Other Layer > Layer 2**.


7. Repeat the process of removing the existing **Magnetic Field** dataset from layer 2 and replacing it with the Magnetic Field dataset from sheet S21-235-07, then click **Apply**.
8. Click the **Layer (2)** button and choose **Other Layer > Layer 3** and repeat the process of swapping the **Position** dataset in sheet S32-014-04 with the Position dataset in sheet S21-235-07, then click **Apply** and close the dialog box.




6.1.2.5 Create a Plot using Plot Setup

The Plot Setup dialog box is useful for a variety of plotting tasks, including creating graphs, modifying the plot type, adding plots to or removing plots from the graph, grouping or ungrouping plots, and editing the plot range.

1. Return to your workbook and ensure that no data are selected. It doesn't matter whether worksheet is active; what is important is that no columns are highlighted.
2. Select **Plot: Multi-Panel: 4 Panel** from the menu. When no data are selected, Origin opens the **Plot Setup** dialog, allowing you to choose the data you wish to plot.
3. Expand the top panel by clicking the  button. Hold down the **Shift** key to highlight the three worksheets. Alternatively, you can just click and drag your selection so that all three worksheets are highlighted.




4. In the middle panel, common columns in all three sheets are displayed. In this case, all three sheets have similar data with matching column names. Click the double arrow button  to show the plot column list. This mode is easier because you don't have to check the X and Y designation check boxes.

X	Y	yEr	L	Column	Long Name	Comments
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<autoX>	From/Step=	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A	Time	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	B	Delta Temperature	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	C	Magnetic Field	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	D	Position	



Column	Long Name	Comments	Sampling Interval
B(Y)	Delta Temperature		
C(Y)	Magnetic Field		
D(Y)	Position		

5. Open the bottom panel of the dialog, the Plot List, if it is not already visible. **Layer 1** is highlighted. Select **Delta Temperature** in the middle panel, and then click the **Add** button. Since you already selected the three worksheets in Step 3, this will add the **Delta Temperature** column from each of the three worksheets to layer 1.




- Repeat these steps to add **Magnetic Field** and **Position** into layerS 2 and layer 3, respectively.


Plot	Range	Show	Plot Type
Layer 1	<input checked="" type="checkbox"/> Rescale	<input checked="" type="checkbox"/>	
Group			
[Book1]S15-125-03! "Time"(X), "Delta Temperature"(Y) [1*:1000"]		<input checked="" type="checkbox"/>	Line
[Book1]S21-235-07! "Time"(X), "Delta Temperature"(Y) [1*:700"]		<input checked="" type="checkbox"/>	Line
[Book1]S32-014-04! "Time"(X), "Delta Temperature"(Y) [1*:850"]		<input checked="" type="checkbox"/>	Line
Layer 2	<input checked="" type="checkbox"/> Rescale	<input checked="" type="checkbox"/>	
Group			
[Book1]S15-125-03! "Time"(X), "Magnetic Field"(Y) [1*:1000"]		<input checked="" type="checkbox"/>	Line
[Book1]S21-235-07! "Time"(X), "Magnetic Field"(Y) [1*:700"]		<input checked="" type="checkbox"/>	Line
[Book1]S32-014-04! "Time"(X), "Magnetic Field"(Y) [1*:850"]		<input checked="" type="checkbox"/>	Line
Layer 3	<input checked="" type="checkbox"/> Rescale	<input checked="" type="checkbox"/>	
Group			
[Book1]S15-125-03! "Time"(X), "Position"(Y) [1*:1000"]		<input checked="" type="checkbox"/>	Line
[Book1]S21-235-07! "Time"(X), "Position"(Y) [1*:700"]		<input checked="" type="checkbox"/>	Line
[Book1]S32-014-04! "Time"(X), "Position"(Y) [1*:850"]		<input checked="" type="checkbox"/>	Line
Layer 4	<input type="checkbox"/> Rescale	<input checked="" type="checkbox"/>	

Note that in each layer, the three data plots are automatically grouped.

- Click the **OK** button to create the graph.




- You'll note that the default legend that is created for each layer is not particularly helpful. The Origin graph legend object is highly customizable so before we go further, we will modify the default legend. Right-click on any of the legend objects and select **Legend: Update Legend** from the shortcut menu.
- In the dialog box that opens, choose the following settings. Note that the **Legend Custom Format** syntax **@WS** is [LabTalk Substitution Notation](#) for the name of the worksheet containing the data for each line plot.



1.

10. We have one extra (empty) layer on the graph page. To delete that layer, click on it once to select it then press the **Delete** key on the keyboard. Take care not to delete the graph window as we will use it in the next section of this tutorial.



6.1.2.6 Plot Groups

Origin offers a plotting option, **Multiple Panels by Label**, that allows you to create a multilayer graph, each layer of which contains multiple plots, identified by the same label.

1. Open the file **Samples\Graphing\Automobile Data.ogw** (Hint: Make sure that your Open files filter is set to **Workbooks(*.ogw)**).

	A(X1)	B(Y1)	C(Y1)	D(Y1)	E(Y1)	F(X2)	G(Y2)	
Long Name	Year	Mean	Minimum	Median	Maximum	Year	Mean	M
Quantity	Power	Power	Power	Power	Power	0~60 mph	0~60 mph	0~
1	1992	125.46	94	126	165	1992	13.35	
2	1993	122.32	100	112	165	1993	13.52	
3	1994	103.57	52	108	169	1994	14.86	
4	1995	92.19	57	91	139	1995	15.57	
5	1996	78.96	62	73	121	1996	15.73	
6	1997	73.48	62	73	102	1997	15.86	
7	1998	68.42	39	69	84	1998	15.70	
8	1999	69.96	55	69	91	1999	16.75	
9	2000	60.72	33	62	85	2000	16.16	
10	2001	63.10	44	64	84	2001	16.59	
11	2002	52.24	36	51	66	2002	15.57	
12	2003	51.27	38	50	70	2003	17.32	
13	2004	49.88	38	50.5	66	2004	16.00	

- Click on top left corner of the worksheet to select the entire sheet. Select **Plot: Multi-Panel: Multiple Panels by Label** to open the **plotbylabel** dialog.
- Set the dialog options as follows, and click the **OK** button to create the graph.

PLOTTING: plotbylabel

Dialog Theme: []

Description: Plot a multiple-layers graph by grouping on column labels

Input: [Book2]Data!([A''Year'',B''Mean''),[A''Year'',C''M]

Group Identifier: Quantity

Plot Type: Line+Symbol


Number of Rows: 3 Auto

Number of Columns: 2 Auto

5 groups in total

Auto Preview

The graph should look like this:



6.1.3 Basic 2D Plotting

6.1.3.1 Summary

Origin's 2D plots are highly customizable. You can easily modify plot attributes, arrange layers, and select different datasets for each layer. This tutorial will teach you the basic plotting skills.

Minimum Origin Version Required: Origin 2015 SR0

6.1.3.2 What you will learn


This tutorial will show you how to:

- Perform simple row statistics
- Create a graph and save as a template
- Plot into your template
- Use the Plot Setup dialog

6.1.3.3 Steps

Simple row statistics

1. Start with an empty worksheet, select **File: Import: Single ASCII...** to open the *Import Single ASCII* dialog, browse to the `\Samples\Curve Fitting` subfolder of the Origin program folder, and import the file *Dose Response - No Inhibitor.dat*.
2. Highlight columns 2 through 4 and select **Statistics: Descriptive Statistics: Statistics on Rows**. Make sure to check the **Mean** and **Standard Deviation** check boxes on the *Quantities* tab to output these results.




3. After you click the **OK** button, two new columns, **Mean(Y)** and **SD(yErr)** are added to the source worksheet. Here, **yErr** means that this is an error column and the data in this column can be used to plot error bars.


Note: To simplify plotting, each column in an Origin worksheet has a plotting designation. To change a column's plotting designation, select the column and click on the **Column** menu. Alternatively, right-click on the column and choose **Set As** from the shortcut menu.

Create a graph and save as a template

1. Highlight the Mean(Y) and SD(yErr-) columns and select **Plot: Line+Symbol: Line+Symbol** to create the plot:




2. Change the X scale to Log. To do this, double-click on the X axis to bring up the **Axis** dialog. On the **Scale** tab, change the axis **Type** to **Log10**:




Click the **OK** button to close the dialog.

3. Select **Graph: Rescale to Show All** from the menu, which will rescale the X and Y axes of the graph. :




- To edit the curve, double-click on any plot symbol to bring up the **Plot Details** dialog. Alternatively, right-click inside the graph and choose **Plot Details** from the shortcut menu. On the **Line** tab of right panel, select **B-Spline** as the connecting line type to get a smoother curve.






Click the **OK** button to close the dialog.


- When all modifications have been made and the graph looks the way you want it, you can use this graph to create a template, to be used in the future with similar data. Select **File: Save Template as** to open the *Save Template* dialog. In the **Category** drop-down list, select *UserDefined*; and then type a proper **Template Name**. In this example, we use *MyTemplate*.

Click **OK** to save the template.




Plot into graph template with the Plot Setup dialog

1. Click the **New Workbook**  button and import the file `\Samples\Curve Fitting\Dose Response - Inhibitor.dat` as above. Perform **Statistics on Rows**, calculating the Mean and SD of this worksheet as you did above, following the same steps.
2. Select **Plot: User Templates: MyTemplate**
3. In the *Plot Setup* dialog, you can choose which columns are to be plotted. (There are three panels in *Plot Setup* dialog, click the  or  button to expand/collapse them.) To finish creating the plot from your template, please follow the steps a - e outlined on the picture below.



And then you will have:



6.1.4 Basic 3D Plotting

6.1.4.1 Summary

In Origin, Contour plots and 3D plots, such as Color Map Surface plots, can be created directly from XYZ data. To plot a smoother 3D surface plot, use one of Origin's built-in gridding routines to convert the XYZ data into a matrix.

Minimum Origin Version Required: Origin 9.0 SR1

6.1.4.2 What you will learn


This tutorial will show you how to:

- Create a 3D graph from XYZ data
- Use the **Layer Contents** dialog to add/remove a data plot
- Convert Worksheet data into a Matrix
- Use the **Plot Details** dialog to customize a graph


6.1.4.3 Create a 3D Surface and Scatter Plot


Tutorials for Origin


1. Import the file `\Samples\Matrix Conversion and Gridding\XYZ Random Gaussian.dat`.
2. Highlight column C and right click. Select **Set As: Z** from the fly-out menu.
3. Select **Plot: 3D Surface: Color Map Surface** to create a 3D Colormap Surface plot (Graph1 by default).




4. Right click the layer icon on the left-top of the graph to open the **Layer Contents** dialog. In this dialog, click on the **A** button and select **3D Scatter/Trajectory/Vector** from the fly-out menu.




5. Select column C from the left panel and click on the **Add Plot**  button to add the 3D scatter plot to the graph. Click **OK** to close the dialog.




6. Double-click on the scatter plot of Graph1 to open the **Plot Details** dialog. In the **Symbol** tab, set **Shape** to **Ball**, **Size** to **12** and **Color** to **Color Mapping: Col(C)**.




- In the **Drop Lines** tab, uncheck the **Parallel to Z Axis** checkbox.




- In the **Colormap** tab, click on the column header *Fill...* to open the dialog. In the **Fill** dialog, choose **Load Palette**, click on **Select Palette**, and select **Rainbow** from the list.



9. Select **Layer1** from the left panel of the **Plot Details** dialog. In the **Lighting** tab, under **Mode**, select **Directional** and under **Light Color** choose the settings that are in the image below. Click **OK** to close the dialog.



The graph should look as below:




6.1.4.4 Smooth the 3D surface plot


If you want to create a 3D surface that is smoother than the surface plot from direct XYZ data, you can use the **XYZ Gridding** tool to convert the XYZ data into a matrix.

1. Activate the workbook **XYZ Random Gaussian** created in the section above.
2. Select **Worksheet: Convert to Matrix: XYZ Gridding** to open the dialog. Expand the **Gridding Settings** section, then expand the **Gridding Method and Parameters** section. Select **Random (Thin Plate Spline)** from the drop-down list, and set both the **Columns** and **Rows** to the value of


30. Click **OK** to convert the XYZ data into a matrix.



3. Activate the matrix, and select **Plot: 3D Surface: Color Map Surface** to create **Graph2**.
4. To apply the same style formats as **Graph1**, activate the layer of **Graph1**, then right-click and select **Copy Format: All Style Format** in the context menu.



Go to **Graph2**, right-click, and select **Paste Format** in the context menu. **Graph2** should look as below:



6.1.5 Plot from User Defined Graph Template

6.1.5.1 Summary


In this tutorial, we will show you how to save a graph as an user-defined template and plot new data into the saved custom template. There are two types of graph templates available in Origin: standard template and cloneable template. Cloneable template can be easily used to clone a graph from a new workbook/worksheet, in despite of complexity of the data composition in target graph, but with one prerequisite that new data should share same data structure with data in target graph. In comparison, standard template has more freedom over data source but lacks of the ability to duplicate a graph with complicated layer hierarchy or data structure.


This tutorial will show you how to:

- Create and save a graph as standard template
- Plot new data into a standard template
- Save a graph as cloneable template
- Plot data with same data structure into a cloneable template

6.1.5.2 Standard Template

Create and Save a Standard Graph Template


1. Go to menu **File: Open Sample Projects: Tutorial Data** to open the opj, in **Project Explorer** browser to **Custom Axis Scale to Show Different Scale Range** folder.
2. Highlight column **B Exothermic Energy** and **C Energy-SD**, click scatter button  on **2D Graphs** toolbar to make a scatter plot with Y error bar.
3. Next we want to customize the symbol to be solid circle with blue color, to do so double click on any data point on the graph to bring up **Plot Details - Plot Properties** dialog.
4. Make sure *Exothermic Energy* is selected on the left panel. Go to **Symbol** tab. Select solid circle from the down-sided triangle button under **Preview** and set **Symbol Color** to be **Individual Color: 4 Blue**. Click OK.



5. To save it as standard template, right click on *Graph1* window title bar and select **Save Template As...** to open dialog.
6. Input *BlueCircle* as **Template Name** and add some descriptions *Blue solid circle* in **Template Description** edit box.
7. If you want the newly created graphs long names to be named after the plot's long name, click the more options button next to **Preset Graph Long Name** edit box and select **@LL: Long Name**. *%(1,@LL)* will show as **Preset Graph Long Name**.
8. Make sure **Mark as Cloneable Template** box is unchecked, click **OK** button to save it as standard template.

Plot New Data into Standard Template


1. Go back to workbook, highlight columns *Temperature* and *Temperature-SD* and go to menu **Plot: User Templates: BlueCircle (UserDefined)** to make the graph. The graph window long name is **Temperature**.




6.1.5.3 Cloneable Template

Save Graph as a Cloneable Template

1. Go to menu **File: Open Sample Projects: Smart Plotting with Cloneable Template** to open the sample project.
2. Double click on the graph with title **Raman Spectrum** to go to **Raman Spectrum** subfolder.
3. Graph **Raman Spectrum** is plotted from data in different worksheets of workbook *Peak1* also with data labeling. It's hard to plot new data like this with one click using standard graph template. So let's save this graph as a cloneable template and clone this graph using data in workbook *Peak2*.




4. To do so, right click on graph **Raman Spectrum** window title bar and select **Save Template As...** to open **Utilities\File: template_saveas** dialog.
5. Input *MyPeakTemplate* as **Template Name**. Now we want to use **Raman Spectrum + Workbook Long Name** as graph Long Name. To do so, click more options button next to **Preset Graph Long Name** edit box and select **@WL: Book Long Name** to insert the right part first. Then input *Raman Spectrum* in front of added $%(1, @WL)$.
6. Make sure **Mark as Cloneable Template** box is checked, expand this node you can choose how to match up the columns and worksheets by **Match Column by** and **Match Sheet by** drop-down option. Now select **Index** from **Match Column by** drop-down list.
7. Click **OK** button to exit the dialog and save the template.




Clone a Graph Using Cloneable Template

1. Activate workbook with title **Peak2**, click template library button  to bring up the dialog.



2. Click to select the cloneable template (indicated by Dolly icon) **MyPeakTemplate** and click **Plot** button to clone the graph.



- Alternatively you can activate workbook **Peak2** and go to menu **Plot: User Templates: MyPeakTemplate (UserDefined)** to directly clone the graph.

6.1.6 Adding a Data Plot to Existing Graph

6.1.6.1 Summary

The Plot Setup dialog can be used to add/reorder/arrange data plots in an existing graph. This dialog provides flexibility in selecting the desired data sheet and then selecting data to be plotted using column meta data such as long name.

Minimum Origin Version Required: Origin 8.0 SR6

6.1.6.2 What you will learn

This tutorial will show you how to:

- Use the Plot Setup Dialog Top Panel to find your dataset
- Add the chosen dataset to existing graph

6.1.6.3 Steps

Choosing the Data Source

1. Click the **New Project** button on the Standard toolbar, to begin with a new project.

2. Click the **Import Wizard** button on the Standard toolbar. The Import Wizard opens. (Note that if this is the first time that you have started the Import Wizard, you will experience a slight delay as Origin compiles the necessary files.)
3. Verify that the **ASCII** radio button is selected in the **Data Type** group.
4. Click the browse button to the right of the File text box. Navigate to the Origin folder; browse to the **Samples** folder and then the **Import and Export** folder.
5. Double-click to select S15-125-03.dat from the list of files. Repeat for files, S21-235-07.dat and S32-014-04.dat.
6. Click **OK**.
7. Leave the **Import Filters for current Data Type** as **Data Folder: VarsFromFileNameAndHeader**. (This filter has the settings to use when importing the file.)
8. Set the **Import Mode** as **Start New Sheets**.
9. Click the **Finish** button. The three data files import into the workbook, each as a new sheet. You will have a book with three sheets: **Trial Run 1**, **Trial Run 2**, and **Trial Run 3**.



Plotting the Data

1. Select **Trial Run 1** sheet.
2. Highlight the D(Y) column.
3. Click the **Line** button on the **2D Graphs** toolbar. A new graph is created.

Adding data to the graph

1. Double-click on the layer 1 icon in the upper-left hand corner of the graph. Click **Plot Setup** button in the opened **Layer Contents** dialog.



In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

2. Select **Layer 1** in the Plot List.
3. Click the blue arrows in the upper right corner of the dialog to **Show Plot Designations**.
4. Again click the blue arrows in the upper right corner of the dialog to **Show Available Data**.
5. Select **Trial Run 2** from the Available Data list.
6. Check **Time** as X and **Position** as Y.
7. Click **Add**.
8. Check the **Rescale** checkbox.

- Click **OK**.


Updating the Legend and Formatting the Plot

- Select **Graph: Legend: Reconstruct Legend**.
- Double-click on the line symbol for the second data plot in the legend. The Plot Details dialog opens.
- Change the **Color** from Black to Red.
- Click **OK**.

6.1.7 Smart Peak Labels with Leader Line

6.1.7.1 Summary

For the line/symbol plot in 2D Cartesian coordinate system, Origin supports smart labels which can be auto re-positioned to avoid overlapping. Leader lines (both straight lines and oblique lines) can be added to connect the data points and their labels.



Minimum Origin Version Required: Origin 2016 SR0

6.1.7.2 What you will learn


This tutorial will show you how to:

- Add smart labels with leader lines
- Add a special data point and customize its label


6.1.7.3 Steps to Add Smart labels

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the **Tutorial Data.opj** and browse to the *Smart Peak Labels with Leader Line* folder in the **Project Explorer**.
2. There are two sheets in **A100527IR** workbook. *100-52-7-IR* is an IR absorbance data and *Peak_Centers1* are peak center result found by Origin's **Peak Analyzer** tool.
3. Highlight Col(B) in sheet *100-52-7-IR* to plot a line graph by selecting **Plot: Line: Line** menu.
4. Double click on layer 1 icon to open the **Layer Contents** dialog. Select col(pcy) in left panel. Click the dropdown list next to **A** button in the middle and select **Scatter** as plot type. Click **->** button to add the data into the graph.




5. In the **Plot Details** dialog, select second plot in the left panel, go to **Symbol** tab, do following settings:



6. Go to **Label** tab, check the **Enable** check box, do settings as below:



7. Click on the **Apply** button, you will see the some labels are overlapped.




- Go back to **Label** tab, check the **Auto Reposition to Avoid Overlapping** check box, select **Y** for the **Reposition Direction** drop-down box and set the **Leader Lines** group as below. Also set **Vertical Offset** to be **170** so the leader lines are more obvious.

Symbol	Drop Lines	Label
<input checked="" type="checkbox"/> Enable <input type="checkbox"/> Show at Specified Indices Only Indices from dataset or space separated numbers (0=Last) <input type="text"/>		
Font	Default: Arial	Size 12
Color	1 Black	White Out <input type="checkbox"/>
Frame	(None)	Vertical Offset 170
Margin (% Font Height)	10	Position Above
Label Form	X	
Numeric Display Format		
Attach to	Data	
X/Y Value		
Lab Talk X1 X2 Y1 Y2 etc. can be used		
<input checked="" type="checkbox"/> Auto Reposition to Avoid Overlapping Reposition Direction Y		
Leader Line <input checked="" type="checkbox"/> Show Leader Line if Offset Exceeds (%) 1 Connect — Straight 0 Style Short Dash Width 0.5 Color Blue		

9. Click OK button to close the dialog. You will see the labels are repositioned smartly.


6.1.7.4 Steps to Customize a Single Point and its Label

1. The highest peak's label can't be seen. Double-click on the Y axis to open the **Axis** dialog, go to **Vertical** icon in **Scale** tab, change **From** and **To** to -0.05 and 0.8 , then click OK to apply the setting.




2. Press CTRL key down and double click the highest peak's label **1730** to open **Plot Details** dialog. A node **18** shows on left panel. It's the row indexing of the special point.

3. Go to **Label** tab of this point and customize the further.




4. Go to **Symbol** tab to change the symbol shape and size.



6.1.7.5 More Customization Steps

The following steps can further customize the graph to be exactly the same as the image in **Summary**.

1. Double click X axis to open **Axis** dialog. set **From** and **To** for X axis to be 400 and 3500.
2. To show top and right frames around the graph, select **Grids** tab in **Axis** dialog. Check **Opposite** check box under the **Additional Lines** branch for both **Horizontal** and **Vertical**.
3. To change the layer size, select **Format: Layer Properties...** from main menu to open the **Plot Details** dialog. On **Size/Speed** tab, change the layer size in the **Layer Area** group as below:




4. Select legend and press **Delete** key to delete the legend.

6.1.8 Error Bars with Fill Area

6.1.8.1 Summary

This graph displays three datasets with error bars. The error bars have been set to draw as lines with fill areas. Transparency has been set for all three curves so that data in overlapping regions can be clearly seen.



Minimum Origin Version Required: Origin 8.5.1 SR0

6.1.8.2 What you will learn


- Plot the error bar with fill area
- Set transparency for error bar
- Set and save custom color

6.1.8.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Line and Symbol**)


1. Open **Tutorial Data.opj** and browse to the **Error Bars with Fill Area** folder in **Project Explorer** (PE).
2. Highlight all columns in the worksheet. In the main menu, click **Plot: Line**, and then click **Line**.



3. Double-click on the plot to open the **Plot Details** dialog. Select the first plot node under Layer1 in the left panel. In the right panel activate the **Group** tab. Choose **Independent** in **Edit Mode**.



4. On the **Line** tab set **Width** as **3**. To set a custom color click on the button right to **Color** and select **Custom** from the drop list.




Right-click on the **Custom** button to bring up **Color** dialog. Click on **Define Custom Colors** to expand the right panel. For further use save the custom color in the **Custom colors:** palette:

1. Select an blank box under the **Custom colors:** palette.
2. Set **Red, Green, Blue** as **155, 187, 89** respectively in the right panel.
3. Click **Add to Custom Colors** to save this color to the **Custom colors** palette.


Click **OK** to close the dialog. Set **Transparency** as **50**

5. Repeat the step 3 for the other two plots. Except, set the colors of the second plot and the third plot as **RGB(192, 80, 77)**, **RGB(79, 129, 189)** respectively.
6. In the left panel, select the first of the three error plots. On the **Error Bar** tab, set **Connect** as **Straight**, then the **Fill Area Under Curve** option will show up in **Style** section. Check the box before it and the **Pattern** tab should now be available.



Set **Color** as **Automatic**.

- On the **Pattern** tab, change the fill color to the custom color saved before to match the line color, and set Transparency to 50.



- Repeat the last two steps for the other two error plots. Click **OK** to complete the graph.

6.1.9 Mark out a segment of plot with different plot style

6.1.9.1 Summary


In Origin, you can mark out a segment of plot with different plot style, such as a segment of dashed in a solid line plot.

Minimum Origin Version Required: Origin 8.0 SR6


6.1.9.2 What you will learn

- Use the **Plot Setup** dialog to create a graph
- Mark out the special segment of a plot

6.1.9.3 Steps

1. Start with an empty worksheet. Select **File: Import: Single ASCII...** from the Origin menu to open the **Import Single ASCII** dialog. Browse to the `\Samples\Graphing` subfolder of the Origin program folder, and import the file `AXES.DAT`.
2. Click the  button on the **Standard** toolbar to create a new graph window and then select **Graph: Plot Setup** from the main menu to bring up the **Plot Setup** dialog.
3. Show all of the three panels of the **Plot Setup** dialog. Select the **AXES** worksheet in the top panel. Then go to the middle panel to select **A** as X and **B** as Y. After that, click **Add** to add this data plot to the bottom panel. Repeat this step three times. Three data plots should be listed in


the bottom panel.




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking and expand **Available Data** panel by clicking again.

Please refer to [Plotting using Plot Setup](#) for more information.

- In the lower panel, click in the **Range** column that corresponds to the first data plot. The button should be activated. Then click this button to open the **Range** dialog box.




- Clear the **Auto** check boxes (if they are selected) and then set **From** to **1** and **To** to **20**. Click **OK** to close the dialog.



- Similarly, set the ranges for other two data plots to "20 to 30" and "30 to 40" respectively.


Plot	Range	Show	Plot Type	Legend
Layer 1	<input checked="" type="checkbox"/> Rescale	<input checked="" type="checkbox"/>		
[AXES.DAT]AXES! A(X), B(Y)	[1:20] $1 < X < 20, -0.96201 < Y < 0.3638$	<input checked="" type="checkbox"/>	Line	B
[AXES.DAT]AXES! A(X), B(Y)	[20:30] $20 < X < 30, -0.96201 < Y < 1.35909$	<input checked="" type="checkbox"/>	Line	B
[AXES.DAT]AXES! A(X), B(Y)	[30:40] $30 < X < 40, -1.08804 < Y < 1.58261$	<input checked="" type="checkbox"/>	Line	B

- Click the **OK** button to close the **Plot Setup** dialog. You should get a graph like this:




- Double-click on the curve in the graph window to open the **Plot Details** dialog. Select the second data plot from the left panel. In the right panel, change the **Style** to **Short Dash**, and then click

the **Ok** button.



9. Finally, we get the plot with a range marked out.



6.1.10 Overview of Customization

6.1.10.1 Summary


Editing your Origin graph is very easy. Any graph element can be selected and with its associated dialog, the properties can be modified. In fact, you can customize your graph right down to a single data point.

This tutorial will show you how to:


- Resize a Layer
- Add a Layer Title
- Customize and Save a Template
- Customize Axes
- Apply a Graph Theme
- Change Plotting Order in a Layer
- Customize a Point
- Customize a Grouped Plot
- Create a Color-mapped Waterfall Plot

6.1.10.2 Re-sizing Layer


1. Open **Customizing Graphs.OPJ** from the **\Samples\Graphing** folder and select the **Resize Graph and Customize Symbol** folder from the **Project Explorer** window.
2. Make **Graph2** active and right-click inside the layer, above the data points to select **Add/Modify Layer Title** from the context menu that opens. Add a title, as shown in the graph below:



- The layer can easily be resized graphically by dragging the sizing handles. To resize it, single click inside the layer, but not on a data point. The layer will become selected as seen below, and then you can drag one of the 8 anchor points to resize the layer. Note: If you hold the CTRL key down while dragging, the aspect ratio will be maintained.




- You can also use the **Plot Details** dialog by specifying exact numbers to dictate the layer size more precisely. Double-click inside the layer to open the **Plot Details** dialog. On the **Size/Speed** tab, set the layer area to the values shown in the image below:




6.1.10.3 Customize Data Plot and Axes

In this section, we will show you how to change the color of a data plot, and customize the axes.

- Click on one of the data points of **Graph2** to select the entire data plot, and change the color of the data points to **red** by using the **Line/Border Color** button  in the **Style** toolbar.

2. Next use the **Axis** dialog to customize the axes. Double-click on the X-axis to open the dialog and set the controls as follows:
 - Select the **Horizontal** icon in the **Scale** tab, select the **Type** under *Major Ticks* as **By Counts** and input 5 as the Count.
 - Select the **Vertical** icon in the **Scale** tab, set the **From** as **0**, **To** as **16**, **Type** for *Major Ticks* as **By Counts** and enter **11** for **Counts**.
 - Go to the **Line and Ticks** tab and select both Top and Right page with CTRL button pressing down. Check the **Show Line and Ticks** box to show the line and ticks for the top X and the right Y axis. Click **OK** to apply the settings and close the dialog. The graph should appear as shown below:




6.1.10.4 Save and Reuse a Template


In this section, we will show you how to save the graph above as a template and reuse it.

1. In the menu, select **File: Save Template As** (alternatively, right-click on the graph window title and choose **Save Template As** from the context menu) and rename the template as


MyGraphTemplate. Then click the **OK** button to save it.



2. Create a new workbook and import the data file **\Samples\Curve Fitting\Sensor2.dat**, by using **File: Import: Single ASCII**. Highlight column B and select **Plot: User Templates: Template library**. Then select **MyGraphTemplate** and click the **Plot** button to create a graph.



The graph should look like:




6.1.10.5 Changing graph using theme


Origin stores the properties of a graph in a theme file. In this section we will show you how to customize a graph by using a theme.

1. With **Graph3** active, select **Tools: Theme Organizer** to open a dialog. Select the **Times New Roman Font** theme and click **Apply Now**. Select **Ticks All In** and click **Apply Now**, then click

the **Close** button to close the dialog. The graph should resemble the following graph:



- The next step is to copy the formatting of the current graph and paste it to **Graph2**. Right-click to the right of the layer, anywhere on an empty white or grey space and select **Copy Format: All Style Formats**. Activate **Graph2**, right-click in a similar spot and select **Paste Format**. **Graph2** should look like the image below:




6.1.10.6 Plotting Order


You can reorder the data plots either by the **Layer Contents** dialog or the **Plot Setup** dialog.

By Layer Contents Dialog


1. Open **Customizing Graphs.OPJ** from the `\Samples\Graphing` folder and select the **Plotting Order** folder from the **Project Explorer** window.
2. Activate Graph 1 window. Double-click on the Layer 1 icon on the top left corner of the graph to open the **Layer Content** dialog.



3. Click the **>>** button to hide the left panel. In the right panel, select the Gauss Fit Count line plot. Click the downward pointing arrow button to move the line plot down in the plotting order.





4. Click the **Apply** button. The Gauss Fit Count line plot is now on top of the column plot. Click the **Close** button to close the dialog.



By Plot Setup Dialog


1. Use the same data as the previous example. In the **Plotting Order** folder activate **Graph 1**. Select **Graph: Plot Setup** from the main menu to open the **Plot Setup** dialog (You can also right-click on layer 1 and select **Plot Setup...**).




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

2. In the **Plot List** panel, drag the line plot and drop it beneath Column/Bar Plot Type.





3. Click the **OK** button and you will see that the red curve is now drawn on top. Notice the legend reflects the new plotting order as well.




6.1.10.7 Customize points

In this section, we will show you how to customize a single data point.


1. We will continue to work in the **Plotting Order** folder. Make sure **Graph 1** is active. Note that if you click to select one of the columns, all columns are selected. Click again to select just that one column. Change the color to **green** using the **Fill Color** button  on the **Style** toolbar.
2. You can also use the **Plot Details** dialog to customize single columns separately from the rest. Hold down the CTRL key while double-clicking on the columns to open the **Plot Details** dialog. The settings in this dialog will edit the properties of just that single data point. Note that the index number for that selected data point is highlighted in the left panel of the Plot Details dialog. Set the **Gradient Fill** group as follows, to fill the column with a yellow to red color gradient.




Your graph should resemble the following image:




3. You can customize a pie chart segment in the same way. In the **Edit Single Data Point** folder, activate the pie graph. Hold down the CTRL key and double-click on one of the slices to open the **Plot Details** dialog. Under the **Pattern** tab, set the **Fill Pattern** to **Dense**, and set **Pattern Color** to **Red**. (Alternatively, you could have clicked once and then clicked again on a slice to select just that one point, and then used the Style toolbar to customize that point.) The graph should appear as the image below:




- You can customize a single data point and label it. Go back to the **Resize Graph and Customize Symbol** folder. Hold down the CTRL key and double-click on one of the scatter points to open the **Plot Details** dialog. Under the **Symbol** tab, click the triangular **Preview** button to open the symbol gallery, and select **Sphere** for the symbol type. Increase the **Size** to **18**, and click the **OK** button to close the dialog.
- Use the annotation tool to add the X and Y values that correspond to the customized data point. Select the **Annotation** button from the **Tools** toolbar (Hint: The Data Reader, Annotation and Data Cursor tools are grouped. If you don't see the Annotation tool, click the arrow to the lower-right of whichever tool is visible on the toolbar).




Move the annotation cursor to the customized data point and double-click on it. Origin will automatically add a text object. Hit the ESC key or click on the Pointer button to exit annotation mode. Single-click and drag to position the text object. A line will automatically be drawn connecting the point and the label.




Right-click on the text object and select the **Properties...** to open the **Annotation-Text** dialog. Then you can customize the text label format in the this dialog. In the **Text** tab enter


`%(1,@LL)=$(Y,.2) %(1,@LU)` in the edit box. And the button  to the right of the edit box provides some [frequently used notations](#) and example syntax.





6.1.10.8 Group plots

So far, we have been customizing data points in a single data plot. In this section, we will show you how to customize a grouped data plot.


1. Select the **Grouped Data** folder. **Book3** will be active. Highlight the entire worksheet and click the line button  on the **2D Graphs** toolbar to create a line graph.
2. Double-click on the X-axis to open the **Axes** dialog box. Set **From** as **0.5** and **To** as **3.0**. Select **Fixed** from the **Rescale** drop-down list (you will need to scroll up in the list). This prevents the **From** and **To** values from changing while rescaling. Click **OK** to apply these settings.
3. Double-click on a blank place above the line plots, to open the **Plot Details** dialog. On the **Stack** tab, select **Auto** in the **Offset** group. Click **OK** to close the dialog.
4. Select **Graph: Rescale to Show All**. The Y scale of the graph automatically rescales, while the X scale doesn't change because the option was set to manual. Resize the layer and drag the legend to the desired spot.




- Click on one of the data plots to select the entire group, and then use the **Line/Border Color** button  on the **Style** toolbar to change the colors. Click on **By Plots** tab, select **Q03 Rainbow7** from the **Increment List** as below.




- Then select the first increment list. The graph should look like this:




- Though these data plots have been grouped, you can also customize each of them individually by clicking on the data plot twice. For example, clicking the yellow data plot twice (click once, pause and click again) and then clicking the **Line/Border Color** button  on the **Style** toolbar will change the color to another color, such as **Olive**.
- You can also customize the graph by double-clicking on one of the data plots to open the **Plot Details** dialog. Under the **Group** tab, you can click the browse button...



...to open the **Increment Editor** dialog. In this dialog, customize the graph as shown in the following image. Note that you can also drag the index of a row and move it to change the order of the color list.




9. Right-click on the inner position of this dialog and select **Save Increment List** to save it as **MyPalette** for future use. Right-click to get the context menu and select the **Load Increment List** option. You will find that **MyPalette** appears as the first entry in the fly-out menu, as the following image shows:






In the following section, we will show you how to use **Palettes** to set colors for a group of data plots.

1. Activate **Book3** and highlight all the columns. Select **Plot: Y-offset/Waterfall: Waterfall** to create a graph. Double-click on the X-axis to open the **Axis** dialog, and set **From** as **0.5** and **To** as **3**. Select **Vertical** from the **Selection** list, and set the **From**, **To**, and **Increment** edit boxes to **-10**,


100 and 20, respectively.



2. Click on one of the data plots and use the **Line/Border Color** button  on the **Style** toolbar to change the colors. You can select the **Rainbow** palette  under **Palettes**. The graph should resemble the image below:




3. You can double-click on one of the plots to get the color list, as the following image shows:




You can find that the **Increment** has been set to **Binned**, so colors are picked from the 256 available in the **Rainbow** palette.

4. We will change the palette to **Reef** by clicking on the browse button to open the **Increment Editor** dialog. Then right-click on the inner portion of this dialog and select **Load Palette : Reef.PAL**, then click **OK**. The color list in the **Plot Details** dialog should be set as shown below:






The graph should appear as shown below:



6.1.10.9 Plot a Color-mapped Waterfall

In this section, we will show you how to create a color-mapped waterfall plot and use a column label row as the Z-axis.

1. Click the **New Workbook** button  on the **Standard** toolbar to create a new workbook.
2. Click the **Import Wizard** button  on the **Standard** toolbar. This opens the **Import Wizard** dialog. Click the browser button to the right of **File** and select *Waterfall3.dat* from the */Samples/Graphing* folder. Make sure *Waterfall3.oif* is picked up automatically for **Import Filters for current Data Type**.




Click **Finish** to import the *Waterfall3.dat* file.

Waterfall3 - Waterfall3.dat


	A(X)	B(Y)	C1(Y)	C2(Y)
Long Name	Time	Amplitude		
Units	sec	(a.u.)		
Comments				
Frequency (Hz)	--	3.91	11.72	19.53
1	0	0.766	0.697	0.406
2	0.012	0.413	0.097	0.03
3	0.025	0.14	-0.34	-0.26
4	0.037	-0.059	-0.628	-0.465
5	0.05	-0.191	-0.784	-0.588
6	0.062	-0.264	-0.823	-0.632
7	0.075	-0.284	-0.76	-0.6
8	0.087	-0.257	-0.61	-0.493
9	0.099	-0.191	-0.39	-0.315

- To plot a waterfall color-mapped using each line's Y value, highlight the whole worksheet and select **Waterfall Y: Color Mapping** from the **2D Graphs** toolbar (Alternatively, Select **Plot: Y-**

offset/Waterfall: Waterfall Y:Color Mapping from the main menu).




The graph should look like the picture below:




4. Double-click on the waterfall plot to open the **Plot Details** dialog. On the **Color Map** tab and set the **Level** as shown below:

- Click on the **Level** column header to change the color levels




- Click on the **Fill** column header to load a color palette or change the filled color list:




Please note that you can also click inside one single cell to change that level individually.


5. To plot a waterfall color-mapped with Z values, highlight the **waterfall** worksheet in **Book 2** and select **Waterfall Z: Color Mapping** from the **2D Graphs** toolbar (Alternatively, Select **Plot: Y-offset/Waterfall: Waterfall Z:Color Mapping** from the main menu).




The graph should look like the picture below:



- Note that the user-defined parameter "Frequency (Hz)" is used as the Z axis automatically. To use another column label as the Z axis, double-click inside the layer to open the **Plot Details** dialog at the **Layer** level. In the **Waterfall** tab select **Auto** from the **Z Value Source** drop-down list.



- To switch between Y and Z color mapping, select the first plot on the left panel of the **Plot Details** dialog and activate the **Line** tab. Expand the **Color** drop-down list, select **By Points** tab, select **Y-value: Color Mapping** under the **Use column values** section, to switch to Y color mapping. You can also select **Z-Value: Indexing** or **Z-Value: Direct RGB** at bottom of **By Plots** tab.



6.1.11 Plotting Overlapping Data and Setting Transparency


6.1.11.1 Summary

In this tutorial, we will show you how to create overlapping column plots, and then set transparency to make the overlapping parts visible.


This tutorial will show you how to:

- Customize the grouped column plots
- Set Transparency


6.1.11.2 Plot Overlapping Data and Set Transparency

1. Start with a an empty worksheet and from the menu, select **File: Import: Single ASCII** or click the **Import Single ASCII** button  to open the file browser.
2. Choose the file *<Origin Installation Directory>\Samples\Graphing\Counts.dat*, check the **Show Options Dialog** check box, and click the **Open** button to bring up the **impASC** dialog.


- Click the triangle button in the upper right corner, and then select **System Default** from the context menu to apply the default settings to this dialog.



- Click the **OK** button to import the data to the worksheet.
- Right-click on the row header of **Units**, and then select **Set As Comment** from the pop-up menu to set the contents to be comments instead of units.




- Highlight all columns in the worksheet, and then from the menu, select **Plot: Column/Bar/Pie: Column** to create a column graph.




- Double-click on the plot to open the **Plot Details** dialog. In the dialog, choose the **Group** tab. Click on the color bar under **Details** and click in the **Fill Color** row. Then click on the button that appears to open the **Increment Editor** dialog. In this dialog, you can set the first three colors to be some specific colors such as Royal Blue, Orange, and Dark Cyan. Click OK to close the


dialog.




8. Select the **Pattern** tab in Plot Details, and set the **Transparency** control to 51%.



9. Select the **Spacing** tab, and set **Gas Between Bars** to zero and **Overlap** to 100.



- Click the **OK** button to close the Plot Details dialog. The resulting graph should look like the image below:



6.1.12 Plotting using Plot Setup


6.1.12.1 Summary

In this tutorial, we will show you how to implement various plotting tasks including creating graphs, modifying the plot type, adding plots to or removing plots from the graph, grouping or ungrouping plots, and editing the plot range, using *Plot Setup* dialog.


This tutorial will show you how to:



- Create line plot with Plot Setup
- Group or ungroup plots with Plot Setup
- Add or remove plots with Plot Setup
- Change plot type and display range with Plot Setup
- Change plot order with Plot Setup
- Create multi-Panel Plots with Plot Setup

6.1.12.2 Create Line Plot with Plot Setup

- Start with an empty worksheet and from the menu, select **File: Import: Single ASCII** or click the **Import Single ASCII** button  to open the file browser.
- Choose the file *<Origin Installation Directory>\Samples\Curve Fitting\Step01.dat*, check the **Show Options Dialog** check box, and click the **Open** button to bring up the **impASC** dialog.

- Click the **OK** button to import the data into the worksheet.
- Return to your workbook and ensure that no data is highlighted.
- Select **Plot: Line: Line**, the **Plot Setup** Dialog will pop up. In the middle panel, you can see the *Long Name* is displayed by default. Select *Column B (Sensor A x)* as X, and *Column C (Sensor A y)* as Y. Click **Add** to add the plot into the bottom panel, which will automatically be added to *Layer 1*. Repeat this operation for *Sensor B*, and *Sensor C*.




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.


6.1.12.3 Group/Ungroup plots with Plot Setup

Next we want to group this three plots together. Use the same graph from the previous example.

1. Press CTRL then select all three plots at the bottom panel, right click and select **Group**. Then these plots would be under the **Group** node.



2. Click **OK** to close the dialog. The graph would appear as follow:



Note:


1. The plot grouping operation enable you to customize the appearance of these grouped data plots in [Group Tab](#) of *Plot Details* dialog.

- To ungroup data plots, you can go back to the bottom panel of *Plot Setup* dialog then click the **Group** node, right click select **Ungroup**.

6.1.12.4 Add or Remove Plots with Plot Setup


Next we are going to remove the data plot of *Sensor C* then add the data plot of *Sensor D* into the graph. Use the same graph from the previous example.

- Activate the graph, then click **Graph: Plot Setup** to go back to the **Plot Setup** dialog. At the bottom panel, highlight the plot of *Sensor C*, then right click to select **Remove**. Click Apply then OK to close the dialog. The *Sensor C* plot would be removed from the graph.



- To add the data plot of *Sensor D*, select the **Group** node in lower panel and go to the upper panel by clicking on the double up-sided blue arrow icon on top right corner, select *Column H (Sensor D x)* as X, and *Column I (Sensor D y)* as Y. Click **Add**. Click **Apply** then OK to close the dialog.
- Next we are going to customize the style of the grouped plot. Double click the plot to enter **Plot Details** dialog. At the plot level, select **Line** tab, set **Width** as 3. Click **Apply** then **OK** to close the


dialog. The graph would appear as follow:




6.1.12.5 Change Plot Display Range with Plot Setup

1. Next we are going to modify the data plot display range.
2. Activate the graph, then click **Graph: Plot Setup** to go back to the **Plot Setup** dialog. Select the data plot of *Sensor A* in the bottom panel. Click the cell of *Range* column, a rectangle button would appear at the end of the cell.

- Click this button. The **Range** dialog would pop up. Uncheck the **Auto** of **From** and **To**. Then Customize it as **From 1 To 15** and click **OK** to close the dialog.



- To apply this display range for other plots, right click the the data plot of *Sensor A* again and select **Apply Range To Group**.
- To rescale the plot, click the checkbox of **Rescale** on the Layer 1 row of the Range Column. Click **Apply** then **OK** to close the dialog.




6.1.12.6 Change Plot Order with Plot Setup


Next we want to change the plot order of these three plots. Use the same graph from the previous example.

- Activate the graph, then click **Graph: Plot Setup** back to the **Plot Setup** dialog.

- At the bottom panel, keep pressing the mouse on the plot of *Sensor B* then drag the plot above *Sensor A*.




- Click **Apply** then **OK** to close the dialog. The graph would appear as follow. You can see that the data plot of *Sensor A* is on top of that of *Sensor B*.



6.1.12.7 Change Plot Type with Plot Setup


Next we want to change these three line plots into scatter plots and modify the data plot range. Use the same graph from the previous example.

1. Activate the graph, right click at the Layer index icon **1** on the graph upper left corner, then select **Plot Setup** to go back to the **Plot Setup** dialog.
2. Select the data plot of *Sensor B* in the bottom panel, then select **Scatter** in the **Plot Type** panel. Click **Replace** to replace the original line plot. Other plots in the same group will automatically be replaced by scatter plot. Click OK to close the dialog.




6.1.12.8 Create Multi-Panel Plot with Plot Setup


Multi-Panel plot with several plots in each layer can be created conveniently using *Plot Setup* dialog.

1. Create a new project, start with a an empty worksheet and from the menu, select **File: Import: Multiple ASCII** or click the **Import Multiple ASCII** button  to open the file browser.
2. Press CTRL and choose the file *Step01.dat*, *Step02.dat*, *Step03.dat*, and *Step04.dat* from the folder *<Origin Installation Directory>\Samples\Curve Fitting\...* Click **Add File(s)**. Check the **Show Options Dialog** check box, and click **OK** to bring up the **impASC** dialog.
3. Under *Import Options*, set **Import Mode** as **Start New Books**. Accept other default settings and click **OK** to close the dialog. Four workbooks *Step01.dat*, *Step02.dat*, *Step03.dat*, and *Step04.dat* will be created.
4. Do not activate any workbook and click **Plot: Multi-Panel: 4 Panel** to go to the **Plot Setup** dialog.

5. Click the double up-sided blue arrow icon on top right corner to open top panel, then select **Worksheets in Project** in **Available Data** drop-down list. All four workbooks would appear in the upper panel.
6. Use Ctrl key to select all four workbooks in the upper panel, then select *Column B (Sensor A x)* as X, and *Column C (Sensor A y)* as Y in the middle panel.
7. Select **Plot Type** as **Line** and select *Layer1* in their bottom panel. Click **Add**. All data plots of *Sensor A* in these four workbooks would be added to *Layer1*.



8. Repeat the previous step to add *Sensor B*, *Sensor C*, and *Sensor D* to *Layer2*, *Layer3*, and *Layer4* respectively. Click **OK** to close the dialog. The graph would appear as follow:




6.2 Axis

- [Multiple Axis Breaks](#)
- [User-Defined Arbitrary Tick Positions](#)
- [Plot and Customize Date Time Data on Graph](#)

6.2.1 Multiple Axis Breaks

6.2.1.1 Summary

Origin supports multiple break on an axis as shown below. The number of breaks and the break positions can be customized in the **Axis** dialog box.



Minimum Origin Version Required: 2015 SR0

6.2.1.2 What you will learn

This tutorial will show you how to:


- Add multiple breaks to both X and Y axes
- Customize axis tick label format
- Fill spans that are broken by missing values vertically

6.2.1.3 Steps to Customize Label Display and Add Axis Breaks


This tutorial is associated with <Origin EXE Folder>\Samples\TutorialData.opj.

Also, you can refer to this graph in **Origin Central**. (Select *Help: Origin Central* menu or press **F11** key, and then open **Graph Sample: Line and Symbol**)


1. Open the Tutorial Data.opj and browse to the *Multiple Axis Breaks* folder in **Project Explorer**. Activate the workbook, Book2D. Highlight Col(A) and Col(B) and select **Plot: Line: Line** from the main menu to plot a line graph. Select and delete the legend.
2. To customize the graph axes double click on an axis to open the Axis dialog box. Click the **Horizontal** icon in **Scale** tab and set the X axis scale as graph below:




3. Go to **Bottom** icon in **Tick Labels** tab, change the display format of tick labels to 15(means year as yy) and add a prefix '.




4. In order to add several breaks to the X axis select the **Horizontal** icon in **Breaks** tab . Check the **Enable** box and set 3 axis breaks.




- Click the **Details...** button to open the **Breaks Details** dialog, set **Break1** from **12/1/1961** to **9/1/1972**, its position is at 25% of axis length by default:




- Select the **Break 2** node in the left panel, change it to be from **3/31/1977** to **8/29/1980**, its position is at 50% by default. Switch to **Break 3** node, change it to be from **7/27/1984** to **3/1/2007**, and its default position is at 75%. Click the **OK** button to apply and exit the **Break Details** dialog and in the **Axis** dialog, click the **Apply** button to view the changes.
- To customize the Y axis, select the **Left** icon under the **Tick Labels** tab and use the format **Engineering:1k** as the tick label display. Set the prefix as "\$". Click **Apply** to view the changes in the graph.




8. Go to the **Breaks** tab again and with the **Vertical** tab selected, enable 2 axis breaks at scale value **3.1 T** to **4.5T** and **6.7T** to **12.5T**, as we had done for the X axis in Step 4 to 6.
9. Click **OK** to apply the settings and get the graph similar as follows:




6.2.1.4 Steps to Add Recession Bars

1. Double-click on X axis to open the Axis dialog. Go to **Reference Lines** tab, click the interactive button  beside the **Reference Lines at Value** text box to select col(C) from worksheet. The x coordinates of all recession periods will be listed in the display table as reference lines. Then check **Alternate Fill** box to fill each period.




2. Click **OK** to apply the settings.




6.2.1.5 More Customization Steps

The following steps can further customize the graph to be exactly the same as the image in Summary.


1. Double click X axis title **Date** in the graph and rename it as **Year**.
2. To change Y axis range, double click on Y axis to open the **Axis** dialog. Go to the **Scale** tab with **Vertical** icon selected, set From, To, Major and Minor ticks as below.




3. Go to the **Breaks** tab again, select the first axis break and click **Details** to open the **Break Details** dialog with the **Break 1** node selected. Clear the **Auto** check box next to the break position option and change it to **38%**. Clear the **Auto Scale** check box and then change the tick settings as below:



4. Select **Break 2** node, set break position, Major Ticks and minor ticks as below:




5. Click **OK** to apply and exit the **Breaks Details** dialog. Click **OK** in the **Axis** dialog to apply settings to graph and close dialog.
6. Select **View: Show: Frame** from the main menu to complete the layer frame.
7. Right click in a blank area inside graph layer 1 and select **Add/Modify Layer Title** from the context menu. Enter *US Recessions and Recoveries* as the layer title.
8. Adjust the page dimension with Graph node selected in **Plot Details** dialog.



6.2.2 User-Defined Arbitrary Tick Positions

6.2.2.1 Summary

This graph will show you how to specify tick locations using a dataset and show customized tick labels at those locations.



Minimum Origin Version Required: Origin 2015 SR0

6.2.2.2 What you will learn



- How to specify the tick location using dataset
- How to show the customized tick labels

6.2.2.3 Steps


1. Copy the [sample data](#), and paste it into row 1 of column A in Origin worksheet. Set the first row as Long Name and the second row as Units.


	A(X)	B(Y)	C(Y)	D(Y)
Long Name	Temperature	Transducer Output	Custom Temperature	Custom Label
Units	°K			
Comments				
F(x)				
1	2.5	1.5	4.2	He Boiling Point
2	2.5	1.5	4.2	He Boiling Point
3	7.3	1.42048	77.36	N Boiling Point
4	13	1.28681	233.15	-40°C/-40°F
5	24	1.06011	273.15	0°C
6	41	0.90549	373.15	H2O Boiling Point
7	70	0.85831		
8	125	0.7679		
9	181	0.63948		
10	246	0.53202		
11	288	0.40753		
12	348	0.24898		
13	399	0.13759		
14	436	0.09435		
15				
16				

2. Highlight columns A and B. Select **Plot:Line + Symbol:Line + Symbol** from the main menu. Alternatively, you can simply click the Line + Symbol button on the **2D Graphs** toolbar.
3. Double-click the graph to open the **Plot Details** dialog. On the **Symbol** tab, change the symbol to a solid circle, and the color to **Olive**. On the **Line** tab, change the line color to Olive and click **OK** to close the dialog and apply the changes.




4. Double-click the X axis to open the **Axis** dialog. For both **Horizontal** and **Vertical** icon in **Scale** tab, enter these settings for the X and Y axes:







5. On **Line and Ticks** tab, go to **Top** and **Right** page, and check on **Show** to show the axis on top (right), Set the ticks style follows the graph below:




- Then, click the **Apply To...** button and go to the **Apply to Others** dialog, set the following:




7. Click **OK** to close the **Apply to Others** dialog and return to the **Axis** dialog.
8. Go to **Display** tab in **Tick Labels** tab, and set the ticks Labels for bottom follows the graph below. In addition, you need to rotate the tick labels by 90 degree in **Format** tab for both top and bottom (which can be done in **Bottom** page) axis.



9. On the **Bottom** page under **Tick Labels** of **X Axis**, set the **Rotate(deg.)** to **90** similarly.
10. Select the **Grids** tab in Axis dialog axis. Check on **Show** in *Major Grid Lines* group for both **Vertical** and **Horizontal**:



11. Click **OK** to close the **Axis** dialog. Adjust the Layer Area in **Format: Layer Properties: Size/Speed** tab. Your final graph should look like this:



6.2.2.4 Sample Data


Temperature	Transducer Output	Custom Temperature	Custom Label
°K	volts		
2.5	1.5	4.2	He Boiling Point
2.5	1.5	4.2	He Boiling Point
7.3	1.42048	77.36	N Boiling Point
13	1.28681	233.15	-40°C/-40°F
24	1.06011	273.15	0°C

41	0.90549	373.15	H ₂ O Boiling Point
70	0.85831		
125	0.7679		
181	0.63948		
246	0.53202		
288	0.40753		
348	0.24898		
399	0.13759		
436	0.09435		

6.2.3 Plot and Customize Date Time Data on Graph

6.2.3.1 Summary

This tutorial will show you how to manipulate the date and time data, and customize the date and time data on the graph.




Minimum Origin Version Required: Origin 2015 SR0

6.2.3.2 What you will learn


- How to plot the date and time data on the graph.
- How to customize the date and time tick labels.

6.2.3.3 Steps


1. Start with a new project and import the data file *Sample\Import and Export\Custom Date and Time.dat* under Origin's program folder.
2. Double-click on A(X) to open the **Column Properties** dialog; set **Format** as *Date*, **Display** as *Custom Display*, and input *dd'.MM'.yyyy hh':mm':ss'.##* in the **Custom Display** box as shown below.




3. Click **OK** button to go back to the worksheet. Highlight col(B) and select **Plot: Line: Line** from the main menu to plot it as a line graph. You will see that the tick labels of X axis are all the same. This is because the tick labels are showing the date information only, but the X data are all in the same day. So we need to change the tick label format to display time.




4. Double-click on the X axis (or select **Format : Axes : X Axis** from the main menu) to open the **Axis** dialog. Select **Horizontal** icon in the **Scale** tab, set the following first:



5. Go to the **Bottom** icon in **Tick Labels** tab, change **Type** to *Time* and select **Display** to *HH:mm* as shown below.



6. Click the **OK** button. The tick labels will now show as the corresponding time as in the graph below:



6.3 Compare Graphs Dynamically by Changing Data Filters

6.3.1 Summary

The **Copy Columns To..** feature allows you to copy columns from a worksheet to a new worksheet while keeping the two sheets linked. Using this feature you can set multiple Filter conditions on one columns by creating a corresponding number of worksheets. For example to set two Filter conditions on the Column **Gas Type** we created two sheets *Type1* and *Type2* that were linked to worksheet *Raw*.

We also used various features to create a dynamic Graph that would update to reflect the changes in Filter conditions in real time. You can watch the video tutorial explaining these concepts here:

<https://www.youtube.com/watch?v=N0Pud-91qCM>

Minimum Origin Version Required: Origin 2015 SR0

6.3.2 What you will learn

This tutorial will show you how to:

- Dynamically compare data with different filter conditions
- Add multiple filter conditions on the same columns using different worksheets
- Add a dynamic filter label in a graph that updates with changes in the filter condition

6.3.3 Steps


This tutorial is associated with the Tutorial Data.opj file under <Origin EXE Folder>\Samples path.

6.3.3.1 Set Up the Worksheets


Open the Tutorial Data.opj file and browse to the folder **Compare Graphs with Filters Data** and active workbook **Book1**. The worksheet **Raw** contains data for the emission of different green house gases in different countries over a period of years.

1. Highlight the last three columns : *Year, Gas Type, Value*

- Right click on one of the columns and in the context menu that opens select **Copy Columns To...**



- In the **DataManipulation\Worksheet: colcopy** dialog that opens, change the **Recalculate** to **Auto** so later when input data is changed the result will be automatically updated. Also make sure the **Destination** is set to **<new>!<new>** meaning a new worksheet and click **OK**




4. Name the new worksheet *Type1*
5. Repeat the above procedure and name the second worksheet *Type2*


	A(X)	B(Y)	C(Y)
Long Name	Year	Gas Type	Value
Units			
Comments			
F(x)			
Filter			
1	2010	N ₂ O	47141
2	2009	N ₂ O	47171
3	2008	N ₂ O	51780
4	2007	N ₂ O	49446
5	2006	N ₂ O	48206
6	2005	N ₂ O	50406
7	2004	N ₂ O	51680
8	2003	N ₂ O	48864
9	2002	N ₂ O	46530

6.3.3.2 Set Filters


1. On Sheet *Raw* highlight column **Country** and select the Filter button.



2. This will create a funnel icon on the top left of the **Country** column. Click on this and in the menu that opens deselect the **Select All** check box and check the **France** check box. Click **OK**




3. The worksheet now only shows information for the country France.
4. In Sheet *Type1* set a Filter on the **Gas Type** column for the gas **HFCs**. Since sheet *Raw* and sheet *Type1* are linked, this worksheet will now show only the HFC emission values for the country France.




5. In Sheet *Type2* set a Filter for **Gas Type** PFCs. This worksheet now only shows PFC emission values for Country France.

6.3.3.3 Creating the Graph and Adding a Linear Fit


1. Without anything highlighted in any of the worksheets go to **Plot: Multi-Panel: Stack....**
2. In the dialog that opens, click on the arrow button next to the **Input** box and select **Select Columns...**




3. In the **Data Browser** dialog select both the **Value** columns in Sheets *Type1* and *Type2*. Click **Add** and OK out.



- In the **Plotting: plotstack** dialog, set **Plot Type** to **Scatter** and OK out, which will result in the following graph:




5. In the newly created graph double click on any axes, in the **Scale** tab set the **Rescale** as **Auto**. Do this for every axes on both plots of this graph so when the worksheet filter is changed and the graph data changes, the axes will rescale automatically.




Note: it is also possible to hold **Ctrl** key and select both **Horizontal** and **Vertical** icons to change **Rescale** for both X and Y axes in the same layer simultaneously, but to change the setting for the axes in another layer, you always need to exit the **Axis** dialog, double click on one axis in the other layer again to open the **Axis** dialog for that layer.


- Go to the **Axis** dialog for Layer 1, go to the **Tick Labels** tab with **Bottom** icon selected, change the **Display** to *2014* (It means to display the date as yyyy, and this option will be dynamically changed with system date, i.e. it shows the year of the current system date):




- Go to the **Line and Ticks** tab with **Right** icon selected and hide the major and minor ticks in right Y axis:



8. Repeat the last 2 steps for the Top X axis and Right Y axis in Layer 2.
9. Delete the two Y axis title objects at the left part of the graph, add a new text label **Value** and rotate it to 90 degrees (right click and select **Properties** to change rotation angle) and use it as the new Y axis title.
10. Next we're going to do a Linear Fit so the emission trends are more apparent.
11. Activate the graph and go to **Analysis:Fitting: Linear Fit...**
12. Set **Recalculate** to **Auto**.
13. Use the arrow button next to the **Input** box to select **Add all plots in active page**. OK out of the dialog




14. Double click on the linear fit curves and go to the **Plot Details** dialog, in the **Line** tab, set the color as **Red** for each curve. Delete the legend objects and move away the report table. The resulting graph will look like this:




6.3.3.4 Add Dynamically Changing Labels

1. Select the Filter Label on the Sheet *Type1*


2. Go to **Edit: Copy: Copy**




3. Select the Text Button **T**, click on the graph and when the blue text box appears hold down **Ctrl + Alt + V**. This will paste the Data Filter Label as a link into the text box.
4. Select the link, right click and select **Programming Control**



5. In the **Programming Control** dialog, enable the **Real Time** check box so the label changes every time the data filter is changed.



6. Do this with the Filter Labels in Sheet *Type2* and Sheet *Raw*. Add the words "Gas Type" before the "PFC" and "HFC" labels and "Country" before the Country Data Filter Label. Also Add a Layer Title:



6.3.3.5 Add Floating Graph to the Worksheet

1. To add the graph to the worksheet, activate the worksheet *Raw*
2. Right click on the grey section of the worksheet and in the context menu that opens select **Add Graph..**

The screenshot shows the 'RawData' window in Origin software. The table contains the following data:

	A(Y)	B(X)	C(Y)	D(Y)
Long Name	Country	Year	Gas Type	Value
Units				grams (Gg) CO ₂ equiv
Comments				
F(x)=				
Filter	France			
127	France	2010	N ₂ O	59833
128	France	2009	N ₂ O	61971
129	France	2008	N ₂ O	65903
130	France	2007	N ₂ O	64881
131	France	2006	N ₂ O	65308
132	France	2005	N ₂ O	67738
133	France	2004	N ₂ O	68231
134	France	2003	N ₂ O	70234
135	France	2002	N ₂ O	72886
136	France	2001	N ₂ O	74903
137	France	2000	N ₂ O	77574
138	France	1999	N ₂ O	78608
139	France	1998	N ₂ O	85477
140	France	1997	N ₂ O	92859
141	France	1996	N ₂ O	91448
142	France	1995	N ₂ O	90020
143	France	1994	N ₂ O	88267
144	France	1993	N ₂ O	87019
145	France	1992	N ₂ O	91240
146	France	1991	N ₂ O	90073
147	France	1990	N ₂ O	91322
148	France	2010	HFCs	16946

The context menu is open, showing options such as Paste, View, Show Organizer, Show Script Panel, Copy Format, Paste Format, Add New Sheet, Add Graph... (highlighted), Add Text..., Add New Column, Clear Worksheet..., Go To..., Mask, and Properties...

3. In the **Graph Browser** dialog that opens, select the graph we just created, and then click **OK**
4. Enlarge the graph by selecting it and dragging the edges. If you change the Filter Types in the worksheet now, the graph will update accordingly.

6.4 Layers

- [Adding and Arranging Layers](#)
- [Merging and Arranging Graphs](#)
- [Multiple Layers with Linked Axis](#)

6.4.1 Adding and Arranging Layers

6.4.1.1 Summary


A typical graph page generally includes three elements: a set of X, Y (and Z) coordinate axes, one or more data plots, and associated text and graphic labels. Origin combines these three elements into a movable, resizable unit called a layer. While a page can contain as many as 121 layers, only one layer can be active at any one time.

6.4.1.2 What you will learn



- How to tell how many layers a graph has?
- How to tell what data is in what layer?
- How to swap layers

6.4.1.3 Steps

Importing data

1. Click the **Import Single ASCII** button, , on the Standard toolbar. The ASCII dialog opens.
2. In the Origin folder, browse to the Samples folder and then the Graphing folder. Select Wind.dat from the list of files.
3. Click **Open**. The data file imports into the worksheet.

Plotting the data

1. Highlight the Speed and Power columns.
2. Click the **Line** button, , on the **2D Graphs** toolbar. A line plot is created. It appears that this data would be better plotted on a double-Y graph, a graph with two controlling Y axes.
3. Click the X to **Close** this window. You will be asked if you want to hide or delete the window. Click the **Hide** button. (If you Delete, you will not be able to Undo, and you will need to re-create the graph. Hiding closes the window from view, but you can later make it visible using the Project Explorer window.)
4. The Speed and Power columns should still be highlighted. Click the **Double-Y Axis** button, , on the 2D Graphs toolbar. This new graph contains 2 layers.


How to tell what data is plotted in a layer?

One way is with the legend:

Tutorials for Origin

1. Double-click on Graph1 from the Project Explorer window. The graph opens and becomes the active child window.
2. Select **Format:Page** and go to the **Legends/Titles** tab.
3. Set the **Auto Legend Translation Mode** to *Data Range*.
4. Click **OK**.

A second way is with the status bar:

1. Double-click on Graph2 from the Project Explorer window. Graph2 is now in front and becomes the active child window.
2. Click the Layer 1 icon,  to make layer 1 active.
3. Look in the lower right of Origin's status bar and you'll see [WIND]WIND!Col(Speed)[1:12].
4. Repeat for Layer 2 and you'll see [WIND]WIND!Col(Power)[1:12].



A third way is from the menu:

1. Make Graph2 active.
2. Right-click on the Layer 1 icon. At the bottom of the context menu, you see the data plot list. The one checked is the active data plot.
3. Right-click on Layer 2 to view the list of data that is plotted in it.
4. Note that you can also select the **Data** menu to view the data plot list.

A fourth way is with the **Plot Setup** dialog.

1. With Graph2 still active, Right-click on the layer 1 icon to select **Plot Setup**.
2. In the opened **Plot Setup** dialog, expand the Plot List to see also the data in Layer 2. You can see the advantage here is that you can see data in all layers at once.



In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

3. Uncheck the Show check box for the **Speed** data plot.
4. Click **OK**. This data plot is only hidden which is why the legend still indicates its presence in the layer.

The last way is from the **Plot Details** dialog.

1. Double-click on any of the line+symbol plots in Graph2.
2. Expand the tree so you see contents of both **Layer1** and **Layer2**.
3. Uncheck the **Speed** and **Power** data plots.
4. Click **OK**.

6.4.2 Merging and Arranging Graphs

6.4.2.1 Summary

The **Merge Graph Windows** dialog allows you to select which graphs you wish to combine, choosing from any graph in the project. It also has controls to specify how you want the individual graphs arranged on the new page.

The **Object Edit** toolbar allows you to quickly align and size multiple layers.

The **Layer Management** dialog lets you add, arrange and link layers on a single graph page.


6.4.2.2 What you will learn



This tutorial will show you how to:





- Resize and align layers quickly
- Add a second axis using a nonlinear relationship with the primary axis
- Use Layer Management for more complex layer positioning and linking
- Merge multiple graphs into one graph

6.4.2.3 Aligning Layers using the Object Edit Toolbar

1. Select **File:Open** and open the OPJ \Samples\Graphing\Layer Management.opj and go to the subfolder **Arranging Layers**. (If you don't see the subfolders, click **View: Project Explorer** to open the Origin Project Explorer window.)
2. We want to use the **Object Edit** tools to rearrange the graph so make sure that this toolbar is visible. If it is not, you can open it from the **View: Toolbars** dialog box.



3. On the graph, hold the **Shift** key down and click on all four layers to select them as a group. Press the **Uniform Width**  and **Uniform Height**  buttons on the **Object Edit** toolbar to apply a uniform height and width. Then click on the white space in the layer to deselect all graph layers.

4. Hold **Shift** key to click and select the bottom two layers and then click the **Bottom**  button on the Object Edit toolbar to align them. Click on the white space in the layer to deselect all graph layers.
5. Hold **Shift** key to click and select the top two layers, then click the **Top**  button to align them. Click on the white space in the layer to deselect all graph layers.
6. Click and select the top and bottom in the left column, and click the **Left align** . Click on the white space in the layer to deselect all graph layers.
7. Click and select the two in the right column and click the **Right align**  button.



The Object Edit toolbar provides a quick way to align and resize layers. The first layer you select is the reference layer and all others are adjusted relative to the first-selected layer. The **Layer Management** tool provides additional options such as layer reordering and linking.

8. Do not save changes to your project, as the same project will be used later to demonstrate the usage of Layer Management.


6.4.2.4 Displaying Opposite Axes with a Nonlinear Formula

An Origin 2D graph layer is a set of X, Y axes, and opposite axes can be turned on for both X and Y. In addition, the opposite axes can also display labels using any user-specified nonlinear formula with respect to the primary axis.

1. Using the Project Explorer window, switch to the subfolder named **Nonlinear Axis**.
2. With the graph active, bring up the Layer Management tool by selecting **Graph: Layer Management**.
3. Switch to the **Axes** tab and expand the **Top** branch and check the **Axis**, **Title**, and **Tick Label** check boxes.
4. We want to display the labels on the top axis in units of Energy and the relationship between wavelength and energy is:


$$\text{Energy (eV)} = 1240/\text{Wavelength (nm)}$$

So in the **Formula** box, enter: $1240/x$ and click **Apply**, then click **OK** to close the dialog.




If you are setting up a nonlinear relationship for the right Y-axis, in the **Formula** you still need to use **x** instead of **y**.

5. Double-click and edit the top X-axis title and change it to: Energy (eV)



6. In the above image, the first tick label of the top axis is a missing value for energy that corresponds to zero wavelength. To hide it, double-click the top axis labels or axis, to open the Axis dialog. Go to the **Special Ticks** tab in **Top** icon. Then select **Hide** in the **Axis Begin** drop-

down list. Click **OK** to apply the settings and close the dialog.




6.4.2.5 Using Layer Management to Link and Position Layers


The Layer Management tool can be used to position, resize, swap, and link layers:

1. Reopen the project `\Samples\Graphing\Layer Management.opj` and then switch to the subfolder named **Arranging Layers**. You can reopen the project by selecting **File: Recent Projects: Layer Management.opj**. Do not save changes to the project.
2. Bring up the **Layer Management** tool from **Graph: Layer Management**. In the left panel, rename the layers so that they are, top to bottom: Peak 3, Peak 2, Peak 4, Peak 1. The layer names now correspond to the legend for each layer.


Note: To rename a layer, double-click on the name.



3. Now drag and arrange the list on the left so that they are ordered Peak 1, Peak 2, Peak 3, Peak 4.
4. The layer number and names now match.




4. Now switch to the **Arrange** tab and do the following:
 1. Check **Show Axes Frame**.
 2. Set **Horizontal Gap** and **Vertical Gap** to 0.




3. Click **Apply**.

This resizes and repositions the layers so they are aligned, and hides ticks and labels where layers overlap.

- Go to the Axes tab, hold down the **CTRL** key and select Peak 1 and 3 on left list, then expand the **Left** branch and set tick direction to **In**, and click **Apply**.



- Now select Peaks 3 and 4, set the **Bottom** tick direction to **In** and click **Apply**. Then select Peaks 1 and 2, set the **Top** ticks to **In** and click **Apply**.
- go to the Link tab and select Peaks 2, 3, and 4 in the left list and link them to layer 1, making sure you have the X-Axes linked **Straight(1 to 1)**, and click **Apply**.




Click **OK** to close the dialog box.

8. Click and select the top left layer, layer 1, then drag and resize the layer, then move the layer. Note that the child layers resize and move too, since they are dimensionally linked to layer 1.



9. Go to the top left layer (layer 1), and double-click the top X-axis. In the X-Axis dialog, change the X-Axis scale From 10 To 35, and click **OK**. You'll see that all the other layers now display the same X-axis scale range.






If the layers are linked, they are treated as one unit. If you need to rearrange layers, you should first unlink them. You can re-link layers after arranging.


6.4.2.6 Merge Multiple Graphs

In this section, we merge two graphs from different subfolders of the same project while treating the four layers in one graph as a unit.

1. Click on the **Rescale** button when the Graph 1 in the **Arranging Layers** subfolder is active.
2. Select **Graph: Merge Graph Windows** in the main menu to open the dialog.
3. Do the following:
 - From the **Merge** drop-down list, choose **All in Project**. **Graph1** and **Graph2** will show in the **Preview** panel.
 - Make sure **Number of Rows = 2** and **Number of Columns = 1**.
 - Make sure **Treat Each Source Graph As a Unit** is selected.
 - Set the **Vertical Gap** to **20**.



4. Click **OK** to close the dialog box. A new merged graph page is created:




- 1.
- 2.
- 3.
- 4.

6.4.3 Multiple Layers with Linked Axis

6.4.3.1 Summary

This tutorial will show how to merge four graphs to one graph, which contains multiple layers with linked axis.



Minimum Origin Version Required: Origin 2015 SR0

6.4.3.2 What you will learn


- How to make a Line + Symbol plot
- How to merge graphs
- How to link axis of layers
- How to customize axis

6.4.3.3 Steps



This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the **Tutorial Data** project and browse to folder *Multiple Layers with Step Plot* in **Project Explorer**.
2. Activate the workbook and highlight column Value1 and make a graph by selecting Origin menu **Plot: Line + Symbol: Line + Symbol**.
3. Activate the graph, right-click the legend and choose **Properties** from the context menu. In the **Object Properties** dialog,


- In the **Text** tab, put this text in the text field: $\backslash b(\textit{Vertical})$ and set **Size** to 36.
- Go to the **Frame** tab, and set as following image. Click the **OK** button. Move the legend to the correct position.




4. Double click on the open white space in layer of the graph to open the **Plot Details** dialog. In the left panel, select **Layer1**. Activate the **Background** tab in the right panel, choose *LT Gray* for the **Color**. Then select the plot in **Layer1** from the left panel, under the **Symbol** tab in the right panel, set **Size** to 15 and **Symbol Color** to red. Switch to the **Line** tab, choose **Step Vert** from the **Connect** drop-down list and set **Width** to 4 and click **OK** to apply settings.




Tutorials for Origin



5. Now we are going to duplicate similar graphs from the other three columns. Right click on the graph window title bar and select Duplicate (Batch Plotting):Duplicate with New Columns from the context menu:



6. In the **Select Column** dialog that opens, hold Ctrl key and click to select all three columns C, D, E and click OK:



7. For graph from each column, the legend text and **Connect** drop-down list will be different, listed below.

For column **Value2**:

legend text = \b(Vertical Center)

Connect = Step V Center

For column **Value3**:

legend text = \b(Horizontal)


Connect = Step Horz

For column **Value4**:


legend text = \b(Horizontal Center)

Connect = Step H Center


8. Activate a graph and then select Origin menu **Graph: Merge Graph Windows** to open the **merge_graph** dialog. Change the settings as the following image shows. Then click the **OK** button to merge these graphs.




9. Activate the new merged graph, choose Origin menu **Graph: Layer Management** to open the **Layer Management** dialog. In the **Layer Selection** panel, rename the layers by double clicking on the name and reorder the layers by clicking on the layer index and dragging up and down. Make sure the final layers' names and order are the same as the image shows below (In the **Preview** panel, the layers' indices and positions can be shown).




- In the **Layer Selection** panel, press **Ctrl** key on the keyboard to select the following layers: *Vertical Center*, *Horizontal* and *Horizontal Center*. Go to the **Link** tab, select **1** from the **Link To** drop-down list. Then both **X Axis Link** and **Y Axis Link** are set to **Straight(1 to 1)**. Then click the **Apply** button.




- Go to the **Axes** tab, select *Vertical* layer from the left panel, then check all **Axis** check-boxes under **Bottom** branch, **Left** branch, **Top** branch and **Right** branch. Also, select *In* for **Tick** drop-down list under **Top** branch. Click the **Apply** button.




12. Select *Vertical Center* layer, in the **Axes** tab, **Bottom** branch, **Left** branch and **Right** branch share the same settings. And settings for **Top** branch shows in the image below. Click the **Apply** button.



13. Select *Horizontal* layer, in the **Axes** tab, check the **Axis** check-boxes under both **Top** branch and **Right** branch. Click the **Apply** button.




14. Select *Horizontal Center* layer, in the **Axes** tab, check the **Axis** check-box under **Top** branch. Click the **Apply** button.




15. Click the **OK** button to close the **Layer Management** dialog.


16. Double click on the X axis of the lower-left layer to open the **X Axis** dialog. In the **Scale** tab, change the axis scale as the image below:




17. Click the **Vertical** icon on the left panel to go to **Scale** tab for **Y Axis** and change the axis scale:




18. Go to **Tick Labels** tab and click **Bottom** icon on the left panel and change the display of X tick labels:



19. Go to **Special Ticks** tab and hide the label at axis end by selecting **Hide** from **Show** drop-down list for **Axis End**:



20. Click on the **Left** icon on left panel, and hide the label at Y axis end by selecting **Hide** from **Show** drop-down list for **Axis End**.
21. Repeat step 16 to step 18 for the X axis of the lower-right layer.
22. Double click on the axis of lower right X axis, go to **Tick Labels** tab and **Format**, change the **Size** to be 30 and check **Bold** box.
23. Click on the **Apply To...** button on the bottom, in the bring up **Apply To** dialog.
24. Check **Size** and **Bold** boxes under **Tick Labels** node and select **This Window** from the drop-down list for both and click **OK** to apply the settings so that all axes' tick label size is set to be 30 now.



25. Change the both Y titles to *Price* and make them bold.

6.5 Graph Template and Theme

- [Copy and Apply a Plot Format to Another Plot](#)

6.5.1 Copy and Apply a Plot Format to Another Plot

6.5.1.1 Summary

It is possible to copy and paste formatting from one plot to another, so there is no need to spend time recreating identical customizations such as size and color of symbols and lines.

Minimum Origin Version Required: Origin 8.0 SR6

6.5.1.2 What you will learn

This tutorial will show you how to:

- Copy a plot format (color, size, etc. of the symbol or the line), and apply it to other plot.

6.5.1.3 Steps

1. Click the **New Project** button on the Standard toolbar to begin with a new project.
2. Select **File: Import: Single ASCII** menu, and import **exponential decay.dat** in the **\Samples\Curve Fitting** subfolder in your Origin program directory.
3. Highlight column B, C and D, and select **Plot: Line+Symbol: Line+Symbol"** menu to plot **these three datasets.**
4. Double-click on the plot to show the **Plot Details** dialog box.
5. Choose **Group** tab in the dialog, and select **Independent** for the **Edit Mode** -- this makes it easier to customize individual plots.
6. Make sure that the top data plot (Time(X) Decay 1(Y)) is selected in the left panel of the **Plot Details** dialog. If not, select this plot branch in the left panel.
7. Select the **Symbol** tab, and change the Size to "5". (You can also change the shape or the color to others of your choice.)
8. Select the **Line** tab, and change the width to "0.2". (You can also change the style or the color to others of your choice.) Click OK. You will see that the **Decay 1** plot has been customized.
9. Click on **Decay 1** plots to select. Right-click on it and select **Copy format**. This will copy the plot format of Decay 1 to the clipboard.
10. On the graph, click on the **Decay 2** data plot to select it, right-click and select **Paste Format to: All**. You will see the plot format of Decay 1 copied to Decay 2.

6.6 Line and Symbol


6.6.1 Line and Symbol

- [Complicated Fill Area](#)
- [Fill Partial Area between Curves](#)
- [Line Graph with Recession Bars](#)
- [Scatter Plot of Decay and Recovery Curves](#)
- [Micro-Raman spectroscopy of complex nanostructured mineral systems](#)
- [Multi-line-plot with Special Position Annotation Line](#)

- [Scatter Central Plot](#)
- [Line Graph with Masked Data](#)
- [Symbol Plot with Color Transparency](#)
- [Symbol Plot with Size and Colormap from Other Columns](#)

6.6.2 Complicated Fill Area

6.6.2.1 Summary



Minimum Origin Version Required: 9.1 SR0


6.6.2.2 What you will learn

- Fill area between curves with two different color.
- Use plot sequence to implement complicated graph.


6.6.2.3 Steps to create stacked fill area plot

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data.opj and browse to folder *Multiple Fill Area*.
2. Activate workbook **Book2** and **Sheet1**. Highlight columns C through F, then click **Plot: Line: Line**. A grouped line plot is created.
3. Select and delete the axis title and legend object from the graph.
4. Double click any of the lines to open **Plot Details** dialog. Go to **Line** tab, set **Transparency** be 100%.




5. Go to **Group** tab, set **Edit Mode** be **independent** so that we can customize fill area mode for each line.




6. Go to **line** tab for the first plot in graph, enable **Fill Area Under Curve** and select **Fill to next data plot - Above Below Colors**.



7. Go to **Pattern_Above** tab, set as below.




8. Go to **Pattern_Below** tab, set **Fill Color** to be *Red*. This is the first fill part of our plot.




- Go to **line** tab for the second plot in graph, enable **Fill Area Under Curve** and select **Fill to next data plot - One Color**.

- Go to **Pattern** tab, set as below.



11. Repeat step 6~8 for the third plot in graph, with above fill color be *None* and below fill color *blue*.


12. Now we created a stacked fill area plot.




6.6.2.4 Steps to Reduce Redundant Fill Area

In the graph we just created above, there are some redundant fill areas that we do not want. To hide them, we can add another white fill area to cover them so they will be invisible.


1. Select **Graph: Layer Contents** from menu. Select Col(B) and Col(C), click right arrow button in the middle of the dialog to add plot to graph.



- Open **Plot Details** dialog again and go to **Line** tab of the new add plot.
- Select Col(F) and Col(G) and add them to graph.




- Click OK to close the dialog.
- Open **Plot Details** dialog again, fill area between those two new line groups by color white. See step9~10 in above section.




6.6.2.5 Further Customizations


1. Add Col(C), Col(D), Col(E), Col(F), Col(H) and Col(I) onto the graph again and assign appropriate color to each of them.
2. Double click X axis to open **Axis Dialog**.
3. In **Scale** tab, change **Rescale Margin(%)** to be **0** so that there will be no margin at the beginning and end of the axis.




4. In **Tick Labels** tab, Choose **Date** as **Type** with **Display** being **MMM**.




5. In **Grids** tab, turn on both **Major Grid Lines** and **Minor Grid Lines** for **Horizontal**.



6. Click **OK** to apply the settings, and you will have a graph as below



7. Notice that some of the grid lines are not visible for the reason that they are behind the white fill area. Open **Plot Details** again and go to layer level, **Display** tab and check **Grid on Top of Data**.




8. Then re-size the layer and add legend, you shall have the graph on top of the page.

6.6.3 Fill Partial Area between Curves

6.6.3.1 Summary

This tutorial shows how to plot two functions and customize the graph by partially filling an area between the two function curves.



Minimum Origin Version Required: 2015 SR0

6.6.3.2 What you will learn


- Generate patterned data.
- Use an F(x) label row formula to set column values.
- Fill areas between two lines with different colors.
- Add and edit objects on your graph.

6.6.3.3 Filling Area Between Parts of Two Curves


To apply different fill colors to two or more portions of the curve, you need to plot curves in segments. In this tutorial, you will learn how to fill an area between curves defined by $X \leq 1$. This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the Tutorial Data.opj and browse to the *Fill Partial Area between Curves* folder. **Book2L** contains two function curves (**Note:** To see how to generate a dataset from a function, see the last section of this Tutorial).
2. Select rows 1~51 ($-4 \leq X \leq 1$) of all three columns in **Sheet1** of **Book2L** and on the menu, click **Plot: Line: Line** to plot two lines. The two datasets (lines) are automatically grouped.


- Now, select rows 51~81 ($1 \leq X \leq 4$), Book2L, Sheet1 and hover over the edge of the

highlighted area until the cursor looks like this . Drag and drop the selected range, onto the graph you just created. If prompted to rescale the axes and show all data, choose **Yes**.


- Select and delete the legend and the axis title.




- Double-click on one of the line plots, to open the **Plot Details** dialog box. Select the 1st plot under the **Layer1** node on left panel. It should be a black line plot of $X \leq 1$.
- Go to **Line** tab and check **Fill Area Under Curve**. Select **Fill to Next Data Plot - Above Below Colors**. Notice that this action adds a **Pattern_Above** and a **Pattern_Below** tab to the dialog box.




7. Go to the **Pattern_Above** tab and set the fill color of the black line to **LT Magenta** with a 50% transparency.



- Go to the **Pattern_Below** tab and set the fill color below the black line to be **LT Cyan**. Note that there is not a separate transparency control for **Pattern_Below** (uses the same transparency settings as **Pattern_Above**).




- Click **OK** to close the dialog box. The area in between the curves where $X \leq 1$ is now filled.




6.6.3.4 Changing X and Y Axis Range


- We want to change the **X** axis display range from **-2.5** to **2.5** and the **Y** axis display range from **-10.5** to **4**. To do this, double-click on the X axis to open the **Axis Dialog** box. Set the X axis(**Horizontal** icon) in **Scale** tab as follows.




2. Go to **Vertical** icon in **Scale** tab and set the Y axis scale as follows.



3. To configure the X and Y axes so that they intersect at **0,0**, Select both **Bottom** and **Left** icon in the left panel of the Axis Dialog. Set **Axis Position** to **At Position = 0**.




4. Click **OK** to close the dialog.



6.6.3.5 Changing Line Plot Colors and Widths

1. To modify the colors of the lines, double-click any line to open the **Plot Details** dialog box. Select the first plot under **Layer1** in the left panel.
2. On the **Group** tab, click the ... button on the **Line Color** row to open the **Increment Editor** dialog box. Delete **Black** from the increment list so the first line in a group will start from red.




3. Go to the **Line** tab. Set **Width** to **2**. Set the same line style for the curve where $X \geq 1$ similarly.
4. Click **OK** to close the dialog box.


6.6.3.6 Adding Symbol and Label for Intersected Points

There is an **Intersect** workbook that contains points where the two function curves intersect (except (0,0)).


1. Double-click the Layer 1 icon in upper left corner of the graph window to open the **Layer Contents** dialog box. Select "Intersection Y" in the result sheet and add it to the graph as a scatter plot.



2. Double-click the graph to open **Plot Details** dialog box. Go to the **Symbol** tab of the scatter plot of intersected points.




3. Go to the **Drop Lines** tab and reproduce settings as shown below.




4. Go to the **Label** tab, reproduce settings as shown below and click **OK** to close the dialog box.

Tutorials for Origin





5. Press CTRL on the keyboard and click on the (2,2) label to select it, then drag it to better position to avoid overlapping with the line.




6.6.3.7 Adding Annotations and Axis Arrows


1. To hide the axis tick labels at (0,0), open the **Axis Dialog** box again and go to **Special Ticks** tab, then for the **Bottom** icon set as below and do the same for the **Left** icon.




- To add arrows to the ends of the axes. Click the  button on the **Tools** toolbar and then click and drag to add an arrow object. If the **SHIFT** key is pressed while adding an arrow object, the object will snap to the vertical or horizontal.
- Resize and drag the arrow to reposition on the axis. Alternately, right-click the arrow object that you just created and select **Properties...**. Go to the **Dimensions** tab and reproduce the settings as shown below. Then click **OK** to apply the settings.




- Add another arrow object and set dimensions to be (0,3) to (0,4).
- To add a straight line at **X=1**, select **Graph: Add Straight Line** from the menu.




6. Right-click on the dotted line and select **Properties...** On the **Arrow** tab, set **End Shape** be a simple straight line.
7. Right-click the line label and select **Properties...** Add "X = " to the beginning of the text and set **Size** to be 18.
8. To add the two curves' formulas to the graph, right-click on a blank area and choose **Add Text...** Type the following formulas. Select the text that should be superscripted and click the  button on **Format** toolbar.

$y = -x^2 + 3x$

$y = 2x^3 - x^2 - 5x$
9. Reposition the labels as needed.
10. Select the **Curved Arrow Tool** and add two curved arrows to connect formula labels to line plots.



11. Your final graph should look something like this:



6.6.3.8 Generating Data for a Function

1. Open a new workbook. Choose **Add New Columns** to the worksheet so there are 3 columns.
2. Right-click Col(A) and select **Fill Column with: A set of Numbers...**
3. In the **patternN** dialog box, set up the following parameters, then...

From	-4
To	4
Increment	0.1
Mode	<input checked="" type="radio"/> Repeat <input type="radio"/> Random
Repeat Times for Each Value	1
Repeat Times for The Sequence	1
Total Number of Whole Set	81


4. Type $-1*Col(A)^2+3*Col(A)$ in the **F(x)** label row of Col(B).
5. Type $2*Col(A)^3-Col(A)^2-5*Col(A)$ in the **F(x)** label row of Col(C).

	A(X)	B(Y)	C(Y)
Long Name			
Units			
Comments			
F(x)		$-1*Col(A)^2+3*Col(A)$	$2*Col(A)^3-Col(A)^2-5*Col(A)$
40	-0.1	0.21	0.40
41	0	0	0
42	0.1	0.29	-0.51
43	0.2	0.56	-1.02

6.6.4 Line Graph with Recession Bars

6.6.4.1 Summary

This tutorial will show how to create a line graph with recession bars. This type of graph is common when plotting economics data with periods of recession marked as vertical bars.



Minimum Origin Version Required: Origin 2017 SR0


6.6.4.2 What you will learn


- Plot a line graph
- Add reference lines and fill paired reference lines to show recession bars
- Set date display format in the **Axis** dialog


6.6.4.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj. Open the **Recession Bars** folder from **Project Explorer** and the workbook *Book1G* is activated.


Add Reference Lines and do Alternate Fill to add Recession Bars

1. Highlight col(A) and col(B) in the worksheet, choose **Plot: Line: Line** to create a line graph. Click on the line plot to select it and then use the **Line/Border Color** button  in **Style** toolbar to set its color to *red*.

2. Double-click on X axis to open the Axis dialog. Go to **Reference Lines** tab, click the interactive button  beside the **Reference Lines at Value** text box to select col(C) from worksheet. Then the x coordinates of all recession periods will be listed in the display table as reference lines.






3. Check **Alternate Fill** box to fill each period. And uncheck the **Line** check box to hide all reference lines (by checking the **Line** check box on **Line** column header and then unchecking it to remove all selections in this column).




Customize the Display of Graph


1. Click the Graph1 icon in the left panel (take care not to clear the check box beside it) and on the **Display** tab, set **Color** as **Dark Cyan**. Click the Layer1 icon, set the **Color** on the **Background** tab as **White**, clear the **Data on Top of Axes** check box and check **Frame** check box in the **Display** tab. Click **OK** to close this dialog.




2. Double-click the X axis to open the **Axis** dialog. Click the **Tick Labels** tab, under **Display** page select **2016** from **Display** drop-down list.




3. Go the **Format** page and change **Rotate (deg.)** to **90**, so that all tick labels will rotate 90 degrees. Click **Apply** to view the settings.




4. Go to the **Scale** tab and set the X axis scale as below:



5. Go to the **Title** tab and change the content in **Text** box to **Year** to modify the X axis title.
6. Highlight **Left** icon on the left panel and change the Y axis title text to be **(Index 2002 = 100)** and click **Apply**.
7. Go to the **Scale** tab again and this time the **Vertical** icon is selected which indicates it is the **Scale** tab for Y axis, set the **From** value to 0. Click the **Apply** button.
8. Go to the **Grids** tab and show the major grid lines in **LT Gray** following the settings below:




9. Click **OK** to apply the settings and close the dialog.
10. Go back to the graph and delete the legend. Right-click on the layer and select **Add/Modify Layer Title** to add a title. Type *Industrial Production: Durable Consumer Goods (IPDCONGD)* in the text box. Highlight the text and click the **B** button on the **Format** toolbar. Adjust the text to an appropriate size by typing or selecting a number in the **Font Size** list in the **Format** toolbar. You should get the following graph.



6.6.5 Scatter Plot of Decay and Recovery Curves

6.6.5.1 Summary

The scatter plot below depicts 3 decay and recovery curves obtained after taking two-photon fluorescence measurements of reversible photodegradation in a dye-doped polymer. To learn more about the graph, please read the [case study](#).




Minimum Origin Version Required: Origin 2016 SR0


6.6.5.2 What you will learn

- How to use the **Plot Setup** dialog to arrange plots in a layer
- How to customize the symbols in your graph


6.6.5.3 Steps


1. Download the zip file from [here](#) and extract the text files .



- Open Origin and click the **Import Multiple ASCII** button  on the **Standard** toolbar to open the **ASCII** dialog and then import the text files.



- In the **impASC** dialog, set **Import Mode** as **Start New Sheets**. Click OK to finish importing.



- We will use the Plot Setup dialog to create a graph with 8 plots. Active the workbook, and make sure that no datasets are now selected. Click the  button on the **2D Graphs** toolbar to open the **Plot Setup** dialog.

Show all of the three panels of **Plot Setup** dialog (if not all of them are shown) by clicking the  and  buttons.

First, we will add 4 line plots into a graph by using the Plot Details dialog. Highlight all dataset in the top panel, and then select column **Timemin** as X, column **Theory** as Ys in the middle panel. Then add them into the bottom panel.

Then we will add 4 scatter plots in to the same graph. Select **Scatter** from the **Plot Type** dropdown list, make sure all dataset in the top panel has been selected, and then select column **Timemin** as X, column **NormData** as Ys in the middle panel. Then add them into the bottom

panel.

Plot Setup: Select Data to Create New Plot

Available Data:

Long Name	Sheet	Cols	Rows	File Name	File Date	Created
[9w pulse.txt]3.5w pulse	3.5w pulse	4	60	3.5w pulse.txt	3/28/2011	7/4/2011 11:45:21
[9w pulse.txt]6w pulse	6w pulse	4	60	3.5w pulse.txt	3/28/2011	7/4/2011 11:45:21
[9w pulse.txt]7w pulse	7w pulse	4	60	3.5w pulse.txt	3/28/2011	7/4/2011 11:45:21
[9w pulse.txt]9w pulse	9w pulse	4	90	3.5w pulse.txt	3/28/2011	7/4/2011 11:45:21

Show(S) [A9w pulse]"3.5w pulse" 6w pulse 7w pulse 9w pulse

Line Type:

Line Type	X	Y	yEr	L	Column	Long Name	Comments	Sampling Interval	Position
Scatter	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<autoX>	From/Step=			0
Line + Sym	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A	Timemin			1
Column	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	B	Data			2
Area	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	C	Theory			3
Stack Area	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	D	NormData			4

Plot List: Drag entries in 1st column to re-order plots. Right click for other options.



Plot	Range	Show	Plot T
Layer 1	<input checked="" type="checkbox"/> Rescale	<input checked="" type="checkbox"/>	
Group			
[9w pulse.txt]3.5w pulse! "Timemin"(X), "Theory"(Y)	[1*:58"] 0 < X < 680 , 0.81 < Y < 0.99894	<input checked="" type="checkbox"/>	Line
[9w pulse.txt]6w pulse! "Timemin"(X), "Theory"(Y)	[1*:58"] 1 < X < 680 , 0.75 < Y < 0.99823	<input checked="" type="checkbox"/>	Line
[9w pulse.txt]7w pulse! "Timemin"(X), "Theory"(Y)	[1*:58"] 0 < X < 680 , 0.68655 < Y < 1.00038	<input checked="" type="checkbox"/>	Line
[9w pulse.txt]9w pulse! "Timemin"(X), "Theory"(Y)	[1*:67"] 1 < X < 680 , 0.62 < Y < 0.99586	<input checked="" type="checkbox"/>	Line

Callouts:

- Hold down the CTRL key, and the select all the sheets that have the just imported data.
- Select Scatter from the Plot Type drop-down list.
- Set col(A) as X, Col(D) as Y.
- Click the Add button after setting the X and Ys to add these Plots into the bottom panel.

Buttons: OK, Cancel, Apply




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.


Please refer to [Plotting using Plot Setup](#) for more information.

5.

In bottom panel, if there is a **Group** branch under **Layer1**, right-click on it to select **Ungroup** from the short-cut menu to ungroup these plots.




Click **OK** to generate the graph which look like the following image shows.




6. Double-click the layer icon at the top-left corner of graph window to open the **Layer Contents** dialog. Then group the **Theory** plots and **NormData** Plots as Group 1 and Group 2 using the **Group** button after highlight the 4 Theory/Norma Data plots separately by using mouse and the


Shift key,





7. Then we will customize the 8 plots in the Plot Details dialog. Select **Format: Plot Properties** to open the Plot Details dialog. In the left panel of the dialog, you could see there are 8 plots: the first 4 plots are line plots, the other 4 are scatter plots.
8. We will first customize the 4 line plots. Open **Plot Details** by double clicking the plot. On the left panel, 4 line plots are put ahead of the 4 scatter plots. You can select the first line plot by selecting the first plot under *Layer 1* in this panel then go to **Line** tab. Select **B-Spline** from the **Connect** drop down list and set the **Width** to **3**. Then click the **Apply** button. In the **Group** tab, click the button that next to the **Line Color** as the screenshot shows to change the color of the 4

lines to **Black**. Click OK to apply these settings.




- Then customize the 4 scatter plots. Go to **Plot Detail** and then select the fifth plot in the left panel, which should be the first scatter plot. Go to **Symbol** tab, change the **Size** to 8. In the **Group** tab, we will mainly customize the symbols in the list box that in the middle of the tab. In the **Symbol Type** row, select **By one** in the **Increment** column. Click the  button to open the **Increment Editor** dialog, in the dialog select **UpTriangle, Circle, Hexagon** and **Square** for the first 4 rows.

In the **Symbol Edge Color** row, select **By one** in the **Increment** column. Click the  button to open the **Increment Editor** dialog, in the dialog select **Green, Blue, Blue** and **Red** for the first 4 rows.


In the **Symbol Interior** row, select **By one** in the **Increment** column. Click the  button to open the **Increment Editor** dialog, in the dialog select **Solid, Solid, Half Left** and **Solid** for the first 4

rows. Click OK button to close the Plot Details dialog, then the graph will look like.




10. Then customize the Axes of the graph. Double click on the X axis to enter Axis Dialog.

First, we customize the axes scale. Go to **Horizontal** icon in **Scale** tab, change **From** to -5, **To** to 690; set **Major Ticks** Type as **By Increment** and **Value** as 100, respectively. Repeat these steps to customize the Y axis range (the **Vertical** icon) as **From** to 0.61 and **To** to 1.01, and **Value** as 0.05.



To customize the Axis Ticks, select **Top** icon in **Line and Ticks** tab, enable the **Show** check box, then go to **Top** icon in **Line and Ticks** tab, select **In** from both *Major Ticks* and *Minor Ticks* drop-

down lists. Repeat the same steps for Right Axis under **Right** icon.



11. Then you will will customize the titles and the legend. Change the titles follows the images shows.

Right click on the legend and select **Properties** from the context menu, and input the following strings into it.


$\backslash(5) 1.7 \text{ \g(m)J/pulse}$

$\backslash(6) 3 \text{ \g(m)J/pulse}$

$\backslash(7) 3.5 \text{ \g(m)J/pulse}$

$\backslash(8) 4.5 \text{ \g(m)J/pulse}$


The final graph will look like



6.6.6 Micro-Raman spectroscopy of complex nanostructured mineral systems


6.6.6.1 Summary

This tutorial will show you how to create a multiple line plot and how to customize it.




Minimum Origin Version Required: Origin 2015 SR0

6.6.6.2 Steps


1. Create a new worksheet. Click the **Import Single ASCII** button  and import the **Micro_Raman_Spectroscopy.txt** file under *<Origin EXE Folder>\Samples\Graphing* path.

	A(X)	B(Y)	C1(Y)	C2(Y)	C3(Y)	C4(Y)	C5(Y)	C6
Long Name								
Units								
1	100.263	762.24	100.263	947.9676	100.263	9966.063	100.263	10919
2	101.997	765.94	101.997	951.6754	101.997	9940.0309	101.997	10928
3	103.728	771.5	103.728	944.2353	103.728	9954.8876	103.728	10917
4	105.461	765.92	105.461	957.2229	105.461	9936.3143	105.461	10929
5	107.194	769.61	107.194	936.8001	107.194	9951.1572	107.194	10919
6	108.927	767.74	108.927	944.2147	108.927	9956.7125	108.927	10929
7	110.657	767.73	110.657	959.035	110.657	9943.7279	110.657	10932
8	112.389	784.39	112.389	955.3154	112.389	9969.6578	112.389	10927
9	114.121	760.3	114.121	955.3027	114.121	9945.5715	114.121	10929
10	115.85	762.14	115.85	951.589	115.85	9952.9684	115.85	10932
11	117.581	765.83	117.581	940.4814	117.581	9945.5616	117.581	10928
12	119.312	773.21	119.312	947.8704	119.312	9928.9203	119.312	10936
13	121.041	763.95	121.041	962.6417	121.041	9952.9419	121.041	1097
14	122.771	767.63	122.771	934.9271	122.771	9945.5469	122.771	10927
15	124.501	771.31	124.501	942.3073	124.501	9951.0786	124.501	10927
16	126.228	784.21	126.228	938.6123	126.228	9947.3817	126.228	10927
17	127.957	765.75	127.957	945.9827	127.957	9938.1579	127.957	10927
18	129.686	774.95	129.686	955.1878	129.686	9963.9533	129.686	10928
19	131.413	762.04	131.413	947.8086	131.413	9945.5224	131.413	10930


- Highlight all the columns in the worksheet. Right-click and select **Set As: XY XY** from the context menu. Then click the **Line** button on the **2D Graphs** toolbar.




Delete the legend. The graph should look like this:




3. Double-click on the **X** axis to bring up the **Axis** dialog box. In the **Scale** tab, set the options as the screenshots below.



4. Click the **Vertical** icon on the left panel to go to the **Scale** tab of **Y Axis** and then set the options as in the screenshots below and Click **OK**.



5. Now, we will apply a Graph Theme to add a top X axis and a right Y axis. Select **Tool: Theme Organizer** to open the **Theme Organizer** dialog. Activate the **Graph** tab and select **Opposite Lines** from the table. Then click **Apply Now**. Click **Close** to close the dialog.




6. Click the **Line** button on the **Tools** toolbar and draw a line across the peaks' centers as the sample image shows. Hold down the **SHIFT** key while drawing the line to force it to snap to the vertical. Double-click on the line. In the **Line** tab, select **Dash** with the **Type** drop-down list. Click **OK**.




7. Click the **Text** button in the **Tools** toolbar. Add a text object near the line object and enter **461** into the text object.




Right-click on the text object and select **Properties** from the shortcut menu. In the **Text** of the dialog, set the options as in the screenshot below. Click **OK**.




8. Right-click on the title of the Y axis and select **Properties** from the short-cut menu. In the **Text** of the dialog, enter *Raman intensity/arb.units* in the edit box, highlight it, click the **Bold** button, and change size to **28**. Click **OK**.



- Right-click on X axis title and select **Properties** from the shortcut menu. In the **Text** of the dialog, enter **Wavenumber/cm-1** in the edit box, highlight it, click the **Bold** button, and change size to **28**. Highlight **-1** click **SuprtScript** button. Click **OK**.




The graph should look like this:



6.6.7 Multi-line-plot with Special Position Annotation Line

6.6.7.1 Summary

This tutorial will show you how to create a multi-line-plot with special position annotation line.




Minimum Origin Version Required: Origin 2015 SR0


6.6.7.2 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Line and Symbol**)

1. Open **Tutorial Data.opj** and browse to the **Multi-line-plot with Special Position Annotation Line** folder in **Project Explorer** (PE).
2. Active to the worksheet in workbook **Multi-line-plot with Special Position Annotation Line**. To plot a multiple line plot, highlight all the columns in the worksheet, and click the **Line**  button


on the **2D Graphs** toolbar. Delete the legend object from graph.




3. Double click the axis to open the axis dialog, set the axis scale and ticks via dialog:
 - o Go to the **Line and Ticks** tab and set the ticks:




- Go to the **Scale** tab in same dialog, set the scale for X and Y axis:
For X (**Horizontal**): From 74505 to 74575;
For Y (**Vertical**): From -2500 to 45000;
4. Go to the **Ticks Labels** tab and change the display format for **Left** into **Scientific: 10³**, then, go to the **Grids** tab with **Horizontal** icon selected, check **Show** for **Major Grid Lines**, click **OK** to close the dialog.




5. Select the **View: Show: Frame** in main menu to added a line frame on the graph. The graph is similar to this now:




6. Double click the plot line to open the **Plot Details** dialog, in **Group** tab, open the **Increment Editor** as shown in graph, designate color for each line, then click **OK** to close two dialog.



- Then, you will add vertical line on Graph, select **Graph: Add Straight Line** in main menu to open the dialog, set the X coordinates in the dialog, and set color: **red**, click **OK** to apply the settings.



- A straight line with text was added on the graph. Edit the Text object above the line object by double click it, the x^2 and x_2 in **Format** toolbar is helpful when creating superscripts and subscripts. Entering the content as shown in graph below:



Then, click somewhere outside the text box to quit the text editing, drag to move the text to a proper position.

Now, the text object get the X coordinates of the line, when you drag to move the line object horizontal, the text also updates simultaneously.

9. Add explanatory strings for line plot, add a title on the graph by using Text Tool as well.



There are 2 ways to edit text labels:

- In-place Text Editing: Double-clicking puts you in WYSIWYG edit mode. Using the **Style** and **Format** toolbars makes it easy to add formatting to any text. For special characters, the **Symbol Map** can be used.

The **Symbol Map** can only be opened while in In-place edit mode. To enter In-place edit mode, double-click on the text label. Then, open the Symbol Map by pressing CTRL+M. Or right-click inside the text label and select Symbol Map.

- Text Control dialog box (from previous versions of Origin): Hold

down the CTRL key when double-clicking text. Highlight any portion of the text and apply the desired style, Greek font, etc.


You can also right-click on a text label and select Properties to open this dialog.

10. The finished graph is similar to the graph in [Summary Section](#) in this tutorial.

6.6.8 Scatter Central Plot

6.6.8.1 Summary

A scatter central plot is a graph with the X and Y axes located in the middle of the layer. In this tutorial, a scatter central plot will be created, then the symbol and the axes will be customized.




Minimum Origin Version Required: Origin 2015 SR0

6.6.8.2 What you will learn


- Set column values using **Set Values** dialog box
- Create a scatter central plot
- Change the color and shape of the scatter points
- Customize axis tick labels

6.6.8.3 Steps


1. Start with an empty worksheet with two columns. We are going to fill a worksheet column with values using the **Set Values** dialog box.
2. Highlight column A, right-click and select **Fill Column with: Row Numbers** from the shortcut menu. Right-click column A again and select **Set Column Values** to open the **Set Values** dialog box. Type **Col(a) - 11** in the text box, then click **Apply** to finish setting values for column A.




3. Click the **>>** button to select column B in the **Set Values** dialog box. Type **Col(a)^2 + Col(a) + 1** in the text box this time. Then click **OK** to set values for column B.




4. Highlight column B and select **Plot: Symbol: Scatter Central** from the Origin main menu. This creates a scatter central plot.




5. We will change the color and shape of the scatter points. Double-click on the scatter plot to open the **Plot Details** dialog, expand **Layer1** node on the left panel and highlight its sub-node. In the **Symbol** tab of right panel, click the down-sided triangle button beside **Preview** and choose the solid circle symbol. Click the button beside **Symbol Color** and choose **Individual Color: Red**. Click **OK** to close **Plot Details**.




6. Now we will customize the axes. Double click on the Y axis to open the **Axis** dialog box. On the **Scale** tab for **Y Axis**, change the **To** value to **450**.
7. Click **Special Ticks** tab, enter **200** in **At Axis Value** column right below **Axis End** and uncheck its correspond box in **Show** column to hide the special tick as displayed in following:




8. Click the **Bottom** icon on the left panel and click to highlight the **Axis End** row, then choose **Hide** from the drop-down list in **Show** column.
9. Click **OK** to finish axes settings. The scatter central plot looks like the following.



10. Now, delete the legend and change the labels of axes **A** to **X** and **B** to **Y** and make the text bold.
11. Right click on the X axis label and select **Properties** shortcut menu and choose **0** from **Rotate(deg.)** drop-down list, and click **OK**. Move the **X** to the end of X axis. Add a text object $Y = X^2 + X + 1$ and customize it as $Y = X^2 + X + 1$ through the following steps:




12. The final graph looks like the following:



6.6.9 Line Graph with Masked Data

6.6.9.1 Summary

You can masking subranges of data graphically. In this tutorial, a line graph is created first, then the masking tool is used to mask the low peaks on the graph.





Minimum Origin Version Required: Origin 2015 SR0

6.6.9.2 What you will learn


- Plot a line graph
- Set the scales of axes
- Mask data on the line graph

6.6.9.3 Steps


1. Create a new workbook, click the **Import Single ASCII**  button to import the file **Line_Graph_with_Masked_Data.txt** under *<Origin EXE Folder>\Samples\Graphing* path.
2. Highlight both columns in the worksheet and select **Plot: Line: Line** from the Origin main menu to plot a line graph.




3. Double click on the X axis to open the **Axis** dialog box. Set the increment value to 0.25 as in the image below:




4. Click the **Vertical** icon on the left panel to set the Y axis scale as in the following image:




5. Click **OK** to close the Axis dialog and delete the graph legend. Change the X label to **Time[s]** and the Y label to **Signal[A.U.]**, and bold both text labels and set the font size as **28**. Create a title by adding a text object that says **Time Series**. Bold the title and set the font size of the title to **36**.



6. Activate this graph, then click and hold the **Regional Mask Tool** button on the Tools toolbar until a menu appears. Select **Mask Points on Active Plot** to enter masking mode.




7. Click an appropriate place on the graph and drag out a rectangle to select the low peaks and, at the same time, mask them. Drag out additional rectangles until all low peaks are masked. Then click the **Pointer** button on the Tool toolbar to exit masking mode.



6.6.10 Symbol Plot with Color Transparency

6.6.10.1 Summary

This tutorial will show you how to create a symbol plot with color transparency, categorical legend and bubble scale. This graph displays a symbol plot of XY data where the size of the symbol and its color have been mapped to two other data columns in the worksheet: Mass and Type. The categorical legend can be utilized to identify Type via color and the bubble scale can be used to check Mass via symbol size. Color transparency has been applied to the plot so that overlapping data points are visible.



Minimum Origin Version Required: Origin 2015 SR0

6.6.10.2 What you will learn

This tutorial will show you how to:

- How to control the size and color of plot symbols using values in worksheet columns.
- How to add a legend from categorical values
- How to add a bubble scale and customize it
- How to set the transparency to the symbol plot
- How to add a frame to the graph

6.6.10.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Line and Symbol**)


1. Open **Tutorial Data.opj** and browse to the **Bubble with Transparency** folder in **Project Explorer (PE)**.

Tutorials for Origin


- Go to **Book2G**, highlight Col(A)~Col(C) in the worksheet and select **Plot: Symbol: Bubble** from the main menu.
- Select **Format: Plot Properties...** in the main menu to open the **Plot Details** dialog. Then go to the **Symbol** tab and set the symbol format as in the following:
 - Set **Scaling Factor** to **3**.
 - Click the down arrow next to the **Preview box** to open the symbol gallery and select the filled circle symbol.
 - In the **Symbol Color** drop-down list, select **Indexing: Col("Type")**.
 - Set **Transparency** to **50%**.




4. Click **OK** to save settings and close the dialog. The graph should now look like this:




5. To update the axes scales and title, select **Format: Axes: X Axis...** to open the **Axis** dialog box. Modify the following settings:
- In the **Scale** tab for **X Axis**, choose the following setting:




- Click **Vertical** icon on the left panel and go to **Scale** tab for **Y Axis** and set the following:



- Go to **Title** tab, and change Y axis title as *Sample Y-Dimension (cm)* and set font and size as following:




- Then click **Bottom** icon on the left panel and change X axis title as *Sample X-Dimension (cm)* and set and size as following:



- Click **OK** to apply the settings.
6. Double click on the bubble scale to bring up **Bubble Scale Control** dialog. Select **Nested** from **Layout** drop-down list and check **Half Circle** and **Show Leader Line** boxes and click **Apply** as


shown in following:




- Click on the left panel to go to **Levels** page, set **From** as **20** and **To** as **50** and change increment **Value** to **10** as shown in following:

The screenshot shows a dialog box titled "Bubble Scale Control - Layer 1". On the left, there is a vertical menu with four items: "Levels" (highlighted in blue), "Labels", "Layout", and "Title". The main area of the dialog is divided into two sections. The top section contains two input fields: "From" with the value "20" and "To" with the value "50". The bottom section is titled "Levels" and contains a "Type" dropdown menu set to "By Increment", a "Value" input field with the value "10", and a "First Level" input field which is currently empty. At the bottom right of the dialog, there are three buttons: "OK", "Cancel", and "Apply".


8. Click **Title** on the left panel, check **Show** box and change content in **Title** to be *Mass*, then set the **Size** to be **28** and check **Bold** box. Click **OK** to close dialog as shown in following:




9. The graph is as following now:




10. Go to **Graph:Legend:Categorical Values...** to bring up **Graph Manipulation:legendcat** dialog. Uncheck **Size** box and click **OK** to close the dialog and move the generated legend to a proper position in top-left corner.




11. Right click on the legend and select **Properties** from shortcut menu, customize the text as shown in the following:



12. Click **OK** to close dialog.
13. Select the **Text Tool**  button on the **Tools** toolbar and click once to the left side of the page just above the frame. Type the following into the text object: *Agate Cross-Section by Type and Location*. Customize the font. Select and re-position the text object as needed.

The final graph should look something like this:




6.6.11 Symbol Plot with Size and Colormap from Other Columns

6.6.11.1 Summary

This tutorial will show you how to create a symbol plot with size and color from other columns.

This graph displays a symbol plot of data from multiple columns where the size and color of the symbol have been derived from other data columns in the worksheets. User defined Colormap has been applied to the plot.



Minimum Origin Version Required: 2016 SR0

6.6.11.2 What you will learn


This tutorial will show you how to:


- How to control the size and color of plot symbols using values in worksheet columns.
- How to set the user defined colormap
- How to edit the grids lines for plot

6.6.11.3 Steps to Construct a Symbol Plot with Size and Colormap from Other Columns

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data project and browse to folder *Symbol Plot with Size and Color Mapping* in **Project Explorer**.

2. Select the Col(X) and Col(Y) in first sheet of the workbook and click **Plot: Symbol: Scatter** to get a scatter plot.
3. Click **Graph: Layer Contents** in main menu with the graph active, and select all the columns with Long name Y, Y1, Y2 and add them into the right panel. Click **Ungroup** button to ungroup all datasets. Click **OK** to close dialog. The order and quantity of column Long name listed in right panel should be exactly the same as the graph, use up and down button to adjust the position, and use  to remove the repetitive items.




4. Double click the scatter to open the Plot Details dialog, go to **Symbol** tab, Set the Symbol for each plot one by one follows the Graph below, after each step setting, please click **Apply** to make a rudimentary saving.


- The next 7 steps will guide you finish the symbol setting for each dataplot. Symbol setting for dataplot 1:




6. Symbol setting for dataplot 2




7. Symbol setting for dataplot 3




8. Symbol setting for dataplot 4




Add label for dataplot 4




9. Symbol setting for dataplot 5




Add label for dataplot 5




10. Symbol setting for dataplot 6 and 7, which act as the legend:






- Then, Click **OK** to close the window. Double click the Axis X to open the Axis dialog, and set the Scale for both **Horizontal** and **Vertical** icons From -50 to 50 with same Major and Minor ticks style:




then click **OK** to apply. you can get a graph like this:




6.6.11.4 Steps to Set the Colormap and Legend

1. The Edge color of the post-Electrical Open and pre-Electrical Open plot both used Map:Col(C), so we will further make some style setting for Color scale in **Colormap** tab. Click **Level** to open **Set Levels** dialog, set levels from 0 to 155 with Major Levels 5.




2. Double click each Level value to edit them and double click each Fill color to edit them as well :




Click Apply to apply these color setting to the graph (for the post-Electrical Open scatter).

3. Then we would like to save the setting as a theme named as mycolor.oth. The theme will be applied to the post-Electrical Open scatter.

Tutorials for Origin




Apply the theme to the pre-Electrical Open scatter.



Click OK to close the window.

4. Click **Graph: Legend: Dataplot** in main menu, a legend will display in the graph. Right click the legend and click **Properties** in list, and edit the content in Object Properties dialog as follows


graph, then click OK.




5. Click **Graph: New Color Scale** in main menu, an Color Scale will display in the graph.

6.6.11.5 More Customization Steps


1. Select **Format: Layer Properties** in main menu to open the **Plot Details** dialog, go to the **Size/Speed** tab, edit the Layer Area as follows:



2. Go to the **Display** tab in **Plot Details** dialog, edit the **Clipping Margins(%)** to -2%, click OK to close dialog.




- Copy the previous Legend and paste it on the graph, edit the new legend in this way:




click OK to close dialog.

- Double click the color scale to open the **Color Scale Control**, go to the **Levels** page, check on **Hide Head and Tail Levels**, then go to the **Labels** page and set the **Display** as graph below:



Add a title *Elapsed Time* for the color scale in **Title** tab, Click OK to apply.

- Double click the axis to open the **Axis** dialog. Set Grids line for both Horizontal and Vertical in **Grids** tab in the same style as shown in graph below:



Click OK to apply the setting and close dialog.

- At last, add a Text "*symbol size is relative to event energy*" in the graph by using **Text Tool** **T** in **Tools** box.

6.7 Column, Bar and Pie


- [2D Pie Chart of a Population Study](#)
- [Bar Graph of African Population](#)
- [Bar and Scatter Plot with Error Bar](#)
- [Column Graph with Error Bars](#)
- [Column/Bar Gap/Offset Across Layers](#)
- [Stack Column With Labels](#)
- [Clustered-Stacked Column Chart](#)

- [Grouped Column with Error Bars and Data Labels](#)
- [Grouped Stacked Column](#)
- [Stack Column Plot with Different Positive and Negative Y Scale](#)
- [Variable Column Width](#)
- [Stack Column and Bar Charts of Rechargeable Battery Statistics](#)

6.7.1 2D Pie Chart of a Population Study

6.7.1.1 Summary

Pie charts created by the default template has a 3D view. However, you can easily convert it to a 2D chart. In addition, you can set the size and rotation of the chart to further customize it. This tutorial will show you how to create and customize a **2D Pie** chart.



Minimum Origin Version Required: Origin 8.5.1 SR0

6.7.1.2 What will you learn

This tutorial will show you how to

- Create a 2D Pie chart


- Customize the Pie chart

6.7.1.3 Steps


1. Create a new worksheet. Import the sample data (See the sample data [here](#)).

	A(X)	B(Y)	C(Y)
Long Name			
Units			
1	Hispanic	45.4	1
2	White	35.7	18
3	African American	9.3	19
4	American Indian	0.4	20
5	Asian/Pacific	8.9	24
6	Other	0.3	18
7			
8			
9			


2. Highlight column **B** and select the **Pie Chart** button on the **2D Graphs** toolbar.




The graph should look like this:



- Now we further customize the chart. Right-click on it and select **Plot Details** from the shortcut menu to open the **Plot Details** dialog. In the **Pie Geometry** tab, set the options as the screenshot below.




4. In the **Labels** tab, set the dialog as the screenshot below.




Click **OK** to close the **Plot Details** Dialog. Rearrange the text label of each pie wedge.

5. Right click on the **Legend** and select **Delete** from the short-cut menu.
6. Select the **Text** button from the **Tools** toolbar. Then click near the top of the layer. Enter **Population by Major Ethnic Groups** to add a title for the graph. Then you can use the tools in the **Format** toolbar to customize the text. The graph should look like:



6.7.1.4 Sample Data

Download the **2D_Pie_Chart.txt** file from http://www.originlab.com/ftp/graph_gallery/data/2D_Pie_Chart.txt. Click the **Import Single ASCII**

button . Select the file to import it into Origin.


The following table contains part of the sample data.

A(X)	B(Y)	C(Y)
Hispanic	45.4	1
White	35.7	18
African American	9.3	19
American Indian	0.4	20
Asian/Pacific	8.9	24
Other	0.3	18

6.7.2 Bar Graph of African Population

6.7.2.1 Summary

In this tutorial, we will create a graph to compare African population distributions for 2010 vs. predictions for 2050.



Minimum Origin Version Required: Origin 2015 SR0

6.7.2.2 What you will learn

Tutorials for Origin

This tutorial will show you how to:


- Duplicate graph with data in other columns
- Set axis scale to reverse a bar chart
- Merge graphs

6.7.2.3 Steps

To create this graph, we must create four separate bar plots, customize them and merge them into one graph.


Prepare Source Bar Plots with Batch Plotting

1. Start with an empty Origin workbook, import the data file **African_Population.dat** under *<Origin EXE Folder>\Samples\Graphing* path. (Or if you do not have the file in your Origin installation, download the zipped data file from [ftp](#).)




	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	Age Group	Population	Population	Population	Population
Units		million	million	million	million
Comments		male-2010	female-2010	male-2050	female-2050
F(x)=					
Sparklines					
1	0-4	15.4267	15.0117	9.27	9.02679
2	5-9	13.4204	13.08944	9.238	9.02129
3	10-14	11.92	11.64616	9.15	8.9538
4	15-19	10.736	10.52617	8.93	8.76722
5	20-24	9.646	9.5354	8.61	8.50235
6	25-29	8.6265	8.21996	8.266	8.19188
7	30-34	6.82	6.76084	7.877	7.79863
8	35-39	5.45	5.41933	7.345	7.25389
9	40-44	4.388	4.45714	6.598	6.50407
10	45-49	3.62	3.77074	5.69	5.62547
11	50-54	2.98	3.17473	4.852	4.84986
12	55-59	2.386	2.58509	4.15	4.21943
13	60-64	1.835	2.0281	3.49	3.62979
14	65-69	1.316	1.51224	2.68	2.88718
15	70-74	0.901	1.09101	1.86	2.09807
16	75-79	0.535	0.67829	1.12	1.37265
17	80-84	0.246	0.34107	0.56	0.79171
18	85+	0.09	0.15258	0.27	0.50594
19					
20					
21					


2. Highlight column B and select **Plot:Column/Bar/Pie:Bar** to plot a bar graph.
3. Now we are going to duplicate similar graphs from the other three columns. Right click on the graph window title bar and select **Duplicate (Batch Plotting):Duplicate with New Columns** from the context menu:



4. In the **Select Column** dialog that opens, hold **Ctrl** key and click to select all three columns C, D, E and click **OK**:




5. Three similar graphs will be created (When you get a **Reminder Message** asking *Would you like to rescale the axes to show all the data*, select **Yes** and click **OK**).
6. We now have four bar graphs of four groups: male-2010, female-2010, male-2050, female-2050.




Customize Bar Plots

We will now individually customize the four bar plots.


1. First we will customize **Graph1** (i.e. the one with legend showing *male-2010*).
2. Double-click on the data plot to open the **Plot Details** dialog box. Expand **Layer1** node on the left panel and highlight its subnode, on the **Pattern** tab on right panel, change the **Color of Fill** to **Blue**. Click **OK** to apply the color setting and close the dialog.
3. Double click on the Y axis (the horizontal axis in bar plot) to open the **Axis** Dialog. On the **Scale** tab for **Y Axis**, set **From = 17**, **To = 0**, **Value of major tick increment = -5**:




4. Click the **Vertical** icon on the left panel and go to **Grids** tab of X Axis and clear the **Show** check box under the **Minor Grid Lines** branch, to hide the minor grid lines. Click **Apply**:




5. Go to the **Line and Ticks** tab and set **Style** under **Minor Ticks** to **None**:




- Now we will hide minor grid lines and minor ticks for all other graphs. Click the **Apply to...** button to bring up **Apply To** dialog and select the check box beside **Ticks** and **Grid Lines**. In the drop-down menus for both, select **All Windows in Folder** and click **OK** to apply settings. Now, minor grid lines and ticks in all graph windows in the same folder of **Project Explorer** will be hidden:




7. Next we will customize the Y axis scales for **Graph2**(female-2010) and **Graph3**(male-2050). Open the **Axis** Dialog for each graph and set the axis scales following the screenshots below:






8. Double-click on X axis of **Graph4** to open the **Axis** dialog to set the X-axis scale following the screenshot below:




9. Double-click on the data plot of **Graph3** (male-2050) and open the **Plot Details** Dialog. Expand **Layer1** node to highlight its subnode, click the **Pattern** tab on right panel, set the **Color** for **Fill** to **Blue**.
10. For **Graph2**(female-2010) and **Graph4** (female-2050), select the tick label for X axis (vertical axis) and press the **Delete** key to remove them. Similarly, remove the axis titles for both X and Y axes. Now you should have four customized bar plots like those below:



Merge Multiple Graphs

Now we have four distinct bar graphs. We will merge these four graphs and do some final customizations, such as adding text annotations.

1. Activate one of the four graph windows and select **Graph: Merge Graph Windows** from the main menu. This opens the **merge_graph** dialog box. Edit the settings as follows and merge these four bar graphs into one graph window.




2. In the merged graph, drag the two Y (horizontal) axis titles "Population (million)" to center align them. Sequentially select and delete the four graph legends.
3. Right click on an open space in the graph layer and select "Add Text". Type to create the four text labels. The text labels used are:

- *Figure 1. African population by five – year age groups and sex, 2010 versus 2050*
- *2010*
- *Males*
N=515,267
- *Females*
N=517,776
- *2050*
- *Males*
N=998,354
- *Females*
N=1,000,112

- Source: Population Division of the Department of Economic and Social Affairs of the United Nations Secretariat, World Population Prospects: The 2008 Revision, <http://www.un.org/en/index.html>, Monday, April 12, 2010; 3:19:17 PM.


You may further customize the position, text font, size, color and alignment of the newly added labels. Your final graph should look much like the the graph pictured below.



6.7.3 Bar and Scatter Plot with Error Bar

6.7.3.1 Summary

Below graph is made of bar chart and scatter plot.



Minimum Origin Version Required: Origin 8.0 SR0

6.7.3.2 What will you learn


- How to add a scatter plot to a bar graph
- How to set the Plus and Minus error bar

6.7.3.3 Steps


This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the Tutorial Data project and browse to folder *Bar Plot with Errors* in **Project Explorer**.


2. Activate the workbook **Book2N**, right-click the col(C) to select **Set as: Y Error** from the context menu.
3. Highlight Col(A), col(B) and col(C), select **Plot: Column/Bar/Pie: Column** from the main menu to plot a column graph with Y error bar.




4. Activate the graph window, and then select **Graph: Exchange X-Y Axes**.




- Highlight the col(D) in the worksheet and then activate the graph window again. Select **Graph: Add Plot to Layer: Scatter** from the main menu to add the col(D) as scatter to the column graph.




- Double-click the column graph to open the Plot Details dialog. Set the **Color** and **Pattern** options in the **Fill** group of **Pattern** Tab as below.




- Select the scatter plot in the left panel, then set the Symbol as below. Then click **OK** button to close the dialog.



8. Activate the graph window, hold the **Ctrl** key and select the first bar to set its pattern as **Dense** as below from the **Style** toolbar.




9. Select **Graph: Legend: Reconstruct Legend** from the main menu to update the legend for graph.
10. Right-click the legend to select **Properties** from the context menu to open the **Objects Properties** dialog. Set **Background** as **Black Line**. Then edit and move the legend as below.



6.7.4 Column Graph with Error Bars

6.7.4.1 Summary

This customized graph shows an example of a bar graph with added error bars. The same Y data is plotted twice, once as a scatter plot and again as a column plot. The error bars are attached to the scatter plot in this case. Error bars can be included in the graph in both the Y and X dimensions.



Minimum Origin Version Required: 2015 SR0

6.7.4.2 What you will learn


- Create and customize a column graph
- Use the Plot Setup dialog to add a new data plot to your graph



6.7.4.3 Steps

This tutorial is associated with the Tutorial Data project: `\Samples\Tutorial Data.opj`. (If you don't have the Project file, please download the data file from [here](#))

1. Go to **File:Open Sample Projects:Tutorial Data** to open the Project file and browse to the folder *Column Graph with Error Bars*. Activate the worksheet and make sure the column plot designations are set as **X**, **Y**, **Y Error** and **Label** accordingly.
2. Highlight column 2 and select **Plot: Column/Bar/Pie: Column** to create a column graph.
3. With the graph window active, select **Graph: Plot Setup...** to bring up the **Plot Setup** dialog box. Click the up-sided double triangle arrow icon to expand top two panels and we will add the scatter


data and error bars from this dialog box, as shown below:




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.


- Click the **Add** button to add scatter data to the column plot. Then click **OK** to go back to column graph window.
- Double-click the columns to bring up the **Plot Details** dialog box. Customize the graph using settings on the **Pattern** tab as shown below:




6. Double-click on the Y axis to open the **Axis** dialog box. Set the Y axis scale as shown in the screenshot below:



7. Then go to the **Tick Labels** tab to set X axis tick labels as shown in following screenshot:



8. Go to the **Grids** tab and click the **Horizontal** icon on the left panel to customize grids for **Y Axis** and turn on major grid lines by duplicating the settings in the image below:




9. Click **Apply** first, and then hold Ctrl key to select both **Vertical** and **Horizontal** icons on the left panel and select the **Opposite** checkbox to turn on opposite additional lines for both X and Y axes.
10. Click **OK** to apply settings and close the **Axis** dialog box. Finally, delete the legend object.

6.7.5 Column/Bar Gap/Offset Across Layers

6.7.5.1 Summary

This tutorial will show you how to create a multiple-layer column graph with gap across layers.



Minimum Origin Version Required: Origin 8.5.1 SR0

6.7.5.2 What will you learn

This tutorial will show you how to

- Create double-Y column graph
- Add gap for the column plots in different layers

6.7.5.3 Steps

1. Copy and paste the sample data below to a new Origin worksheet.


Site	potassium	phosphorus
--	mg/kg	mg/kg
1	38.22409	6.25809

2	12.83141	6.56709
3	21.27226	5.32531
4	86.46412	7.74898
5	42.91068	9.90374
6	48.95083	1.63804
7	96.68733	4.5168


- Set the first row as **Long Name** and the second row as **Units**.

	A(X)	B(Y)	C(Y)
Comments			
Long Name	Site	potassium	phosphoru
Units	--	mg/kg	mg/kg
1	1	38.22409	6.25809
2	2	12.83141	6.56709
3	3	21.27226	5.32531
4	4	86.46412	7.74898
5	5	42.91068	9.90374
6	6	48.95083	1.63804
7	7	96.68733	4.5168
8			
9			


- Plot a double-Y graph: Highlight all columns. In Origin's main menu, click **Plot**, point to **Multi-Y**, and then click **Double-Y**. Alternatively, you can simply click the Double-Y button on the 2D Graphs toolbar.



4. Double-click the graph to open the Plot Details dialog. In this dialog's left menu, select a plot (as below) and change the plot type to **Column/Bar**. Do this for both plots.





5. In the Plot Details dialog's left menu, select the top level (Graph2 in the example below). On the **Miscellaneous** tab, select the **Column/Bar Gap/Offset Across Layers** check box.



Note: When the **Column/Bar Gap/Offset Across Layers** check box is selected, you can customize the gap between bars by modifying the **Gap Between Bars (in %)** on the **Spacing** tab of the **Plot Details** dialog of the data plot in Layer 1; the corresponding controls in Layer 2 will grey out.


Note: To enable the **Column/Bar Gap/Offset Across Layers** check box, all the layers in the plot should be linked to Layer 1.

6. In the left panel, select the first plot and apply the following styles to the columns as shown below. Do the same for the second plot, using the second image as a reference.



7. Click OK to close the dialog. Your final graph should look like this:


1 2



6.7.6 Stack Column With Labels

6.7.6.1 Summary

This graph displays a stack column plot. Each data point in each column has been labelled using the associated data value, and custom formatting applied to column fills and labels.



Minimum Origin Version Required: 2015 SR0

6.7.6.2 What will you learn

This tutorial will show you how to


- Create a stack column plot
- Add labels for columns
- Customize the column graph

6.7.6.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open **Tutorial Data.opj** and browse to the **Stack Column With Labels** folder in **Project Explorer** (PE).


2. Activate the worksheet and select columns B through E. In the main menu, click **Plot**, then point to **Column/Bar/Pie** and click **Stacked Column**. Alternatively, you can click the **Stacked Column** button on the 2D Graph toolbar.




3. Double-click the X axis tick labels to open the **Axis** dialog box. Go to **Tick Labels** tab and set the X axis tick labels as following:




4. Select the **Grids** tab and hold Ctrl key to select **Horizontal** icon in left panel to simultaneously apply changes to the **Y Axis**. , Check the **Opposite** box to add lines opposite both the X and Y axes:



5. Go to the **Scale** tab and click **Vertical** icon on the left panel to set the value of **To** to **102** for Y axis and click **OK** to apply settings and close the Axis dialog box.
6. Double-click the plot to open the **Plot Details** dialog box. On the **Group** tab, set the **Fill Color** as shown below:




7. On the **Label** tab, select **Enable**. Set the **Font**, **Color**, and **Size** to **Verdana**, **white**, and **18**. Set **Label Form** to **Custom** and enter "\$((y),.0%)" for the **Format String**.




8. On the **Spacing** tab, set **Gap Between Bars(in %)** to 30.



9. On the **Pattern** tab, set **Gradient Fill** as shown below:



10. In the left panel, select **Layer1**. On the **Background** tab, set **Color** and **Gradient Fill** as shown below:




11. Click **OK** to close the dialog box. To complete the graph, change the X and Y axis labels to "Year" and "Population (%)", then add the graph title "U.S. Population by Race."

6.7.7 Clustered-Stacked Column Chart

6.7.7.1 Summary

This tutorial will show you how to create a clustered-stacked column chart in Origin. This graph consists of two graph layers, each of which has a stacked column.



Minimum Origin Version Required: Origin 8.5.1 SR0

6.7.7.2 What will you learn

This tutorial will show you how to

- Create a stacked column graph.
- Create a graph that has two stacked column graphs.
- Customize a column chart.


6.7.7.3 Steps



1. Import the sample data [Data 1](#) and [Data 2](#) into different worksheets in Origin. Set the first line as Long Name for them and set the sheet names as 2010 and 2011 respectively.

	A(X)	B(Y)	C(Y)	D(Y)
Long Name		Product A	Product B	Product C
Units				
Comments				
1	Jan	42	33	40
2	Feb	88	85	37
3	Mar	99	34	82
4	Apr	51	43	38
5	May	21	66	52
6	Jun	74	31	28
7				

2. Create a new graph layer by selecting **File : New : Graph** from the main menu. And then select **Graph: New Layer: No Axes(Link XY Scale and Dimension)** from the main menu to add another layer to the graph window you just created.
3. Right-click on the graph to select **Plot Setup...** from the context menu to open the **Plot Setup** dialog. In this dialog, select **Stacked Column/Bar** in the **Plot Type** box, select worksheet *2010* and *2011* in the top panel respectively, assign col(A) as X and col(B)~col(D) as Y in the middle


panel, and then click the **Add** button to add them to **Layer 1** and **NoAxes** layer respectively.




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.


- Click **OK** button to close the **Plot Setup** dialog. Click the **Rescale** button, you will get a graph with two stacked column graphs overlapped as shown below:



- Double-click on the graph to open the **Plot Details** dialog. Select **Graph1** level in the left panel, go to the **Miscellaneous** tab in the right panel, and check the **Column/Bar Gap/Offset Across Layers** check box.





- Click **OK** button, you will see the plot with two stacked columns will show side by side with an auto gap.




- Double-click on the graph to open the **Plot Details** dialog again. Set the **Border Color** and **Fill Color** respectively, as shown below:


Tutorials for Origin



- Go to the **Pattern** tab to set the **Transparency** as *40*, **Border Width** as *0.2*, and **Gradient Fill** as shown for both graph layers:




- Click **OK** button to close the **Plot Details** dialog.




- Right-click on the graph legend, select **Update Legend** from the context menu to open the **LegendUpdate** dialog. Set the **Update Mode** as **Reconstruct**, **Legend** as **One Legend for**

All, Layer Order as Descending and Plot Order within Layer as Ascending.



11. Click **OK** button to close the dialog and then update the axis labels, you will get the final graph shown below:



6.7.7.4 Sample Data**Data 1**

	Product A	Product B	Product C
Jan	42	33	40
Feb	88	85	37
Mar	99	34	82
Apr	51	43	38
May	21	66	52
Jun	74	31	28


Data 2

	Product D	Product E	Product F
Jan	96	87	35
Feb	62	66	15
Mar	65	86	51
Apr	32	24	87
May	77	26	34
Jun	69	33	71

6.7.8 Grouped Column with Error Bars and Data Labels

6.7.8.1 Summary

Origin supports grouped column graphs with indexed data. Multiple group levels are supported. Grouping information can be shown in tick label tables on the X or Y axes.



Minimum Origin Version Required: 2015 SR0

6.7.8.2 What will you learn

This tutorial will show you how to

- Plot grouped column and error bar with indexed data
- Customize tick labels, colors, gaps, error bars and data labels
- Update legend to show grouping information.


6.7.8.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Column and Bar**)

1. Open **Tutorial Data.opj** and browse to the **Grouped Column with Error Bars and Data Labels** folder in **Project Explorer (PE)**.


- In the following steps, we want to customized the order of values shown in the graph but not change the source data. Right click Column **B** in workbook, select **Set As Categorical** in the list menu, double click the literal "Unsorted" to open the **Categories** tab. Then select **Ascending** in **Sort** list and click **OK** to close the dialog.



- Do the same operation for Column **C** and **F** to set the Column **C** and **F** as categorical data as well and set the order of categorical values as **Ascending**.
- We are going to create a grouped column chart from worksheet. Highlight column **D(Y2)** and **E(yErr)** and select **Plot: Column/Bar/Pie: Grouped Column - Indexed Data...** from the main menu.
- In **plot_gindexed** dialog, click  in the "Group Column(s)" to add columns **B**, **C**, and **F** (in that order) to the Group List. Click the **OK** button.




A grouped column plot with error bar is created. The 3-row tick label table at the bottom shows the grouping information. Note that a worksheet is created to contain the data used to create this graph.




- To hide the first tick label row, double-click on any tick label in the row, e.g. **EC2**. The **Axis** dialog box will open with the **Bottom 3** icon selected in the left panel. uncheck the **Show** box and click


Apply.




7. We want to customize the appearance of the **Bottom 2** tick label rows. Select the **Bottom 2** icon on the left panel and clear all **Border** check boxes in **Table** tab, then click the **OK** button.




Two tick label rows remain, each with different layout.




- To show color information in the legend, right click the legend and choose **Legend: Categorical Values**. Check on the **Fill Color** check box.



Click **OK** to apply the setting, delete the top two legend entries which are not needed.




9. The graph should appear as follows.




6.7.8.4 Further Customizations

The tutorial steps that follow, further customize the graph so that it looks like the image in the **Summary** section.

1. To turn on grid lines, go to the **Axis** Dialog **Grids** tab. Check the **Show** box for **major grid lines** in **Horizontal** icon. Click **Apply** to apply the settings.



2. To turn on frames for both X and Y axes, Select both **Horizontal** and **Vertical** in left panel, check on **Opposite** checkbox in **Additional Links** group. Click **OK** button to apply.
3. To show labels on top of each column, open the **Plot Details** dialog box by clicking on the graph bars. Go to the **Label** tab and check the **Enable** box. Duplicate the settings as shown below.




- To add a gap between each week, go to **Spacing** tab and set the **Gap Between Subsets(%)** to **15**.

The image shows a software interface with a tabbed menu at the top containing 'Pattern', 'Spacing', 'Panel', 'Label', and 'Color List'. The 'Spacing' tab is selected and highlighted with a pink box. Below the tabs, there are several settings:

- 'Gap Between Bars (in %)' is set to 20.
- 'Overlap (in %)' is set to 0.
- A 'Subset' section contains:
 - 'Enable Subset' with radio buttons for 'None', 'By Size', and 'By Column' (the latter is selected).
 - 'Column' is set to 'Col(A)'.
 - 'Gap Between Subsets (%)' is set to 15, and this entire section is highlighted with a pink box.
- 'Width (in %)' is set to 'None'.
- 'Scaling Factor' is set to 1.


- To control pattern by the worksheet data in column F, add a color gradient fill to the plot columns, go to **Pattern** tab of **Plot Details** and set as follows. The gradient fill direction should be

Horizontal Center Out.




6. To customize the pattern list, go to the "Pattern List" tab in **Plot Details** dialog. Check the **Use custom increment list** check box and create a custom pattern list. Note that you don't need to


delete patterns beyond the 3rd one in the list since only the 1st 3 pattern style are used.




7. To remove negative error bars, select the error bar plot in the left panel of **Plot Details**, (The second dataset under **Layer1**), then go to the **Error Bar** tab and clear the **Minus** check box.




8. To change the graph page background color, select the **Graph** icon in the left panel of the **Plot Details** dialog box. Go to the **Display** tab and set color to **LT Gray**.




- To change layer background color to white, select **Layer1** node on left panel of the **Plot Details** dialog. Go to the **Background** tab and set **Color** to *White*.



- To show pattern information in the legend, right click the legend and choose **Legend: Categorical Values**. Check on the **Fill Pattern** check box.
- To arrange legends horizontally, right-click on the legend object and select **Properties...** from the shortcut menu. In **Text** tab of **Text Object** dialog box, arrange the remaining text in a single line.



Go to **Frame** tab, select **None** under **Frame** drop-down list. Click **OK**.




12. Drag the legend to an appropriate position. Select and press **Delete** to remove the Y axis title.

6.7.9 Grouped Stacked Column

6.7.9.1 Summary

In Origin, multiple datasets can be plotted as a stacked column graph. Usually these datasets are grouped together by default. In addition, subgrouping is possible for stacked column graphs such as the one shown below with 2 subgroups:



Minimum Origin Version Required: 2015 SR0

6.7.9.2 What will you learn

This tutorial will show you how to:


Tutorials for Origin

- Plot a stacked column graph
- Subgroup the stacked column
- Create and customize an X axis table for the graph


6.7.9.3 Steps to Create a Grouped Stacked Column Plot

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data.opj file and browse to the *Grouped Stacked Column* folder in **Project Explorer**.
2. Activate the workbook **Book1J**, highlight col(B)~col(G) and select **Plot: Column/Bar/Pie: Stacked Column** from the menu to create a stacked column graph:




3. Double-click on the column plot to open the **Plot Details** dialog. On the **Group** tab, select **By Size** for **Enable subgroup** and set **Subgroup Size** to **3**.




4. On the **Label** tab, check the **Enable** checkbox.



5. Select **Layer1** in left panel of **Plot Details** dialog and click the **Stack** tab. Check the **Use Subgrouping (in Group tab) for Cumulative** check box. Click the **Apply** button.




- Click **OK** to close the dialog. Select **Graph: Rescale to Show All** from the main menu.




6.7.9.4 Steps to Create a Tick Label Table for X Axis

- To create two rows of tick labels for the X axis, double-click on the X axis tick labels to open the **Axis** dialog.
 - Go to **Bottom** icon with **Tick Labels** tab selected.
 - Under **Format** tab, change **Font Size** to **16**

- Under **Table** tab, check the **Enable** checkbox and set **Number of Rows** to **2**. **Bottom** icon will change into **Bottom 1** and **Bottom 2** on the left panel.
- Set the Table layout as shown below:




- Select the **Bottom 2** icon and set **Dataset Name** to `[Book1J]Sheet1!label` in **Display** tab, and set the Font size to 10 in the **Format** tab. This will change the tick label row to the car names from the worksheet **label (Y)** column.
- Set the table layout as the dialog below:




- To show a frame around the layer, select the **Grids** tab, Check on the **Opposite** checkbox under the **Additional Lines** branch and click **OK** button for both **Horizontal** and **Vertical** icons.

6.7.9.5 More Customization Steps


The following steps can further customize the graph to be exactly the same as the image in **Summary**.

1. Double-click on the column plot to open the **Plot Details** dialog. On **Group** tab, click the  button in the '**Details** column of the **Fill Color** row. **Increment Editor** opens.


2. Click on the arrow to the right of the first color, then click on an empty color well under **Custom**. In the **Color** dialog that opens, set the **Red**, **Green** and **Blue** values to **165**, **196** and **0**, then click **OK**.
3. Create five more custom colors using these RGB values: (243, 62, 12), (243, 200, 30), (0, 64, 127) (119, 0, 31), and (124, 191, 243).
4. Click the number (7) to left of the next color in the Increment Editor list, then scroll to the bottom of the list, press **Shift** then click on the number to the left of the last color. Click **Delete** to remove the selected colors so that you have just the six custom colors that you just created. Click **OK** to close the Increment Editor.



5. On the **Label** tab, set **Size** to **18**, **Position** to **Center** and click on the **Bold** button. This adjusts the labels on the columns.



- Click the **Spacing** tab and increase the **Gap Between Bars(in %)** to **30**.




- On the **Group** tab, change **Edit Mode** to **Independent**.
- Select the 4th plot in the left panel and click on the **Label** tab. Set **Color** to **LT Gray**. Click **Apply** button.
- Select the 5th plot in the left panel, and on the **Label** tab change **Color** to **LT Gray** and **Size** to **11**. Click **OK** to close the dialog.
- Select and delete the X and Y axis titles.
- Right-click on an empty portion of the graph window and select **Add/Modify Layer Title** from the context menu. Type **Sales** as a layer title.

12. Select and drag the legend box to an appropriate position. Resize as needed, using the green selection handles.

6.7.10 Stack Column Plot with Different Positive and Negative Y Scale

6.7.10.1 Summary

We will show how you can use axis break without a gap to produce this graph, that has much larger Y scale range for the negative bars.



Minimum Origin Version Required: 2015 SR0

6.7.10.2 What You Will Learn


This tutorial will show you how to:

- create a stacked column plot with error bars.
- enable an axis break without a gap.
- divide one axis into several segments and set scales separately.

6.7.10.3 Steps to Add Axis Break with No Gap


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open **Tutorial Data.opj** and browse to the *Custom Axis Scale to Show Different Scale* folder in **Project Explorer** and activate the workbook **sample**.
2. select all the columns and choose **Plot:Column/Bar/Pie:Stacked Column** to create a stacked column plot with error bars.




3. Positive columns cannot be seen since their absolute values are too small comparing to those of negative columns.
4. We can break the Y axis at Y=0 and use different axis scale for those two segments. First double click on the Y axis to open the **Axis** dialog and set Y Range (in **Vertical** icon) to be from -180000


to 80



- Then go to the **Breaks** tab with **Vertical** icon active, and enable 1 axis break. Also set the Break Half Length to 0 so the break indicator will not show. Set both the **Break From** and the **Break To** to **0** so the axis will break at 0 and no break gap shows.




- Set Custom Scale for the region after break ($Y>0$) by clicking **Details**:



- Click **Apply** to apply the settings and view the updated graph, you can see the axis scales are different for the regions above or below the $Y=0$ line and the columns for positive values can also


be seen in the graph.



6.7.10.4 More Customization Steps


The following steps can further customize the graph to be exactly the same as the image in Summary.

1. Set the X scale to be from -2 to 20, *Major tick* by increment 2.
2. Go to the **Grids** tab and select both **Vertical** and **Horizontal** icons, select the **Opposite** check box so the grid lines opposite to both X and Y axes will show.




3. Click **OK** to apply the settings and close the **Axis** dialog.

- To change the positive and negative column colors to light gray and gray, double click on the columns to open the **Plot Details** dialog to make the changes shown below



- To customize the legend, right click on the legend object and select **Properties** to open the **Object Properties** dialog, arrange the two legend entries to be in the same row as below and

click **OK**




6. Move the legend to be above the graph.

6.7.11 Variable Column Width

6.7.11.1 Summary

Origin allows you to specify a dataset to control column/bar width. When the Scaling Factor is 0, the dataset values determine bar width in terms of X axis scale values.



Minimum Origin Version Required: Origin 2015 SR0

6.7.11.2 What will you learn


This tutorial will show you how to


- Plot a stack column graph
- Set the width of column with a variable
- Customize the axis ticks and tick labels


6.7.11.3 Steps

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the Tutorial Data project and browse to folder *Variable Column Width* in **Project Explorer**.
2. Activate the workbook **Book3A**, highlight col(F), col(A) and col(B) and select **Plot: Column/Bar/Pie: Stacked Column** from menu to plot a stacked column.



3. Double-click on the plot to open the **Plot Details** dialog. Click the **Group** tab then click the button  to open the **Increment Editor**. Select two custom colors as **Fill Color**.




4. Go to the **Spacing** tab, select *Col(C): "w"* as **Width (in %)** and set **Scaling Factor** to 0. After clicking Apply, it will be displayed as '<0=Use X Unit>' .


Tutorials for Origin




5. Go to the **Label** tab, set **Position** to *Center* and select *Col(C): "w"* from the **Label Form** drop-down list.




6. Click **OK** to close the dialog. Double-click on the X Axis to open the **Axis** dialog.
 - o Select **Horizontal** icon in the **Scale** tab, select **By Custom Positions** for **Type** and *[Book3A]Sheet1!F"Product Share (%)"* for **Position**.



- Go to **Bottom** page in **Tick Labels** branch, set **Type** to **Tick-indexed dataset** and **Dataset Name** to *[Book3A]Sheet1!D"Item"*.




- Go to the **Grids** tab and check the **Opposite** check box under the **Additional Lines** branch for both **Vertical** and **Horizontal**
 - Click **OK** to close the dialog.
7. Double-click on the Y axis title and change it to **Unit Sales**. Right-click the legend box and select **Properties...** from fly-out menu. Edit the legend to display on one line. The graph should look like the following:



6.7.12 Stack Column and Bar Charts of Rechargeable Battery Statistics

6.7.12.1 Summary

This tutorial will show you how to create a Stack Column bar graph.



Minimum Origin Version Required: Origin 2015 SR0

6.7.12.2 What will you learn

This tutorial will show you how to


- Create a Stack Column bar graph.
- Customize the graph.

6.7.12.3 Steps


1. Create a new worksheet. Import [the sample data](#).

	A(Y)	B(Y)	C(Y)	D(Y)
Long Name	Year	Lion	NiMh	Nicd
Units				
1	1991	777719	--	--
2	1992	759629	--	--
3	1993	807048	72204	--
4	1994	879264	204666	12000
5	1995	872698	306106	32029
6	1996	694384	356218	125388
7	1997	703296	580930	193496
8				


- Highlight all the columns and click the **Stack Columns** button on the **2D Graphs** toolbar.




The graph should look like




- Then apply a graph theme to add a top X axis and a right Y axis. Select **Tool: Theme Organizer** to open the **Theme Organizer** dialog. Activate the **Graph** tab and select **Opposite Lines** from the table. Then click the **Apply Now** button. Click the **Close** button to close the dialog.



- Double-click on the Y axis to open the **Axis** dialog. Go to **Horizontal** icon in **Grids** tab, and check **Show** checkbox under the *Major Grid Lines* section. Click the **OK** button to add grid lines to the graph.



5. Go to the **Title** tab to change the title of Y axis to **Millions of Unit Batteries**. Then choose **Top** icon and add a graph title **Rechargeable Batteries CCC**. The graph should look like:



6.7.12.4 Sample Data

Download the **Stack_Column_and_Bar_Charts.txt** file from http://www.originlab.com/ftp/graph_gallery/data/Stack_Column_and_Bar_Charts.txt. Click the **Import**

Single ASCII button  and select the file to import it into Origin.

The following table contains part of the sample data.

year(X)	Nicd(Y)	NiMh(Y)	Lion(Y)
1991	777719	--	--
1992	759629	--	--
1993	807048	72204	--
1994	879264	204666	12000
1995	872698	306106	32029
1996	694384	356218	125388
1997	703296	580930	193496


6.8 Multi-Axis and Multi-Panel

- [Double Y](#)
- [3Ys Y-YY](#)
- [Stack Lines by Y Offsets](#)
- [Vertical 2 Panel Line](#)
- [Multiple Axis Plot](#)
- [Energy-Level Structure of the Er³⁺ Ion in A YAG Crystal](#)
- [Create an 8 layer multi-panel plot template](#)
- [Panel Graph with Inset Plots of High-resolution Electron Energy-loss Spectra](#)


6.8.1 Double Y

Tutorials for Origin


- Double click on the plot to open the **Plot Details** dialog box. In the left panel, select the plot in Layer1, and set the plot type to **Scatter**, symbol to **Triangle** and size to **10**.




- Choose the first plot in Layer2, then change the **Plot Type**, **Size** and **Color** as shown below.




- Choose the Error bar plot in Layer2, then change **Color** to **Gray** in the **Error Bar** tab.
 - Click **OK** to apply your customizations and close the dialog box.
4. Double click on X axis to open the **Axis** dialog box. On the **Scale** tab for **X Axis**, set the X axis scale to be from 92 to 83 with increment of -2.




5. Click **Vertical** icon on the left panel and go to the **Scale** tab for **Y Axis** and apply the following settings to the left Y axis:



6. Click **Horizontal** icon on the left panel to go to **Title** tab and change the X Axis title to *Transition Temperature (K)*:




7. Click **Left** icon on the left panel to change the Y Axis title to *Deposition Pressure (Torr)*. Click **OK** to apply settings and close the dialog box.
8. Double-click on the right Y axis to open the **Axis** dialog for Layer 2. Repeat the settings as in step 5 - 6, but with scale **From** = 765, **To** = 795, **Type** = *Linear*, also for **Major Ticks**, change the **Value** for **Increment** to be 10. Go to **Title** tab and change **Text** to *Annealing Temperature (1+(0)C)*.
9. Go to **Line and Ticks** tab and set both **Major Ticks** and **Minor Ticks** to *In* and click **OK** to apply settings.



10. Click the legend to select it, then right-click and choose **Properties** from the shortcut menu. This opens the **Object Properties** dialog box. Go to **Frame** tab, change **Frame** to **Box**. In the **Text** tab, enter the following:

\(1.1) As Grown

\(2.1) Annealed




11. Click **OK** to close the **Properties** dialog box. Move the legend to an appropriate position.

6.8.2 3Ys Y-YY

6.8.2.1 Summary

This tutorial will show how to create a graph with three Y axes; one left Y axis and double right Y axes.



Minimum Origin Version Required: Origin 2015 SR0

6.8.2.2 What you will learn

- Create a graph with three Y axes; one left Y axis and double right Y axes.
- Customize scatter plots.
- Change axis scale, type, title, etc.
- Add an axis to an existing graph.
- Update the graph legend.

6.8.2.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Multiple Axis and Multiple Panel**)


1. Open **Tutorial Data.opj** and browse to the **3Ys Y-YY** folder in **Project Explorer** (PE).
2. Highlight all data columns in the worksheet, then on the **Plot** menu, click **Multi-Y: 3Ys Y-YY** to create a graph with three Y axes - one left Y and two right Y.
3. Customize data plots:

Tutorials for Origin


- Double-click on the plot to open the **Plot Details** dialog box. In the left panel, select the plot in Layer1, then change the plot type, symbol and color as shown below (be careful not to clear the check box to the left of the plot):




- Click the data plot in Layer2 and change the plot type and symbol shape as shown in the following:




- Choose the Error bar plot in Layer2, then change its color to **Black**.
- Choose the plot in Layer3. Change the **Plot Type** to be **Line + Symbol** and go the **Symbol** tab (right panel), choose the following settings:




- Select the **Line** tab (with Layer 3 still selected) and change **Connect** to **B-Spline**. Click **OK** to close **Plot Details**.




4. Double-click on the X axis to open the **Axis** dialog box. Configure the X axis scale as shown in the following:




5. Go to **Tick Labels** tab and click **Top** icon on the left panel, check the **Show** box and show tick labels of top axis.




6. Then go to **Line and Ticks** tab, check **Show Line and Ticks** box to show line and ticks for top axis and click on **Apply**.



7. Go to the **Scale** tab and click the **Vertical** icon on the left panel and duplicate the following settings:



8. Go to **Title** tab and change the Y Axis title to *Deposition Pressure (Torr)* and select **Auto** from color drop-down list.



9. Click **OK** to close the Axis dialog box and apply the axis settings to layer 1.
10. Double-click on the right red Y axis. In the **Y Axis - Layer 2**, repeat step 4, but with scale from 765 to 795, and an increment of 10. Change the axis title to *Annealing Temperature (+0)C* and select **Auto** from **Color** drop-down list. Click **OK** to close the Axis dialog box.
11. Double-click on the right blue Y axis. Change the axis scale to read from 0 to 6 with an increment of 1. Under **Title**, enter $\lg(D)T-(c) (K)$ for **Text** and select **Auto** from **Color** drop-down list.
12. Click **OK** to apply settings and close the dialog box. On the graph, right-click the legend object and choose **Properties** from the shortcut menu. This opens the **Object Properties** dialog box. Go to **Frame** tab, and change **Frame** to **Shadow**. Go to **Text** tab, and enter the


Tutorials for Origin

text shown below, then click **OK** to close the dialog box. Reposition the legend object, as needed.


\(1) As Grown

\(2.1) Annealed

\(3.1) $\lg(D)T\text{-}(C)$




13. Add a graph title by creating a text object and typing *Characteristics of Samples Grown Under Different Conditions*. Reposition as needed.
14. Right click on the page (area other than the plot) and select **Fit Page To Layers...** and choose **OK** in the bring-up dialog to auto adjust the page dimension properly.
15. Reposition the blue Y axis properly so it becomes the following graph:



6.8.3 Stack Lines by Y Offsets

6.8.3.1 Summary

This tutorial will demonstrate how to create a graph with stack lines by Y offsets.



Minimum Origin Version Required: Origin 2015 SR0

6.8.3.2 What you will learn

- How to create a graph with stack lines by Y offsets
- How to customize a rectangular object
- How to add a new XY scaler

6.8.3.3 Steps

This tutorial is associated with the **Tutorial Data** project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

Create a Stack Line Plot

1. Open the **Tutorial Data** project and browse to folder *Stack Lines by Y Offsets* in **Project Explorer**.
2. Highlight all the columns in the data worksheet of **Book6A**, and choose menu **Plot: Y-offset/Waterfall: Stack Lines by Y Offsets** to create a graph with stack lines by Y offsets.

Customize the Stack Line Plot

1. Delete the following objects by selecting them and pressing the **Delete** key on your keyboard:


Legend

Y axis


Y axis labels

Y axis title

X axis title



2. Double click on the X axis to open the **Axis** dialog. On the **Scale** tab, change the value of **To** to 10. Click **OK** to close the dialog.




Add XY Scaler

1. Click the **Rectangle** button on the **Tools** toolbar and then create a rectangle on the graph.
2. Double click on the rectangle to open its properties dialog. Change the following settings.

Fill Pattern tab

Fill Color = LT Yellow



Dimensions tab


Units = scale

Left = 0.25

Top = 9000

Width = 3.5

Height = 4000



3. Click OK to close the **Object Properties** dialog.
4. Select **Graph: New XY Scaler** from the Origin menu to create a new XY scaler.
5. Double click on the scaler to open the **Scaler Properties** dialog. Set the following properties in the dialog:

Font Settings branch

Font Size = 24

X branch

Length(Scale) = 2


Title = 2

Y branch

Position = Right

Length(Scale) = 2500


Title = 2500




6. Click OK to close the **Scaler Properties** dialog.
7. Move the scaler object onto the rectangle you created.

Drag and Change Plot Offset

1. Click on the top data plot (purple one) twice to select it. (Click only once will select the whole group):



2. Click and drag the mouse to move the data plot.




Note: an alternative is to go to the **Offset** tab in **Plot Details** dialog and change the Y offset.

6.8.4 Vertical 2 Panel Line

6.8.4.1 Summary

This tutorial will demonstrate how to merge and customize two graphs.




Minimum Origin Version Required: Origin 2015 SR0

6.8.4.2 What You Will Learn

In this tutorial, you will learn how to:


- Merge graph windows
- Customize graph axes after merging
- Apply a graph theme

6.8.4.3 Steps


1. Create a new worksheet. Click the **Import Single ASCII** button  and import the **Vertical_2_Panel_Line.txt** file under <Origin EXE Folder>\Samples\Graphing path.

	A(Y)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)	G(Y)	H(Y)
Long Name	Year	All Persons	All Males	All Females	Black Males	White Males	Black Females	White Females
Units								
1	1965	42.3	51.6	34	59.2	50.8	32.1	34.3
2	1974	37.2	42.9	32.5	54	41.7	35.9	32.3
3	1979	33.5	37.2	30.3	44.1	36.5	30.8	30.6
4	1983	32.2	34.7	29.9	41.3	34.1	31.8	30.1
5	1985	30	32.1	28.2	39.9	31.3	30.7	28.3
6	1987	28.7	31	26.7	39	30.4	27.2	27.2
7	1990	25.4	28	23.1	32.2	27.6	20.4	23.9
8	1991	25.4	27.5	23.6	34.7	27	23.1	24.2
9	1992	26.4	28.2	24.8	32	28	23.9	25.7
10	1993	25	27.5	22.7	33.2	27	19.8	23.7
11	1994	25.5	27.8	23.3	33.5	27.5	21.1	24.3
12								


2. Select column 2 to column 4 and click the **Line + Symbol** button on the **2D Graphs** toolbar.




The following graph will be created:




Go back to the worksheet. Select column 5 to column 8 and click the **Line + Symbol** button on the **2D Graphs** toolbar to create a new graph as shown below:




3. To merge the two graphs, select **Graph: Merge Graph Windows** from the menu. Accept the default settings and click **OK**. The two graphs will merge in one window:




4. Ensure that Layer 1 is selected on the top left corner of the graph and double-click on the **Y** axis of Layer 1 to open the **Axis** dialog. In the **Scale** tab, set the dialog options as shown below:




5. Click **Horizontal** icon on the left panel, and go to **Tick Labels** tab, uncheck the **Show** box to hide the tick labels in Layer 1 and click **OK** to apply settings.




6. Delete the X axis title in Layer 1. Set the same scale for the Y axis of Layer 2. The graph should now appear as shown below:



- Apply a theme to add a top X axis and a right Y axis. Select **Tool: Theme Organizer** from the main menu to open the **Theme Organizer** dialog. Activate the **Graph** tab and select the **Opposite Lines** from the table and click the **Apply Now** button. Use the **Close** button to close the dialog.




8. Select the **Legend** of Layer 1 and right-click on it to select **Properties** from the short-cut menu. Set the dialog options as shown below:



Move the legend to the desired position.

9. Select the **Line** button from the **Tools** toolbar and draw a line on the Layer 1 as shown in the sample image. Hold down the **SHIFT** key while drawing to ensure that the line is vertical. Double-click on the line to open the Properties dialog of the line object. In the **Line** tab, select **Dash** in the **Type** drop-down list and enter **2** in the **Width** edit box. Activate the **Control** tab. Select both the **Horizontal Movement** and the **Vertical Movement** check boxes. Click the **OK** button to finish.
10. Repeat steps **8-9** for Layer 2.
11. Select the **Text** button in the **Tools** toolbar. To add a title for the graph click in the middle of the graph and enter **Cigarette Smoking by Persons 18 Years and Over in the United States**. Double-click on the **Y** axis title of Layer 1 and Layer 2 and enter **Percent Who Smoke**.


The final graph should appear as shown below:



6.8.5 Multiple Axis Plot


6.8.5.1 Summary


This tutorial will demonstrate how to create a 4-Y plot and add recession bars.




Minimum Origin Version Required: Origin 2015 SR0

6.8.5.2 Steps


1. Create a new workbook, click the **Import Single ASCII** button  and import the **multi_axis_plot.txt** file under *<Origin EXE Folder>\Samples\Graphing* path.
2. Place the mouse cursor near the top left corner of the worksheet. When the cursor changes to a down-right arrow, left-click to select the whole worksheet.




- Right-click and select **Set as: XY XY** from the short-cut menu to set proper plotting designations for the worksheet columns.




- Highlight all the columns. From the main menu, select **Plot: Multi-Y: 4Ys YY-YY** to create a plot as shown below:




5. Double-click on the graph to open the **Plot Details** dialog shown below. In the left panel, select the second plot in Layer 1 and set the **Plot Type** option at the bottom of the dialog as Line. In the right panel **Line** tab, choose the settings shown below and **Apply**.




6. Select the **Pattern** tab. Set the dialog options as shown below and click **OK**.




7. Ensure Layer 1 is selected in the top left corner of the graph and double-click on the bottom X axis to open the **Axis** dialog for Layer 1. On the **Scale** tab, change the dialog options as shown below and **Apply**.



8. Go to **Tick Labels** tab, change the dialog options as shown below and **Apply**.




9. Go to **Line and Ticks** tab, click the **Top** icon on the left panel and check **Show Line and Ticks**. Then choose **In** for **Style** under **Major Ticks** and **None** for **Style** for **Minor Ticks** and click **OK** to apply settings.



10. Click on the legend to select it and use the mouse to drag it to the desired position.


The final graph should appear as shown below:



6.8.6 Energy-Level Structure of the Er³⁺ Ion in A YAG Crystal

6.8.6.1 Summary

This tutorial will demonstrate how to create a graph showing the energy-level structure of the Er³⁺ ion in a YAG crystal.




Minimum Origin Version Required: 2015 SR0


6.8.6.2 What you will learn

This tutorial will demonstrate how to:


- Create a graph by selecting part of the data from a column
- Set symbol properties
- Merge graphs
- Change the size and position of a layer

6.8.6.3 Steps


1. Start with an empty worksheet and use the **Single Import ASCII**  icon to browse to the `\Samples\Graphing` subfolder of the Origin program folder, and import the file **Van_Rudd_Er_Energy_Levels.txt**.
2. Highlight column B and create a symbol plot by selecting menu **Plot: Symbol: Scatter**.
3. Double click the data points scatter to open the **Plot Details** dialog. In the **Symbol** tab of the right panel, change the symbol and symbol color as shown below:




4. In the **Drop Lines** tab, check the **Horizontal** box and set **Width** to 1. Click **OK** to apply the changes.




5. Double click on the X axis to open the **Axis** dialog. Set the X axis scale from 0 to 1 in the **Horizontal** icon in **Scale** tab :




- Go to the **Line and Ticks** tab, **Tick Labels** tab, and **Title** tab respectively, make sure **Bottom** icon is selected and deselect the **Show Line and Ticks** or **Show** box to hide all elements in the bottom X axis including line & ticks, labels and title:




- In the **Vertical** icon in **Scale** tab, set the following for the Y axis scale: **From**: 0, **To**: 24000, **Value**(in *Major Ticks* Group): 2000.
- Go to **Left** icon in **Title** tab, change the **Text** for the Y axis title to *Energy Levels (cm⁻¹)*:



9. Go to the the **Left** icon in **Line and Ticks** tab, select **In** from the drop down menu for *Major Ticks* and *Minor Ticks*:




- Use **OK** to save the axis settings. Delete the legend object in the graph by selecting it, right-clicking and choosing delete from the drop down menu. The graph should appear as shown below :




11. Highlight cell 1-8, cell 9-15, cell 16-21, cell 22-26, cell 27-31, cell 32-43, and cell 44-48 respectively, to plot scatter graphs by selecting menu **Plot: Symbol: Scatter** and then repeat step 3 through step 11 to make another 7 graphs. Set the increment value of the Y axis (step 7) to 100, and the **From** and **To** values as 0 to 600, 6500 to 6900, 10200 to 10500, 12300 to 12800, 15200 to 15600, 18300 to 20800, 22200 to 22700, respectively. The **Title in Y axis** (step 8) are also different and should be set as $|+(4)l-(15/2)$, $|+(4)l-(13/2)$, $|+(4)l-(11/2)$, $|+(4)l-(9/2)$, $|+(4)Fl-(9/2)$, $|+(4)Fl-(7/2)$ $|+(2)H2l-(11/2)$ $|+(4)Sl-(3/2)$, and $|+(4)Fl-(3/2)$ $|+(4)Fl-(5/2)$, respectively. Then set the Y axis **Major Ticks** and **Minor Ticks** to **None**.


12. In order to change the rotation angle of the Y title created in step 9, select the Y title, choose **Properties** from the right-click menu and set the **Rotate(deg.)** to 0 in the **Object Properties** dialog that opens.




13. Activate one of the graphs and select menu **Graph: Merge Graph Window**. Change the settings as shown below and click the **OK** button to merge the 8 graphs previously created.



14. Double click on the merged graph to open the **Plot Details** dialog. In the **Size/Speed** tab of Layer 1, change the **Layer Area** as shown below:



15. Set the other layers' sizes to 15 x 15 (Width and Height in step 15), and move them to the desired position. Adjust the size of the Y axis label and add the corresponding arrows and circles. The graph should appear as shown below:



6.8.7 Create an 8 layer multi-panel plot template

6.8.7.1 Summary

All child windows in Origin, with the exception of the Notes window, are created from template files. These template files describe how to construct the window. For a graph window, the template file determines all page and layer characteristics, such as page size, number of layers, inclusion of text labels and data plot style information to name a few.

Minimum Origin Version Required: 2016 SR0

6.8.7.2 What you will learn

This tutorial will show you how to:

- Create an 8 layer multi-panel plot

- Apply axis settings from one axis to all axes
- Save a graph template
- Reuse the template with similar data

6.8.7.3 Steps

Choosing the Data Source

1. Click the **New Project** button on the Standard toolbar, to begin a new project.
2. Open **Import Wizard** using the Import Wizard button on the Standard toolbar. (Note that if this is the first time that you have started the Import Wizard, you will experience a slight delay as Origin compiles the necessary files.)
3. Verify that the **ASCII** radio button is selected in the **Data Type** group.
4. Click the browse button to the right of the File text box. Navigate to the Origin folder; browse to the Samples folder and then the Curve Fitting folder. Select Step01.dat from the list of files.
5. Click the **Add File(s)** button and save changes with **OK**.
6. Leave the **Import Filters for current Data Type** as **Data Folder: step**. (This filter has the settings to use when importing the file.)
7. Click the **Finish** button. The data file imports into the worksheet.

Plotting the Data

1. Highlight the entire worksheet of data. (Note that you can select an entire worksheet by placing your cursor in the blank area in the upper left corner of the worksheet. When the cursor becomes a downward pointing arrow, click once to select the entire worksheet.)
2. Select **Plot:Multi-Panel:9 Panel**. A new 9 layer graph with 9 graphs is created.
3. Select the empty graph and ensure the 9th layer on the top left corner of the window is selected. Pressing the **Delete** key will now delete this graph and this layer leaving 8 graphs on 8 separate layers behind.
4. Select **Graph:Layer Management**. In the **Layer Management** dialog that opens select the **Arrange** tab.
5. Set **Number of Rows** to 4 and **Number of Columns** to 2.
6. Clicking the **Apply** button gives a preview in the small window on the right side of the dialog, showing a 2x4 arrangement.
7. Click **OK** to save the changes.

Editing the Graph

The goal is to save this 8 panel graph as a template; i.e. a new plot type, so that it can be used again with new similar data. Since the template will also save plot style information, we will customize the graph a bit further.

1. Double-click on the X axis in layer 1. The **Axis** dialog opens.
2. Select the **Grids** tab, check the **Show** boxes under both **Major Grid Lines** and **Minor Grids Lines** tree node to display major and minor grid lines for X axis.
3. Set the **Color** for both Major and Minor grids to **LT Gray**.
4. Click **Apply to...** button to open the **Apply To** dialog, make sure the **Apply From** is chosen as **Bottom**.
5. Select the check box **All Below** and then select **This Window** in the drop-down menu.
6. Click the **OK** button to apply the same setting to all axes in all layers of this graph page.

Saving as a new graph template

1. Select **File:Save Template As**. A dialog opens allowing you to choose the category that the template will be saved in as well as the name given to the new template.
2. Change the **Template Name** to **PAN8**. (Note that the **Template Name** that appears when the dialog opens is the name of the original template that was used to create the graph.)
3. Select the option **Mark as Cloneable Template**.
4. Click **OK**.


Plotting into your new template

1. Click the **New Folder** button on the Standard toolbar.
2. Click the **Import Wizard** button on the Standard toolbar. The Import Wizard opens.
3. Click the browse button to the right of the File text box. Navigate to the Origin folder; browse to the Samples folder and then the Curve Fitting folder. Select Step02.dat from the list of files.
4. Click the **Add File(s)** button.
5. Click **OK**.
6. Leave the **Import Filters for current Data Type** as **Data Folder: step**. (This filter has the settings to use when importing the file.)
7. Click the **Finish** button. The data file imports into the worksheet.
8. Highlight the entire worksheet of data. (Note that you can select an entire worksheet by placing your cursor in the blank area in the upper left corner of the worksheet. When the cursor becomes a downward pointing arrow, click once to select the entire worksheet.)
9. Select **Plot: User Templates: PAN8** to plot.

6.8.8 Panel Graph with Inset Plots of High-resolution Electron Energy-loss Spectra

6.8.8.1 Summary

Origin can be used to create a three panel graph with inset plots similar to the image shown below:



Minimum Origin Version Required: 2015 SR0

6.8.8.2 What you will learn


This tutorial will demonstrate how to:


- Use the **Plot Setup** dialog to create curves on one graph using data from multiple workbooks.
- Add Inset Graphs.
- Copy and Paste Style formats.
- Use the **Layer Management** dialog to link axes.



6.8.8.3 Steps

Using the Plot Setup dialog

This tutorial is associated with <origin exe folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data.opj and go to the folder *Three Panel Graph with Inset Graphs*.
2. Activate the workbooks **Measured** and **Original name: BOS**.
3. Ensure that nothing is selected in either workbook and click the line button  on the **2D Graphing** toolbar.
4. This will bring up the **Plot Setup** dialog box.




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

- Under **Available Data** select the **Worksheets in Folder** option from the drop-down list. This will ensure that in the panel to the right, data is available from all the workbooks in the current folder.



- Make sure that the **Original name: BOS** worksheet is selected as shown above. In the center panel enable the box corresponding to **X** and **A4** and the second box corresponding to **Y** and **B4**.
- This will set col(A4) as the X values and col(B4) as the Y values regardless of column designation in the workbook. Select **Add** and a new curve will be created in the pre-existing Layer on the third panel:



- On the first panel, change the highlighted workbook to **Measured**.
- On the left, set **Plot Type** to **Scatter**.

10. On the second panel, select the check boxes as shown below:

Plot Setup: Select Data to Create New Plot

Available Data:

Long Name	Sheet	Cols	Rows	File Name	File I
Measured	Sheet1	6	3049		
Original name: B0	Sheet1	8	1001		

Worksheets in Folder
 Include Shortcuts

Right-click on various panels to bring up context menus.

Plot Type:

- Line
- Scatter**
- Line + Symbol
- Column / Bar
- Area
- Stacked Area
- Fill Area
- High - Low - Close


Show(S) [Measured]Sheet1

X	Y	yEr	L	Column	Long Name
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A	From B5
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	B	From B5
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	C	From 13039807.GAN
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	D	From 13039807.GAN
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	E	From 13039801.DAT
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	F	From 13039801.DAT

Plot List: Drag entries in 1st column to reorder or to move between layers. Right click for other opti

Plot	Range
Layer 1	<input checked="" type="checkbox"/> Rescale
[Original name: B0]Sheet1! A4(X), B4(Y)	[1*:1001*] -
[Measured]Sheet1! "From 13039801.DAT"(X), "From 13039801.DAT"(Y)	[1*:3020*] -

11. Select **Add** and the plot will be added to the Layer in the third panel. Select **OK** to close the dialog box. Your graph should look like the one shown below:





12. Activate one of the workbooks and follow the procedure above to create two more graphs using the following designations in the **Plot Setup** dialog (remember to change the plot type to Scatter for the data from *Measured*):

<i>Graph 2</i>		
Worksheet Name	Set X as	Set Y as
Original name: BOS	A1	B1
Measured	C	D


<i>Graph 3</i>		
Worksheet Name	Set X as	Set Y as
Original name: BOS	A2	B2
Measured	A	B


Adding Inset Graphs

1. Select the **Add Inset Graph With Data** button  on the **Graph** toolbar to add an inset graph to each graph. Each inset graph appears on its own layer and each graph can be customized, zoomed, panned and moved around like the full-size parent graph it was created from.
2. Select and drag each graph to the center:




Merging Graphs


1. From the Origin menu select **Graph: Merge Graph Windows: Open Dialog**. Alternatively select the  button on the **Graphs** toolbar.
2. In the **Graph Manipulation: merge_graph** dialog that opens, under **Arrange Settings**, set the **Number of Rows** as **3** and the **Number of Columns** to **1**. The Preview will appear on a panel to the right.
3. Enable the check box for **Treat Each Source Graph as a Unit**, to keep the graphs and the corresponding inset graphs linked.
4. Enable **Show Axes Frames** to add frames around each graph:



5. Click **OK** to exit the dialog.


Customizing Plots and the Copy Format Feature

1. Double-click the first graph to open the **Plot Details** dialog box.
2. Use the  button to expand the left panel. Click on the arrow next to the **Layer1** icon to expand it and show the layer 1 contents.
3. Select the plot *[Measured]Sheet1!E[X]...* and on the **Symbol** tab, change the symbol to a circle, the **Size** as **5** and the **Symbol Color** to **Red** as shown below. Select **Apply**.




4. Select the plot *[Fitted]Sheet1!A4[X],B4...* and on the **Line** tab set the line color as **Blue**.
5. Click **OK** to exit the dialog box.

- The next step is to apply this color scheme to all the parent graphs and inset graphs to avoid manually changing them all. Right-click on the customized graph and from the context menu select **Copy Format: All Style Format**:




- Right-click on each remaining graph and select **Paste Format** from the context menu.




Using the Layer Management Dialog Box to Link and Customize Axes

The next step is to set the scales on the axes and add axis breaks to show the important parts of the graphs.

1. Select **Graph: Layer Management**. In the dialog box that opens there will be a panel named **Layer Selection** on the left. It lists all six of the layers in this graph - 3 for parent graphs and 3 for inset graphs.
2. In order to customize one parent graph axis and have the changes implemented on the other two parent graphs, the axes are linked in the **Link** tab. The first Layer cannot be linked so it is the one that is customized and the other graphs are linked to it. Select **Layer 3** and in the **Link** tab set **Link to** as **1** and set **X Axis Link** and **Y Axis Link** as **Straight[1 to 1]** as shown below:




3. Click **Apply**.
4. Do the same for **Layer 5** and click **Apply**.
5. Click **OK** to exit the dialog box.
6. Double-click any axis on the first graph to open the **Axis Dialog**.
7. Go to **Horizontal** icon in **Scale** tab, set **From** and **To** to **-250** and **1500**. Set the Increment Value on the *Major Ticks* section as **250**.





8. Go to **Horizontal** icon in the **Breaks** tab, set **Number of Breaks** to **1**.
9. Select **Break 1** under the **Breaks** node and create a break **From: 850, To: 1250**.


- On the same page, clear the **Auto** check box for **Position (% of Axis Length)** and set it as 75.




- Go to **Vertical** icon in **Scale** tab, set the scale as From: 0, To: 0.22 with increments of 0.1.



12. Select **OK**. All three graphs will now reflect your changes.
13. To customize the Inset Graphs, zoom into the first one on Layer2 using the **Zoom Pan** button  on the **Tools** toolbar. Use the mouse wheel to zoom in.



14. Once zoomed in, select the **Pointer** button  on the **Tools** toolbar to exit the zoom mode. Double-click on the Inset Graph to open the **Plot Details** dialog. Select the *[Measured]Sheet1!E[X]...* graph and on the **Drop Lines** tab, check the **Vertical** box. Click **OK**.

The figure shows two parts of the software interface. On the left is a tree view of the graph structure. On the right is the 'Plot Details' dialog box.

Tree View:

- Graph4
 - Layer1
 - InsetWithData (checked)
 - [Fitted]Sheet1! A4(X), B4(Y) [1*:1001*] (checked)
 - [Measured]Sheet1! E(X), F(Y) [1*:3020*] (checked)
 - Layer3
 - InsetWithData1
 - Layer5
 - InsetWithData2

Plot Details Dialog (Drop Lines tab):


- Horizontal: Horizontal
- Vertical: Vertical
- Style: Solid
- Width: 0.5
- Color: Auto
- Data Points Display Control: Skip Points 2

15. Double-click on any axis.


16. In the **Axis Dialog** that opens, set the scale for the **X Axis** on the **Scale** tab **From: 1350, To: 1450**, with increments of **50**.
17. Under the **Vertical** icon, set the scale **From: 0, To: 0.03**. Go to **Lines and Ticks** tab and on the **left** icon, set the *Major Ticks* to **None** and the *Minor Ticks* to **None**.
18. Select **OK** to exit the dialog box. Select the tick labels on the left Y axis and press **Delete** to remove them. Do the same with axis labels.
19. Press **CTRL+W** to zoom out and return to normal graph size.
20. Select the customized Inset Graph, right-click and choose **Copy Format: All Style Formats** from the context menu.
21. Select, right-click and **Paste Format** to the other two Inset Graphs, to duplicate the drop lines settings.
22. Repeat the last two steps, this time selecting **Copy Format: Scales** to duplicate the axis settings.

Adding Titles, Legend and Text Objects


1. Activate the first Layer by clicking the layer icon on the top left corner of the graph. Right-click on the graph and from the context menu choose **Add/Modify Layer Titles**. Type **Wurtzite GaN** in the box that opens, change the font size and type face as desired and drag to an appropriate position:





2. Select the legend objects for the second and third graphs and press **DELETE**.
3. Select the remaining legend, right-click and choose **Properties**. In the **Text** tab of **Object Properties** dialog box, type **Fitted** in place of **%(1)** and **Measured** in place of **%(2)**. Place both on the same line. Set the font size as desired. Go to **Frame** tab, and set the **Frame** to **None**. Click **OK** and drag the legend object to an appropriate place.




4. Delete the first and third Y-axis titles. Double-click the second one and type **Intensity [arb. units]**. Do the same for the single X-Axis title, labeling it **Energy Loss [cm-1]**.
5. Right-click on the graph and choose **Add Text** from the context menu or choose the **T** button on the **Tools** tool bar. Add text objects as shown below. Use the **x₂** button for writing subscripts:



6. Select each of the inset graphs and change size or position as desired. Use the  button on the **Tools** toolbar to create arrows where desired on the Inset Graphs:



7. The final graph should appear as shown below:




6.9 Contour

- [XYZ Contour](#)
- [Contour Plots and Color Mapping](#)
- [Ternary Contour](#)
- [Combining Line and Contour Plots](#)
- [Contour Graph with XY Data Points and Z Labels](#)
- [Contour Plot with Vector Overlay](#)
- [Create Heat Map with Virtual Matrix and Colormap Bar Plot](#)

6.9.1 XYZ Contour

6.9.1.1 Summary

This tutorial will show you how to create a contour from XYZ data.



Minimum Origin Version Required: 2015 SR0

6.9.1.2 What will you learn


This tutorial will show you how to

- Create a Contour Plot from XYZ data
- Customize levels, lines, and color mapping
- Use a Custom Boundary
- Customize the Color Scale
- Customize the axes of the plot


6.9.1.3 Steps

This tutorial is associated with the 2D and Contour Graphs project:\Samples\2D and Contour Graphs.opj.


1. Open the *2D and Contour Graphs: Contour: XYZ Contour* folder in the **Project Explorer**. Activate **Book1B** and highlight column **D** and then click **Contour-Color Fill** button from the **3D and Contour Graphs toolbar**.




The graph should look like:




2. Double-click on the contour plot to bring up **Plot Details** dialog. Select the **Contouring Info** tab and set the options in the dialog as the screenshot below:




3. Select the **Color Map/Contours** tab, click the **Level** heading and set the dialog as the following screenshot shows:




- Click the **Fill** heading, select **Load Palette** and then select **Rainbow** from the Palette list and click **OK** to close dialog.
- Click the **Lines** heading, make sure that **Show on Major Levels Only** is selected. Select the **Color** check box under **Apply to All** and choose **LT Gray** from the drop-down list as contour line color. Click **OK** to close dialog.
- Click on the line at value 30 to customize it separately and click **OK** to close dialog.





4. Then go back to the **Colormap / Contours** tab, clear the check box **Follow Contour Line** under **Boundary** so that the boundary line could have separate style.
5. Click **OK** to close the **Plot Details** dialog, then select **Format: Axes: X Axis...** to open the **Axis** dialog. Then do the following things.
 - o Select the **Scale** tab and make sure the **Horizontal** axis icon is selected so X axis scale is being updated, set **From**, **To** equal to **-127**, **-65**.
 - o Select the **Vertical** axis icon to customize the Y axis scale, set **From=23**, **To=50**.
6. Click **OK** to apply the setting and close the **Axis** dialog.
7. Now we are going to change the layer size/aspect ratio and turn off the XY axes and its frame. Make sure the graph window is active and select **Format:Layer Properties** to open the **Plot Details - Layer Properties** dialog, first go to the **Size/Speed** tab and change the values in **Layer Area** as below:




8. Go to the **Display** tab and clear the **X Axes** and **Y Axes** check boxes under **Show Elements**. Click **OK** to apply the setting and close the dialog.
9. Right click on the white space in graph layer and select **Fit Page to Layers**, accept the default dialog settings and click **OK** to make all elements visible.
10. In the graph, select the axis title object **Latitude** and **Longitude**, hit the **Delete** key to remove them from the graph.
11. Now we will customize the color scale object. Double-click on the color scale to bring up the **Color Scale Control** dialog. Then do the following settings:








○



12. Click **OK** to apply the settings and close the **Color Scale Control** dialog.

13. Right-click above the contour plot and select **Add Text** to add a graph title *30-Year Mean Temperature for the Month of January*. Use the **Format** toolbar and/or double-click on the completed text label to update the font, font size, etc. The graph should look like

30-Year Mean Temperature for the Month of January



6.9.2 Contour Plots and Color Mapping

6.9.2.1 Summary

Origin offers rectangular, polar, and ternary contour plots. For **rectangular contour plots**, the data can be either in a matrix or in a worksheet in XYZ format. **Polar contour plots** can be generated from three columns of data in a worksheet, organized either as R Θ Z or Θ R Z. **Ternary contour plots** can be generated from worksheet data organized in X Y Z Z format where the 2nd Z-column contains the 4th parameter which is the height value at a given XYZ point in the ternary space.


Many options are available for customizing contour plots, such as setting different major and minor contour levels, displaying contour lines only at major levels, applying color palettes, and also control for a custom boundary in the case of contour plots created directly from the worksheet.


6.9.2.2 What You Will Learn

This tutorial will show you how to:


- Set values in a Matrix and create a Contour Plot
- Customize levels, lines, and color mapping
- Extract data from contour lines
- Create a Contour Plot directly from XYZ data
- Use a Custom Boundary

6.9.2.3 Create Contour Plot from Matrix

1. To create a new matrix click the **New Matrix button** . Move the cursor to the upper left corner of the matrix until the shape of the pointer changes as in the following image and click to select the entire matrix.



To set the dimensions, right-click and select **Set Matrix Dimension/Labels** in the context menu. On the XY Mapping tab, change setting as shown below .




2. Input data into the matrix by highlighting it and right-clicking. Select **Set Matrix Values** in the context menu to open the **Set Values** dialog. Type $i*\sin(x) - j*\cos(y)$ in the **Formula** edit box and click the **OK** button to generate data. The matrix should look like this:

	1	2	3	4	5
1	-1	-1.90017	-2.80133	-3.70448	-4.61058
2	-0.995	-1.79034	-2.58767	-3.38898	-4.19618
3	-0.98007	-1.66063	-2.34419	-3.03371	-3.73208
4	-0.95534	-1.51134	-2.07133	-2.63927	-3.21901
5	-0.92106	-1.34295	-1.76984	-2.20664	-2.65821
6	-0.87758	-1.15616	-1.44073	-1.73721	-2.0514
7	-0.82534	-0.95184	-1.08532	-1.2327	-1.40075
8	-0.76484	-0.73102	-0.70517	-0.69521	-0.70886
9	-0.69671	-0.49491	-0.3021	-0.12714	0.02123
10	-0.62161	-0.24489	0.12186	0.46876	0.78613
11	-0.5403	0.01756	0.56446	1.08951	1.58209
12	-0.4536	0.29081	1.02324	1.73186	2.40504
13	-0.36236	0.57312	1.49563	2.39233	3.25065
14	-0.2675	0.86267	1.97887	3.06729	4.11436


3. Each data point in the matrix corresponds to two different kinds of indices. One is the column and row indices. The other is the X and Y coordinates. Select **View: Show X/Y** from the main menu to see the X, Y coordinates:

	0	0.1	0.2	0.3	0.4
0	-1	-1.90017	-2.80133	-3.70448	-4.61058
0.1	-0.995	-1.79034	-2.58767	-3.38898	-4.19618
0.2	-0.98007	-1.66063	-2.34419	-3.03371	-3.73208
0.3	-0.95534	-1.51134	-2.07133	-2.63927	-3.21901
0.4	-0.92106	-1.34295	-1.76984	-2.20664	-2.65821
0.5	-0.87758	-1.15616	-1.44073	-1.73721	-2.0514
0.6	-0.82534	-0.95184	-1.08532	-1.2327	-1.40075
0.7	-0.76484	-0.73102	-0.70517	-0.69521	-0.70886
0.8	-0.69671	-0.49491	-0.3021	-0.12714	0.02123
0.9	-0.62161	-0.24489	0.12186	0.46876	0.78613
1	-0.5403	0.01756	0.56446	1.08951	1.58209
1.1	-0.4536	0.29081	1.02324	1.73186	2.40504
1.2	-0.36236	0.57312	1.49563	2.39233	3.25065
1.3	-0.2675	0.86267	1.97887	3.06729	4.11436

4. You can also select **View: Image Mode** to show the image form of the matrix:




5. Select **View: Data Mode** to exit the image mode. Create a contour plot by activating the matrix and selecting **Plot: Contour/Heat Map: Color Fill**. The graph should appear as shown below:




6.9.2.4 Customize Levels, Lines and Color Map

Origin makes it easy to customize every aspect of the contour plot, including the color scale and adding labels:


1. Double click on the contour plot to open the **Plot Details** dialog. Make sure the left panel is expanded by clicking on the arrow button on the bottom left of the dialog. Click on **Layer1** in the left panel (leave the check-box checked, and click on the word itself), and select the **Size/Speed** tab in the right panel. Disable the **Matrix data, maximum points per dimension** box to turn off Speed Mode.
2. Expand the **Layer** option in the left panel and select **[MBook1]MSheet1!1(Z)(1:10201)** under it to open the matrix level options. Select **Colormap/Contours** in the right panel and click on the **Level** heading to open the **Set Levels** dialog. Click the **Find Min/Max** button and set **Major Levels** to 8 and **Minor Levels** to 32. Click the **OK** button.




3. Now load a palette for the contour. Click on the **Fill** heading. In the dialog that opens, select the **Load Palette** radio box. Click the **Select Palette** button and select the **Rainbow** palette from the drop-down. Click **OK**.



4. Click the **Line** heading to open the **Contour Lines** dialog. Check the **Show on Major Levels only** box and click **OK**. Then click the **OK** button to close the **Plot Details** dialog.
5. Set the properties for the color scale. Right click on the color scale and select **Properties** from the context menu to open the **Color Scales Control** dialog. Select **Levels** in left panel, select **All Major Levels** for the **Show on** drop-down list.




6. click **OK**. The contour should resemble the following image:




- Click twice on a contour line (two separate single clicks) to select all lines at that level.

Change the color to **Green** by using the **Line/Border Color** button  in the **Font** toolbar.

Change the width to **3** by using the **Line/Border Width** button  in the same toolbar.



Make sure only one contour line is selected (not all the contour lines at that level) and right click on the selected contour line. Select **Add Contour Label** to add a label.



8. Click twice on a contour line to select it, right click and select **Extract Contour Lines**. Origin will extract the data for that contour line to a worksheet. The following image shows part of the data in the worksheet:

	A(X)	B(Y)
Long Name		
Units		
Comments		
F(x)=		
Z-Level	39.500000	39.500000
Area	12.70802	12.70802
	10.28145	10.28145
	6.06732	6.06732
	2.85618E-4	2.85618E-4
Sparklines		
1	0.36099	10
2	0.36218	9.9
3	0.36377	9.8
4	0.36581	9.7
5	0.36832	9.6
6	0.37133	9.5
7	0.37487	9.4
8	0.37895	9.3
9	0.38362	9.2
10	0.38889	9.1
11	0.39479	9
12	0.4	8.92026
13	0.4014	8.9
14	0.40891	8.8
15	0.41716	8.7


6.9.2.5 Create a Contour Plot from XYZ Data

Origin can create contour plots directly from XYZ data in a worksheet without the need for an intermediate matrix. Delaunay Triangulation is used to compute and draw the contour lines.


1. Create a new worksheet and import the **3D XYZ.dat** from the **\Samples\Matrix Conversion and**


Gridding folder by using the **Import Single ASCII** button .

2. Highlight the third column and right click on it to select **Set As: Z**. Select **Plot: Contour/Heat Map: Color Fill** to create a graph as in the following image:




6.9.2.6 Show the Triangulation Grid


1. Show the triangulation grid that is used to create a contour plot from the data. The individual data points are located at the nodes or vertices of the grid. Create a new worksheet and import the **XYZ Random Gaussian.dat** file from the **\Samples\Matrix Conversion and Gridding** folder by using the **Import Single ASCII** button  .
2. Highlight the third column and right click on it to select **Set As: Z**. Select **Plot: Contour/Heat Map: Color Fill** to create a graph.



- Double click on the contour plot to open the **Plot Details** dialog. On the **Colormap/Contours** tab, click on the **Line** heading to open the **Contour Lines** dialog. Deselect **Shown on Major Levels Only** and select **Hide All** to hide all the contour lines. Click **OK** to close this dialog. Then select the **Show Grid Lines** and **Show Data Points** check boxes. Click **OK** to close the **Plot Details** dialog.




The contour plot with its superimposed grid should look like this:




6.9.2.7 Apply Custom Boundary

A custom boundary can be applied to contour plots created directly from XYZ data where user provides the data points for the boundary in additional columns of the same worksheet. This feature is useful when there is a specific boundary data that defines the outline of an object, for example the profile of an engine where the contour shows engine temperature.


1. Continue to use the worksheet and the contour plot that was created with the **XYZ Random Gaussian.dat** in the previous example.
2. In the **XYZRandomGaus** workbook, click the **Add New Columns** button  twice to add two columns. Highlight the two columns and right click on them. Select **Set As: XY XY** from the context menu and enter four rows of data such as below:

12	10
18	12
16	18
14	16

- Double click on the contour plot to open the **Plot Details** dialog. Select the **Contouring Info** tab in the right panel. Set the dialog as in the following image to customize the boundary for the contour plot. Remember to uncheck the **Show Grid Lines** and **Show Data Points** check boxes in the **Color Map/Contours** tab. Click **OK** to close the Plot Details dialog.




The graph should resemble the following image:



6.9.3 Ternary Contour

6.9.3.1 Summary

This tutorial will show you how to create a Ternary Contour graph and to overlay a scatter plot.



6.9.3.2 What will you learn

- Create the Ternary Contour graph
- Overlay a scatter plot using the Plot Setup dialog box.
- Customize the graph using the Plot Details dialog box.


6.9.3.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Contour**)


1. Open **Tutorial Data.opj** and browse to the **Ternary Contour** folder in **Project Explorer (PE)**.



2. Activate **Book1A**, highlight the entire worksheet and select **Plot: Contour: Ternary Contour** to create a Ternary Contour graph. The graph should look like this:



3. Now we will overlay a scatter plot on the ternary contour graph. Right-click on the layer icon and select **Plot Setup** from the context menu. This opens the **Plot Setup** dialog box.
4. In the upper-left corner of the dialog box, set **Available Data** to **Worksheets in Folder**. Select **Book1**, set **Plot Type** to **Scatter** and select check boxes to the left of columns A, B and C so that they plot as X, Y and Z, respectively. Click **Add** to add the scatter plot to Plot list at the bottom of

the Plot Setup dialog box. The settings should duplicate those shown in the following image:




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.


- Now we will customize the contour graph and the scatter plot. Double-click on the contour plot to bring up the **Plot Details** dialog box.

6. Select the **Color Map/Contours** tab, click on the **Level** heading, then duplicate the settings as shown in the image.




7. Click **OK** to close the **Set Levels** dialog box. Click on the **Fill** heading to open the **Fill** dialog box. Select **Load Palette**. Select **Rainbow** from the **Palette** list and click **OK**.
8. In the left panel of **Plot Details**, select the scatter plot and customize the symbols as follows (note that to enable the **Fill Color** list, you must click the downward-pointing arrow beside

Preview and choose one of the unfilled symbols from the gallery):



9. Click **OK** to close the **Plot Details** dialog box.


10. Drag the color scale to resize it and move it to a suitable place on the graph. The graph should now look something like this:



6.9.4 Combining Line and Contour Plots

6.9.4.1 Summary

This tutorial will show you how to create a Word Map by combining Line Plot and Contour graph.




6.9.4.2 What will you learn

- Create a contour graph
- Combine a Line Plot and a Contour graph
- Customize the contour graph


6.9.4.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open **Tutorial Data.opj** and browse to the **Map Combining Line and Contour Plots** folder in **Project Explorer (PE)**.
2. Activate **MBook1A** matrix and highlight entire matrix. Select **Plot: Contour/Heat Map: Contour - Color Fill** to create a contour graph.




- At this step, we will add a Line plot to the contour graph. Select **Graph: Layer Contents** to open the dialog. In the top-right available data drop-down list of the dialog, choose **Worksheets in Folder**. Select B(Y) column of the Book5 in the left panel, choose **Line** plot type, and add to the right panel. Then click **OK** button. Delete the legend for the added line plot.




4. In the following steps, we will customize the graph. Select **Format: Layer Properties** to open the Plot Details dialog. Select the **Size/Speed** tab, disable two checkboxes that in the **Speed Mode, Skip Points if needed** group.
5. Expand the **Layer1** branch and select contour plot in the left panel of the Plot Details dialog. Then do the following things:
 - o Go to the **Color Map/ Contours** tab, click the **Level** heading to open the **Set Levels** dialog. Set the dialog as the following image shows:




- o Click OK button to close the dialog. Click the **Fill** head to open the **Fill** dialog, select **Introduce Other Colors in Mixing** radio box. Then set **From** to **Orange** and **To** to **Navy**.
- o Click OK button to close the dialog. Click the cell the in the **Fill** column and **<0.5** row to set fill color to **Red**.




- Click OK button to close the dialog. Click the cell the in the **Fill** column and **>7** row to set fill color to **Black**.
- Click OK button to close the dialog. Click the **Lines** heading to open the Contour Lines dialog, uncheck the **Show on Major Levels only** check box and then select the **Hide All** option.
- Click OK button to close the dialog. Click the **Color** box that in the **Missing Value** group, set fill color to **White**. Click OK button.




6. Go to **Numeric Formats** tab of **Plot Details** dialog, select **Decimal Places** radio box and keep the default value **1**.
7. Click **Ok** button to apply the settings to the graph. The graph should look like:




Double click on the **Color Scale** to open the **Color Scale Control** dialog and go to the **Layout** page, do the following setting:



Go to the **Levels** page, do settings as below:




8. Resize and reposition of the color scale. Then modify the X, Y axis tick labels, titles and add the graph title as the example graph shows. The graph should look like



6.9.5 Contour Graph with XY Data Points and Z Labels

6.9.5.1 Summary

This tutorial will show you how to create a contour from XYZ data and add Z value as label for each XY data point.




6.9.5.2 What will you learn

This tutorial will show you how to


- Create a Contour Plot from XYZ data.
- Customize levels, lines, and color mapping.
- Plot a scatter plot on a contour graph.
- Show the labels for scatter points.

6.9.5.3 Steps


1. Start a new workbook and import the file
Sample/Matrix_Conversion_and_Griding/XYZ_Random_Gaussian.dat.
2. Highlight col(C) and set it as Z. Then highlight all columns and select **Plot: Contour/Heat Map: Color Fill** from the main menu to plot a contour graph.




3. Double-click the layer icon to open the **Layer Contents** dialog. In this dialog, select col(B) in the left panel, set the **Plot Type** as *Scatter*, then add it to the right panel.




4. Click **OK** button to close the dialog. The scatter plot will be added to the contour graph.




5. Double-click the graph to open the **Plot Details** dialog. In this dialog, go to the **Colormap/Contours** tab, the contour plot in the left panel is selected. Click the **Level...** header to open the **Set Levels** dialog to set the **Minor Levels** as 4.



6. Click **OK** button to go back the **Plot Details** dialog. Go to the **Label** tab while the scatter plot is selected in the left panel, check the **Enable** check box to activate this tab. Set the **Size** as **12**, **Position** as *Below* and **Label Form** as *Col(C)*.




- Click **OK** button to close this dialog. The Z values will be added as labels to the graph. Click the **Rescale** button  to rescale the graph.

6.9.6 Contour Plot with Vector Overlay

6.9.6.1 Summary

This tutorial will demonstrate how to create a contour plot with vectors overlay.



6.9.6.2 What you will learn

This tutorial will show you how to:

- Create and customize a contour graph and its color scale
- Create the XYAM vector graph
- Merge the two graphs


6.9.6.3 Steps

This tutorial is associated with *<Origin EXE Folder>\Samples\Tutorial Data.opj*.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Contour**)

Create the Contour Graph

1. Open **Tutorial Data.opj** and browse to the **Contour Plot with Vector Overlay** folder in **Project Explorer (PE)**.
2. Activate the **W147** matrix and select **Plot: Contour/Heat Map: Color Fill** in the menu. The graph should appear as shown below:




3. Select **Format: Plot Properties** to bring up the **Plot Details** dialog. In the **Colormap/Contours** tab customize the Contour settings as shown below:
 - In the **Level** heading set the following levels:




- In the **Fill** heading select **Load Palette**, and choose **Temperature** from the **Palette** list. Click **OK**.
- In the **Line** heading, enable the **Color** check box under **Apply to All** and choose **Gray** in the **Color** drop-down list. Click **OK**.

4. In the **Numeric Formats** tab of the **Plot Details** dialog, select the **Significant Digits** radio button and set the value to **1**. Click **OK**.




5. To prepare for merging with the **XYAM Vector** Graph that will be created below, the axes must be hidden. Select **Format: Layer Properties** and in the **Display** tab deselect the **X Axes** and **Y**


Axes check boxes. Click **OK**.




6. Right click on the Y Axis title and choose Delete. Do the same for the X Axis title.
7. To change the color scale, double-click on the scale object. Update the settings as given below:
 - o In the **Labels** node,
 - Set the **Font** to **Verdana**.
 - Set the **Size** to **22**.



- In the **Layout** page,
 - Select **Black Line** from the **Background** drop-down list,
 - Set **Color bar thickness** to **100**.




- In the **Line and Ticks** page, uncheck **Show Line and Ticks on Right** and **Show Border** check box




Click **OK** and position the color scale in the desired location on the right side of the graph by selecting and dragging it.

The contour plot should now appear as shown below:




Create the XYAM Vector Graph

1. Activate the **WOR81147** worksheet, highlight the last three columns and select **Plot: Specialized: Vector XYAM** in the menu.
2. Double-click on any vector to bring up the **Plot Details** dialog on the **Vector** tab. Use the settings shown below:




Then click **OK**.

3. To update the axis scales, select **Format: Axes: X Axis...** to open the dialog and complete the following:
 - o On the **Scale** tab, set **X From = 1**, **To = 10** and **Value of Increment = 2**.




- On the **Scale** tab, choose **Vertical** icon in the left panel of **Axis** dialog. Set the scale of Y as **From = 5**, **To = 95**, and **Value of Increment = 10**.
- Go to the **Line and Ticks** tab in the **Axis** dialog. Press **Ctrl** key to select the **Top** and **Right** icon in the left panel. Then check **Show Line and Ticks** check box, and set the **Style of Major Ticks** and **Minor Ticks** to **In**. The top X and right Y axis will be shown with line and ticks.





- Click **OK**.
4. At this stage, you may notice that the vectors extend outside the axes (layer frame). To make sure they display within the layer frame, select **Format: Layer Properties** and in the **Display** tab

check the **Clip Data to Frame** box. Click **OK**.




5. Right-click on the legend of the vectors graph, and select **Properties...** in the context menu to open the **Object Properties**. Set the dialog as shown below:





Merge the Two Graphs

The contour and vector graphs are generated by the steps above, and are ready to be merged into one.


1. **Minimize** or **Hide** all other graphs except for the contour and vector graphs created using the instructions above. With one of the two graphs active, select **Graph: Merge Graph Window...** from the main menu.
2. In the **Merge Graph** dialog, specify the settings as the following:
 - Expand the **Arrange Settings** node, and set the **Number of Rows** as **1**.
 - Expand the **Spacing (in % of Page Dimension)** node, and enter a value of approximately "25" in the **Right Margin** text box to show the color scale legend from the contour plot. Click **OK**.



3. Click the **Text Tool** button  to create a text at the top color scale legend, and enter **w (ms⁻¹)**.

Highlight **-1** in the text and click on **Superscript** button  in the **Format** toolbar. Set the font size to **26**.


4. To set font type as **Verdana** for all the objects:

- Set the objects individually, by clicking on the object and selecting **Verdana** in the **Font** button  in the **Format** toolbar.

Or

- Use [Theme Organizer](#) to create and apply a font theme to the current graph.

The final graph should look something like this:




6.9.7 Create Heat Map with Virtual Matrix and Colormap Bar Plot

6.9.7.1 Summary

This tutorial create two kinds of graph, a Heat Map Plot based on a virtual matrix together with a Bar Plot with Color Map, and merged them together.

1 2



Minimum Origin Version Required: 2015 SR0

6.9.7.2 What you will learn

This tutorial will show you how to:

- Create Heat Map Plot based on an Virtual Matrix.
- Create Bar Plot with Colormap.
- Merge the Heat Map Plot and Bar Plot together.

6.9.7.3 Steps


Create Heat Map Plot from Virtual Matrix

1. Select **File: Open Sample Projects: Tutorial Data**, and browse to the folder: *Heat Map and Virtual Matrix Manager*. Open workbook *Electricity Usage* with first sheet active.
2. The XYZ mapping of workbook is shown in graph below, this will help you to understand how the Heat Map plot is created in next steps:

	Z1(Y)	A(X)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)
Long Name		X →	1:00	2:00	3:00	4:00	5:00
Units							
Comments							
F(x)=		↓ Y			Z		
1	Jan	1/1/2013	14327	14190	13785	13730	13820
2	Jan	1/2/2013	14919	14732	14721	14817	15098
3	Jan	1/3/2013	16864	16547	16361	16285	16649
4	Jan	1/4/2013	16547	16209	16083	16117	16513
5	Jan	1/5/2013	16298	16000	15870	15943	16107
6	Jan	1/6/2013	14175	13902	13747	13706	13828
7	Jan	1/7/2013	14805	14645	14549	14702	15082
8	Jan	1/8/2013	16355	16130	16160	16240	16614
9	Jan	1/9/2013	15391	15102	14967	14852	15143
10	Jan	1/10/2013	14337	14103	14100	14220	14555
11	Jan	1/11/2013	14175	13882	13595	13637	13815
12	Jan	1/12/2013	12831	12409	12272	12128	12250
13	Jan	1/13/2013	11632	11303	11073	11012	11008
14	Jan	1/14/2013	12501	12391	12352	12464	12951
15	Jan	1/15/2013	15090	14799	14724	14777	15008
16	Jan	1/16/2013	15450	15180	15053	14898	15145
17	Jan	1/17/2013	15088	14521	14448	14388	14710


3. Highlight all cells in Z region. In order to quickly select all, select the Cell in Column(B)-Row 1 and use the worksheet scroll bars to show the cell in last column and last row, hold **Shift** key and click this cell to select all. click **Plot: Contour/Heat Map: Heat Map** in main menu to open the plotvm dialog for Heat Map plot.

4. Specified the X, Y ranges as shown in graph below.




- In this dialog, check **Format X Data** and **Format Y Data** check boxes, click the button


 respectively to format X and Y data following the graph below:




- The tick labels in Y axis are too dense to be seen, so now we are going to change that. Double click the axis in the graph to open the **Axis** dialog:
 - Select **Left** icon in **Tick Labels** tab, go to **Display** tab, select *Date* as the **Type**, and set **Display** drop-down list to *Dec(Current Month)*, click **Apply** to save the setting.




- Go to the **Table** tab, check on **Enable** box, click **Apply** to save. You will find that the month names are shown as tick labels for Y axis in the form of a table.




7. Next, we will specify the scale and tick labels for X axis:
 - o Go to **Bottom** icon in **Tick Labels** tab, and make sure **Time** is selected as the Type in **Display** tab, change the **Display** to *hh pm*, click **Apply** to save the setting.



- o Go to **Horizontal** icon in **Scale** tab, make sure the settings resemble the screenshot below, click **Apply** to save the setting. Click **OK** to close the dialog. Remove the title for X axis.




8. Click the tick labels for both XY axes in the graph, change the font size to 10 via **Format** Toolbar.
9. Select **Format: Plot Properties** in main menu with Heat Map graph active.
 - o Set the Level for Colormap follows the graph below:




Click **OK** to close the Set Levels dialog



- o Click the Fill color of the Colormap on head cell(blue area) to set Fills follows the graph below:




- Scroll down to the Colormap tail, set its fill color to red in the same way.
- Click **Save** in **Colormap/Contours** tab to save the pattern as heatmap.oth which will be used in the second parts of the graph.




10. In the **Plot Details** dialog, click the first tree node in left panel (should be **Graph1** by default), change page size to 11*11 inch in **Print/Dimensions** tab, click **Apply**, then in the left panel, select the sub tree node for **Layer1**, go to the **Size/Speed** tab, change the Layer area follows graph below, click **OK** to apply the settings and exit the dialog:



11. We will turn off the speed mode by click the  in Graph Toolbox to view the graph with higher resolution. The finished graph for Heat Map should be similar to the graph below:




Once the Virtual Matrix were created, they will be saved internally. You can browse them in Virtual Matrix Manager. The saved Virtual Matrix can be used for Contour/Heat Map/3D surface plot directly, you can select the virtual matrix from the input box of the plot dialog as shown in graph below:




Create the Bar Plot with Colormap

1. Go to the Temp sheet in Electricity Usage workbook, highlight the worksheet and select **Plot: Column/Bar/Pie: Bar** in main menu to create a Bar plot.
2. Now, we will defined the style of axis:
 - Double click the axis to open the **Axis** dialog, change the **Scale** of axis (X) follows the graphs below in Vertical page of the **Scale** tab.




- Then, change the Scale for axis(Y) in Horizontal page from -55 to 55 with *Major Ticks* value 25 and *Minor Ticks* counts 1, then click **Apply**.




- We will also hide the line and ticks for X axis in **Line and Ticks** tab by uncheck the box of **Show Line and Ticks**. Besides, grids can be hide by using similar ways in **Grids** tab.
 - Click **OK** to close the dialog.
 - Change the Y axis title to *CDD/HDD* by double clicking on the Y title object and entering the in-place edit mode. Delete the ticks labels and axis title of X axis by select it and hit **Delete** key.
3. Next, we will create the Colormap for the graph, the Colormap theme should be identical to the Heat Map created before. Click the **Format: Plot Properties** in main menu to open the **Plot Details** dialog:
- Set the color for both Border and Fill as **Map:Col(B)**.


Tutorials for Origin



- Go to the **Colormap** tab, load the heatmap.oth as Colormap Theme.





- Click the Level of the Colormap to set Levels follows the graph below:




Click **OK** to close the **Set Level** dialog and Click **Apply** in Plot Properties dialog to save the settings.

- In the left panel, select the first tree node (by default, **Graph2**), change page size to 11*11 inch in **Print/Dimensions** tab, click **Apply**, then switch to the **Layer1** tree node and go to the **Size/Speed** tab, change the Layer area follows graph below, then,click OK to close dialog:

Tutorials for Origin




The finished bar plot is similar to the graph below:




Merge the Heat Map Plot with Bar Plot and More Customization Steps

1. Select **Graph: Merge Graph Window** in main menu with Heat Map graph active, merge Graph1 and Graph2 together, the **Rearrange Layout** should be unchecked, click **OK** to apply the setting.




hen, you will resize the size of the merged graph (Graph3), click **Format: Page Properties >> Print/Dimensions** tab, change the page size to 11*11 inch again, click **OK**. Click **CTRL+W** to adjust the graph view.


2. Specify the style of the color scale:
 - Double click the color scale to open the Color Scale Control dialog, set the Levels page as shown in graph below:



- Set the Labels page as shown in graph below:




- Set the Layout page as shown in graph below:



Click **OK** to apply the settings, drag the outline of the color scale in the graph to reach a proper size and location.

3. Select the unwanted axis title or legend and delete them, add text object with graph information by using text tool.

The finished graph is similar to the graph below:



6.10 Statistics


- [Box Plot](#)
- [Grouped Box Chart with Color Indexed Data Points](#)
- [I Shaped Box Plot](#)
- [Marginal Distribution Curve](#)
- [Overlapping Box Chart](#)

- [Two-Level Grouped Box Chart](#)
- [Unbalanced Grouped Box Chart](#)
- [Grouped Box Plot](#)
- [Notched Boxes with Variable Width Control](#)
- [Simple Dot Chart](#)
- [Multi-Data Dot Chart](#)
- [Add multiple fitted curves in a Histogram](#)
- [Weibull Probability Plot](#)
- [Q-Q Plot](#)
- [Scatter Matrix](#)
- [Histogram with Distribution Curve overlay](#)

6.10.1 Box Plot

6.10.1.1 Summary

This tutorial demonstrates how to create the following box plot in the Statistical and Specialized Graphs project (\Samples\Statistical and Specialized Graphs.opj):



Minimum Origin Version Required: Origin 2015 SR0

6.10.1.2 What you will learn


This tutorial will show you how to:

- Create a data overlapped box plot
- Customize box plot settings
- Change the layer background


6.10.1.3 Steps

This tutorial is associated with : <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open **Tutorial Data.opj** and browse to the **Box Plot** folder in **Project Explorer (PE)**.
2. Activate the **BoxData** worksheet, select the January(Y), February(Y), and March(Y) columns and plot them as a Box Chart using **Plot: Statistics: Box Chart**.
3. Double-click on one of the box charts to bring up the **Plot Details** dialog. In the **Group** tab select **None** from the **Border Color** drop-down list and use **Apply** to save the changes. This prevents the border colors of the box plots from automatically incrementing.
4. In the **Box** Tab, set as shown below to enable the data plot to the left of box:




5. The **Data** tab shows up because data plot is also included in the plot. In this tab, change the settings as shown below to create a distribution curve and change the binning options:




- In the **Pattern** tab adjust the settings as shown below. To create a custom color, select the **Color** option, click **Define Custom Colors** and in the dialog box that appears specify the **Red**, **Green** and **Blue** values in the bottom right of the dialog as shown below:




- In the **Lines** Tab set the line style for Whisker. The style of caps is set to "Auto" so it follows the Whisker style, and the style for Median Line and Distribution Curve follows the box style set in the **Pattern** tab:



8. The next step is to customize the data symbols in the **Symbol** tab:



9. The style of the Percentile points is also changed in the **Percentile** tab:




10. The next step is to change the background color. In the same **Plot Details** dialog, select **Layer 1** in the left panel to activate the tabs of layer level. If the left panel is not expanded use the




button on the bottom left of the dialog to expand it. In the **Background** tab, click on the **Color** option. Select **Define Custom Colors** in the Color box that opens and set the values for the Red, Green and Blue edit boxes as on the bottom right of the dialog that opens as: R:177, G:237, B:254. Click **OK** to accept the setting and close the dialog.


11. In order to customize the axes, double-click on the Y Axis to open a **Axes** dialog box and on the **Scale** tab, set the following axis scale specifications:




- Go to the **Title** tab, select **Left'** icon in the left panel, change the Y axis title to *Discharge* $[ft^{3}/sec]$:




13. On the **Title** tab, choose **Bottom** icon in the left panel. Then check the **Show** check box, and change the X axis title to *Month*



14. Open the **Grids** tab, select **Horizontal** icon in the left panel, enable the **Major Grid Lines** and the **Opposite** box under **Additional Line**:



15. Enable the **Opposite Line** check box on the **Grids** tab when the **Vertical** icon is selected in left panel :




Click **OK** to save the setting and close the dialog.

16. The legend can be deleted if desired by selecting it and pressing the delete key.
17. Right-click the layer and select **Add/Modify Layer Title** from the menu that appears. Enter the text *Water Discharge at Station 120011* in the edit box. Existing layer titles and axes titles can be modified by double clicking on them till the text cursor appears.

6.10.2 Grouped Box Chart with Color Indexed Data Points

6.10.2.1 Summary

Origin can be used to create grouped box plots from raw data with data points and distribution curves.



Minimum Origin Version Required: 2015 SR0

6.10.2.2 What you will learn

This tutorial will demonstrate how to:

- Create a grouped box plot from raw data
- Add a data plot with indexed symbol color
- Add and customize a distribution curve
- Customize the table-axes

6.10.2.3 Steps

Creating the Box Plot from Raw Data


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open **Tutorial Data.opj** and browse to the folder *Grouped Box with Index Color DataPoint*.
2. Activate the workbook **Book 5**.

- Highlight col(E) - col(J):


	A(X)	B(Y)	E(Y)	D(Y)	H(Y)	G(Y)	K(Y)	J(Y)
Long Name	ID	Machine	CC	MI	CC	MI	CC	MI
Units								
Comments			SEG 1	SEG 1	SEG 2	SEG 2	SEG 4	SEG 4
Filter								
1	AW390-0004	A386	4452.104	3071.058	4450.663	2589.701	5455.25	2979.168
2	AW390-0006	A386	6292.571	4381.999	4904.638	3202.871	5190.99	3454.301
3	AW390-0060	A386	10878.101	10025.173	9108.109	--	14491.19	10921.643
4	AW310-0139	A386	11236.832	6416.926	16297.672	10051.399	14981.875	8422.052
5	AW200-0040	A386	13334.318	9335.14	13429.485	9453.363	12235.172	8046.704
6	AW220-0009	A386	7562.084	--	7909.844	4473.576	10180.23	7816.758
7	AW170-0015	A386	8144.457	6306.148	9991.454	7582.644	10140.814	7416.709
8	AW098-0011	A386	1969.712	954.747	3752.383	1617.506	3237.382	1147.074
9	AW098-0047	A386	8094.329	5437.389	8912.438	6785.827	8785.203	5694.113
10	AW098-0127	A386	6629.159	3712.809	4808.346	4007.431	4957.694	2748.815
11	AW080-0020	A386	4798.724	4063.268	3556.263	3416.191	4933.238	--
12	AW080-0032	A386	3890.026	1969.526	6330.462	4160.389	6933.1	3504.334
13	AW080-0058	A386	6647.061	3728.53	6982.513	3753.326	6973.886	4319.772

- On the **2D Graphs** toolbar click the small triangle at the bottom of the sixth button to reveal the fly out menu. Select **Grouped Box Charts - Raw Data** as shown below:




- In the **Plotting: plotgboxraw** dialog, set the **Group Number** to **2**, the **1st Group Row** to **Comments** and the **2nd Group Row** to **Long Name**. This will create a box chart with the

column data arranged in three groups of two, with X axis row names derived from the Comments and the Long Names on the worksheet:




- Click the **OK** button. The grouped box chart from raw data is created with two grouping levels as shown below:




- To add data points in the graph, double click the plot to open the **Plot Details** dialog. Expand the **Layer1** option on the left panel and select the first plot under it.


- On the **Box** tab, set **Type** to **Box[Right] + Data [Left]**. Click the **Apply** button. This will add two new tabs to the dialog: **Data** and **Symbol**




- To add a Distribution Curve, on the **Data** tab, set Distribution Curve **Type** to **Normal**. Set **Bins Alignment** to **Right** to orient the curve.





- Click the **OK** button. The data points and distribution curves will appear on the graph as shown below:



Customizing the Boxes and Statistical Markers

1. Double click on the any one of the boxes to re-open the **Plot Details** dialog.
2. On the **Group** tab set both **Border Color** and **Box Color** to increment **By One** so each box in subgroup has a different color.
3. Click the  button on the **Details** section of **Border Color**. In the **Increment Editor** dialog that opens, click the first color and change it to be **Red**. Change the second color to **Gray**. Click OK.

- Click the  button on the **Details** section of the **Box Color** to open the **Increment Editor** dialog. Click 1st color and click **Define Custom Color** button.



- Set **RGB** values in **Red**, **Green**, **Blue** boxes on bottom right to be **255**, **51** and **51**, and click **OK** to close dialog.
- Do the same for the 2nd color. Set Define **RGB** value to be **143**, **143** and **143**, and click **OK** to close dialog. Then click **OK** to close **Increment Editor** dialog and apply settings.
- This step is to customize the descriptive statistic markers whether to show on the plot such as the **99%**, **1%**, **Max** and **Min** marks.


Go to the **Percentile** tab, and set the **Edge Color** to **White** and click **Apply** button. Since background of the graph is also white, **Max**, **Min**, **99%**, **1%** will look like disappeared in graph.



On **Percentile** tab, users can also hide a Marker by setting the **Type** as **None**(the last shape) in the dropdown list.

- On the **Lines** tab set the **Color** for the **Whisker** and the **Caps** to **Gray** and **Median Line** to **White**.

Click **OK**. The plot should appear as shown below:




Customizing Data Symbols and Distribution Curves


1. Double click any box in the graph to open the **Plot Details** dialog.
2. On the **Symbol** tab. Set the **Size** to **5**, the **Shape** to **2 Circle** and the **Interior** to **Open**.
3. Click the **Edge Color** dropdown list and choose **Indexing: Col(B):Machines**. The symbol's edge colors will be indexed to column B. All symbols with Machine value **A386** will be one color and the ones with **C334** will be a different color:

	A(X)	B(Y)	
Long Name	ID	Machine	
Units			
Comments			SI
Filter			
15	AW080-0115	A386	23
16	AW078-0092	A386	49
17	AW192-0095	A386	84
18	AW560-0069	A386	159
19	AW480-0118	A386	59
20	AW340-0079	A386	60
21	AW287-0138	A386	70
22	AW390-0004	C334	32
23	AW390-0006	C334	35
24	AW390-0060	C334	70
25	AW310-0139	C334	77
26	AW200-0040	C334	96

- When symbol color is indexed, another tab **Color List** will appear in the dialog. To set a user defined color increment list, go to the **Color List** tab. Enable the **Use custom increment list** box and set the first two **Color Values** as **Blue** and **Dark Cyan**.



- To customize the distribution curve color, on the **Lines** tab, set the Distribution Curve **Color** to **Gray**.
- Click **OK** to close the dialog.




Customizing the Axes


For grouped plots support multi-row tick label tables. The corresponding axis icons in the **Tick Labels** tab of **Axis dialog** starts from the last table row, e.g. **Bottom 1**, **Bottom 2**, ..., **Bottom N**. This means the first row from the bottom will correspond to **Bottom1** and so forth.

Tutorials for Origin


1. To move the tick label row with **SEG 1**, **SEG 2** and **SEG 3** to the top X axis, double click on this tick label row.
2. This opens the **Axis Dialog** with the **Bottom 1** axis icon selected. Right click the **Bottom 1** icon on the left panel and choose **Move to Opposite**.




3. Click the **Apply** button. The **SEG 1**, **SEG 2** and **SEG 3** tick label row will now appear at the top X axis on the graph, and as the axis icon is renamed as **Top 1** on the left panel in the dialog.
4. The previous **Bottom 2** icon will become the **Bottom 1** icon. Select the **Bottom 1** icon. Go to the **Table** tab. Set the **Number of Rows** to **3**. Click the **Apply** button. Three identical bottom tick label tables will appear on the graph and they are **Bottom 1**, **Bottom 2** and **Bottom 3**.
5. To fill first bottom tick label row with light gray, select the **Bottom 3** icon on the left panel, make sure you are still at the **Table** tab and clear the **Auto** check box to enable separate control of tick label table layout. Set **Fill Color** as **LT Gray** and deselect the **Inside Border** check box under **Table Layout** node.
6. The second row derives the labels from col(C) of the second worksheet **A386_CC.MI**. Select the **Bottom 2** icon and go to the **Display** tab, set the **Type** to **Text from dataset** and set the **Dataset Name** from the drop down as **[Book5]"A386_CC.MI"!C"N"**.
7. Go to the **Format** tab and clear the **Auto** check box, change the **Color** to **White**. Then go to the **Table** tab and set as the following:




8. Select the icon **Bottom 1**, go to the **Display** tab, set the **Type** to **Text from dataset** and then set the **Dataset Name** as `[Book5]"C334_CC.MI"!C"N"` since it uses col(C) from the third worksheet **C334_CC.MI**.
9. Go to the **Table** tab and set the table layout as below:



10. Select the **Top 1** icon, go to the **Table** tab and set the table layout for top axis as below:




11. Then go to the **Format** tab, set **Font Size** to 22 and change the tick labels to **Bold**:



12. For the Y Axis change to the following settings:
 - **Scale** tab (**Vertical** icon): Set **Increment** to **5000**
 - **Tick Labels** tab >> **Display** tab (**Left** icon): Set **Display** to **Scientific 10^{^3}**
13. Click **OK** to close the dialog.
14. Select Y axis title **Range** and press the **Delete** key to remove it.

Updating the Legend and Adding Text Objects


1. Right click the box chart legend and select **Legend: Box Chart Components...** to open the **Enhanced Box Legend: legendbox** dialog. Deselect all the components except for **Data**:




2. Click the **OK** button. The legend will show only the data symbols. Double click the legend text to go into in-place edit mode. Delete the first row of the legend. Select and drag to move the legend object to a better location.
3. To remove the black line around the legend, right click the legend object and choose **Properties....** In the **Object Properties** dialog, go to **Frame** tab to set **Frame** to **None**.
4. Origin doesn't support tick label table titles yet. But users can add text objects manually. Right click on the white space to the left of the second bottom tick label row and choose **Add Text...**

from the context menu that appears. Type **NA386=**. Then, still in in-place edit mode, highlight A386 and click the x_2 button on the **Format** toolbar to change it into subscript. Select and drag to adjust the positioning.

5. Add another text object NC334= to the left of the third tick label row and change C334 into subscript.



The final graph should appear as shown below:



6.10.3 I Shaped Box Plot

6.10.3.1 Summary

Origin's box plot is highly customizable. This tutorial shows how to create a I-Shaped box chart with overlapping data points and customized percentiles.

Weather History for Boston, Fall (Sep, Oct, Nov)



Minimum Origin Version Required: 2015 SR0


6.10.3.2 What you will learn

- Customize box plot settings
- Customize the axis dialog for box plots
- Add a line object to a box plot


6.10.3.3 Steps to Create a I-Shaped Box Chart with Data Point

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data.opj and browse to folder *I-Shaped Box*.
2. Activate workbook **Book1, Sheet1**. Highlight columns A through K and then select **Plot: Statistics: Box Chart**. Next, select and delete the legend object from the graph.
3. Double-click on one of the plot boxes to bring up the **Plot Details** dialog box. Go to the **Box** tab and set **Type** to **Box + Data Overlap**, **Style** to **I-shaped Box** and **Whisker Range** to **Min-Max**, and check **Outliers** box.



4. Go to the **Data** tab and set **Data Width (%)** to 0.


Group	Pattern	Spacing	Box	Percentile	Lines	Data	Symbol
Type	Dots						
<input type="checkbox"/>	Jitter Points						
<input type="checkbox"/>	Single Block Barplot						
<input type="checkbox"/>	Snap Points To Bin						
<input checked="" type="checkbox"/>	Automatic Binning						
<input checked="" type="radio"/>	Bin Size	5					
<input type="radio"/>	Number of Bins	14					
	Begin	20					
	End	90					
	Bin Height (0-100)	100					
Bin Worksheet							
<input type="checkbox"/>	Add Distribution Curves						
							Go
				Distribution Curve			
				Type None			
				Bins Alignment			
				<input checked="" type="radio"/> Center			
				<input type="radio"/> Right			
				<input type="radio"/> Left			
				Data Width (%) 0			
				Preview			
							
The Counts column in the Bin Worksheet can be used for fitting.							

5. Click **OK** to apply the settings.




6.10.3.4 Further Customizations to Box Style


1. Double-click on one of the plot boxes to bring up the **Plot Details** dialog box again. Go to the **Group** tab and set **Border Color Increment** to **None**.




2. Go to the **Symbol** tab, set symbol **Shape** as **1 Square** and **Interior** as **Open**, then set both **Edge Color** and **Fill Color** to **15 Orange**. Clear **Follow line transparency** and set the **Transparency** slider to 80%.




3. Go to the **Pattern** tab and set **Border Color** to **Purple** and **Width** to 1.5.



4. Go to the **Spacing** tab and set **Gap Between Boxes(in %)** to 0.
5. Go to the **Percentile** tab and duplicate the settings as shown below for **Type** and check **Custom Percentiles at <P, 100-P>** box.




6. Go to the **Lines** tab and duplicate settings as shown below.




7. Click **OK** to apply the settings.

6.10.3.5 Further Customizations to Axes


1. Double-click on the X axis to open the Axis Dialog box. Go to the **Scale** tab and set **Minor Ticks Count** to 1.




2. Go to the **Format** tab under **Tick Labels** page and hold Ctrl key to select both **Bottom** and **Left** icons on left panel and set label **Color** to **Black**.




3. Go to the **Grids** tab and click to select only **Vertical** icon on left panel and duplicate **Minor Grid Lines** settings as shown below.




4. Go to **Line and Ticks** tab and click on the **Top** icon on left panel and check the **Show Line and Ticks** box to show top axis.
5. Hold Ctrl key to select both **Bottom** and **Top** icons on left panel, duplicate settings as shown below and click **Apply** to see your changes.




6. To customize the Y Axis, go to **Scale** tab and click **Vertical** icon on left panel and duplicate the settings as shown below.




7. Go to the **Title** tab and type **Temperature (°F)** into the **Text** box.
8. Go to **Grids** tab and check the **Opposite** box under **Additional Lines** node.



9. Go to **Line and Ticks** tab and set **Color** under **Line** node to be **Gray**.




10. Click **OK** to apply your settings.




6.10.3.6 Adding a Line to Mark the Mean

1. Highlight all the columns in Book1. The global mean value will be calculated automatically and shown on the Status bar.



2. Activate the graph window and select **Graph: Add Straight Line** from the menu. In **addline** dialog, duplicate settings as shown below.




3. Right-click on an empty portion of the graph and select **Add/Modify Layer Title**. Type **Weather History for Boston, Fall (Sep, Oct, Nov)**
4. Drag and re-position the axis and layer titles as needed.

6.10.4 Marginal Distribution Curve

6.10.4.1 Summary

Graphs in Origin are highly customizable. This tutorial will show how to customize the marginal histogram to display distribution curves instead of columns.



Minimum Origin Version Required: 2015 SR0

6.10.4.2 What you will learn


- Create marginal histogram
- Use filter lock to create plots with different filter conditions.
- Group plots manually

6.10.4.3 Steps to Use the Filter Lock


Origin9.1 includes a special feature that allows you to set up different data filters in a single source worksheet and to, for instance, graph data for each filter condition without destroying the previous plot. This is made possible by copying filtered data to a new sheet and placing a "filter lock" on the filtered data.

1. Import <Origin EXE Folder>\Samples\Statistics\automobile.dat to a new blank workbook.
2. Highlight col(A), right click and select **Filter: Add or Remove Filter**.
3. Click the filter icon in the column header and select **Between....**
4. In the **Between** dialog, set **From** to 1992, **To** to 1995 and press **OK**.
5. Highlight Col("Power") and Col("Weight"), right-click and select **Copy Columns to....**

- In the **colcopy** dialog, enter **1992~1995!<new>** in the **Destination Columns** text box as shown below and click **OK**.




- In the newly created sheet, click the green lock in the Col(A) heading and select **Worksheet Filters: Lock**.




- Go back to the "automobile" sheet and repeat steps 4~7 twice more with Col("Year")'s filter conditions set to 1996~1999 and 2000~2004, respectively. You need to type a sheet name in **colcopy** dialog manually each time. The filter conditions are locked with each sheet, you can push them back using **Worksheet Filters: Push Back**.

6.10.4.4 Steps to Create a Plot with Marginal Distribution Curves


1. Go to sheet "1992~1995", highlight all columns and select **Plot: Statistics: Marginal Histograms**




2. Double-click any on any bar in the top histogram to open the **Plot Details** dialog. Go to the **Data** tab and set **Distribution Curve: Type** as **Normal**. This is for **Layer 2**.




3. Go to the **Pattern** tab and reproduce the settings shown below to hide bin bars.



4. Go to the **Line** tab and set **Color** to Black. Click **Apply** to see the changes.





5. Repeat steps 2~4 for Layer3 (right histogram).



6.10.4.5 Steps to Plot Grouped Marginal Distribution Curves

1. Select **Graph: Plot Setup** from menu.



In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

2. Select **Layer 1** in lower panel. Set controls as shown below and click **Add**.

Available Data:

Long Name	Sheet	Cols	Rows	File Name	File Date	Created	Modified
automobile.d automobile	7	360	automobile.dat	9/4/2014	9/5/2014 17:53:18	9/5/2014	
automobile.d 1992~1995	2	360	automobile.dat	9/4/2014	9/5/2014 17:53:18	9/5/2014	
automobile.d 1996~1999	2	360	automobile.dat	9/4/2014	9/5/2014 17:53:18	9/5/2014	
automobile.d 2000~2004	2	360	automobile.dat	9/4/2014	9/5/2014 17:53:18	9/5/2014	

Right-click on various panels to bring up context menus.

Plot Type:

Show(S) [automobile]1996~1999

X	Y	yEr	L	Column	Long Name	Comments	Sampling Interval	Position
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<auto>	From/Step=			0
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A	Power			1
<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	B	Weight			2

Plot List: Drag entries in 1st column to reorder or to move between layers. Right click for other options.

Replace Add

Plot	Range	Show	Plot Type	Legend
Layer 1	<input type="checkbox"/> Res	<input checked="" type="checkbox"/>		
[automobile.dat]1992~1995! "Power"[X], "Weight"[Y]	[1*:116*]	<input checked="" type="checkbox"/>	Scatter	Weight
Layer 2	<input type="checkbox"/> Res	<input checked="" type="checkbox"/>		
Layer 3	<input type="checkbox"/> Res	<input checked="" type="checkbox"/>		

3. Add the "Power" histogram to layer2.

The screenshot shows the Origin software interface. At the top, the 'Available Data' panel lists four data sheets: 'automobile.c automobile', 'automobile.c 1992~1995', 'automobile.d 1996~1999', and 'automobile.c 2000~2004'. The 'automobile.d 1996~1999' sheet is selected. Below this, the 'Plot Type' dropdown menu is open, showing options like 'Pie', 'Bar', 'Stacked Column / Bar', 'Stacked Bar', 'XYZ Contour', 'Box', and 'Histogram'. The 'Histogram' option is highlighted. In the 'Show(S)' panel, a table lists columns 'A' and 'B' with long names 'Power' and 'Weight' respectively. The 'Power' row is selected. At the bottom, the 'Plot List' panel shows three layers. Layer 2 is selected and highlighted in blue. The 'Add' button in the 'Plot List' panel is highlighted with a pink box.

Long Name	Sheet	Cols	Rows	File Name	File Date	Created	Modified
automobile.c automobile	automobile	7	360	automobile.dat	11/11/2013	11/11/2013 14:39:25	11/11/2013 14:39:25
automobile.c 1992~1995	automobile	2	360	automobile.dat	11/11/2013	11/11/2013 14:39:25	11/11/2013 14:39:25
automobile.d 1996~1999	automobile	2	360	automobile.dat	11/11/2013	11/11/2013 14:39:25	11/11/2013 14:39:25
automobile.c 2000~2004	automobile	2	360	automobile.dat	11/11/2013	11/11/2013 14:39:25	11/11/2013 14:39:25

Y	Column	Long Name	Comments	Sampling Interval	Position
<input checked="" type="checkbox"/>	A	Power			1
<input type="checkbox"/>	B	Weight			2

Plot	Range	Show	Plot Type	Legend
Layer 1	<input type="checkbox"/> Rescale	<input checked="" type="checkbox"/>		
[automobile.dat]1992~1995! "Power"[X], "Weight"[Y] [1*:116*]		<input checked="" type="checkbox"/>	Scatter	Weight
[automobile.dat]1996~1999! "Power"[X], "Weight"[Y] [1*:112*] 39 < X < 121 , 739 < Y < 2281		<input checked="" type="checkbox"/>	Scatter	Weight
Layer 2	<input type="checkbox"/> Rescale	<input checked="" type="checkbox"/>		
[automobile.dat]1992~1995! "Power"[Y]	[1*:116*]	<input checked="" type="checkbox"/>	Histogram	Power
Layer 3	<input type="checkbox"/> Rescale	<input checked="" type="checkbox"/>		
[automobile.dat]1992~1995! "Weight"[Y]	[1*:116*]	<input checked="" type="checkbox"/>	Histogram	Weight

4. Add the "Weight" histogram to Layer3.

- Repeat steps 2~4, to add 2000~2004 data to each layer. The plot list should look like the following.


Plot List: Drag entries in 1st column to reorder or to move between layers. Right click for other options. Replace Add ⌵

Plot	Range	Show	Plot Type	Legend
Layer 1	<input type="checkbox"/> Rescale	<input checked="" type="checkbox"/>		
[automobile.dat]1992~1995! "Power"(X), "Weight"(Y)	[1*:116*]	<input checked="" type="checkbox"/>	Scatter	Weight
[automobile.dat]1996~1999! "Power"(X), "Weight"(Y)	[1*:112*] 39 < X < 121 , 739 < Y < 2281	<input checked="" type="checkbox"/>	Scatter	Weight
[automobile.dat]2000~2004! "Power"(X), "Weight"(Y)	[1*:112*] 33 < X < 85 , 724 < Y < 1847	<input checked="" type="checkbox"/>	Scatter	Weight
Layer 2	<input type="checkbox"/> Rescale	<input checked="" type="checkbox"/>		
[automobile.dat]1992~1995! "Power"(Y)	[1*:116*]	<input checked="" type="checkbox"/>	Histogram	Power
[automobile.dat]1996~1999! "Power"(Y)	[1*:112*] 39 < Y < 121	<input checked="" type="checkbox"/>	Histogram	Power
[automobile.dat]2000~2004! "Power"(Y)	[1*:112*] 33 < Y < 85	<input checked="" type="checkbox"/>	Histogram	Power
Layer 3	<input type="checkbox"/> Rescale	<input checked="" type="checkbox"/>		
[automobile.dat]1992~1995! "Weight"(Y)	[1*:116*]	<input checked="" type="checkbox"/>	Histogram	Weight
[automobile.dat]1996~1999! "Weight"(Y)	[1*:112*] 739 < Y < 2281	<input checked="" type="checkbox"/>	Histogram	Weight
[automobile.dat]2000~2004! "Weight"(Y)	[1*:112*] 724 < Y < 1847	<input checked="" type="checkbox"/>	Histogram	Weight


- Click **OK** to close the **Plot Setup** dialog box and rescale the graph.

6.10.4.6 Steps to Group the Plots

- Right-click the layer icon **1** at the upper-left corner of the graph window and select **Layer Contents...**
- Highlight all three plots and click **Group**, then click **OK**.



- Repeat step 2 for layer2 and layer3.



6.10.4.7 Steps to Further Customization

1. Double click the bottom axis to open the **Axis Dialog** for layer 1, then go to the **Scale** tab, and set the axis scale for the **Horizontal**(X axis) and **Vertical**(Y axis) as below respectively:

X Axis - Layer 1

Scale | Tick Labels | Title | Grids | Line and Ticks | Special Ticks

Horizontal
Vertical

From: 20
To: 180

Type: Linear

Rescale: Normal

Rescale Margin(%): 8

Reverse:

Major Ticks

Type: By Increment

Value: 20

First Tick:

Minor Ticks

Type: By Counts

Count: 1

Y Axis - Layer 1

Scale | Tick Labels | Title | Grids | Line and Ticks | Special Ticks | E

Horizontal
Vertical

From: 500
To: 2500

Type: Linear

Rescale: Normal

Rescale Margin(%): 8

Reverse:

Major Ticks

Type: By Increment

Value: 500

First Tick:


Minor Ticks

Type: By Counts


Count: 1

Tutorials for Origin


2. Click **OK** to close axis dialog. Double click on the graph to open the **Plot Details** dialog box and select the first dataplot in **layer 1** to go to **Group** tab. Set **Symbol Type** as **None** and duplicate the following settings:




3. Click **Ok** to close the dialog. Go to the **Symbol** tab and duplicate the following settings.



4. Go to **Layer 2, Data** tab and set the bin scale to be the same as the X scale, then click **Apply**.




5. Go to the **Group** tab for plots in Layer 2 and set the **Edit Mode** to **Independent** so that we can individually customize the plot styles, click **Apply**.




6. Go to the **Pattern** tab and hide bars for all three dataplots in Layer2 as what we did in [Steps to Create a Plot with Marginal Distribution Curves, Step3](#).
7. Go to **Line** tab of the 1992~1995 data plot and set as below.



8. Repeat step 7 for the other two plots in Layer2 and set line color to the corresponding symbol color in Layer1.
9. Repeat steps 5~8 for Layer3, click **OK** to close **Plot Details** dialog and apply settings.
10. Activate Layer1 and select **Graph: Legend: Data Plots** from the menu.
11. Right click the legend object and click **Properties...**, set **Background** to **Black Line**, and font Size to be **18**. Click **OK**.
12. Use **Format:Page Properties** to open the **Plot Details - Page Properties** dialog, go to **Legends/Titles** tab and set as the following so that worksheet name will be used as legend text:




13. Drag and move the legend to a new position as needed. At this stage the graph should look like below:




6.10.4.8 Steps to Reposition the Graph Layers


1. Double click bottom axis to open **Axis Dialog** for layer 1, go to the **Grids** tab, hold **Ctrl** key to multiple select **Vertical** and **Horizontal** icon and set the following:



- Click **OK** to close dialog. Open the **Axis Dialog** for layer 2. Go to the **Line and Ticks** tab, make sure **Bottom** axis icon is selected and clear the **Show Line and Ticks** check box to hide the bottom axis line. Do the same for the axis line of **Left** in layer 3.
- Open the **Layer Management** dialog box, highlight Layer2 then go to the **Size/Position** tab, select **Move** and set **Top** to be -35. Click **Apply**.




- Set **Left** for Layer3 to be 102. Click **Apply**. Then click **OK** to close the dialog box.



6.10.5 Overlapping Box Chart

6.10.5.1 Summary

All Origin graphs are created from a graph template. Templates serve to recall previous customizations but they also serve as a starting point for new customizations. This tutorial will show you how to create the following highly-customized box chart:



Minimum Origin Version Required: 2016 SR0

6.10.5.2 What you will learn


- Customize box plot settings
- Customize the axis dialog for box plots
- Merge and link several graphs
- Exchange X-Y axis

6.10.5.3 Steps to Create the First Box Chart


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the Tutorial Data.opj and browse to folder *Overlapped Box Chart*.
2. Activate workbook **Book1B** and **Sheet1**. Highlight columns B through F, then click **Plot: Statistics: Box Chart**. A box chart is created.
3. Select and delete the legend object from the graph.
4. Double-click on any box in the plot to open the **Plot Details** dialog box. Go to the **Group** tab and set the **Increment** for **Border Color** to **None** (other elements should already be set to **None**).


Tutorials for Origin




5. Go to the **Pattern** tab and duplicate settings as shown below.




6. Go to the **Spacing** tab and set **Gap Between Boxes (in%)** to be 40.



7. Go to **Box** tab and duplicate settings as shown below.




- Go to **Percentile** tab and clear all symbols. Click **OK** to close the dialog.




6.10.5.4 Steps to Create the Overlapped Box Chart


1. Right click the graph window title bar and select **Duplicate**. Repeat twice more. You should now have four identical graph windows.




2. Double-click any box in Graph2 to open **Plot Details**. Go to the **Box** tab and set the **Coef** value to be 0.95, **Box Width (%)** be 15 and **No Whiskers**.




3. Repeat step2 for Graph3 with **Coef** = 0.75, **Box Width (%)** = 40 and **No Whiskers**.
4. Repeat step2 for Graph4 with **Coef** = 0.5, **Box Width (%)** = 70 and **No Whiskers**.




5. Select **Graph: Merge Graph Windows** to open the `merge_graph` dialog box. Duplicate the settings as shown below and click **OK**.




6. Select **Graph: Layer Management** from the menu to open the dialog box.
7. Select **Layer2** and go to the **Link** tab. Duplicate settings as shown below and click **Apply**.



- Go to the **Axes** tab, clear all checkboxes and click **Apply**.




- Repeat Steps 7~8 for **layer3** and **Layer4**. Click **OK** to close the dialog box.





6.10.5.5 Steps for Further Customization


1. Double-click the Y axis to open **Axis Dialog** box. Go to the **Scale** tab and duplicate settings as shown below for the Y axis (**Vertical**).




2. Go to the **Tick labels** tab and duplicate settings as shown below.





- Go to the **Grids** tab and duplicate settings as shown below.




4. Go to the **Line and Ticks** tab, hold **Ctrl** key to select both **Bottom** and **Left** icons, then select **Use Same Options for Bottom and Top**, and change the line and ticks setting as below.




5. Go to the **Tick labels** tab again. Duplicate settings as shown below for X axis, after this, click **OK** to close the **Axis** dialog and apply all settings:



6. Right-click the Y axis title and select **Properties....** Duplicate settings as shown below and click **OK**.




7. Activate Layer1 by clicking on the layer icon at the upper-left corner of the graph window. Select **Graph: Exchange X-Y Axes.**
8. Repeat step 7 for layers 2~4.
9. Resize and/or reposition the graph layer as needed, so that everything fits comfortably within the graph window.



6.10.6 Two-Level Grouped Box Chart

6.10.6.1 Summary

Origin's box chart is advanced and customizable, this tutorial shows how to create a two-level grouped box chart from indexed data in Origin.



Minimum Origin Version Required: 2015 SR0

6.10.6.2 What you will learn

This tutorial will demonstrate how to:


- Use the data filter to select worksheet data.
- Stack column for box chart.
- Controlling the categorical values.
- Create a grouped box chart from indexed data.
- Customize box chart settings.
- Customize the axis dialog for box charts.
- Add a graph into box chart.


6.10.6.3 Data Preparation

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj, so you should open **Tutorial Data.opj** and browse to the folder *Two-Level Grouped Box Chart* at first.

Using data filter to select worksheet data

In the following steps, you can select the data you want to analyze by data filter:

1. Active the workbook **US Mean Temperature** and then highlight **Column B**.
2. Click the **Add/Remove Data Filter** button  on the **Worksheet Data** toolbar to add empty data filter to **Column B**.
3. Click the Filter icon on the column header of **Column B**, clear the check boxes before **Select All**, and check CA, FL and TX again.
4. Click **OK** to apply the filter.




Stacking columns to convert data into index mode

In the following steps, you can convert data from the raw mode into index mode:

1. Highlight **Column C** to **Column N**, and then select **Worksheet: Stack Columns** from the main menu to open the **Stack Columns** dialog
2. Check the box before **Include Other Column(s)**, then change the **Group Column Long Name** to **—Month** and **Data Column Long Name** to **—Temperature**




3. Click **OK** to launch the new worksheet **StackCols1**
4. Click the **Lock** icon on the column header, and select **Recalculate Mode: None** in the context menu.



Controlling the categorical values


In the following steps, you can customize the order of values shown in the graph but not change the source data:

1. Highlight **Column B** and **Column C** in Worksheet **StackCols1**, and then right click to select **Set as Categorical**.



2. Double click the Categories cell –unsorted” of **Column B** to open the **Categories** dialog.
3. Uncheck the **<auto>** checkbox, and then specify the order of items into: CA-TX- FL by using


Move to Top button , **Move up** button , **Move Down** button  and **Move to Bottom** button .




4. Redo step2 and step3 in **Column C** to specify the order of items into: January to December.

6.10.6.4 Create a grouped box chart from indexed data

1. Highlight **Column D** in Worksheet **StackCols1**, and then select **Plot: Statistics: Grouped Box Chart – Indexed Data...** in the main menu.
2. In the open dialog **Plotting: gboxindexed**, click the triangle button at the top right corner in **Group Column(s)** section, and then select **C(Y): Month** and **B(Y): State** in order in the context menu item.




3. Click **OK** to create a grouped box chart with two levels.




6.10.6.5 Customize box chart settings

Tutorials for Origin


1. Select the graph layer (click somewhere in the lower-middle portion of the layer seems to work best), and then drag the control handle to resize it as you want (put the cursor on the control handle, and drag it when the cursor becomes a two-headed arrow).




2. Select **Graph:Fit Page to Layers** in the main menu to open the dialog, and then select **Width Only** in the drop-down list of **Adjust Direction** to match the page width to that of the bounding box.




The graph will look like as below:




3. Double click on any one of the boxes to open **Plot Details** dialog, go to **Group** tab and set both **Border Color** and **Boxed Color** to increment **By One**, so each subgroup has a different color.
4. Click the color scale on the **Details** section, and select **S01 Gray Scale** in the drop down list for both **Border Color** and **Boxed Color**.




5. Go to **Pattern** tab, uncheck the checkbox **Follow the line transparency** and set transparency to 30%.




6. Go to **Spacing** tab to set the gap value between and within subgroup.




7. Go to **Box** tab to set the range of box and whisker.




8. Go to **Percentile** tab, clear the check box before the **99%**, **1%**, **Max** and **Min**, and then select the shape and size of **Mean** marker.



9. Go to **Line** tab to customize the caps of whisker and uncheck the **Median** checkbox.




10. Click **OK** button to apply the setting.




6.10.6.6 Customize the axis dialog for box charts

1. For the **X Axis**, change as the following steps:
 - Double click **X Axis** to open the **Axis Dialog**, and then select **Bottom1** on the left panel
 - Go to **Tick Labels** tab, set the font size of **Bottom1** with 14 in **Format** tab, and duplicate settings as shown below in **Table** tab.




- Select **Bottom2** on the left panel, uncheck the **<Auto>** checkbox and set the font size of **Bottom2** with 11 in **Format** tab, and duplicate settings as shown below in **Table** tab.





The elements of table layout are shown as below:





- o Go to **Line and Tick** tab, and change the style of major ticks into **In**.




2. For the **Y Axis**, change scale, title, font size of label tick and the style of ticks as shown below:






- Hide the top and right axis of the plot:
Press CTRL and select both **Top** and **Right** in the left panel, and then go to **Line and Ticks** tab to uncheck **Show Line and Ticks**.



- Click **OK** to apply your setting.
- Select **Legend** and press **Delete** to remove it, the graph should appear as below




6.10.6.7 Add a graphical symbol of the box into box chart

If you want to add a graphical symbol of to tell the meaning of each line in box, you can follow these steps:


1. Active Workbook **US Mean Temperature**, right click the label of worksheet below and select **Add** to add a new worksheet into workbook.
2. Enter 1 to 5 in each row respectively in **Column A**.

	A(X)	B(Y)
Long Name		
Units		
Comments		
F(x)=		
1	1	
2	2	
3	3	
4	4	
5	5	
6		
7		
8		
9		
10		
11		
12		


3. Highlight **Column A** and then select **Plot: Statistics: Box Chart** to create a simple box chart.




4. Double click the plot to open the **Plot Details** dialog.
5. To object **Graph2**, set the width and height of page on **Print/Dimension** tab.





- To object **Layer1** , go to **Size/Speed** tab and set the size of **Layer1**.




- To object box, go to **Pattern** tab and set as shown below.



- Go to **Percentile** and **Line** tab, and select the same setting of grouped box chart **Graph1**.




- Go to **Box** tab, check the box before **Box Label**, **Whisker Label** and **Mean Value Label**, and shown them in **Percentile**, and then change the width of box into 20%, besides set the range of box and whisker.




10. Click **OK** to apply your setting.

11. Select and delete X axis, Y axis, Y axis title **Range** and **Legend** of **Graph2**.



12. Press CTRL + C in **Graph2**, and then press CTRL + V in **Graph1** to copy the graphical symbol into the box chart.
13. Select the graphical symbol in **Graph1**, and then resize it and move it to a nice location.

At last, you will get the final graph.




6.10.7 Unbalanced Grouped Box Chart

6.10.7.1 Summary

Origin can be used to create unbalanced grouped box plots from raw data with custom table axis.

Female Tertiary education (ISCED 5 and 6) Enrollment



Minimum Origin Version Required: 2015 SR0

6.10.7.2 What you will learn

This tutorial will demonstrate how to:

- Create a unbalanced grouped box plot from raw data
- Add a top axis table row with additional grouping information
- Customize the table-axes

6.10.7.3 Steps


Creating the Box Plot from Raw Data

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open **Tutorial Data.opj** and browse to the folder *Unbalanced Grouped Box Chart*.
2. Activate the workbook **Book 3**.
3. Highlight all the columns except col(A):

	A00	B(Y)	C(Y)	D(Y)	E(Y)	L(Y)	J(Y)	K(Y)	G(Y)	H(Y)	E(Y)	F(Y)
Long Name												
Units												
Rank												
Continents		Developed	Developed	Developing	Developing	Developed	Developed	Developing				
Country		America	America	America	Russian	Ukraine	UK	Germany	Japan	S. Korea	China	India
1	2012	-	-	-	-	52.273	-	-	-	-	-	-
2	2011	56.963	-	49.774	-	52.962	56.362	50.634	46.024	39.63	50.161	41.761
3	2010	57.071	-	50.018	-	54.48	56.565	-	45.94	39.371	49.704	39.999
4	2009	57.133	-	50.232	56.633	54.78	56.974	-	45.787	38.856	49.24	39.31
5	2008	57.189	-	50.27	56.822	54.405	57.224	-	45.744	38.451	48.795	-
6	2007	57.346	-	50.287	56.834	54.273	57.238	-	45.604	37.972	47.891	39.128
7	2006	57.364	-	50.252	56.937	54.152	57.325	-	45.651	37.493	47.062	39.909
8	2005	57.23	-	50.252	57.055	54.062	57.195	-	45.689	37.075	45.988	39.411
9	2004	57.069	-	49.962	57.023	53.919	57.043	-	45.848	36.846	45.515	38.198
10	2003	56.644	-	49.647	56.816	53.795	56.904	-	45.596	36.654	43.837	38.445
11	2002	56.298	-	49.933	-	53.375	56.242	-	45.123	36.39	-	39.099
12	2001	56.874	-	49.049	-	53.051	54.544	-	44.849	36.025	-	38.666
13	2000	55.761	56.01	48.718	-	52.587	53.942	-	44.878	35.626	-	37.77
14	1999	55.653	55.979	48.298	-	52.725	53.195	-	44.674	35.178	-	-
15	1998	55.648	55.651	48.056	-	52.307	52.665	-	44.592	35.016	-	-
16	1997	-	-	47.72	-	-	51.794	45.765	-	36.991	-	36.277
17	1996	55.528	53.221	47.397	-	-	50.477	44.579	-	35.131	-	36.046
18	1995	55.375	52.852	46.703	-	-	50.951	43.394	44.036	34.995	-	34.435
19	1994	55.068	52.665	46.069	-	58.278	50.053	42.323	43.758	34.6	33.288	-
20	1993	54.968	52.899	45.185	54.31	-	49.591	41.973	-	35.279	-	-
21	1992	-	54.237	-	54.05	-	48.759	41.395	40.489	32.729	-	-
22	1991	54.497	54.153	-	54.06	-	48.247	-	38.547	31.574	-	33.077
23	1990	54.284	54.103	-	-	-	47.625	-	38.536	30.768	-	32.454
24	1989	54.025	48.619	-	-	-	46.747	-	37.813	30.021	-	31.746
25	1988	53.533	-	-	-	-	46.48	-	37.152	29.611	-	31.46
26	1987	52.937	-	-	-	-	46.179	-	36.901	29.61	-	29.767
27	1986	52.491	-	-	57.426	-	45.516	-	34.888	29.702	-	29.887
28	1985	52.103	-	-	-	-	44.813	-	34.365	31.011	-	29.268
29	1984	51.674	-	35.714	-	-	44.43	-	33.734	28.125	-	27.803


- On the **2D Graphs** toolbar click the small triangle at the bottom of the sixth button to reveal the fly out menu. Select **Grouped Box Charts - Raw Data** as shown below:



5. In the **Plotting: plotboxraw** dialog, set the **Group Number** to **2**, the **1st Group Row** to **Continents** and the **2nd Group Row** to **Country**. This will create a box chart with the column data arranged in three groups of two, with X axis row names derived from the two selected label rows on the worksheet:




6. Click the **OK** button. Select the legend and delete it and the grouped box chart from raw data is created with two grouping levels as shown below:




Customizing the axis table to display unbalanced groupings


1. The color and sub-group gap need some work. So, begin by changing all boxes to gray. Select **Format: Plot Properties** from the menu. In the **Plot Details** dialog box, click the Group tab. Set **Border Color Increment** to **None** so that box border color does not increment by dataset.




2. Go to the **Pattern** tab and duplicate the settings as shown below:



3. Go to the **Spacing** tab and set **Gap Between Subgroups (in%)** to **0** to remove the gap between sub-groupings.




- Click **OK** to apply the settings. Now our unbalanced grouped box chart is correctly drawn (we will adjust the labels later).




Add a top axis table row

We will now add an axis table top of the graph to display extra grouping information.


- Open the **Axis Dialog** again (**Format: Axes: X-Axis**). Go to **Tick Labels** tab and click to highlight the **Bottom 1** icon only on the left panel.
- Go to **Table** tab in **Tick Labels** page and change **Number of Rows** to **3**.




3. Click to select the newly added **Bottom 3** icon on the left panel and go to **Display** tab to set the **Display** list to **Rank** (note that this is another worksheet label row).




4. Click **Apply** to see the changes. A new table row is added to the bottom X axis. Next, we will move it to the top of the graph.



5. Right click the **Bottom 3** icon on the left panel and select **Move to Opposite**.




6. Click **OK** to apply the change.




Further customization

Now, let's do some further customization so that our graph looks like the one pictured in the introduction to this tutorial.


1. Double click on the grouping table on the bottom of graph to bring up **Axis Dialog**, go to **Tick Labels** tab and click to select **Bottom 1** icon only again.
2. Go to **Table** tab, clear the **Far Parallel Border** check box for **Bottom 1**.




3. Click to highlight the **Bottom 2** icon on left panel, uncheck **Auto** box and clear the **Inside Border** and **Outside Border** check boxes.
4. Click to highlight the **Top 1** icon on left panel and clear the **Far Parallel Border**, **Inside Border** and **Outside Border** check boxes. Select the **Tick at Beginning of Cell** and **Tick at End of Cell** check boxes.




5. Click **Apply** and then go to **Line and Ticks** tab and set **Style** under **Major Ticks** node to be **In & Out**.




6. Go to **Grids** tab and customize both major and minor grid lines settings as **Color = Black**, **Style = Dot** and **Thickness = 0.5**.




7. Click **Apply** and go to **Scale** tab, click **Vertical** icon on left panel and change scale **Type** to **Log10**, and adjust the other settings as shown below.



8. Go to **Tick Labels** tab and enter a **Suffix** of % to apply this character to each of the Y axis labels.



9. Click **OK** to apply the above changes.




10. Click **Format:Page Properties** and set **Width = 14.0** (you can leave the **Height** setting, as it is).
11. Double-click on the **Country** labels in the graph and set font **Size = 14**.
12. To add a graph title, click the **Text** tool, click somewhere in the heading of the graph and enter *Female Tertiary Education (ISCED 5 and 6) Enrollment*, and change Y axis title to be *Enrollment Rate*.

6.10.8 Grouped Box Plot

6.10.8.1 Summary

In Origin, a grouped box chart can be created from either indexed data or raw data. The indexed data is arranged as one data column and one or more group columns, while the raw data is arranged as multiple data columns grouped according to the column label row(s).

Once a grouped box plot has been created there are many options to customize the box plots and the axes. The customization options are the same for grouped box plots created from raw data as well as those created using indexed data.



Minimum Origin Version Required: 2015 SR0

6.10.8.2 What You Will Learn

This tutorial will show you how to:

- Create a grouped box plot from indexed data
- Create a grouped box plot from raw data
- Customize the box plot using the **Plot Details** dialog
- Customize the table-style axis tick labels


6.10.8.3 Steps

Create Grouped Box Plot from Indexed Data


This tutorial is associated with the **Tutorial Data** project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the **Tutorial Data** project, browse to the folder *Grouped Box Plot and Axis Tick Table* and activate the workbook **Book4G-CC.MI-Index**.
2. The data in the **CC.MI-Index** worksheet is indexed data. Column E is the data column and columns C and D can be used as grouping columns.
3. Highlight column E and select **Plot:Statistics:Grouped Box Charts - Indexed Data** to open the **plot_gboxindexed** dialog.
4. Beside **Group Column(s)**, click the triangle button at the top right corner and click the context menu item **Select Columns**. This opens the **Column Browser** for selecting grouping ranges.

- In the column browser, highlight columns C and D simultaneously by holding down the **Ctrl** key while selecting them. Click the **Add** button to add them to the bottom panel. Click **OK** to apply the selection and close the column browser.
- Make sure the dialog settings the same as the image below:




- Click **OK** to create a grouped box plot, the plot will resemble the image below:




Create Grouped Box Plot from Raw Data

In the previous section, when the grouped box plot was created, an **Output Data** worksheet was generated as well. The data in this worksheet is arranged as raw data. A box plot graph will be created from the raw data as well.

1. Highlight all the columns in the worksheet **Output Data**. Select **Plot:Statistics:Grouped Box Charts - Raw Data** from the main menu to open the **plotgboxraw** dialog.
2. We will use the labels in the SEG and Type label rows to group our data into 2 subgroups: Set **Group Number** to 2, **1st Group Row** to **SEG** and **2nd Row Group** to **Type**.
3. Enable, **Sort by Group Labels** and accept the default Graph Theme.




- Click **OK** to create another grouped box plot, the plot should resemble the image below:




Customization by Plot Details Dialog

Both the graphs created in the previous two sections can be customized in the same manner. In the following sections, the graph created from the indexed data will be used as an example for customization.


1. Activate the graph window created from the indexed data. Select and delete the legend object.
2. Select **Format:Plot Properties** to open the **Plot Details** dialog.
3. On the **Box** tab, check the **Outliers** box. Note that **Outliers in Line** will also be checked automatically. Outlier points will be shown in the graph. Click **Apply** to apply settings first and the **Symbol** tab will appear.
4. To customize Symbol style select the **Symbol** tab and set the following:




5. On the **Spacing** tab change **Gap Between Subgroups (in %)** to 5.
6. On the **Lines** tab change the line colors as shown below:




7. On the **Percentile** tab in order to set the **Max/99%/1%/Min** to none, select the last option in the symbol map. Set the rest of the options as shown below:




8. On the **Group** tab set the **Increment** for **Border Color** as **By One**.
9. Next, click the ... button on the right end of the **Details** column to open the **Increment Editor**. Select the first color and click on **Define Custom Colors**. In the **Color** dialog that opens set Hue=0, Sat=240, Lum=180, Red=255, Green=128 and Blue=128. **OK** to close the dialog. Follow the same procedure for the second color in the **Increment Editor** dialog with the settings Hue=160, Sat=240, Lum=164, Red=94, Green=94 and Blue=255. **OK** out of the **Increment Editor**:



10. Choose the same settings for **Box Color**. The **Group** tab will appear as shown below:




- Click **OK** to apply all the previous settings and close the **Plot Details** dialog. The graph should resemble the image below:




Customization by Axis Dialog


1. Continue with the graph from the previous section. Select **Format:Axes:X Axis** to open the **Axis** dialog.
2. Go to the **Tick Labels** tab, right click on the **Bottom 1** icon and select **Move to Opposite** to move it to the top axis.




3. Now the previous **Bottom 1** becomes **Top 1**, and **Bottom 2** becomes **Bottom 1**.


4. Click the new **Bottom 1** icon and set the tick label format and table layout as shown below:






5. Click the **Top 1** icon and set the following:








6. Click the **Left** icon (for Y axis) and change the display format for the Y tick labels:



7. To turn on major and minor grid lines, go to the **Grids** tab and set as following for X(**Vertical**) and Y(**Horizontal**) grids respectively:




8. Click **OK** to apply the settings and close the **Axis** dialog. The final graph should appear as shown below:



6.10.9 Notched Boxes with Variable Width Control

6.10.9.1 Summary

Origin's box plot is highly customizable. This tutorial shows how to create a notched box plot and control the box width by another dataset.



Minimum Origin Version Required: 2015 SR0


6.10.9.2 What you will learn

- Customize box plot settings
- Use a dataset to control the box width
- Customize the axis dialog for box plots
- Add a fill area plot to a box plot as background


6.10.9.3 Steps to Control Box Width by Variable

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the **Tutorial Data.opj** and browse to the *Box Variable Width* folder.
2. Activate workbook **Book1CAA**, go to **Sheet1**. Highlight columns **B** to **I** (do not select column **C**) and then select **Plot: Statistics: Box Chart**. Next, select and delete the legend object from the graph.
3. Double-click on one of the boxes to open the **Plot Details** dialog and go to the **Box** tab. Set **Style** to **Notched Box**. Select the **Box Width by Parameter** box and then set **Box Width (%)** to **Units** and enter *1.2* for **Scaling Factor**. Select the **Outliers** box. **Outliers in Line** is automatically checked.



4. Click **OK** button. The graph will look as below.




6.10.9.4 More Box Style Customization Steps


The following steps can further customize the box plot.

Tutorials for Origin


1. To use the same color for each box, double-click on any box to open the **Plot Details** dialog box. Go to the **Group** tab and change the **Increment of Border Color** to **None**:




2. Go to the **Pattern** tab. Set **Border Color** as **Orange**. Set **Width** as **1.5**.




3. To fill the boxes with color, click **Fill Color** drop down list and choose **Define Custom Color**. Add a custom color as below.






4. Note that checking **Outliers** checkbox in **Box** tab added a **Symbol** tab. Use controls on this tab to customize the outlier symbol as shown below:




5. To hide the 99% and 1% symbols, go to the **Percentile** tab and clear the symbol for both **99%** and **1%**. Select the 2nd symbol in the first row for **Mean**:




6. Click **OK** button to accept all the changes.

6.10.9.5 More Axis Customization Steps


1. To show solid grid lines between each boxes, double click on the X axis to open the **Axis** dialog box. Go to the **Scale** tab with **Horizontal** icon selected and set the **Count of Minor Ticks** to 1:




2. Select the **Grids** tab and select the **Vertical** icon. Check **Show** under **Minor Grid Lines** branch and set the **Style** as **Solid**.




3. Go to the **Line and Ticks** tab and set the tick styles for X axis (**Bottom**):




4. Hold **Ctrl** key and multiple select the **Top** and **Right** icons. Check the **Show Line and Ticks** box to also display line and ticks of top X and right Y axis:



5. Go to the **Scale** tab again and select **Vertical** icon. Set the following:



6. Go to the **Tick Labels** tab, make sure **Left** icon is selected and enter a prefix of \$.




7. Go to the **Title** tab, make sure **Left** icon is selected and change the text of Y axis title to *Gasoline Prices*.
8. Click **OK** to close the **Axis** dialog.
9. To add a title and footnote in the graph, right click in white area of the graph and select **Add/Modify Layer Title** context menu. Type *US Weekly Retail Gasoline Prices*. Select the title and use the **Format** toolbar to set font size as **26**. Right click below the X axis tick labels and choose **Add Text...** context menu. In in-place edit mode, click **I** button on **Format** toolbar and then type *Box width indicates number of vehicles in each area* as a footnote. It will show in italics.


6.10.9.6 Steps to Add National Average Line and Min&Max Range

Note: If you right-click on status bar and select **Min** and **Max**, then highlight column **C** (with long name **national**) of **Book1CAA Sheet1**, you can see the **Average=3.54**, **Min=3.198** and **Max=3.877** of this column on status bar of Origin. Min and Max values have been put to Sheet2 so we can plot them as filled area in box chart.


1. To add a National Average line in graph, select **Graph:Add Straight Line** to add a horizontal line to represent the national average value = **3.54** and click **OK** button.




2. Right click **3.54** label and choose **Properties...** context menu. Enter the text and set style as below.




- To add national average range as a filled area in the graph, double click Layer1 icon on top-left corner of the graph to open **Layer Contents** dialog. Select **B(Y)** and **C(Y)** from **Sheet2**. Choose Plot Type to be Line. And click -> button to add two line plots into the box chart.



- Double click the newly added line to open the **Plot Details** dialog. Go to the **Line** tab and set the line transparency to be **100** so the lines will not display in graph.




5. The **Pattern** tab is added when fill area is enabled. Set the Fill color and Transparency as below and then click **OK** button.




6. We can use Graph theme to change all text font in the graph to **Verdana**. Select **Tools:Theme Organizer** menu.
7. There is no Graph theme called Verdana Font. But there is a **Times New Roman Font** theme. You can create a Verdana Font theme based on it.


8. Right click **Times New Roman Font** theme and choose Duplicate.



9. Double click the Duplicated theme and rename it as **Verdana Font**.
10. Right click **Verdana Font** theme and choose **Edit...**
11. In **Theme Editing** dialog that opens, change the **Face** to **Verdana** and click **Save** button. Also, you can update the **Description** on this dialog. Then click on the **Save** button to save the setting and close the dialog.



12. With **Verdana Font** still selected in **Theme Organizer**, click the **Apply Now** button to apply the font to all text objects in the graph.




13. Manually reposition the text objects, as needed, so that your graph looks like the one in **Summary**.

6.10.10 Simple Dot Chart

6.10.10.1 Summary

Dot chart is a statistical chart which consists of data points plotted on a simple scale. It is often used as a substitute for the pie chart, as it allows for quantities to be compared easily. This tutorial will teach you how to create a simple dot chart plot:



Minimum Origin Version Required: Origin 2015 SR0

6.10.10.2 What you will learn

This tutorial will show you how to:

- Create a scatter graph
- Change the X-Y Axis
- Use the Plot Details dialog to customize your graph


6.10.10.3 Steps

Start with the following data which represents various elements in a compound:

Element	Content
---------	---------


C	36
Cl	2
H	28
N	10
O	12
P	7
S	5

1. Create a new workbook using the **New Workbook** icon in the **Standard** toolbar, and input the data:




	A(X)	B(Y)
Long Name	Element	Content
1	C	36
2	Cl	2
3	H	28
4	N	10
5	O	12
6	P	7
7	S	5
8		
9		
10		
11		



2. Highlight Col(A) and Col(B). Select the **Plot: Symbol: Scatter** menu item from the main menu to create a scatter plot as shown below:




3. Select **Graph: Exchange X-Y Axis** from the menu.




4. Double-click on the graph to bring up the **Plot Details** dialog, change the symbols and the symbol color using the different tabs as shown below:







5. Click the **OK** button to save the changes and close the dialog. The graph should appear as shown below:




6. The next step is to reset the X and Y Axes. Double-click the horizontal axis to open the **Axis** dialog. On the **Scale** page, set **From** as **0** and **To** as **40**. Set the **Increment** as **10**.



7. Go to the **Line and Ticks** page, select the **Left** icon in the left panel, and set both **Major Ticks** and **Minor Ticks** to **None**. Click **OK** to save the changes.




8. The completed Dot chart should appear as shown below:



6.10.11 Multi-Data Dot Chart

6.10.11.1 Summary

A **Dot Chart** is a statistical chart which consists of data points plotted on a simple scale. It is often used as a substitute for the pie chart because it can make comparing quantities easy. This tutorial will teach you how to create the Multi-Data Dot Chart.



Minimum Origin Version Required: Origin 2015 SR0

6.10.11.2 What you will learn

This tutorial will show you how to:

- Create a scatter graph
- Change the X-Y Axis
- Use Layer Management
- Customize the axes
- Add objects on the graph

6.10.11.3 Steps


The following data concerning the element content of several areas at different times can be used to create a multi-data dot chart:

Sulphate	0.346	0.560	0.333	0.887	0.310	0.899
Nitrate	0.382	0.780	0.456	0.732	0.456	0.732
Chloride	0.441	0.880	0.120	0.656	0.221	0.673
Ammonium	0.481	0.900	0.256	0.890	0.434	0.825


1. Create a new workbook using the **New Workbook** icon on the **Standard** toolbar and input the data.

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)	F(Y)	G(Y)
Long Name							
Units							
Comments							
1	Sulphate	0.346	0.56	0.333	0.887	0.31	0.899
2	Nitrate	0.382	0.78	0.456	0.732	0.309	0.785
3	Chloride	0.441	0.88	0.12	0.656	0.221	0.673
4	Ammonium	0.481	0.9	0.256	0.89	0.434	0.825
5							

2. Hover the cursor over the very first cell of the col(B) till it turns into a downward arrow. Left-clicking highlights col(B) and dragging highlights col(C). Select **Plot: Symbol: Scatter** from the main menu to create a graph, and select **Graph: Exchange X-Y Axis**. An alternate way of creating scatter graphs is using the scatter icon in the **2D Graphs** toolbar.
3. Repeat step 2 twice to create two more graphs with col(D) and col(E), as well as col(F) and col(G).
4. To Merge the three graphs, select **Graph: Merge Graph Windows: Open dialog**. In the dialog box that opens expand **Arrange Settings**, set the **Number of Rows** as **3** and the **Number of Columns** as **1**. The Preview window on the right shows how the three graphs will be arranged and which layers they will be on. Click the **OK** button to save . This creates a new graph which contains three layers each containing a separate graph.




- To clean up the graph, delete the legends and axis titles in the graphs by selecting them and pressing the **Delete** key.




- Select **Graph: Layer Management** from the main menu. Select Layer 2 on the left. In the right panel **Link** tab set **Link to** as **1**. This links the Y axis of the second layer containing the second graph to the first layer containing the first graph. Set the **Y Axis Link** as **Straight (1 to 1)**, this will ensure that the axis for the two graphs is the same. Click the **Apply** button.

Check the **When dragged to reposition, also reposition parent layer** box. This setting will ensure that when one axis is moved, the other follows accordingly.




7. Select Layer 3 on the left and repeat the previous step. Click the **OK** button to save changes.


8. In order to reset the X and Y Axes, make sure Layer 1 is the active layer by clicking on **1** at the top left corner of the graph. Double-click on the horizontal axis of the graph layer. On the **Scale** page when **Horizontal** icon is selected, set the values shown below (since the layer axes were linked in the last step, these changes are applied to all three axes):




9. Go to the **Line and Ticks** page, select **Top** icon in the left panel, check the **Show Line and Ticks** check box to show the top Y axis. And then set **Major Ticks** as **Out** and **Minor Ticks** as **None**.




10. Select **Bottom** icon in the left panel, in the **Line and Ticks** page, set **Major Ticks** and **Minor Ticks** as **None** to remove the ticks.




11. Go to **Tick Labels** page in the right panel, select **Top** icon in the left panel, check **Show** check box.




- Go to the **Special Ticks** page, select **Top** icon in the left panel, choose **Hide** for both **Axis Begin** and **Axis End**.




13. Go the **Tick Labels** page, select **Top** icon in the left panel, clear the **Show** check box.




14. Go the **Tick Labels** page, select **Bottom** icon in the left panel, clear the **Show** check box.




15. Go to the **Line and Ticks** page, select **Left** icon in the left panel, check **Use Same Options for Left and Right** check box. And then set both **Major Ticks** and **Minor Ticks** as **None**:




- Go to the **Grids** page and select **Horizontal** in the left panel, check **Show** check under the **Major Grid Lines** branch.




17. Click the **OK** button to apply the settings and close the **Axis** dialog. The graph should now appear as shown below:




18. Right click on Layer 1 and choose **Copy Format:All Style Formats**. Right click on the graph page and choose **Paste Format** to copy and paste the style from Layer 1 to the whole page.




19. Double click on the top axis in Layer 2, go to the **Line and Ticks** page, select **Top** icon in the left panel, set **Major Ticks** and **Minor Ticks** as **None**. Do the same for the top axis of Layer 3.
20. In the **Axis** dialog of Layer 3, go to the **Line and Ticks** page, select **Bottom** icon in the left panel, set **Major Ticks** to **Out**.
21. On the **Tick Labels** page, select **Bottom** icon in the left panel, check **Show** check box.
22. Go to the **Special Ticks** page, select **Bottom** in the left panel, and choose the **Hide** option for both **Axis Begin** and **Axis End**. Click **OK**.





23. The graph should appear as shown below:




24. Double-click the graph to bring up the **Plot Details** dialog. Change the settings as shown below. Setting the **Edit Mode** as **Independent** ensures that the symbols can be customized separately for each data set on one layer. For **Symbol shape**, uncheck the **Custom Construction** check box, click the down arrow button to select different symbol shape. For symbol color, in the **Symbol** tab click on the **Symbol Color** option and select **Individual Color** to set one color to all the symbols as in this tutorial:










25. Repeat the previous step (step 24) for the Layer 2 and Layer 3. Click the **OK** button and the graph will appear as shown below:




26. Select  in the **Tools** toolbar to draw three rectangles on the graphs. For each rectangle:
1. Double-click on the rectangle to bring up the **Object Properties** dialog.
 2. In the **Fill** tab, set the desired **Fill Color** which will designate the color of the rectangle:



3. In the **Dimensions** tab, adjust the size and position of the rectangle:




27. Select the Text Tool **T** in the Tools toolbar and click inside the rectangles to add the desired text.
28. To create a legend for the symbols, select **Graph: Legend: Data Plots** from the main menu. Move the legend to a suitable place, right-click on it and select **Properties**. Change the settings as below:



29. Activate the top X axis of Layer 1 to move it to a suitable place.

The complete multi-data dot chart graph should appear as shown below:



6.10.12 Add multiple fitted curves in a Histogram

6.10.12.1 Summary

Origin allows you to fit the peaks from the result of frequency count. Also, fitted curves can be added into the new layer in the Histogram.


6.10.12.2 What you will learn

- Plotting the Histogram
- Using Frequency Count to do statistics
- Using Peak Analyzer to find peaks and do fitting

- Adding new layers

6.10.12.3 Steps

Copy and paste [the sample data](#) into Origin and set the column as Y (Highlight the column and choose **Column: Set As Y** from the Origin menu). Plot this data as a Histogram by clicking **Plot: Statistics: Histogram** from the menu.



Frequency Count

1. Highlight the sample data, then open the **Frequency Count** dialog by selecting **Statistics: Descriptive Statistics: Frequency Count**.
2. Click **OK** to finish. A new result sheet will be generated.

Fit peaks



1. Select Col(Counts) and then open the **Peak Analyzer** dialog from **Analysis: Peak and Baseline: Peak Analyzer**.
2. In the start page, select **Fit Peaks** as **Goal**, then click **Next**.
3. In the **Baseline Mode** page, set the baseline as **Y=0** when the **Custom** radio box is checked.
4. Click the **Next** button twice to go to the **Find Peaks** page. Click the **Find** button under the **Enable Auto Find** check box to find two peaks.
5. Click the **Next** button again to open the **Fit Peaks** page. Click **Fit Control** at the bottom of this page to open the **Peak Fit Parameters** dialog.

6. In this dialog, the default fitting function is **Gaussian**, which is the right function for normalizing the data. Close the **Peak Fit Parameters** dialog and go back to the **Peak Analyzer** dialog. Click **Finish** to complete the fitting.

Add the fitted curves

1. Activate the Histogram graph and add a layer by selecting **Graph: New Layer(Axes): Right-Y** from the main menu.
2. Right-click the **Layer2** icon and select **Plot Setup** from the short menu to open the **Plot Setup** dialog.




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

3. Select the sheet **FitPeakCurve1** from the top panel, then set col(C) as X and col(D) as Y, and add them into the Layer **RightY** in the bottom panel.
4. Do the same things for col(E) and col(F). After that, both fitted peaks have been added into the Layer **RightY**.
5. Click OK. Two fitted curves had been added to the Histogram.
6. Double-click the graph to open the **Plot Details** dialog. Select **RightY** from the left panel, then open the **Link Axes Scales** tab in the right panel and select **Straight(1 to 1)** for both **X Axis Link** and **Y axis Link**. Click OK to close the dialog.

7. The fitted curves are added into the Histogram with the proper scale. The following is the result graph, with the right Y-axis removed.



Sample Data

0.631
0.642
0.652
0.662
0.669
0.676
0.677
0.69

Tutorials for Origin

0.691
0.696
0.697
0.699
0.699
0.7
0.7
0.708
0.712
0.718
0.731
0.744
0.749
0.751
0.752
0.753
0.758
0.758

0.759
0.761
0.761
0.763
0.763
0.763
0.765
0.767
0.768
0.768
0.769
0.769
0.77
0.771
0.771
0.772
0.774
0.775

Tutorials for Origin


0.775
0.776
0.776
0.776
0.777
0.778
0.779
0.78
0.78
0.781
0.784
0.784
0.785
0.785
0.789
0.789
0.791
0.794

0.795
0.796
0.798
0.798
0.803
0.82
0.831

6.10.13 Weibull Probability Plot

6.10.13.1 Summary

The probability plot shows a graph with observed cumulative percentage on X axis and expected cumulative percentage on Y axis. The Weibull probability plot is used to test whether or not a dataset follows Weibull distribution. And its X scale type and Y scale type are Log10 and Double Log Reciprocal respectively. If all the scatter points are close to the reference line, we can say that the dataset follows the Weibull distribution.



Minimum Origin Version Required: Origin 2016 SR0


6.10.13.2 What you will learn

- How to create a Weibull probability plot
- How to add the fill area between the percentiles lines

6.10.13.3 Steps


You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: Statistical Graphs**)

1. Download the data from [here](#). Highlight column A and right-click to select **Set As: Y** from the context menu.




2. Keep this column highlighted, select **Plot: 2D: Probability** from the Origin main menu to open the **plot_prob** dialog. In this dialog, change **Distribution** to **Weibull** and then click the **OK** button to

create a Weibull probability plot with column A.




3. Double-click on the Lower Percentiles line to open the **Plot Details** dialog. Go to the **Line** tab, set **Color** to **Red**, **Transparency** to **80%**, then check **Fill Area Under Curve** check box and select

Fill to next data plot - One Color in the below drop-down list.




4. Go to **Pattern** tab, set **Fill Color** to **Red**. And make sure the **Follow line transparency** is checked.




Tutorials for Origin


5. Go to the **Line** tab of Upper Percentiles line set **Color** to **Red**, **Transparency** to **80%**. Click **OK** to apply the setting and close the dialog.




6. Double click on the X axis on the graph to open the **Axis** dialog. Go to **Scale** tab for **Horizontal** axis, change scale from **10** to **100**, and set the increment value of **Major Ticks** to **20**.



7. Go to **Scale** tab for **Vertical** axis, change scale from **1** to **99.99**. Click **OK** to apply the setting and close the dialog.




The final graph should look like this:



6.10.14 Q-Q Plot

6.10.14.1 Summary

The Q-Q plot is a graphic method that tests whether or not a dataset follows a given distribution. The Q-Q plot has independent values on the X axis, and dependent values on the Y axis. If all the plotted points are close to the reference line, then we conclude that the dataset follows the given distribution.




Minimum Origin Version Required: Origin 2016 SR0

6.10.14.2 What You Will Learn


- How to create a Q-Q plot
- How to mask a suspected outlier in the source data and recalculate the Q-Q plot

6.10.14.3 Create a Q-Q Plot

You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: Statistical Graphs**)


1. Click the  button to import the **Q-Q plot.dat** file under *<Origin EXE folder>\Samples\Graphing* path.
2. In the **QQplot** workbook, activate the **Q-Q plot** worksheet, highlight column B, right click, and from the context menu, select **Plot: Statistics: Q-Q Plot...** In the **Plotting:plot_prob** dialog,

make sure that the **Score Method** drop-down is set to **Benard**. Click **OK**.




3. Double-click on the Lower Percentiles line to open the **Plot Details** dialog. Go to the **Line** tab, set **Color** to **Red**, **Transparency** to **80%**, then check **Fill Area Under Curve** check box and select


Fill to next data plot - One Color in the below drop-down list.




4. Go to **Pattern** tab, set **Fill Color** to **Red**. And make sure the **Follow line transparency** is checked.



5. Go to the **Line** tab of Upper Percentiles line set **Color** to **Red**, **Transparency** to **80%**. Click **OK** to apply the setting and close the dialog.




Your graph should look as shown below.





6.10.14.4 Mask a Suspected Outlier

1. Click on the green lock icon to make sure the **Recalculate Mode** is **Auto**.




2. Click on the **Data Reader** tool and click to select the suspected data point in the **Q-Q Plot**.





The **Data Info** window shows the value of the outlier point.



3. Activate the **Q-Q plot** worksheet and highlight column B.



4. From the Menu Bar, click on **Window:Command Window** and at the prompt, enter the script shown below.

```
colmask cond:=eq val:=x;
```


5. The outlier point will be shown in red in the **Q-Q plot** worksheet, and it will not be included in the graph.



6.10.15 Scatter Matrix

6.10.15.1 Summary

A scatter matrix consists of several pair-wise scatter plots of variables presented in a matrix format. It can be used to determine whether the variables are correlated and whether the correlation is positive or negative. This tutorial will show you how to create a Scatter Matrix plot.



Minimum Origin Version Required: Origin 2016 SR0

6.10.15.2 What you will learn


- How to create a Scatter Matrix plot with a histogram
- How to customize Scatter Matrix plot
- How to set a grouping range for showing the color index
- How to specify to hide scatter plots on the bottom/top of the diagonal

6.10.15.3 Steps

Creating Scatter Matrix plot


1. Start with an empty worksheet, select **File: Import: Single ASCII...** to open the Import Single ASCII dialog, browse to the `\Samples\Statistics` subfolder of the Origin program folder, and import the file *Fisher's Iris Data.dat*.
2. Highlight columns (A) to (D) but not col(E), and select **Plot: Statistics: Scatter Matrix** from the main menu.

3. In the dialog, select **Histogram** from the **Show in Diagonal Cells** drop-down list, and select **Alternate** from **Show Tick and Label** drop-down list.



4. Click **OK** to close the dialog. The **PlotData1** sheet for the scatter matrix plot is generated in the same workbook as the original data. It contains the data for the different graphs in the scatter matrix and can be accessed by clicking on the second tab labelled **PlotData1** at the bottom of the


workbook. The graph should appear as below:




Customizing Scatter Matrix plot

There are multiple layers in the Scatter Matrix graph. This section will explain how to customize the background color, the type and color of the data plots and the axis tick labels of the scatter matrix. Starting with Origin 2016, by default, if you change the plot style or axis setting of one layer, all other layers will follow (for independent editing, see the tip at the end of this section).

1. Double click on the scatter data to open the **Plot Details** dialog. To change the symbol color click on the **Symbol Color** drop-down menu and select a color from the **Individual Color** option. Specify the type and color of the symbol as shown in the following image, and click **OK**.




This change will be applied to all scatter data plots in this graph.




- To change the background color of the entire window, select **Format: Page Properties** to open the **Plot Details** dialog. This dialog can also be accessed by double clicking inside the Scatter Matrix window. In the **Display** tab, click on the **Define Custom Colors** button in the Color option.


- In the **Color** dialog, specify the color as *Red=235, Green=235, Blue=255* in the lower left corner of the box. Add as a custom color and click **OK**.



- To specify the background color of the layers with scatter plots without changing the background color of the histograms or the rest of the graph, double click on the one layer of the scatter plot to open the dialog. Go to **Background** tab, and set **Color** to **White**.




Then click **OK** in the dialog. This change will be applied to all layers with scatter data plots.




5. Double click on any tick label in the graph to open the **Axis** dialog for that layer. Go to the **Tick Labels** tab, then the **Format** tab, specify **Size** to **36** for the **Top** axis. Click **Apply**.


- Click the **Apply To...** button to open the **Apply To** dialog, set the following to apply the previous customization of tick label size to all the other axes in this window.




7. The graph will appear as shown below:




If you want to customize each layer independently, select the **Independent Layer Control** check box on the **Miscellaneous** tab (Page level) of the **Plot Details** dialog box.




Add Grouping Range

1. To add a **Grouping Range**, click on the green lock icon on the upper-left corner. Select **Change Parameters** to bring up the **Plotting: plot_matrix** dialog.
2. Click the triangular button  next to the **Grouping Range** option. Click on the **Select Columns** to open the **Column Browser** dialog, and choose column E (Species) as the group range. Use **Add** to add it to the panel below and click **OK**.




3. Click the **OK** button in the **Plotting: plot_matrix** dialog. The graph will appear as shown below:




Customizing Matrix Display

Tutorials for Origin

1. To hide the layers on the bottom of the diagonal in Scatter Matrix graph, click on the green lock icon on the upper-left corner. Select **Change Parameters** to bring up the **Plotting: plot_matrix** dialog.
2. Under **Matrix Profile** branch of the dialog,
 - Select **Upper Triangular** from the **Matrix Display** drop-down list
 - Select **All** from **Show Tick and Label** drop-down list
 - Enter **2** in the **Gap (in % of Page Dimension)** text box



The complete graph should appear as shown below:



6.10.16 Histogram with Distribution Curve overlay

6.10.16.1 Summary

After you plot a Histogram, Origin allows you to overlay a distribution curve on the binned data by selecting **Normal**, **Lognormal**, **Poisson**, **Exponential**, **Laplace**, or **Lorentz** from the **Type** drop-down list in the **Data** tab of the **Plot Details** dialog.


6.10.16.2 What You Will Learn

- How to create a Histogram
- How to add the Distribution Curve
- How to create the Bin worksheet with distribution curve data.

6.10.16.3 Steps


1. From the Main Menu, select **File: Import: Single ASCII...: Sample: Graphing: Histogram2.dat**.

- Highlight column B, and from the Main Menu select **Plot: Statistics: Histogram**.



- From the Main Menu, select **Format: Plot Properties....** From the **Plot Details - Plot Properties** dialog box select the **Data** tab.
- From the **Distribution Curve: Type** list, select **Normal** and click **Apply**. Select the **Add Distribution Curves** check box and click **Go**. The **Plot Details - Plot Properties** dialog box

closes and a worksheet of binned data (**Histogram2_B Bins**) is added to the workbook.



- In the **Histogram2_B Bins** worksheet, the box at the intersection of row **Comments** and column **B(Y2)** shows the **Mean** and **SD** values for the data. Right-click on the box, and from the drop down menu select **Copy**.


	CumulativeSum(Y)	CumulativeProbab(Y)	A(X2)	B(Y2)
Long Name	Cumulative Sum	Cumulative Probability	Distribution	Normal
Units				
Comments	Bins	Bins		Mean= 60.705455707568, SD=11.630702803337
1	1	1	30	1.05156
2	16	16	30.08008	1.07083
3	54	54	30.16016	1.09039
4	79	79	30.24024	1.11026
5	95	95	30.32032	1.13044
6	98	98	30.4004	1.15093
7	98	98	30.48048	1.17174
8	100	100	30.56056	1.19286
9			30.64064	1.21431
10			30.72072	1.23609

- Right click within the histogram plot frame (but not directly on the plot) and from the context menu select **Add Text....** Right click within the Text Box and select **Paste**. Click inside the Text Box, select all numbers to the right of the tenths place for **Mean** and for **SD**, and hit the Delete key.

Place your cursor after **Mean= 60.7** and hit the **Enter** key. The final graph should appear as below.

Note : If data fit the chosen distribution well, the overlay curve will also approximately agree with the histogram well.

7.



6.11 Polar

- [Polar Contour](#)
- [Polar Plot with Error Bar](#)
- [Polar Crop](#)
- [Polar Graph with Custom Radial Axes](#)
- [Polar Graph with Multiple Layers](#)
- [Polar Graph with Columns and Stack Columns](#)
- [Polar Graph with Custom Angular Scale](#)

6.11.1 Polar Contour

6.11.1.1 Summary

This tutorial will show you how to create a Polar Contour graph from both XYZ worksheet data and matrix data.

Minimum Origin Version Required: 2015 SR0

6.11.1.2 What will you learn

- Create a Polar Contour graph from both XYZ data and matrix data
- Customize the graph using the Plot Details dialog box

6.11.1.3 Steps


Plot Polar Contour from XYZ data

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: Contour**)


1. Open the Tutorial Data project and browse to folder *Polar Contour* in **Project Explorer**.
2. Activate **Book2BA** containing the temperature and location data and select column **C**. Select **Plot: Contour/Heat Map: Polar Contour Theta(X) r(Y)** from the menu to create a polar contour

graph. The graph should look like this:




3. Next, we will customize the contour graph using the **Plot Details** dialog box. Double-click on the contour plot to bring up the Plot Details dialog then select the **Color Map/Contours** tab and click

the **Fill** heading. Edit dialog box settings as shown in the following:




4. Click the **Contouring Info** tab and select the **Layer Boundary** radio button.




Click **OK** to close the **Plot Details** dialog box.


5. Next, we will customize the graph axes. Double-click on the axes to open the **Axis** dialog box, then...
 - o Go to **Scale** tab and make sure **Angular** is chosen in the left panel. Under the **Major Ticks** tree node, set the **Type** to **By Increment** and **Value** to **60**.




- o Go to **Tick Labels** tab and select **Angular - Outer** in the left panel. In the right panel, go to **Display** tab, select **Tick-indexed dataset** in **Type** drop-down list and then select **[Book3B]Sheet1!B"Longitude"** from the **Dataset Name** drop-down list.




- Go to **Scale** tab, and select **Radial** in the left panel. In the right panel set **From** and **To** to **0** and **7**. Also under the **Major Ticks** tree node, set the **Type** to **By Increment** and **Value** to **2**.




- Go to **Tick Labels** tab. Pressing **Ctrl** key and select both **Radial - Outer 1** and **Radial - Outer 2** in the left panel. In the right panel, go to **Display** tab, select **Tick-indexed dataset** in **Type** drop-down list, then select **[Book3B]Sheet1!A"Latitude"** from the **Dataset Name** drop-down list.




- Go to **Grids** tab, and make sure **Radial** is selected in the left panel. Edit the dialog box settings as in the following image. Click **OK** to close the **Axis** dialog box.




6. Double-click on the **Color Scale** to open the **Color Scale Control** dialog box and edit settings as follows
 - o In the **Labels** page, set font size to **20**.




- In the **Layout** page, uncheck **Reverse Order** check box, and set **Color Bar Thickness** to **100**.



- In the **Title** page, enter $(\text{+}(o)F)$ in the **Title**, which is supposed to be displayed as $(^{\circ}F)$ as the unit for temperature. And set the **Position** to **Bottom**.




- In the **Line and Ticks** page, uncheck **Show Line and Ticks on Right** and **Show Border** check box. Then Click **OK** to save the setting and close the dialog.



Note: The text used for **Title** is $(1+(o)F)$, which is supposed to be displayed as $(^{\circ}F)$ as the unit for temperature.

7. Add the graph title **Temperature Contour Map**, axis title **Latitude** to the graph. The graph should look like this:




Plot Polar Contour from Matrix data


Tutorials for Origin


This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Contour**)


1. Open the Tutorial Data project and browse to folder *Contour from Matrix* in **Project Explorer**.
2. Activate *MBook1*. Select **Plot: Contour/Heat Map: Polar Contour Theta(X) r(Y)** from the menu or click the **Polar Contour theta(X) r(Y)** button on the **3D And Contour Graphs** toolbar, to create a polar contour graph.




3. Double click the axes to open the **Axis** dialog, we also can customize the **Radial Axes** for this polar graph.
 - o Click on the **Radial Axes Configuration** button  on the right-top of this dialog to open the dialog. In the dialog, choose **0** under the **Angles List** drop-down list.




- Go to **Show** tab, then make sure choose **Radial - Inner 1** in the left panel. Select **End Angle** in **Angle At** drop-down list, and choose **Negative** option for **Flow Direction**




- Choose **Angular - Outer** in the left panel. Go to **Show** tab, and **Rotate (deg.)** set to **-30**. Click **OK** to save the setting and close the dialog.




4. Double click on the graph to open **Plot Details** dialog. Go to **Colormap / Contours** tab, click on the **Level** header to open the **Set Levels** dialog. Then set the levels as the following image:



Then click on the **Fill** header to open the **Fill** dialog. Set color from **Red** to **Blue**:




5. Select **Layer** level on the left panel and go to **Size/Speed** tab. Customize the **Layer Area** as the following image:




Click **OK** to save the setting and close the dialog.


6. Double-click on the **Color Scale** object to open the **Color Scale Control** dialog.
 - In the **Level** page, check the **Hide Head and Tail Levels** check box.




- In the **Layout** page, uncheck **Reversr Order** check box, and set **Color Bar Thickness** to **400**.




- In the **Title** page, uncheck **Show** check box.



- In the **Line and Ticks** page, uncheck **Show Line and Ticks on Right** and **Show Border** check box. Then Click **OK** to save the setting and close the dialog.




7. Click on the Color Scale object and use the anchor points to resize it from vertical direction. The resulting graph should look like this:



6.11.2 Polar Plot with Error Bar

6.11.2.1 Summary

This tutorial will demonstrate how to create a Polar graph with error bars:




6.11.2.2 What you will learn

This tutorial will teach you how to:


- Create a Polar graph with error bars
- Customize the graph using the Plot Details and Axis dialogs

6.11.2.3 Steps


1. Import the data file **PolarPlotwithErrorBar.dat** under <Origin EXE Folder>\Samples\Graphing\ path (Minimum Origin Version: 2015 SR0), or you can download [this data file](#) directly and import into Origin.
2. Hover your cursor over col(C) till it appears as a downward pointing arrow and click to highlight column C. Right-clicking produces a menu where this column can be set as **Y error**.
3. In order to plot the Polar graph of the data with error bars highlight all the columns. In the main menu select **Plot: Specialized: Polar theta(X) r(Y)**. Alternatively, you can click the Polar theta(X) r(Y) button on the **2D Graphs** toolbar.




4. Double-click inside the plot to open the **Plot Details** dialog. In the **Error Bar** tab change the **Color** to Magenta and remove the negative error bars by deselecting the **Minus** box as shown below:




5. If the left panel of **Plot Details** is hidden, click the button with the two arrows on the bottom left of the dialog box. The left panel presents a tree-view display of the layer and data the user is modifying. It also displays a **Plot Type** list at the bottom. Use the **Plot Type** list to change the plot from **Line** to **Scatter**. This will change the tabs on the right panel and add a **Symbol** tab. In the Symbol tab, change the symbol style, color, and transparency as shown below. To select the symbol color, use the **Individual Color** option in the **Symbol Color** button. Click **OK** to close the dialog.




6. The next step is to modify the radial axes grid lines. These are the circular grid lines between the inner and outer angular axes. Double-click the vertical axis on the left side of the graph, (i.e. the Radial Axis) to open the **Axis** dialog. In the **Grids** page, choose **Radial** on the left panel. Change the Major Grids Line **Style** to **Dash**, and then clear the Minor Grids **Show** check box as shown below:



- Use the same procedure to modify the angular axes grid lines, the grid lines that radiate out from near the center of the plot to the edges. In the **Grids** page, choose **Angular** on the left panel. Change the Major Grids Line **Style** to **Dash**, set **Start at** to **Radial Start**, and then clear the Minor Grids **Show** check box. **OK** to save changes.




8. The completed polar plot should appear as shown below:



6.11.3 Polar Crop

6.11.3.1 Summary

This tutorial will demonstrate how to create a cropped polar graph:



Minimum Origin Version Required: 2015 SR0

6.11.3.2 What You Will Learn

This tutorial will show you how to:

- Customize the axes settings for a polar graph
- Crop the graph to show only a portion of the data

6.11.3.3 Steps to Create the Polar Graph and Customize the Axes

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: Polar Graphs**)

1. Open the **Tutorial Data** project, and browse to the folder *Polar Crop* in Project Explorer. Open the workbook **Book1AK**.
2. Highlight all the columns and choose **Plot:Specialized:Polar theta(X)r(Y)** from the main menu to create a polar graph:




3. Custom the **Angular Axes**

- The data is difficult to interpret since the range is too small to be adequately represented in a 360 degree plot (Origin sets units to degrees by default). Double-click on the axis to open the **Axis Dialog**. Go to **Scale** tab and choose **Angular** in the left panel. Expand **Units Definition** node and select the **Units** to **Radians** from the drop down. Change the **Value** option under **Major Ticks** to **0.25**, **Count** under **Minor Ticks** to be **9**.




- To change the orientation of the plot, go to **Show** tab and make sure the **Angular - Outer** is selected in the left panel. Set **Direction** to **Counter Clock-Wise** and the **Axis Start at(deg)** to **270** as shown below:




4. Custom the **Radial Axes** scale

- Go to the **Scale** node and choose the **Radial** in the left panel. Change the **To** value to 5.01 (the 0.01 will show the last tick), the **Value** option under **Major Ticks** to **0.5** and the **Count** option under **Minor Ticks** to **0**.




5. Add a **Inner Radial Axis**


- In the **Show** tab, click on the **Add a radial axis** button on the top of the left panel. Then the **Radial - Inner Axis 1** is added in the left panel.
- To change the orientation of the new inner axis from vertical to horizontal, under **Axis Position** section, set the **Reference** as **Clock Dial** and the **Clocks** option as **3 O'Clock**. Select the **Negative** radio button to shift the tick labels to the opposite side of the axis:




- To add tick labels on **Inner Axis 1**, go to **Tick Label** tab, under **Display** subtab and select **Tick-indexed string** from the **Type** drop-down. Type `0A "" Lv1 "" Lv2 "" Lv3 "" Lv4` in the **Display** edit box (Spaces within the double quotation marks are to indicate no text label at this tick, so that only every second tick is labelled). Set the Formatting options as shown below:



- Go to the **Format** subtab and change the tick label format as below:




- Go to **Special Ticks** set **Axis Begin** and **Axis End** to **Hide**. Click **OK** to close the dialog and these settings should create an axis as shown below:




6. Custom the position of **Outer Radial Axes**

- Double click on the axis to bring up **Axis** dialog again. Go to **Show** tab, and select **Radial - Outer 1** in the left panel. Set **% of Radius** to **-46**.



- Go **Special Ticks** tab, set the **Axis Begin** option to **Hide** for **Radial - Outer 1** axis.




- Repeat the above two steps for **Radial - Outer 2** and click **OK** to exit the dialog box.


6.11.3.4 Steps to Crop the Polar Graph

The crop tool allows you to magnify and emphasize any particular section of the polar plot.


1. Double click on any axis to open the Axis Dialog again. Click on the **Crop...** button to open the **Miscellaneous** dialog. Check the **Enable** box and set the values shown in the image below. Click **OK** to exit the dialog box.




2. The graph will now appear as shown below:




- In order to change the layer size to match the sample project select **Format: Layer Properties** from the main menu to open the **Plot Details** dialog. In the **Size/Speed** tab, set the following values:



- Expand **Layer1** and select the first data set. Use the **Plot Type** drop-down on the bottom left of the dialog to change the plot to scatter. Customize the symbol shape and color to resemble the final image (symbol color = Navy, symbol shape = filled circle, error bar color = red).
- To remove the negative error bars as in the sample, select the second dataset under **Layer1**. In the **Error Bar** tab on the right, clear the **Minus** box as shown below. The error bar color and thickness can also be adjusted here. **OK** to exit the dialog box.




- The final graph should appear as shown below. Delete any unwanted legends and the axis title by selecting them and pressing the **Delete** key:



6.11.4 Polar Graph with Custom Radial Axes

6.11.4.1 Summary

Origin's polar axis dialog allows for flexible customization of both angular and radial axes.



Minimum Origin Version Required: 2015 SR0

6.11.4.2 What You Will Learn

This tutorial will show you how to:


- create a polar graph
- hide angular axis
- customize radial axis

6.11.4.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Create a Polar without Angular Axis


1. Open the Tutorial Data.opj file and browse to the *Custom Radial Axis* folder and activate workbook **Book1E**.
2. Highlight column B and select **Plot:Specialized:Polar theta(X) r(Y)** to generate a polar graph.
3. Select the legend object and delete it.




- To hide the Outer axis (the outer circle) of the polar graph, double-click on any axis to open the **Axis** dialog. Go to **Show** tab, select **Angular - Outer** in the left panel, and clear **Show** check box.




- To hide all angular grid lines, go to **Grids** tab and make sure **Angular** is selected in the left panel. Clear the **Show** check boxes under **Major Grid Lines** and **Minor Grid Lines** section.



- Go to **Scale** tab and select **Radial** in the left panel. Set the axis scale as shown below:




7. Go to the **Grids** tab and set as below:




Add Radial Axis on each Major Tick


1. To show radial axis on each major tick position of angular axis, click the '**Radial Axes Configuration**' button to open the dialog. In the dialog, check the **Major Ticks** option under the **Axes Inside Polar** section.




2. To hide axis titles, go to **Title** tab and choose **Radial - Major Axes** in the left panel. Uncheck the **Show** check box. Click **Apply** button.



- There are 4 0's show in center of polar. To hide them, go to the **Special Ticks** tab. Select **Hide** from the **Axis Begin** drop-down list.



Click **OK** to close the dialog.




When radial axis is set to show on each major ticks, if you go to **Scale** tab of **Radial** and change major ticks, the radial axis will show in new major tick positions.

Use Configuration Dialog to Customize Radial Axis


Origin supports two kinds of radial axes. One is the frame border kind of axis around the polar graph. The other is inner axis from center of polar outwards.

1. Continue with the graph from the previous section, click on the **Radial Axes Configuration** button on the top of left panel. In **Radial Axes Configuration** dialog, under **Axes Inside Polar** branch, set **Angles List** as below, and click **OK** to close dialog.




2. Click **Apply** button. Four four radial inner axes show in the left panel.


3. Go to **Title** tab, select **Radial - Inner Axis1** in the left panel. Then check **Use Same Options for All Radial Axes** check box and clear the **Show** check box to hide all the titles. Then this setting will be applied to four radial axes.




4. Go to **Tick labels** node and check **Use Same Options for All Radial Axes**. Under **Format** subtab, set **Rotate(dge.)** to be **0**.




5. Go to the **Special Ticks** tab, and click **Use Same Options for All Radial Axes** check box. Set **Axis Begin** to **Hide**.
6. Go to **Show** tab, press **Shift** key to select **Radial - Inner Axis 3** and **Radial - Inner Axis 4** two axes, change **Flow Direction** to **Negative** under **Axis Position** section.



7. Go to **Tick labels** tab, enter a minus sign(-) in the **Prefix** edit box under the **Display** subtab.



8. Click **OK** button.



Further Customization

- To change the line plot color to red and a little thicker, select the line plot and on **Style** toolbar, set **Line/Border Color** as red, and set **Line/Border Width** to **1.5**.



- To add an equation to this graph as graph title, right-click on the graph and select **Add/Modify Layer Title**, then enter $r = \exp(q \cdot \cot(79.5p/180))$ into the edit box.

- Origin supports rich text. So highlight **q** in the text and click $\alpha\beta$ button on **Style** toolbar to turn it into θ . Also turn **p** into π . The text will look as below.


$$r = \exp(\theta \cdot \cot(79.5\pi/180))$$

- To add shadow to the text and make the font bigger, right-click on the title and click **Properties...** to open the **Object Properties** dialog. In the **Text** tab, set font size to **26**, and go to **Frame** tab to change **Frame** to **Shadow**. Click **OK** to save the setting.
- Drag the equation to the desired position. The graph should look like the one in **Summary**.

6.11.5 Polar Graph with Multiple Layers

6.11.5.1 Summary

The multi-layered graph allows the placement of several polar plots with different ranges on one graph page. This graph is generated by first creating 3 independent polar graphs, and then using the merge graph function to combine the three graph pages into one three-layer polar graph.



Minimum Origin Version Required: 2015 SR0

6.11.5.2 What You Will Learn

This tutorial will show you how to:

- Customize the Angular axis and Radial axis.
- Duplicate a graph with new data.
- Create multi-layered polar graph.
- Create one legend for the whole page.


6.11.5.3 Steps

This tutorial is associated with the **Tutorial Data.opj** file under the <Origin EXE Folder>\Samples\ path.


Create a Polar Graph for the Measured Data

Tutorials for Origin


1. Open the Tutorial Data.opj file and browse to the folder *Polar Graph with Multiple Layers*. Double-click the workbook **Book26** to open the workbook window.
2. Highlight Column A and Column B and select **Plot: Specialized: Polar theta(X) r(Y)** from the main menu to create the polar graph.




3. Right-click on any tick label of the Angular axis to open the dialog. Go to the **Scale** tab for Angular axis. Set the **Scale** of the Angular Axes as **From 60 To 150**. Set the **Value** for increments under **Major Ticks** as **30**. Click the **Apply** button to see the changes on the graph.




- Go to **Tick Labels** tab and make sure **Angular - Outer** is selected in the left panel. Under **Display** subtab, type $\backslash(176)$ in the **Suffix** text box to add the degree symbol to the Angular tick labels. For more details of supported text formatting commands, please refer to the [escape sequences](#) page.




5. Click the **New Configuration...** button to open the **Radial Axes Configuration** dialog.
 - Check the **Axes Inside Polar** box and configure it as shown below:
 1. Set the **Angles List** as **Custom**.
 2. Set the **Value** text box as **60 150** to place an axis at 60 degrees and one at 150 degrees.
 - Set the **Axes Outside Polar** options as shown below:
 1. Select **Upper** from the **Right** option drop-down to place an axis at the upper right of the layer frame.
 2. Set **%s of Radius** as **0**.




6. Click **OK** to apply the settings.
7. Go to **Scale** tab, and select **Radial** in the left panel. Set radial axis **From** as **2** and **To** as **6**. Change the increment **Value** for the **Major Ticks** to **1**.




8. Go to **Tick Labels** tab and select **Radial - Inner 2** in the left panel. Uncheck **Show** check box to hide the tick labels for this axis.




- Go to **Title** tab and select **Radial - Outer 1** in the left panel. Uncheck **Show** check box to hide the title of the outside polar axis. Click the **OK** button.



10. Double-click the plot to open the **Plot Details** dialog. In the left panel of the **Plot Details** dialog, click the **Graph** page to go to the page level of this dialog. In the **Legends/Titles** tab, deselect the check box **Indicate Active Dataset**, so that the red box around the legend symbol will be hidden.
11. Expand the **Layer** node on the left panel and select the graph under it. On the **Line** tab in the right panel, change **Width** to **4** and **Color** to **Blue**.




12. Click the **OK** button to apply customizations to the first polar graph.



Duplicate a Polar Graph with the Calculated Data


1. Right-click the header of the polar graph to open the shortcut menu. Select **Duplicate (Batch Plotting): Duplicate with New Columns...** to open the **Select Column** dialog. Select the column **C:Calculated** and click **OK** to duplicate a polar graph with data from Column C.




2. Since the data range in Column C is quite different from Column B, the **Reminder Message** window will pop up, asking whether to rescale the axes of the new graph to show all data. Leave the **Yes** radio button selected and click **OK**.
3. Follow steps 3 from the last section to set the scale of the Angular Axes. Set **From** as **240** and **To** as **360** and the increment of the **Major Ticks** to **15**.
4. On the **Scale** tab, choose **Radial** in the left panel and then set **From** as **2** and **To** as **6** and the increment of the **Major Ticks** as **1**.
5. Go to **Show** tab
 - Choose **Radial - Inner 1** in the left panel. Under **Axis Position** section, set the **Value (Degrees)** as **240** to move the first inside polar axis to 240 degrees.
 - Choose **Radial - Inner 2** in the left panel. Set the **Value (Degrees)** as **360**.
 - Choose **Radial - Outer 3** in the left panel. Select **Left-Lower** in **Axis at** drop-down list to move the outside axis to the lower left of the layer frame.

Click the **OK** button to finish customizing the axes.

- Double click the plot to open the **Plot Details** dialog. Change the line **Color** to **Red** and **Width** to **4** in the **Line** tab. Click **OK**.




Create a Polar Graph to Show Full Range Grids

- Open the workbook **Book26**.
- Select Column D and click the **Polar theta(X) r(Y)**  button in the **2D Toolbar** to create an empty polar graph.
- Repeat steps 3 in the [Create the Polar graph for the Measured data](#) section to set the scale of the Angular Axes as **From 0 To 360** and the increment **Value** of the **Major Ticks** as **30**.
- Go to **Show** tab, select **Angular - Outer** on the left panel and uncheck **show** box. Then select **Angular - Inner** on the left panel and check **Show** box.
- Go to **Tick Labels** tab, select **Angular - Inner** in the left panel, and uncheck the **Show** check box to hide the tick labels of the inner Angular axis.
- Go to **Grids** tab, make sure **Angular** is selected in the left panel. Uncheck the **Show** option in the **Major Grid Lines** and the **Minor Grid Lines** sections.
- Go to **Scale** tab, select **Radial** in the left panel, and change the scale **From 2 To 6** and set the increment **Value** of the **Major Ticks** as 1.
- Go to **Show** tab, select **Radial - Outer 1**, and check **Use Same Options for All Radial Axes**. This will apply the settings on this page to **Radial - Outer 2** axis as well. And then uncheck **Show** check box. Click the **OK** button.


Create the Multi-layered Graph with One Legend

1. With a graph window activated, select **Graph: Merge Graph Window** from the main menu.
2. Set the **Merge** option as **Specified** and make sure only **Graph1**, **Graph2** and **Graph3** (the three new graphs just created) are selected in the **Graphs** text box.
3. In the **Arrange Settings** section set both **Number of Rows** and **Number of Columns** to **1** to overlay the three graphs.
4. Check the box next to **Link Source Graphs**.
5. In the **Page Setup** section, set both **Width** and **Height** to **15**.




6. The preview of the graph can be seen in the right panel.
7. Keep the rest of the default settings and click **OK**.
8. Right-click the legend and select **Legend: Update Legend** from the shortcut menu, to open the dialog.
9. Set the **Update Mode** to **Reconstruct** to create a new legend.

10. Set the **Legend** to **One Legend for Whole Page** to create only one legend for this multi-layered graph.
11. Set the **Layer Order** as **Descending** to place the Layer 2 legend above the Layer 1 legend.
12. Set the **Auto Legend Translation Mode** as **@LA: Long Name** to use the Long Name data for the legend. Click **OK**.



13. Right-click on the new legend and select **Properties...** to open the dialog.
14. Set the **Background** as **(None)** and delete the first line in the lower text box. Click **OK**.
15. Drag the legend to the center of the inner Angular axis.
16. Use the **Font Size** text box to change the size of the fonts on this graph. Drag the tick labels to move them to an appropriate position.
17. Right-click one of the inner radial axis titles (**Calculated** or **Measured**) and select **Properties...** from the shortcut menu.
18. In the **Object Properties** dialog that opens, in the **Frame** tab, choose the **None** from **Frame** drop-down list. This clears the grid lines and other background from behind the axis title making it easier to read. Click **OK**.
19. Repeat the same operation for the other inner radial axis title.
20. The final graph should appear as shown below:



6.11.6 Polar Graph with Columns and Stack Columns

6.11.6.1 Summary

By default, Origin polar graphs are line plots. Note, however, that you can convert an existing polar line plot to column/bars. Further, a grouped column plot in polar coordinate system can be stacked. Minimum Origin Version Required: 2015 SR0

6.11.6.2 What You Will Learn


This tutorial will show you how to:

- plot polar graphs with columns
- control the column width using a dataset
- create a stacked column plot in the polar coordinate system

- customize the polar axes

6.11.6.3 Steps


Polar Graph with Columns




This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Polar Graphs**)


1. Open the Tutorial Data project and browse to the folder *Column and Stack Column* and activate **Book18**.
2. Highlight column B and select **Plot:Specialized:Polar theta(X) r(Y)** to create a line plot in the polar coordinate system. Click on the legend object and delete it from the graph.
3. Double-click on the line plot to open the **Plot Details** dialog box. Make sure the left panel is expanded and set **Plot Type** to **Column/Bar**. This will change the line plot to a column plot.
4. In the **Pattern** tab, under the **Fill** section, set **Color** to **Color Mapping:Col(D)**. This will map column colors in the plot using the row value in column D of the worksheet (note that a **Colormap tab** is added to **Plot Details**. Click on this tab to see how values are mapped to fill color).
5. Set the **Transparency** in this tab to **70%**, and **Width** of border to **2** :




6. Go to the **Spacing** tab, select **Col(C):"Size"** from the **Width(in %)** drop-down menu and type in **8** as **Scaling Factor**. This causes values in column C to determine the width of the columns in the plot.



7. Go to **Colormap** tab, click **Level** head. Set the level from **0** to **1** and **Increment** to **0.2** in the **Set Levels** dialog,



8. Go to **Size/ Speed** tab under **Layer1** level, and set **Layer Area** as following:




Click **OK** to close the **Plot Details** dialog.

9. Now we will customize the graph **Angular Axes**.

- Double-click on an axis (Angular or Radial) to open the **Axis** dialog. Go to the **Scale** tab under the **Angular** tree node and set the **Value** under **Major Ticks** to **45**, and set the **Count** under **Minor Ticks** to **2**.
- Go to **Format** tab under **Tick Labels** tab of **Angular -Outer** tree node. Check **Bold** check-box.
- Go to **Grids** tab under **Angular** tree node. Change **Style** of **Major Grid Lines** to **Dash**.
- Go to **Line and Ticks** tab under **Angular -Outer** tree node. Change **Thickness** of **Line** to **1.5**.


10. In the **Axis** dialog, we also can customize the **Radial Axes** for this polar graph.

- Click on the **Radial Axes Configuration** button  on the right-top of this dialog to open the dialog. In the dialog, choose **0 90 180 270** under the **Angles List** drop-down list.




- Go to the **Scale** tab under the **Radial** tree node. Set scale from **0** to **1**.
- Go to the **Format** tab under **Tick Labels** tab, and then
 - select the **Radial - Inner1**, change **Size** to **12**, check **Bold** box, and set **Rotate (deg.)** to **0**.
 - select the **Radial - Inner2**, change **Size** to **12**, and check **Bold** box.
 - select both **Radial - Inner3** and **Radial - Inner4**, then uncheck **Show**.
- Go to the **Display** tab under **Tick Labels** tab of **Radial - Inner1** tree node. Choose **Custom** in **Display** drop-down list, and enter **.2*** in **Custom Format** text box.
- Go to the **Title** tab and highlight all radial axes node. Uncheck **Show** check box.
- Go to the **Grids** tab under **Radial** tree node. Uncheck **Show** check box under **Minor Grid Lines**. Click **OK** to save the setting and close the dialog.


- Go to **Line and Ticks** tab, select all radial axes. Change **Thickness** of **Line** to **1.5**. And set **Style** to **In & Out**, **Length** to **5** for both **Major Ticks** and **Minor Ticks**.




- Go to **Special Ticks** tab of **Radial - Inner 1**, then set **Axis Begin** value to **Show**, **Axis End** value to **Hide**. Choose **Radial-Inner 2**, set both **Axis Begin** and **Axis End** value to **Hide**. Click **OK** to apply the setting and close the dialog.
11. Select **Graph: New Color Scale** to add the color scale legend. To customize the color scale legend, double click on the color scale to open the dialog.
- In the **Color Scale Control** dialog, go to **Level** page, and check the **Hide Head and Tail Levels**
 - Go to **Labels** page, check **Set Decimal Places** check box and enter **1** in the **Decimal Places** text box.

- Go to **Layout** page, select **Separated** in the **Layout** drop-down list. Click **OK** to apply the setting and close the dialog.

12. Click on the Enable/Disable Anti-Aliasing button . This polar column plot should look something like this:




Polar Graph with Stack Columns




This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data project and browse to folder *Column and Stack Column* and activate **Book3F**.
2. Highlight columns B through D and select **Plot:Specialized:Polar theta(X) r(Y)** to create a grouped line plot in the polar coordinate system.
3. Double-click on the line plot to open the **Plot Details** dialog box. Make sure the left panel is expanded and set **Plot Type** to **Column/Bar** and click **Apply** to change the plot to a grouped column plot.
4. On the **Group** tab, click the ... button to the right of **Fill Color**. This opens the **Increment Editor**. Right-click on the first Background Color, black, and delete it from the increment list:





5. Click **OK** to apply the new increment list and close the **Increment Editor**.
6. Go to the **Spacing** tab and set **Gap Between Bars (in %)** to **30**.
7. In the left panel of the **Plot Details** dialog, click **Layer 1** (take care not to clear the check box) to see the **Layer Properties**. Go to the **Stack** tab and recreate the following settings so that the columns will be stacked and normalized to 100%:




8. Go to the **Display** tab and select the check box **Grid on Top of Data** to draw grid lines on top of data plot. Clear the **X Axes** check box under **Show Elements** to hide the Angular axis and its associated grid lines in the graph:




9. Click **OK** to apply the settings and close the **Plot Details** dialog box.
10. Click the  button in the **Graph** toolbar to rescale the radial axis of the graph from 0-1 to 0-100 (Or you can press **CTRL+R**).
11. We have created a 100% Stack Column graph in polar coordinate system, and now we will customize its axes. Double-click on any axis to open the **Axis** dialog. Click on the **Radial Axes Configuration** button to open the dialog box. Recreate the following settings to display only one Radial axis at 120 degrees on the polar graph. Click **OK**.




12. Go to **Show** tab and you will see the **Radial - Inner 1** in the left panel. Select it, and change the **Flow Direction** to **Negative** so that the tick label will be displayed outside the data plot.




- Go to the **Scale** tab and make sure **Radial** is selected in the left panel. Set **From: 10** and **To: 100**. Under **Major Ticks** section, choose **By Custom Position** in the **Type** drop-down list, and enter **40 80** in the **Position** text box. Set **Count** to **0** for minor ticks




14. Go to the **Grids** tab. For Radial Axes, set the major grid lines as following image:




15. Go to the **Tick Labels** tab, add a % suffix under **Display** subtab. Add set a horizontal offset under **Format** subtab.






16. Go to the **Title** page and clear the **Show** check box to hide the axis title.
17. Click **OK** to close the **Axis** dialog box. Your graph should look something like this:



6.11.7 Polar Graph with Custom Angular Scale

6.11.7.1 Summary

Normally, the polar angular axis unit reads in degrees, radians or gradians. However, Origin's polar graph also supports use of custom units.



Minimum Origin Version Required: 2017 SR0

6.11.7.2 What You Will Learn

This tutorial will show you how to:

- use a dataset to control symbol size and color in a polar graph.
- use a custom unit for the angular axes.
- add and custom the bubble scale


6.11.7.3 Steps

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Polar Graphs**)

1. Open the **Tutorial Data** project and browse to folder *Scale Unit Control* and activate **Book2F**.
2. Highlight column B and select **Plot:Specialized:Polar theta(X) r(Y)** to create a line plot in polar coordinate system.
3. Double-click on any axis to open the **Axis** dialog. Go to the **Scale** tab and select **Angular** in the left panel. In this right panel, expand **Units Definition** node, and choose **Radians** as **Units**.


Make sure the scale from **0** to **2 PI**. Then change the **Value** of increment to **0.2**




4. Go to the **Show** tab for **Angular-Outer** axis, then change the **Direction** to **Clockwise** and set **Rotate (deg.)** to **90**.



5. Go to the **Scale** tab and select **Radial** in the left panel. Then set the scale from **0** to **1.2**, and change the **Value** of increment to **0.4**.




6. Go to **Tick Labels** tab for the **Radial- Outer 1** axis. Choose **Format** subpage, and check the **Bold** check box. Then click the **Apply To...** button. In the pop-up dialog, make sure **Apply From** is **Outer 1** and **Apply to** is **All Axes**, then check the **Bold** under the **Tick Labels**. Click **OK**.




In Axis dialog, click **OK** to apply settings and close the **Axis** dialog.

7. Double-click on the line plot to open the **Plot Details** dialog, make sure the left panel is expanded and set **Plot Type** as **Scatter**. In the **Symbol** tab, recreate the following settings, in the sequence shown in the screenshot:




Click **OK** to apply the settings and close the **Plot Details** dialog.


8. Select **New Bubble Scale** in the **Graph** main menu to add a bubble scale in this graph.
9. Right-click on the bubble scale, and choose **Propertise...** to open the control dialog. Go to the **Level** page, set the level from **0** to **1**, and change the **Value** of increment to **0.25**.




- Go to **Labels** page, check the **Set Decimal Places** check box and enter **1** in the **Decimal Places** text box.



- Go to **Layout** page, choose **Nested** in **Layout** drop-down list. Select **Black Edge and No Fill** as **Bubble style** and change the **Label Offset from Symbol Center** to **150**. Check the **Show Leader Line** check box, then expand the node to check the **Auto Reoisition to Avoid Overlapping** check box. Click **OK** to apply the setting and close the dialog.



Manually move the legend object. The final graph should look like this:



6.12 3D Graphs


- [3D Pie Chart](#)
- [3D Vector](#)
- [3D Scatter Plot with Line Projections of Core Drilling Locations](#)
- [3D Bar and Symbol](#)
- [Surface with Missing Values](#)
- [Creating Intersecting Surface Plots from Worksheets](#)
- [Intersecting Color Surfaces](#)
- [Surface with Symbols and Droplines](#)
- [Colormap from Second Matrix](#)

- [Color Map Surface Graph](#)
- [Parametric Surface with Colormap from Data](#)
- [Stacked 3D Surface Plots](#)
- [Multiple Surfaces in Same Layer](#)
- [3D Scatter with Colormap](#)
- [3D Scatter with Droplines](#)
- [Surface With Transparent Plane](#)
- [3D Bar on Flatten Surface](#)
- [3D Bar with Labels](#)
- [3D Surface with Point Label](#)
- [Transparent Parametric Surfaces combined with Scatter Plot](#)
- [Convert Data from Spherical Coordinate to XYZ and Make a 3D Plot](#)
- [Flattened Colormap Surfaces with Increasing Z Offset](#)
- [3D Ternary Colormap Surface with Contour Lines Projection](#)
- [3D Ternary Scatter Plot with drop lines](#)

6.12.1 3D Pie Chart

6.12.1.1 Summary

Origin's 3D Pie Chart gives you complete control over the look of the plot. Set the thickness of the pie slice, displacement, view angle, and size and rotation of the chart. You can even choose to explode the view of one or more pie slices.




6.12.1.2 What you will learn

- Create 3D pie chart and change the view angle
- Explode the view of pie slices
- Customize pie slices individually

6.12.1.3 Steps

You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: Statistical Graphs**)

1. Import the data `\Samples\Graphing\3D Pie Chart.dat` into worksheet, and rename the column long name as *Demographic* and *Percent*.
2. Highlight the 2nd column and create a 3D Pie Chart from **Plot: Column/Bar/Pie: 3D Color Pie Chart**.
3. Double-click the pie chart to bring up the **Plot Details** dialog. In the **Pattern** tab, set the **Fill color** to **Increment** and red as starting color. Next, select the **Pie Geometry** tab and change the **Rotation** to 68 degrees. Then check the checkbox for *American Indian* and *Other* in the **Explode Wedge** group as shown below and click **OK**.



4. Then hold the **Ctrl** key and double click each pie slice to open the **Plot Details** dialog and change the **Fill Color** in the **Pattern** tab.

6.12.2 3D Vector

6.12.2.1 Summary

Origin can plot 3D Vectors from two different data structures: **XYZ XYZ** and **XYZ dXdYdZ**.

XYZ dXdYdZ defines the tail and head data for the vector, while XYZ dXdYdZ provides the vector's tail data and the distance between tail and head projections on X, Y, and Z axes.

6.12.2.2 What you will learn


- Create a 3D Vector from XYZ dXdYdZ worksheet data.
- Customize the 3D Vector

6.12.2.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: 3D Symbol Bar and Wall**)

1. Open **Tutorial Data.opj** and browse to the **3D Vector** folder in **Project Explorer** (PE).
2. Select workbook **Book2**. Click in the upper left corner of the worksheet to select all data.
3. On the main menu, select **Plot**, then point to **3D Symbol/Bar/Vector**, and then click **3D Vector XYZ dXdYdZ**. This will create a 3D Vector graph with our built-in template.




4. Double-click on the vector plot to open the **Plot Details** dialog box. Ensure that the **Original** vector plot has been selected in the left panel of the dialog box. Select the **3D Vector** tab.
 - In the **3D Vector** tab of **Plot Details** dialog box, set the parameters as shown in the following graph. Click the **Color** button and select **Dark Green** from the menu.

Tutorials for Origin




Click **OK** to apply these settings and close the dialog box.

5. Go to **Lighting** tab in **Format: Layer Properties** dialog, Set the lighting attribute follows graph below:




6. Rotate the graph to a proper perspective. The final graph should look something like this:



6.12.3 3D Scatter Plot with Line Projections of Core Drilling Locations

6.12.3.1 Summary

This tutorial will demonstrate how to create a 3D scatter plot and show the projections of the plots.





Minimum Origin Version Required: Origin 2015 SR0

6.12.3.2 Steps


This tutorial is associated with the Tutorial Data.opj file under <Origin EXE Folder>\Samples\.


1. Open the Tutorial Data.opj file and browse to the folder **3D Scatter with Line Projections**, activate the workbook **3DScatterPlot**.
2. Activate the **The_First_Curve_of_3D_Scatter** worksheet. The column designation for the three columns is already set as XYZ so you could directly create a 3D scatter plot. Highlight column **C** and select **Plot: 3D Symbol/Bar/Vector: 3D Scatter** to create the plot.
3. Activate **The Second Curve of 3D Scatter** worksheet. Highlight column **C**. Move the mouse

cursor to the right edge of the selection area until the shape of the cursor changes to . Hold down the left mouse button and drag the highlighted data into the newly created graph window. The resulting graph should appear as shown below:




4. Double-click on the Z axis to open the **Axis** dialog, go to the **Scale** tab with **Z** icon on left panel selected and reverse the Z axis by exchanging **From** and **To** values.

- Click **OK** to close dialog. Select **Format: Layer Properties** from the main menu to open the **Plot Details** dialog. Alternatively you can double-click on the plot to bring up the dialog. If the left panel is not visible, use the  button on the bottom left of the dialog box to open it up. Expand the **Layer1** node. Choose the first plot and select **All Together** from the **Edit Dependencies** page. This applies the same settings to the original data and all the projections.




- Expand the first plot node and select **Original** and **XY/XY/YZ Projection** check box.
- Set the dialog options to those shown in the screenshot below. To set the color, click on the **Color** button and choose the desired option from the **Individual Color** drop down. Since the **All Together** radio button was selected in the previous step, these settings automatically apply to the projections as well.






- Select the **Symbol** tab and change the **Shape** to **Cube**:

Tutorials for Origin




9. In a similar fashion, select the second plot and set the dialog options to match those in the screenshots below:





10. The final graph should appear as shown below:




6.12.4 3D Bar and Symbol

6.12.4.1 Summary


This graph is a combination of a 3D bar plot showing the changes in HPI (Home Price Index) and a 3D scatter plot showing the Unemployment Rate. The data is of several Census Divisions during different years. Colormapping is introduced to both plots based on the Z values.

2. Activate book **Home Price Index Changes & Unemployment Rate**, highlight columns A(X), B(Y), and C(Z), and then select **Plot:3D Symbol/Bar/Vector:3D Bars** to plot a 3D bar graph.




3. Right-click on the layer icon and choose **Plot Setup** from the context menu. In the **Plot Setup** dialog, set columns A, B, and G1 as X, Y, and Z respectively. Then click the **Add** button to add



this plot to the current layer. After that, click the **OK** button to close the **Plot Setup** dialog.



4. Double-click on the plot to open the **Plot Details** dialog. In this dialog, select the second plot in the left panel and set the **Plot Type** as **3D Scatter/Trajectory/Vector**.








In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.


5. Select **Original** in the left panel, then go to the **Symbol** tab in the right panel, select Col("Unemployment rate") for both **Size** and **Color**, and set the **Scaling Factor** of size as **2**.



- Go to the **Colormap** tab, set **Level** and **Fill** as shown below.




7. Go to the **Label** tab, check the Enable check box, set **Label From** as $Col(F)$ and **Position** as *above*.




8. Go to the **Numeric Format** tab, select **Decimal Places** and set it to 0.




9. Select **Layer1** in the left panel. In the right panel, go to the **Planes** tab, uncheck **YZ** and **ZX**, select **At Position=** for the **Position** dropdown list and enter **0** for the **Percent/Value** blank box.




10. Go to the **Axis** tab in the right panel, do settings as below:




11. Select the first plot under Layer1 in the left panel, go to the **Pattern** tab, use Col("Changes in HPI") as the colormapping for both bar border and shape fill.




12. Go to the **Outline** tab, set the **Width(in%)** to 30 as below.




13. Go to the **Numeric Format** tab, select **Decimal Places** and set it to 0.



14. Go to the **Colormap** tab, click **Level...** header to open the **Set Levels** dialog. Do settings as below.




15. Click OK button to close the **Set Levels** dialog. Click **Fill...** and select the **Pumpkin Patch** as the palette. Click OK to close the Fill dialog.




16. Click the **OK** button to close the **Plot Details** dialog.
17. With the graph window active, select **Graph: New Color Scale** from the main menu to add a color scale for the first plot. Double-click on the color scale to open the **Color Scale Control**

dialog. In this dialog, apply settings below.




18. Click OK button to close the **Color Scale Control** dialog. Then right-click the layer icon to activate the other plot from the context menu, then select **Graph: New Color Scale** from the main menu to add another color scale. Double-click on this color scale to open the **Color Scale Control** dialog. In this dialog, do the settings as the previous step does.

19. Add titles **Changes in HPI** and **Unemployment Rate** for these two color scales. Finally, you will get the graph given below.



6.12.4.4 Controlling the Categorical Values


1. In the following steps, we want to customize the order of values shown in the graph but not change the source data. Right click on window title of source data book, select View: Categories, a new column label named **Categories** will be added to the head of the worksheet. Double click the "unsorted" to open the **Categories** dialog :




2. Uncheck the **<auto>** checkbox, then you can specify the order of the items by using




buttons based on the order of census division shown in graph below:



3. Double click the Categories cell of column **B**, "Unsorted", to open the **Categories** dialog. Select **Ascending** in the **Sort** list, click **OK** to close the dialog.




- The 3D bar graph will be updated automatically with the new order of Categorical data.



6.12.5 Surface with Missing Values

6.12.5.1 Summary

In this tutorial, a 3D color map surface graph as shown below will be created from a matrix with missing values. It will also demonstrate how gridlines can be skipped by customization.



Minimum Origin Version Required: Origin 2015 SR0


6.12.5.2 What you will learn

This tutorial will show you how to:


- Create a 3D surface plot from a matrix by ignoring missing values
- Skip gridlines on a 3D surface plot
- Set contour lines
- Set contour levels and fill colors


6.12.5.3 Steps


1. Start with a new worksheet and import the file `\Samples\Graphing\Surface With Missing Values.dat`. Hover the cursor over the cell in the top left corner of the worksheet till it appears as a slanting black arrow and click to highlight. Select **Plot: 3D Surface: Color Map Surface** from the Origin main menu to create a graph. This is a virtual matrix so the **plotvm** dialog (plot virtual matrix dialog) will appear. Use the system default settings as below:




2. The graph should appear as shown below:




3. Double click on the graph to pull up the **Plot Details** dialog. If the left panel is not expanded use the  button on the bottom left of the dialog to open it. Expand the tree node on the left panel to make sure that the box under **Layer1** is selected. The next few steps will customize the graph using the settings in the **Plot Details** dialog. Activate the **Colormap / Contours** tab on the right panel. Click the **Level** heading to open the **Set Levels** dialog and set the dialog as shown in the following image.:




- Click on the **Fill** heading to open the **Fill** dialog. In this dialog, choose the **Load Palette** radio button and then click the **Select Palette** button to choose the **Reef** palette. Ensure the **Link to Palette** check box has been enabled. Click the **OK** button to return to the **Plot Details** dialog.




5. Click on the **Line** heading to open the **Contour Lines** dialog. Check **Color** check box under **Apply to All**, and set **Color** to **LT Gray**. Click the **OK** button to return to the **Plot Details** dialog.




6. Activate the **Mesh** tab on the right panel. Deselect the box before **Enable** as the following screenshot shows. Click **Apply**. This will remove the mesh lines on the graph:




7. Click on the **Layer1** on the left panel, and select **Lighting** tab on the right panel. Select **Direction** in Mode. Click **OK** to save the setting and close the dialog.



8. Double click on the axis title object(s) to modify them to X and Y for X and Y axis respectively.
9. Click the layer spacer to activate the 3D transform control toolbar, then select the **Rotate** button to rotate the 3D graph to a desired orientation:



10. The final graph should appear as shown below:



6.12.6 Creating Intersecting Surface Plots from Worksheets

6.12.6.1 Summary

Many plot types, such as 3D Surface, 3D Bars, and Contour, can be created from data contained in a matrix object or from data arranged in a block of cells in a worksheet. The latter arrangement is referred to as a **Virtual Matrix**. Whereas a typical matrix object only supports a linear mapping of X and Y coordinates, a virtual matrix supports nonlinear mapping as well. In this tutorial, we show you how to create intersecting color map surface plots from virtual matrix data.

Minimum Origin Version Required: Origin 2015 SR0

6.12.6.2 What you will learn

This tutorial will show you how to:

- Create a Color Map Surface plot using virtual matrix data from a worksheet
- Add one surface graph to another to create intersecting surface plots
- Set transparency


6.12.6.3 Steps

Create Surface Plots from Virtual Matrix Data

This section will demonstrate how to create surface plots from data in a worksheet.

1. Start a new project.
2. Click the **Import Multiple ASCII** button  on the **Standard** toolbar.
3. In the dialog that opens, navigate to the `\Samples\Graphing` folder and select both *VSurface 1.dat* and *VSurface 2.dat* by holding down the Ctrl key and clicking **Add File(s)**

4. Select the **Show Options Dialog** check box.



5. Press the **OK** button.

6. In the **impASC** dialog, modify the settings according to the following image, so that the two data files will be imported as two worksheets with name **VSurface1** and **VSurface2** in one workbook:

Import and Export: impASC

Dialog Theme <sheet>

Description Import ASCII file/files

Import Options

Add Sparklines Yes(if less than 50 columns)

Import Mode Start New Sheets

Template Name

File Structure

Columns

Header Lines

(Re)Naming Worksheet and Workbook

Auto Rename Using Filename

Rename Sheet with (Partial) Filename

Trim Filename From 1

Trim Filename To 0

Rename Book with (Partial) Filename

Trim Filename From 1

Trim Filename To 0

Rename Long Name for Book only

Include File Path when Renaming Book


Append Filename to Workbook Comment

Append Filename to Worksheet Comment

Append Filename to Column Comment

Include File Path when Appending Filename

- Click **OK** to import these two data files.




The data has X coordinate values in the top row and Y coordinate values in the first column. Note that the X coordinates have nonlinear spacing.


- With the "VSurface 1" sheet active, hover the cursor over the cell in the top left corner of the worksheet till it appears as a slanting black arrow and click to highlight. .
- Select the menu item **Plot: 3D Surface: Color Map Surface** to open the **plotvm** dialog.

Note: This dialog opens every time a 3D or Contour plot menu item is invoked with a group of worksheet cells selected. The dialog allows you to define where the X and the Y coordinate values are located.


10. In this dialog, adjust the settings as shown in the image below:



11. Click **OK** to generate a Color Map Surface plot and a virtual matrix as shown below:



12. Repeat the last step to plot another Color Map Surface plot using data from the VSurface 2 worksheet. This time **VSurface 2** will be automatically used as Z title in the **plotvm** dialog.




Add Another Surface Plot to Layer


This section will demonstrate how to add a surface plot to a graph layer that already contains another surface plot.

1. Activate Graph1, right-click on the Layer 1 icon **1** on the top left corner of the graph and select **Layer Contents** from the context menu.
2. In the **Layer Contents** dialog that opens, select **VSurface2** from the Available Data panel on the left and add it to the Layer Contents box on the right using the arrow that points to the right in the center of the dialog box (The arrow below it can be used to shift selected items from Layer

Contents to Available Data).



3. Click **OK** to add the second surface, the graph will now appear as shown below:




Note the two surfaces are displayed with proper intersection.

Set Surface Transparency


The next step is to set the transparency of the second surface so that parts of the first surface are visible in this intersection plot.

1. Double click on the second colormap surface to open the **Plot Details** dialog.

2. In the **Surface** tab, move the **Transparency** slider to 40% and click **Apply**, then **OK**.



The completed graph should appear as the the image shown below:



6.12.7 Intersecting Color Surfaces

6.12.7.1 Summary

Origin supports multiple intersecting surfaces.

Minimum Origin Version Required: Origin 9.0 SR0

6.12.7.2 What you will learn

This tutorial will show you:

- How to create intersecting color surfaces from different matrix objects.
- How to customize the colormap surface plot.
- How to construct additional color scale for multiple colormap surfaces.

6.12.7.3 Steps


This tutorial is associated with the **Tutorial Data** project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the **Tutorial Data** project and browse to folder *Intersecting Surfaces* in **Project Explorer**.
2. Active the **MBook36** matrix. Note that the matrix displays two thumbnail images above the data, one for each matrix object in the matrix.




To plot intersecting surfaces, each matrix object must have identical dimensions and XY Mapping. This requirement is automatically fulfilled when the two objects are contained in the same matrix.


3. Select either thumbnail image. From the main menu, select **Plot**, then point to **3D Surface**, and then click **Multiple Colormap Surfaces**. This will generate an intersecting surface plot of every matrix object in the matrix sheet.
4. Open the **Layer Properties** dialog by double-clicking on the graph layer, or by selecting **Format:Layer Properties...** from the main menu. Go to the **Lighting** tab, and change the **Mode** to **Directional** to turn on the lighting effect.




Click on **Apply** button, you can find the graph showing as this:





- Expand the **Layer 1** branch in the left panel, select **[MBook36]MSheet1!_1(Z)[1*:400*]** to open the **Plot Properties** dialog. In the right panel, go to the **Colormap/Contour** tab, uncheck the **Enable Contours** check box to turn off contour lines
- Click the **Fill...** column header to open the **Fill** dialog box. Click the default **Rainbow** palette to open the palette menu. On the palette menu, select **Pastel**. Click **OK** to close the **Fill** dialog box.




- Select **[MBook36]MSheet1!_2(Z)[1*:400*]** in the left panel. Uncheck the **Enable Contours** check box. And click **Apply** to see the modifications so far. Do the same for **[MBook36]MSheet1!_1(Z)[1*:400*]**.
- Keep **[MBook36]MSheet1!_2(Z)[1*:400*]** selected, and go to the **Mesh** tab and clear the check box before **Enable** to turn off the mesh lines. Do the same for **[MBook36]MSheet1!_1(Z)[1*:400*]**.
Click **OK** to close the **Plot Details** dialog box and update the graph.
- Now we will construct the an additional color scale for the second surface, change that plot to be active by click **Data:2 [MBook36]MSheet1!_2(Z)[1*:400*]**, then click **Graph:New Color Scale** to create color scale for this plot.
- Double click on the newly added color scale object to open the **Color Scale Control**, change the settings according to the screenshots below, then drag and put the color scale object to a desired place on the layer:






11. You can use the 3D rotation button  to rotate the graph and gain an overhead perspective. This button is a part of the 3D annotation toolbar which can be brought out by clicking the graph

layer once 


Your final graph should look something like this:




6.12.8 Surface with Symbols and Droplines

6.12.8.1 Summary

Origin supports transparency in most graph types. This feature permits the visibility of parts of a graph that would otherwise be obscured by overlapping plots. In this tutorial, we will add a fitted surface to a scatter plot, set transparency to make data points "behind" the surface visible, and add drop lines and error bars for data points.



Surface with Symbols and Droplines



Surface with Symbols and Error Bar

Minimum Origin Version Required: 8.5 SR0


6.12.8.2 What you will learn

- Create a 3D scatter plot from worksheet data and add a color fill surface to it.
- Draw drop lines or error bars for data points.
- Set surface transparency.

6.12.8.3 Steps


Create a surface graph with symbols and droplines

1. Open the **Tutorial Data** folder by clicking **File: Open Sample Projects: Tutorial Data** from the main menu.
2. Under this folder, go to **Surface with symbols and droplines** folder.
3. Active the worksheet *XYZRandomGauA*, highlight the XYZ to plot a 3D scatter by selecting **Plot: 3D Symbol/Bar/Vector: 3D Scatter** from the main menu.




4. Now we will add a 3D Color Fill Surface plot to this 3D scatter graph. In the top left corner of the graph window, double-click the layer **1** icon to open the **Layer Contents** dialog.
5. In the **Layer Contents** dialog box, select **Matrices in Folder** from the dropdown menu in the upper left. In the left panel, select **MBook 3**, Click the **triangle button** next to **A** and select **3D - Surface**.




Click  to add it to the right panel.




- Click **OK** button to apply the change and close the **Layer Contents** dialog. Double-click the graph to open the **Plot Details** dialog box. In the left panel of this dialog, expand all items and select **Original** (or choose **Plot Properties** from the **Format** menu). In the right panel, on the **Symbol** page set **Size** as 9 and **Color** as *Olive* from **Individual Color** fly-out menu and click **Apply**.




- In the left panel, select the surface plot, and then go to the **Fill** tab in the right panel, change the **Fill piece by piece** as **Red**. Set **Transparency** to **60** and click **Apply**.




- Go to the **Mesh** tab, set the **Line Width** as **1** and **Set Total Number of Majors** as **X=9** and **Y=9**, and **Major Line Color** as **Black** and click **Apply**.



9. Now we will draw the drop lines. In the left panel, select the scatter plot (Original). In the right panel, select the **Drop Lines** tab. Select the **Parallel to Z Axis** check box, change the drop line **Width** to **2** and set the **Drop to** **Surface**.




10. Click **OK** to close the dialog and delete the legend. Your final graph should look like this:




Create a surface with symbols and error bar

1. Follow steps 1 through 8 above and click **OK** to create a 3D surface graph with a scatter plot.
2. Add a new column in the worksheet "XYZRandomGauA". Select the column and right-click. In the **Fill Column with** context menu, click **Uniform Random Numbers**.
3. Double click on the newly created graph to open the **Plot Details** dialog. Expand the node to select the plot (Original) in the left panel. On the **Error Bar** tab, select the **Enable** check box, and select **Col(D)** from the **Error Data** dropdown menu.




4. Click **OK** to close the dialog and delete the legend. Your final graph should look like this:



6.12.9 Colormap from Second Matrix

6.12.9.1 Summary

Origin can represent four-dimensional data by color-mapping a surface plot using a second matrix.



Minimum Origin Version Required: Origin 2015 SR0

6.12.9.2 What you will learn


- Create a Color Fill Surface from a matrix.
- Color map a surface plot using a second matrix.
- Customize color map levels and palette.
- Control lighting on the graph (From Origin 9 SR0)

6.12.9.3 Steps


This tutorial is associated with the **Tutorial Data** project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

1. Open the **Tutorial Data** project and browse to folder *Surface with Colormap from Another Matrix* in **Project Explorer**.
2. Active the **MBook1D** matrix, You should see two image thumbnails above the matrix data, just under the title bar. (If you do not see image thumbnails, right-click on the matrix title bar and select **Show Image Thumbnails**.) Select image thumbnail 1."


- On the main menu, click **Plot**, point to **3D Surface**, then click **Color Fill Surface** to generate a surface plot.




- Double click on the plot to open the **Plot Details** dialog. In the left panel, select **(MBook1D)MSheet1**. In the right panel, select the **Fill** tab. Choose **Contour Fill from Matrix**, and select **Mat(2)** for front surface.




- Go to **Colormap/Contours** tab, click the **Level...** title to open the Set Levels dialog. In this dialog, click **Find Min/Max** button and set the **#Major Levels** and **#Minor Levels** as **10** and **9**. Click OK button to close the dialog.




6. Click the **Fill...** title to open the **Fill** dialog. select **Load Palette** and then click **Select Palette** button to select **Rainbow** palette. Click **OK** button to close this dialog.




7. Check the **Enable Contours** check box. And then click **Line...** to open the **Contour Lines** dialog. In this dialog, check the **Show on Major Levels Only** check box and set the **Line Properties** as below. Click **OK** button to close the dialog.




8. Go to the **Mesh** tab, uncheck the **Enable** box to disable the mesh lines.
9. Select **Layer1** in the left panel, go to **Lighting** tab in the right panel. Select **Directional** under **Mode**. Set **Horizontal** and **Vertical** as *124* and *40*, and change the color of **Diffuse** as *LT Gray* and **Specular** as *Gray*. Then set the **Shininess** as *37*.



- Go to the **Planes** tab, set the color as **Gray** and select **Front Corner** for the Cube drop-down menu.




- Go to **Axis** tab and do settings as below. Click **OK** button to close this dialog.




Background	Size/Speed	Display	Miscellaneous	Axis	Planes	Lighting
Length						
X	69.9	Azimuth	322.5			
Y	133	Inclination	39.5			
Z	48.9	Roll	356.3			
Link Axis Length to Scale (isometric)				Off		
Orientation of Labels & Titles & Ticks						
<input checked="" type="radio"/> All in Axes Plane						
<input type="radio"/> All In Plane of Screen						
<input type="radio"/> Titles in Axes Plane						
<input type="radio"/> Ticks in Axes Plane						
<input type="radio"/> Tick Labels in Axes Plane						
<input type="radio"/> Ticks & Tick Labels in Axes Plane						
Go to each axis node in Axes dialog for separate control of Rotate settings.						

12. Keep the graph window active. Select **Graph: New Color Scale** to add a new color scale in the graph window.
13. Double-click anywhere on the color scale to open the **Color Scale Control** dialog box. Select **Layout** in the left panel, change **Color bar thickness** to **150** and check the **Reverse Order** check box.




14. Select **Labels** in the left panel, set the **Font Size** to 14 in the right panel as below:



Click **OK** to close the **Color Scale Control** dialog box.

15. Double-click the X, Y and Z axis title and enter "X distance", "Y distance" and "Height". Add a text object "Pressure(psi)" above the color scale.


16. Your final graph should look like this:



6.12.10 Color Map Surface Graph

6.12.10.1 Summary

This tutorial will show you how to create a 3D color map surface.



6.12.10.2 What will you learn


This tutorial will show you how to

- Create a 3D color map surface graph
- Customize the 3D surface graph


6.12.10.3 Steps

This tutorial is associated with [this Graph Galley page](#).


1. Download the project by clicking the Download Project link at the top of this page.
2. Open the project in the zipped file. Highlight **HFT data** matrix and select **Plot: 3D Surface: Colormap Surface with Projection** to create a 3D graph.




3. Choose **Format: Plot Properties** to go to the plot level of the **Plot Details** dialog.
4. Select the surface plot, go to the Mesh tab, uncheck the **Enable** box to turn off the mesh lines. Go to **Colormap/Contours** tab, click Line title to open the **Contour Lines** dialog. In this dialog, uncheck **Show on Major Levels Only** and select **Hide All** to hide all contour lines.



5. Select the projection plot in the left panel, go to **Surface** tab, Enter 0 as the following image shows to put the projection to the bottom of the graph.




6. Go to the **Mesh** tab, uncheck the **Enable** box to disable the mesh lines. Go to **Colormap/Contours** tab, hide all contour lines like the step4 does.
7. Click Layer 1 in the left panel, and then in the right panel select the **Lighting** tab. Change the setting as following to enable lighting effect:



Then Click **OK** to close the dialog.


8. Finally, change axis titles and add a graph title as the following graph.



6.12.11 Parametric Surface with Colormap from Data

6.12.11.1 Summary

This tutorial demonstrates how to create a 3D sphere using the data from three matrices. It also shows how the surface is filled to display the surface temperature contour using the data from a different matrix.



Minimum Origin Version Required: Origin 2015 SR0

6.12.11.2 What you will learn


This tutorial will show you how to:


- Create a parametric surface from matrix data
- Set contour fill from another matrix
- Customize the 3D parametric surface plot

6.12.11.3 Steps


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: 3D Function Plots**)


1. Open **Tutorial Data.opj** and browse to the **Parametric Surface with Colormap from Data** folder in **Project Explorer (PE)**.
2. Activate the matrix *FUNCA:1/4*, and highlight the data. Click the  button on the **3D and Contour Graph** toolbar to create a colormap surface as shown below. You can also create this colormap surface by selecting **Plot: 3D Surface: Color Map Surface** in the main menu.




3. Double click on the plot to bring up the **Plot Details** dialog. In the **Surface** tab check the **Parametric Surface** box and set **X Matrix**, **Y Matrix** as **Mat(2)**, **Mat(3)** respectively.




Click **OK** to close the dialog.


4. In order to display the complete colormap surface in the axes area use the rescale  button in the **Graph** toolbar. The colormap surface should appear as shown below:




5. Double click on the plot to open **Plot Details** dialog. This dialog box is used to customize the surface. In the **Fill** tab Front Surface section deselect the box before **Self** and set **Contour fill from matrix** as **Mat(4)**. Click **Apply**.




6. Activate the **Colormap / Contours** tab. Click the **Level** heading to open the **Set Levels** dialog. Click **Find Min/Max** and set **Major Levels**, **Minor Levels** as **16**, **8** respectively. Click **OK**.




7. Click **Fill** to open the **Fill** dialog. This dialog is used to customize the color scale. The **Load Palette** option allows the user to select from a list of possible palettes. Set **Load Palette** as **Temperature**. Click **OK**.




8. Click on the **Mesh** tab. Set **Line Width** as **0.05** by clicking on the font box and typing the value instead of using the drop down menu. Set **Line Color** in the Front section as **LT Gray**. Click **Apply**.




9. In the **Numeric Formats** tab choose the **Decimal Places** radio button and set its value as **0**.




Click **OK** to apply the settings and close the **Plot Details** dialog. The graph should appear as shown below:




10. The next step is to modify the axes. Double click on the Z axis to open the **Axis** Dialog. Go to the **Scale** tab, select **Z** icon. Set the value of **From** and **To** as **-400** and **400** respectively.




- Go to the **Title** tab, hold **Ctrl** key and click to select **X**, **Y** and **Z** together. Deselect the **Show** check box to hide the axis title for all axes and click **OK** to close the dialog.




- Double click on the XY Plane to open **Plot Details - Layer Properties**. In order to hide the axes, in the **Display** tab, deselect the **X Axes**, **Y Axes**, **Z Axes** boxes under the Show Elements section.




- To hide the YZ and ZX planes, click on the **Planes** tab, and deselect the boxes before **YZ**, **ZX**. Set the **Color** of the remaining **XY** plane as **LT Gray**. Click **OK** to close the dialog.



14. The next step is to customize the color scale. Double click on it to open the **Color Scale Control** dialog, go to the **Labels** node and set the Font as **Verdana**.




15. Go to the **Line and Ticks** node and hide the border and ticks:




16. Click **OK** to apply the setting and close the dialog. Select and drag to move the color scale object to the desired location.


17. Right click on the white area of the graph layer to bring up a context menu and choose **Add/Modify Layer Title**. Click else where to deselect the text box, then right-click on it and select **Properties...** from the shortcut menu to open the **Object Properties** dialog. Set the font as **Verdana** and type **Surface Temperature (l+(o)C)** in the content table. Click **OK**.



18. Click on the graph layer within the 3D frame (not the data plot), and click the **Rotate** button as shown in the image below, to activate the rotation mode. Other ways to rotate the 3D plot include using the red rotate button in the **Tools** toolbar, the various buttons in the **3D Rotation** toolbar or by selecting in the plot, pressing the **R** key and using the cursor.




Rotate the plot to get a better view. The graph should resemble the image shown below:



6.12.12 Stacked 3D Surface Plots

6.12.12.1 Summary

This tutorial shows how to create stacked 3D colormap surfaces from different matrix objects. The surfaces in the plot display the topology before and after volcanic eruption:



Minimum Origin Version Required: Origin 2015 SR0

6.12.12.2 What you will learn

This tutorial will show you how to:

- Create stacked 3D colormap surfaces.
- Customize axes display and layer properties.
- Resize and rotate a 3D plot.


6.12.12.3 Steps

Create Multiple Colormap Surfaces

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: 3D Surface**)

1. Open **Tutorial Data.opj** and browse to the **Stacked 3D Surface Plots** folder in **Project Explorer** (PE).
2. Activate the matrix book **Mbook1** which contains two matrix objects, then click **Plot: 3D Surface: Multiple Colormap Surfaces** to create two 3D surfaces from these two matrix objects as shown below:




3. Double click on the plot to open the **Plot Details** dialog. If the left panel is not open the use the arrow button on the bottom left of the dialogue. There are two surfaces under the **Layer1** node on the left panel. To shift the "After eruption" surface in Z axis, activate the second plot under **Layer1** on the left panel, and in the right panel, select the **Surface** tab. Check the **Shift in Z by percent of scale range** box, and enter **70** in the text box.


Tutorials for Origin




4. In the **Fill** tab Front Surface section, deselect the **Self** box to fill contour by the same matrix object (Mat "Before") as the other surface used.



5. Select the **Colormap / Contours** tab. Click **Level..** to bring up the **Set Levels** dialog. Set the parameters as shown in the following graph and click **OK**.



Then uncheck the **Enable Contours** checkbox to hide the contour lines. Click **OK**.




6. In the **Mesh** tab deselect the **Enable** box to disable the mesh line.
7. Repeat steps 5 to 6 for the first plot under the **Layer1** node.
8. In this project the two surfaces use the same matrix as contour fill, so they can share one color scale.

To set the numeric format of the color scale, activate the first plot on the left panel of the **Plot Details** dialog. Select the **Numeric Formats** tab on the right panel. Select **Scientific: 10^3** from the drop down list next to the **Format**, and set **Significant Digits** as **2**. Click **OK**.



To customize the color scale, double click on the color scale to open the **Color Scale Control** dialog. Check the **Reverse Order** box and set **Color bar thickness** as **100**. Click **OK**.




Customize Axes Display

The next step is to change the the axes scale and tick labels' format in the **Axes** dialog. To open this dialog, select **Format: Axes: X Axis...**


1. Change the settings on the **Scale** tab:
 - Set scale from **558000** to **566500** for the X Axis (click **X** icon), from **5108200** to **5121800** for the Y Axis (click **Y** icon), and from **0** to **10000** for the Z axis (click **Z** icon).

- For the X axis, set **Type** of **Major Ticks** as **By Counts** and set **Count** as **5**. For the Y and Z axis, set **Type** of **Major Ticks** as **By Increment** and set **Value** as **2000**. To hide all the minor ticks, set **Count** of **Minor Ticks** as **0** for all axes.
2. Customize the **Tick labels**:
- First, ensure that the **Use Only One Axis for For Each Direction** is enabled in the top of the **Axis** dialog.
 - Go to the **Tick Labels** tab, hold **Ctrl** key to select **X**, **Y** and **Z** icons together so they will be customized together. Select **Custom** for **Display** and select **P*3** from the drop down list of **Custom Format** to show the tick label as base-10 scientific notation with 3 significant digits. Click **OK**. For more information about the options in this drop down list, please refer to [Custom Display Format](#).




Customize Layer Properties


1. Double click on the blank space outside the plots or click **Format: Layer Properties...** from the menu to open the **Plot Details - Layer Properties** dialog.
2. Activate the **Miscellaneous** tab on the right panel. Check the box before **Enable** in the **Clipping** section, which will clip the image outside the axes area according to the settings in the **Clipping** section.





- In the **Planes** tab set **Color** as **LT Gray** for all planes. Select **Front Corner** from the drop-down list in the **Cube** section to show the cube's border.



- Select the **Lighting** tab. In the **Mode** section, choose **Directional** to enable lighting mode. Set **Light Color** as shown in the following graph. Click **OK**.



Resize and rotate the plot

1. Click on the cube (not the data plot) to activate the 3D toolbar. Click the Resize button , a 3D Cartesian coordinate will show up. Place the cursor on Y axis, which will then be highlighted, at this moment drag-and drop the Y axis to stretch the plot in Y axis direction. Do the same to X direction and Z direction.
2. Click the rotate button  to activate rotation mode. A sphere will be displayed at the center of the plot. Rotate the plot to get a better view.


The 3D toolbar allows you to resize and rotate the plot freely. However, you can also achieve the same view as Graph1 in this sample project by setting the value in the **Axis** tab of the **Layer Properties** dialog as shown in the following graph.

Background	Size/Speed	Display	Miscellaneous	Axis	Planes	Lighting
Length						
X	70.2	Azimuth	32.4			
Y	125	Inclination	39.5			
Z	98.5	Roll	359.6			
Link Axis Length to Scale (isometric)				Off		
Orientation of Labels & Titles & Ticks						
<input checked="" type="radio"/> All in Axes Plane <input type="radio"/> All In Plane of Screen <input type="radio"/> Titles in Axes Plane <input type="radio"/> Ticks in Axes Plane <input type="radio"/> Tick Labels in Axes Plane <input type="radio"/> Ticks & Tick Labels in Axes Plane						
Go to each axis node in Axes dialog for separate control of Rotate settings.						

6.12.13 Multiple Surfaces in Same Layer

6.12.13.1 Summary

The four stacked surfaces shown below were created from the same matrix. The first layer from the top is a wire frame, the second layer is a flattened contour line plot, the third layer is a color filled surface with lighting effect, and the bottom layer is a flattened color filled contour plot.



Minimum Origin Version Required: Origin 2015 SR0

6.12.13.2 What You Will Learn

This tutorial will show you how to:

- Add multiple surface plots to a single graph layer
- Explore ways in which you can customize surface plots


6.12.13.3 Steps

Create a Graph with Multiple Surfaces


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.

Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: 3D Surface**)

1. Open **Tutorial Data.opj** and browse to the **Multiple Surfaces in Same Layer** folder in **Project Explorer (PE)**.
2. Select the **MBook8** worksheet and highlight all that data. From the Main Menu select **Plot: 3D Surface: Colormap Surface**. The graph window should appear as shown below:




- With the new graph window active choose **Graph: Layer Contents....** In the **Layer Contents - Layer 1** dialog box, select the **MBook8** matrix in the left panel and click the Add plot button (the right-pointing arrow in the center of the dialog) three times. Click **OK**. This will add the same MBook8 data to the graph layer four times. Note that at this point there only a single plot, the following steps will change that.




- Double-click on the plot to open the **Plot Details - Plot Properties** dialog box. Select the first plot in the left-hand panel and in the **Surface** tab check the **Flat** box, check **Shift in Z by**


percent... and enter **0** in the accompanying text box. Select the second plot, leave **Flat** unchecked, check **Shift in Z...** and enter **23**. Select the third plot, check **Flat**, check **Shift in Z...** enter **65**. Select the fourth plot, leave **Flat** unchecked, check **Shift in Z...** and enter **82**. Click **OK**.




5. Double-click on the Z axis, and in the **Axes Dialog** box, go to the **Scale** tab, make sure Z axis icon is selected and set **From** to **0** , and **To** to **900**.




6. Go to the **Tick Labels** tab, hold **Ctrl** key to select **X** and **Y** icons together. In the **Display** tab, for **Divide by Factor**, enter **10000**.




7. Go to the **Title** tab, select the **X** icon and enter **X Coordinate/ $10^{+}(5)$ meter** as the text for X title. Select the **Y** icon and enter **Y Coordinate/ $10^{+}(5)$ meter** as title text.



8. Go to the **Grids** tab, hold **Ctrl** key to select **X**, **Y** and **Z** icons together. Under **Major Grid Lines** clear the **Show** check box to hide the grid lines for all axes.




9. Click the **OK** button. The graph should now display four separate surfaces as shown below:




Customize the flattened color filled contour plot

1. Double-click on "Surface 1" to open the Plot Details dialog. Select the **Colormap/Contours** tab and click on the **Fill...** header to open the **Fill** dialog. In the **Fill** dialog, select **Load Palette** then click **Select Palette** and select the **Reef** palette. Click **OK** to close the **Fill** dialog.



2. In the **Colormap/Contours** tab, clear the **Enable Contours** check box.




3. Select the **Mesh** tab and clear the **Enable** check box.




4. Click **Apply** to update your graph.

Customize the color filled surface

1. Select the second data set (do not clear the accompanying check box), click the **Fill** tab, select **Fill piece by piece** and choose **Dark Yellow** from the drop-down.



2. Select the **Colormap/Contours** tab and clear the **Enable Contours** check box.




3. Select the **Mesh** tab and clear the **Enable** check box.




4. Click **Apply** to update your graph.

Customize a flattened contour line plot


1. Select the third data set, click the **Fill** tab and clear the **Enable** check box.



2. Select the **Colormap/Contours** tab click on the **Line...** header to open the **Contour Lines** dialog. In this dialog, select the **Link Line to Colormap Color** checkbox. Click **OK** to close the **Contour Lines** dialog.




3. Select the **Mesh** tab and set the **Line Width** to **1**. In the **Major Minor Lines** section, choose the settings shown below and in the **Line Color** section select the **Use Colormap** check box




4. Click **Apply** to update your graph.

Customize a wireframe surface


1. Select the fourth data set, click the **Fill** tab and clear the **Enable** check box.




2. Select the **Colormap/Contours** tab and clear the **Enable Contours** check box.




3. Select the **Mesh** tab and set the **Line Width** to **1**. In the **Major Minor Lines** section, choose the settings shown below and in the **Line Color** section set **Major Line Color** to **Black**.




4. Select **Layer1** in the left panel. In the **Lighting** tab choose **Directional** for **Mode** and set the **Direction** group controls as shown below:



5. Select the **Planes** tab. Specify the colors of the **YZ** and **ZX** planes as shown below (a custom color approximating "eggshell" for **YZ** and LT Gray for **ZX** works well).



6. Click **OK** to update your graph.
7. Rotate the 3D graph if you want to. Your graph should resemble the image shown below.



Minimum Origin Version Required: 2015 SR0

6.12.14.2 What you will learn

This tutorial will show you how to:

- Generate a 3D scatter plot with Z colormap
- Set the symbol size proportional to data in a specified column
- Add and customize the scatter projections on axis planes


6.12.14.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: 3D Symbol Bar and Wall**)


1. Open **Tutorial Data.opj** and browse to the **3D Scatter with Colormap** folder in **Project Explorer** (PE).

2. Activate the workbook **A3DScatter**, and highlight col(C). Select **Plot: 3D Symbol/Bar/Vector: 3D Scatter** to generate a scatter plot.
3. A **Reminder Message** window like the one shown below will pop up, stating that the graph might not be correctly displayed if the OpenGL version is less than 2.1. The OpenGL version of your video card is listed on the **Reminder Message** window. Click **OK** to close the window.




Note: Speed Mode might be turned on if the OpenGL version is too low.

4. Double click on the plot to open the **Plot Detail** dialog. If the left panel is not expanded use the  button on the bottom left of the dialog to expand it. Expand the **Layer1** option and select the **Original** level, this contains the original data. This dialog box is where the 3D scatter is customized.
5. In the **Symbol** tab, set **Shape** as **Ball**. In order to use the ball sizes to show the differences of Engine Displacement, select **Size** as **Col("Engine Displacement")**, and set **Scaling Factor** as **0.005**. Type manually into the edit box instead of using the drop down menu. Set **Color** as **Color Mapping: Col("Power")** to introduce Z colormap, and set **Transparency** to **25%**.





6. Select the **Colormap** tab. Click the **Level...** title to open the **Set Levels** dialog. Set **From** as **30**. Select **Increment**, and set it as **15**. Set **# Minor Levels** as **9**. Click **OK**.




7. Click the **Fill...** title to open the **Fill** dialog. Select **Limited Mixing**. Click the default color of **From** and then click the square box under **Custom** section in the color setting panel to open the **Colors** dialog. In the **Colors** dialog, set the **Red**, **Green** and **Blue** option in the bottom

right as 74, 74, 255. Do the same thing for **To** color and set the **Red**, **Green** and **Blue** option as 255, 100, 255. Click **OK**.






8. Click on the fill color of <30 level to open the **Fill** dialog. Set **Fill Color** as **None**. Click **OK**. Repeat the this step to set fill color of >168 level as **None**. This will ensure that there is no color for levels above and below the specified range.




9. Activate the **Numeric Formats** tab. Select **Decimal Places** and set it as **0**.


- The next step is to add the data projections. In the left panel of the **Plot Details** dialog, select the option above **Original**, and select the **Fully Independent** radio button. This will ensure that when the projections have been enabled, each can be customized separately. Check the boxes for **XY Projection**, **ZX Projection** and **YZ Projection** to enable the scatter projections on all three planes.
- To customize the colors of the projections, in the **XY Projection** level **Symbol** tab, set its color as **Olive**(the 12th common color). Set the symbol color of **ZX Projection** and **YZ Projection** as **Red** (the second common color) and **Orange** (the 15th common color) respectively. Click **OK**.




- In order to remove the grid lines, double click on the X axis to open the **Axes** dialog. Select the **Grids** tab on the right panel, hold the CTRL key and select Y and Z axes to customize the settings together, then deselect the **Show** box under **Major Grid Lines** to hide the major grid lines of all axes.







13. The next step is to change the scale for the axes. On the **Scale** tab for each axis set the following; for X Axis, change the **From**, **To** value and the increment **Value** of major ticks to **5**, **30**, **5** respectively, and then check the **Reverse** check box; for Y Axis, to **5**, **40** and **10**, and then check the **Reverse** check box; And for Z Axis, to **20**, **180** and **20**. Click **OK**.
14. To designate the color for the background of the entire window, open the **Plot Details** dialog again. In the left panel, select the **Graph** level above the **Layer1** option. Select the **Display** tab. Set **Color** as **LT Gray**. Click **OK**.




15. Delete the legend object created by default, we are going to add a color scale legend instead.

16. In order to add a color scale legend, click the **Add Color Scale**  button in the **Add Object to Graph** toolbar. Double click on the color scale to bring up the **Color Scale Control** dialog. Set the color scale format according to the screenshots below:






17. Right click on the page layer to bring out the context menu. Select **Add/Modify Layer Title** and type *Symbol Size proportional to Engine Displacement* in the text box that appears as the layer title.
18. The graph should appear as shown below. Rotate to explore all sides:



6.12.15 3D Scatter with Droplines

This graph consists of a flat surface and an XYZ scatter with labels. The US Map is a matrix with 1's and 0's, displayed as a flat surface. The population data is an XYZ scatter plot with droplines.



Minimum Origin Version Required: Origin 9.0 SR0

6.12.15.1 What you will learn


This tutorial will show you how to:

- Plot a flat surface.
- Add a 3D scatter to the existing graph window.
- Turn on and customize the labels.


6.12.15.2 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open **Tutorial Data.opj** and browse to the **3D Scatter with Droplines** folder in **Project Explorer** (PE).
2. Activate **MBook1B**, select **Plot:3D Surface:Colormap Surface** from the main menu. A graph window will be generated.




3. Double-click on the plot to open the **Plot Details** dialog. In the **Surface** tab, check the **Flat** check box.




4. Go to the **Colormap/Contours** tab, click the **Fill...** header to open the **Fill** dialog. In this dialog, select **Limited Mixing** and set the **From** and **To** colors as shown below.





5. Click the **OK** button to close the **Fill** dialog.
6. Click the **Level...** header to bring up the **Set Levels** dialog. Set the levels as given below.




7. Click the **OK** button to close the **Set Levels** dialog.
8. Go to the **Mesh** tab, uncheck the **Enable** check box.




- Click the **OK** button to close the dialog. On the graph window, right-click on the layer icon to select **Layer Contents...** from the context menu to open the **Layer Contents** dialog. In this dialog, select **Worksheet in Folder** from the top-left drop-down list, select col(D) in the left panel and select **3D Scatter/Trajectory/Vector** as plot type, check the **Rescale on Apply** check box, and then click the arrow to add col(D) to the right panel as a 3D scatter plot.




- Click **OK** button to close the **Layer Contents** dialog. The population data will be added to the graph as shown below.




- Double-click on the 3D scatter plot to open the **Plot Details** dialog. Go to the **Symbol** tab, set the **Size** as 18 and set the color as colormap defined by col(Population).




- Go to the **Colormap** tab, click on the **Level...** header to open the Level dialog. Set the level as given below.




- Click **OK** to close the **Set Levels** dialog. Click on the **Fill...** header to open the **Fill** dialog. In the **Fill** dialog, select **Load Palette** and then click the **Select Palette** button to select the **Watermelon** palette. Click **OK** to close the **Fill** dialog.




- Go to the **Label** tab, apply settings given below.




15. Select **Layer1** in the left panel and then go to the **Size/Speed** tab in the right panel. Uncheck the check boxes under **Speed Mode, Skip Points if needed**.



16. Select Graph level in the left panel and then go to the **Display** tab, set the **Color** as *LT Gray*.




17. Click **OK** to close the **Plot Details** dialog. Finally, you will get the graph given below.



6.12.16 Surface With Transparent Plane

This graph shows the topography of Lake Ontario. It is a combination of a 3D surface and a

transparent plane.



Minimum Origin Version Required: 2015 SR0

6.12.16.1 What you will learn


This tutorial will show you how to:

- Plot a 3D color map surface graph
- Plot a transparent plane onto the existing 3D surface plot
- Set the lighting for a 3D surface plot


6.12.16.2 Steps


This tutorial is associated with the **Tutorial Data** project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the **Tutorial Data** project and browse to folder *Surface With Transparent Plane* in **Project Explorer**.
2. Activate **MBook3L**, and highlight all data. Select **Plot:3D Surface:Colormap Surface** from the main menu. A graph window will be generated as shown below:




- Right click on the layer icon **1** at the top right of the graph and select **Layer Contents...**, add **MBook2** as a 3D surface into this layer by shifting it from the left panel to the right panel using the arrow button in the center of the dialog as shown below. Then click **OK** to close dialog.




- Double-click on the graph to open the **Plot Details** dialog. If the left panel is not expanded use the  button. This dialog is where the 3D plot will be customized. Select *Layer1* in the left panel, and in the **Axis** tab in the right panel apply the settings shown below:




5. Select the first plot in the left panel under the **Layer1** option and in the **Colormap/Coutours** tab, click on the **Level...** header to open the **Set Levels** dialog. In this dialog, apply the settings below:




- Use the **OK** button to close the **Set Levels** dialog. Click on the **Fill...** header to open the **Fill** dialog. In the **Fill** dialog, select **Load Palette** and click the **Select Palette** button to select the **Watermelon** palette. Click **OK** to close the **Fill** dialog.




- To remove contours, in the **Colormap/Contours** tab deselect the **Enable Contours** check box as shown below:



8. To remove the mesh, in the **Mesh** tab, deselect the **Enable** check box as shown below:




9. In the **Side Walls** tab, check the **Enable** box and set the X and Y side walls as shown below:




10. In the **Numeric Formats** tab, set **Decimal Places** to **0**.


11. Select the second plot in the left panel and in the **Surface** tab, set the **Transparency** as **48**:




- Open the **Fill** tab of the **Plot Details** dialog, select **Fill piece by piece** and set the color as **Blue**. Click **Apply** to review changes.




- The next step is to set the lighting effect. Select **Layer1** in the left panel and in the **Lighting** tab, apply the settings shown below:




14. In the **Planes** tab, deselect the **XY**, **YZ** and **ZX** plane boxes. Click the **OK** button to close the Plot Details dialog.




15. The next step is to add a title. Right-click on the blank area of the graph window and select **Add/Modify Layer Title** from the menu that appears, enter *Lake Ontario* as the layer title. Right-click on the title and select **Properties...** from the menu to open the **Object Properties** dialog. In the **Text** tab, set font size to 31, then go to **Frame** tab and set **Frame** to **Shadow**.




16. To customize the color scale, double-click on the color scale to open the **Color Scale Control** dialog. Select **Line and Ticks** on the left panel, on the right panel, deselect **Show Line and Ticks on the Right** and **Show Border** to hide the line, ticks and border.




17. Select **Layout** on the left panel, modify **Color Bar Thickness** as *150* to change the width of the color scale, set **Label Offset from Bar Edge** as *0* to move the label closer to the color scale.



18. Select **Title** on the left panel, on the right select **Show** to display the title, and add (*m*) at the end of the **Title** text box to display the title as *Elevation(m)* for the color scale. Change **Size** under the **Font** branch as 18. Click **OK** to apply the settings and close the dialog.




19. You can double click the color scale title to activate the in-place edit mode, place the cursor after $\%(?R,@LA)$ and press ENTER on the keyboard to start a new line for (m) . The complete graph should appear as shown below:



6.12.17 3D Bar on Flatten Surface

This graph is a combination of a flattened 3D surface of US Map with state divisions and 3D bars representing the city populations, the bars locate the longitude and latitude of the cities.



Minimum Origin Version Required: Origin 9.0 SR0

6.12.17.1 What you will learn


This tutorial will show you how to:

- Plot a flattened 3D surface.
- Add a 3D bar graph to an existing 3D surface graph.


6.12.17.2 Steps

This tutorial is associated with the **Tutorial Data** project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the **Tutorial Data** project and browse to folder *3D Bar on Flat Surface* in **Project Explorer**.
2. Activate **MBook1E**, select **Plot:3D Surface:Colormap Surface** from the main menu. A graph window will be generated.



- Double-click on the graph to open the **Plot Details** dialog. In the Surface tab, check **Flat** and **Shift in Z**, set the **Z offset** to 0 and the **Transparency** to 50.




- Go to the **Colormap/Contours** tab, click on the **Level...** header to open the **Set Levels** dialog. In this dialog, set the **Major Levels** to 8.




- Click the **OK** button to close this dialog. Click on the **Fill...** header to open the **Fill** dialog. In the **Fill** dialog, select **Load Palette**, click **Select Palette** button to select *Thermometer* palette and


uncheck the **Link to Palette** check box.




- Click **OK** button to close the **Fill** dialog. Click the fill cell of last level and set its color as White.




- Uncheck the **Enable Contours** in the **Colormap/Contours** tab.



8. Go to **Mesh** tab, uncheck the **Enable** check box.






9. Select **Layer1** in the left panel, go to the **Planes** tab in the right panel. Uncheck the **XY**, **YZ**, and **ZX** check boxes.



10. Click **OK** to close the **Plot Details** dialog. Right-click on the layer icon and choose **Plot Setup** from the menu. In the **Plot Setup** dialog, choose **Worksheets in Folder** for Available Data, **3D-Bars** as Plot Type and **USMetropolitan** as the data source sheet. Set Longitude, Latitude, and

Population as X, Y, Z respectively. Click **Add** to add the 3D bar graph to the current layer.




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.


Please refer to [Plotting using Plot Setup](#) for more information.

- Click **OK** to close the **Plot Setup** dialog. Select **Graph: Rescale to Show All** to rescale the graph.

12. Double-click on the 3D bar graph to open the **Plot Details** dialog. In the **Pattern** tab, set the color of **Border** and **Fill** as red, and set **Gradient Fill** as shown below.




13. Click **OK** to close the **Plot Details** dialog. On the graph window, right-click on the layer icon and select **Layer Contents...** from the context menu to open the **Layer Content** dialog. In this dialog, select **Worksheets in Folder** for the top-left drop-down list, add col(C) and Col(D) in Sheet **Label** as a 3D bar graph and a 3D scatter respectively to the current layer.




14. Click **OK** to close the **Layer Content** dialog. Double-click on the 3D bar graph to open the **Plot Details** dialog. Select the third plot in the left panel, and go to the **Pattern** tab, apply the settings


given below.




15. Go to the **Outline** tab, set the **Width(in%)** to 15 as below.



16. Select the forth plot in the left panel, go to the **Label** tab and apply the settings below.




17. Finally, you will get the graph shown below.



6.12.18 3D Surface with Point Label

6.12.18.1 Summary

This tutorial will demonstrate how to add a 3D Scatter to a 3D Surface and include labels as shown below:



Minimum Origin Version Required: Origin 2015 SR0

6.12.18.2 What you will learn

This tutorial will teach you how to:

- Create the 3D Surface with side walls
- Add a 3D scatter to the 3D Surface and include labels
- Change the label position in 3D graphs
- Add a line to connect the symbol and the label


6.12.18.3 Steps

Create the 3D Surface with side walls:


This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: 3D Surface**)


1. Open **Tutorial Data.opj** and browse to the **3D Surface with Point Label** folder in **Project Explorer (PE)**.
2. Activate **MBook4**, and highlight everything. Select **Plot:3D Surface: Color Map Surface** from the main menu. A 3D Colormap graph will be generated as shown below:




3. Select **Format: Axes: Z Axis...** in the menu to open the **Axes** dialog. (Or double-click one of the axes on the graph). Set Z axis scale **From: -500** and **To: 8000**. Click **OK**.




4. Select **Format: Plot Properties** in the menu to open the **Plot Details** dialog. (Or double click anywhere on the graph). If the left panel is not expanded use the  button on the bottom left of the dialog to expand it and select the first option under **Layer1**. In order to create and customize side walls, in the **Side Walls** tab, check the **Enable** box. Change the color of **X** and **Y** side walls to **Gray** and **LT Gray**.




5. To adjust the color scale, in the **Colormap/Contour** tab, click on the **Fill** column header to open the dialog. Select the **Limited Mixing** option, and set **From: Blue** and **To: Green** as shown below. Click the **OK** button to close the **Fill** dialog.




6. In the **Mesh** tab, select color of **Major Minor Lines** as **Black** and select apply **Apply**.



7. The next step is to add and customize the lighting effect. In the same **Plot Details** dialog, expand the left panel and select **Layer 1**. In the **Lighting** tab, choose the **Directional** Mode, enter **279** and **-3** in the **Horizontal** and **Vertical** boxes respectively. Set the **Ambient** color to **LT Yellow**.





8. To adjust the planes, in the **Planes** tab deselect the **YZ** and **ZX** boxes to hide the two planes in the graph. Click the **OK** button.





Add the 3D scatter in the 3D Surface with labels:


1. In order to add symbols in the desired position on the 3D graph, select **Graph: Layer Contents** from the main menu to open the **Layer Contents** dialog (Or double click on the layer icon **1** on the top left of the graph). In the dialog that appears, select **Worksheet in Folder** from the drop-down on the top left.
2. Click on the **Plot Type** button shown below to specify **3D Scatter/ Trajectory/ Vector** as the plot type:




3. To shift components from the left panel to the right panel, holding down the Ctrl key, select two **Height** columns in the left panel and click on the **Add plot** button . This will add the two columns to Layer1. Click the **OK** button.




Use the  **Rotate Tool** button on the **Tools** toolbar or hold down the **R** key and use the mouse to rotate the graph. You can find two red symbols are added to the 3D surface and the graph will appear as shown below:



4. To add labels to the two symbols, double click on either one to open the **Plot Details** dialog. Make sure the left panel of the **Plot Details** dialog box is expanded and displaying **Original** under the *Position1* plot-level. In the **Label** tab check the **Enable** box. In the **Label From** drop-down list, select **col("Label")** as the label source. Specify the **Offset** for the label as shown in the image below:



- In the left panel, click on **Original** under the *Position2* plot-level. In the **Label** tab repeat the above step making the selections given below. Click on the **OK** Button. Labels should now appear on the graph.



- To add leader lines to connect the symbols and the labels, when the graph window is active select **Window:Script Window** from the main menu and run the following script:

```

layer.plot=2;


set %C -ql 5;

layer.plot=3;

set %C -ql 5;

```


7. Highlight the script and press Enter. Leader lines connecting the labels and the symbols will appear and the graph should resemble the image shown below:



6.12.19 Transparent Parametric Surfaces combined with Scatter Plot

6.12.19.1 Summary

This tutorial will show you how to create 3D Scatter plots and combine them with 3D Parametric Surfaces.



Minimum Origin Version Required: Origin 2016 SR0

6.12.19.2 What you will learn

- How to create the 3D Scatter plot with symbol color indexing.
- How to plot 3D confidence ellipsoid by app


6.12.19.3 Steps



Create the 3D Scatter plot with color index

You can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: 3D Symbol Bar and Wall**)

1. Import the file <Origin EXE Path>\Statistics\Fisher's Iris Data.dat into a new workbook.
2. Select **Plot > Templates: System Template Library** from the main menu. In the **System Templates** dialog, expand the **Graph Template -> 3D Symbols & Bars & Vectors** node, then select **gl3d**. Click the **Plot Setup...** button at the bottom left corner of the dialog.
3. In the **Plot Setup** dialog, set column C, D, and A as the X, Y, and Z columns, respectively. Click the **Show Plot List** button (double downward-pointing arrows in the lower right corner of Plot Setup) to expand the dialog (if it is not already expanded) and select the **Add** button, then click


OK.




In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.


4. Select **Format: Plot Properties** in the menu to open the **Plot Details** dialog. In the **Symbol** tab, set **Color as Index: Col(Species)**.




- Go to **Color List** tab, check the **Use custom increment list** check box, and custom the color list as the following image. Click **OK**.



- Right-click on the graph legend and select **Legend: Reconstruct Legend** in the context menu.
- Right-click on the graph legend and select **Properties...** to open the dialog. Set the font size to **22**, and custom the text as following image:




The 3D Scatter graph will be generated as shown below:



8. To ensure that the legend is not overwritten during the next steps, select **Format: Page Properties** in the menu to open the **Plot Details** dialog. Go to **Legends/ Titles** tab and choose

None from the **Legend Update Mode** drop-down list.




Add transparent parametric surfaces on the active graph


1. Download **3D Confidence Ellipsoid** app in this file exchange page: [3D Confidence Ellipsoid](#)
2. Drag- and-drop the app into Origin program to install it, then the **3D Confidential Ellipsoid** icon will be listed in the Apps Gallery



3. Active the graph and click this **3D Confidential Ellipsoid** button in the Apps Gallery. This will open the **Plot 3D Confidence Ellipsoid** dialog. Accept the default settings and click **OK**. Three ellipsoid are added to the graph, each envelops the group of data with the same color.



The final graph should appear as shown below:



6.12.20 Convert Data from Spherical Coordinate to XYZ and Make a 3D Plot

6.12.20.1 Summary

In this tutorial, we will look at what is involved in creating the 3D graph with spherical coordinate data, as well as using X-Function *sph2cart* to convert data in a workbook or matrix from spherical coordinate to Cartesian coordinates.

It is important to go over the [Converting Algorithm for sph2cart](#), and notice that Origin use ϕ as the **elevation** and θ as the **azimuth** in the transform formula.

$$\begin{aligned}x &= r * \cos(\phi) * \cos(\theta); \\y &= r * \cos(\phi) * \sin(\theta); \\z &= r * \sin(\phi); \end{aligned}$$

6.12.20.2 What will you learn

- Convert data in a worksheet (virtual matrix) from spherical coordinate to Cartesian coordinates and make a 3D surface plot.
- Convert data in a matrix object from spherical coordinate to Cartesian coordinates and make a 3D surface plot.
- Convert data in three matrix objects from spherical coordinate to Cartesian coordinate and make a discrete 3D surface plot.
- Convert data in a worksheet(XYZ) from spherical coordinate to Cartesian coordinate(XYZ) and make a 3D space curve.

6.12.20.3 Steps

3D Surface plot with colormap for data in virtual matrix

Origin can create surface plot with data in virtual matrix (spherical coordinate) and add colormap for it. The following steps introduce the plot of a ellipsoid with colormap surface.

1. Select **File: Open Sample Projects: Tutorial Data**, and browse to the folder: *Spherical Coordinates*.
2. Open the virtual matrix data *spheriPlot* in tutorial data, the structure of the virtual matrix is shown in graph below:


ellipsoid						
	A(X)	B(Y)	C1(Y)	C2(Y)	C3(Y)	C4(Y)
Long Name						
Units				azimuth		
Comments						
F(x)=						
1		0	4	8	12	16
2	-90	0.70711	0.70711	0.70711	0.70711	0.70711
3	-88	0.70733	0.70733	0.70733	0.70733	0.70733
4	-86	0.70799	0.70799	0.70799	0.70799	0.70799
	elevation	-84	0.70907	0.70907	0.70907	0.70907
		-82	0.71059	0.71059	0.71059	0.71059
7		-80	0.71254	0.71254	0.71254	0.71254
8		-78	0.71493	0.71493	radius	0.71493
9		-76	0.71774	0.71774	0.71774	0.71774
10		-74	0.721	0.721	0.721	0.721
11		-72	0.72469	0.72469	0.72469	0.72469
12		-70	0.72882	0.72882	0.72882	0.72882
13		-68	0.73338	0.73338	0.73338	0.73338
14		-66	0.73839	0.73839	0.73839	0.73839
15		-64	0.74383	0.74383	0.74383	0.74383
16		-62	0.74971	0.74971	0.74971	0.74971

In this example, the azimuth θ is from 0 to 360, and the elevation ϕ is from -90 to 90. The unit used for angle is degree.


- Open the Script Window, type in code below and run:

```
sph2cart -d;
```



Setting the sph2cart dialog follows graph below, then click **OK**. Three new matrix objects will be created which are corresponded to XYZ.




- Then add an extra matrix object after the matrix Z in Matrix Layer to act as the colormap.




- Copy the data in *colormap* matrix in Spherical Coordinates folder, paste the data to the new added matrix object.




- Now, you will plot the Matrix into a 3D surface, active the matrix object Z, click **Plot: 3D Surface: Colormap Surface**




Double click the surface to open the Plot Properties dialog. Set the Parametric Surface in dialog follows graph below, and click **OK** to apply the settings.




7. Click CTRL+R to rescale the axis, double click the axis to open the Axis dialog, change to scale for XYZ axis from -1.2 to 1.2, click **OK** to close the dialog.



You graph may look like this:




8. Next we will apply the colormap to the ellipsoid, double click the surface to open the **Plot Details** dialog, go to the **Fill** tab, change the **Contour fill from matrix** into Mat(4).




9. Go to the Colormap/Contours tab, you can click the table head to open the Set Levels, Fill and Contour Lines dialog. Set the Level by **Find Min/Max**, click **OK** to apply, and set Fill by

load palette "Maple", click **OK**, then select "Hide All" to hide all lines, click **Apply** to apply the settings.



Go to the **Mesh** tab, deselect the **Enable** checkbox to close the mesh line, click **OK** to close the dialog.

10. the finished graph is similar to this:




The azimuth and elevation can be unevenly spaced in (r, θ, φ) space.

Convert data in a matrix object and make a 3D surface plot

1. Origin can construct a $R(\theta, \varphi)$ surface function under spherical coordinates. The azimuth, elevation and radius are placed in the same matrix. Before set matrix values form a spherical coordinates equation, you can refer to [sph2cart](#) for the transforming relations and definition of azimuth and elevation in our system.
2. Create a new a matrix, and select **Matrix: Set Dimension and Labels** in main menu. Set the Dimension 100×100 , and map Column to X by $(0, 2\pi)$, map Column to Y by $(-\frac{\pi}{2}, \frac{\pi}{2})$. X and Y are the Angle Data, where X is the azimuth which is across columns and Y is the elevation.

In this example, the azimuth θ is from 0 to 2π , and the elevation ϕ is from $-\frac{\pi}{2}$ to $\frac{\pi}{2}$. The unit used for angle is radian.



3. Select **Matrix: Set Values** in main menu. The formula entered in the Set Values dialog should be

```
abs(sqrt(0.5)*0.25*(15/pi)^0.5*sin(pi/2-y)*sin(pi/2-y)*(sin(2*x)-cos(2*x)))
```


We set the matrix values by using spherical harmonics, Y_l^m is specific set of spherical harmonics, and the linear combinations of Y_l^m is corresponded to the d-orbitals of the hydrogen atom (i.e. d_{xy}).

$$|d_{xy}| = \left| \sqrt{1/2}(Y_2^{-2} - Y_2^2) \right| \quad (1)$$

Y_2^2 and Y_2^{-2} in function (1) are:

$$Y_2^2 = \frac{1}{4} \sqrt{\frac{15}{\pi}} \sin^2\left(\frac{\pi}{2} - \varphi\right) \cos(2\theta)$$


$$Y_2^{-2} = \frac{1}{4} \sqrt{\frac{15}{\pi}} \sin^2\left(\frac{\pi}{2} - \varphi\right) \sin(2\theta)$$



4. Next you can convert the matrix from spherical coordinates to Cartesian by using X-Function *sph2cart*. Select **Window: Script Window** in main menu, then enter the script below and click **Enter** to execute :


```
sph2cart -d
```

Set the sp2cart dialog follows graph below, the single matrix object is used as input data:




After clicking **OK**, the results will be created in a new Matrix Sheet (MSheet2).

- Now, you will plot the Matrix into a 3D surface. With Matrix object **Z** in **MSheet2** active,




select **Plot: 3D Surface: Color Map Surface** in main menu.


- Double click the surface to open the **Plot Details** dialog, set the parametric surface follows graph below, and click **OK**.




7. Click CTRL+R to rescale the axis, double click the axis to open the **Axis** dialog, change to scale for XYZ axis from -0.5 to 0.5, set the vvalue for **Major Ticks** to 0.2, click **OK** to close the dialog.



8. The graph created is similar to this:




9. Double click the surface to open the **Plot Properties**. Go to the **Colormap/Contours** tab, click the Level/Fill/Line button and set the dialogs separately.



Then go to the **Mesh** tab, deselect the **Auto** checkbox for Transparency and change the value to about 70%.




You can refer to [Parametric Surface](#) tutorial for details about colormap setting. The finished Graph are shown below:



Convert data in three matrix objects and make a 3D surface plot

Origin can construct a $R(\theta, \varphi)$ surface function under spherical coordinates. The azimuth, elevation and radius are placed in the different matrix. The following steps shows how to construct multiple surfaces by using three matrix and use **sph2cart** to convert them into XYZ space.

1. Create a new matrix. Set the Matrix Dimension 98×33 in **Matrix Dimension and Labels** dialog, then click **OK**.
2. Click the D button on the right corner of the matrix and click **Add** to add another two matrix objects in MatrixBook.




3. The azimuth will be put into the first matrix object. With the first matrix object active (Click the D button and switch between 1/2/3), click **Matrix: Set Values** in main menu. The matrix values for azimuth will be set in this way:

Column(j)	Data
0 to 32	$(0, 2\pi)$
34 to 65	$(0, 2\pi)$
66 to 98	$(0, 2\pi)$

4. Set the Matrix value use the expression below:

$(j==33 \mid j==66) ? 1/0 : (\pi/32 * j * (j < 33) + \pi/32 * (j - 33) * (j > 33 \&\& j < 66) + \pi/32 * (j - 66) * (j > 66))$



The value from 0 to 2π loop 3 times, and the Column (33), Column (66) should be missing values.

5. The elevation will be put into the second matrix object (select matrix 2 in graph in step 2). Set the values for elevation by using expression:

$$\text{pi}/32*(i-17)$$

6. The radius (expression below) will be put into the third matrix object.

$$Col(i, j) = \begin{cases} 1 & \text{if } i \in [1, 32] \\ 0.7 & \text{if } i \in [33, 65] \\ 0.4 & \text{if } i \in [66, 98] \end{cases}$$


The way for setting the values for radius is also piecewise, you can refer to the step 3, 4, 5 and use the set value code below :

$$1*(j<33)+0.7*(j>33\&j<66)+0.4*(j>66)$$

7. After setting values for three matrix, you can convert the data to XYZ space by using **sph2cart**. Open the Script Window, type in code below and run:


```
sph2cart -d;
```

Setting the sph2cart dialog follows graph below, then click **OK**. Three new matrix for XYZ will be created.



8. Create 3D surface graph by using XYZ matrix object created in new matrix layer. The steps are very similar to steps 5,6,7,8 in [above section](#) **Convert data in a matrix object and make a 3D surface plot.**


The finished Graph is showed below:




Convert data in three columns and make a 3D space curve

Origin can create 3D space curve with unevenly spaced data in XYZ column (spherical coordinates). The following steps introduce the plot of a non-isometric spiral with a sphere shape.

1. Create a new workbook with three columns X, Y and Z. Set values from $\frac{\pi}{100}$ to 20π for X column by **Fill Column With: A set of Numbers**



Set value for Y column by **Set Column Values**




Set value for Z column by **Set Column Values** and set as constant value "4"

In this example, the X, Y, Z are corresponded to Azimuth, Elevation, Radius, respectively.

2. Open the Script Window, type in code below and run:



```
sph2cart -d;
```

Setting the sph2cart dialog follows graph below, then click **OK**. Three new columns for XYZ will be created.




3. Plot the new XYZ with **Plot: 3D Symbol/Bar/Vector: 3D Scatter**. Set Symbol size to 0 and connect Symbols with line,click **OK**.

Tutorials for Origin



4. Further adjust the scales and the perspective view, the finished graph is similar to graph below:



5. a 3D surface can be created with new created XYZ data as well by selecting **Plot: 3D Surface: Color Map Surface** with XYZ columns highlighted.




The azimuth and elevation in X and Y can be evenly or unevenly spaced in (r, θ, φ) space.

6.12.21 Flattened Colormap Surfaces with Increasing Z Offset

6.12.21.1 Summary

This tutorial will show you how to plot a stacked flattened colormap surface with Z offset.




6.12.21.2 What will you learn


- How to import multiple matrix into Origin as the matrix object.
- How to plot Multiple Colormap Surfaces in a graph layer.

6.12.21.3 Steps


1. Create a new matrix and select **File: Import : Image to Matrix** to import **myocyte1~myocyte8** under the *\Sample\Image Processing and Analysis* folder. In the **Implmage** dialog, keep **Mult-File (except 1st) Import Mode** as **Start New Objects**.



2. Click the OK button to import the files to matrix as matrix objects.





3. Select **Plot: 3D Surface: Multiple Colormap Surfaces** from the main menu to plot a surface graph.




4. Select **Format: Plot properties** from the main menu to open the Plot Details dialog.


5. Select the first plot, check **Flat** and **Shift in Z by percent of scale range**, and set the shift value as 0. And go to the **Mesh** tab, uncheck the **Enable** check box to not show the grid lines.



6. Select the 2nd-8th plot in order, check **Flat** and **Shift in Z by percent of scale range**, and set the shift value as 14, 29, 42, 57, 71, 85 and 100. And go to the **Mesh** tab, uncheck the **Enable** check box to not show the grid lines. Click the OK button to close the dialog.




7. Rotate the graph to get a flattened colormap surface as shown below:



6.12.22 3D Ternary Colormap Surface with Contour Lines Projection

6.12.22.1 Summary

In this tutorial, a 3D ternary surface with Z colormap and its projection with contour lines are generated from XYZZ worksheet data.



Minimum Origin Version Required: Origin 2015 SR0

6.12.22.2 What you will learn

This tutorial will show you how to:


- Generate a 3D ternary surface plot with Z colormap.
- Project color-mapped contour lines onto the XYZ axis plane.

6.12.22.3 Steps


Creating 3D ternary surface

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data project and browse to folder *3D Ternary Surface*.
2. Activate the worksheet **Ternary Surface** in **Book1F**, and highlight col(C) and col(D). Select **Plot: 3D Surface:3D Ternary Colormap Surface** to generate a colormap surface.
3. We will modify the plot to show the edges of the 3D prism. Double-click on the plot to open the **Plot Details** dialog box. Highlight **Layer1** in the left panel (take care not to clear the check mark beside the Layer1 icon). Go to the **Plane** tab, set **Prism** to **Whole Prism** and enable **Plane Border**.




4. Expand the **Layer1** node, highlight the dataplot icon and click the **Fill** tab. Check **Enable** box and select **Colormap**. Check the box beside **Fill back surface** and set color as **LT Gray**.




5. Click the **Colormap / Contours** tab. Click the **Level** heading and in the **Set Level** dialog box, set controls as follows, then click **OK** to close the dialog box.




6. To add contour lines on the ternary surface, check the box next to **Enable Contours**.




- To customize the contour lines, click the **Line** heading to open the **Contour Lines** dialog. Under *Line Properties*, check the box before **Color** and **Style** and set the Color as **Dark Gray** and Style as **Short Dash**, then click **OK**.




- Go to the **Mesh** tab, clear the **Enable** box, then click the **OK** button.



- To customize the scale and the major ticks of the X/Y/Z axes, click on a graph axis to open the **Axis Dialog** box. Expand the X, Y and Z nodes, then press CTRL while selecting **Scale** for the X, Y and Z axes. Set **Major Ticks > Value** to **0.2**.





10. Expand the Zh axis node and select **Scale**. Duplicate the scale range and the **Major Ticks > Value** settings as shown below.




11. Click **OK** to close the **Axis Dialog** box.

Creating projection with contour lines


1. With the graph page active, select **Graph: Layer Contents** from the main menu to open the Layer Contents dialog. Select **Worksheets in Folder** from the drop-down.
2. To add another ternary surface to the graph, press CTRL and in the left panel, select the datasets **XC** and **CRC299** of sheet "Ternary Surface", then click the **Add plot** button  to add them to the right panel. Click **OK**.




3. Double-click on the plot to bring up the **Plot Details** dialog box. Under **Layer1**, click on the second plot, then click on the **Surface** tab. Under **Display**, choose **Flat** and **Shift in Z by percent of scale range, 0 = bottom, 100 = top**.




4. On the **Colormap / Contours** tab, select **Enable Contours**. Click the **Line** heading and edit the **Contours Lines** dialog box settings as in the following image and then click **OK**.




5. On the **Colormap / Contours** tab, click the **Level** heading and in the **Set Level** dialog box, set # **Major Levels** to **20** and # of **Minor Levels** to **5**. Click **OK** to close the dialog box.
6. Go to **Fill** tab and clear the **Enable** box.



7. On the **Mesh** tab, clear the **Enable** box. Click **OK** to close the dialog box.
8. To change the grid lines on the axis planes dashed lines, double click the axis to bring up the **Axis Dialog** box. In the left panel, expand the **X** node and select **Grids**. Press **Select Others** to choose grids for all the axis planes. Customize the *Major Grid Lines* section as follows:




9. Rotate the plot by dragging a hotspot (hint: click once inside the graph frame - but not on the plot -- to activate the move/resize/rotate functions). Alternately, you can use the tools on the 3D Rotation toolbar.



6.12.23 3D Ternary Scatter Plot with drop lines

6.12.23.1 Summary

In this tutorial, a 3D ternary scatter plot is generated from XYZZ worksheet data. Initially, the plot is created as a **3D Ternary Surface** and then changed to a **Scatter** plot. Drop lines are added to the data points to indicate their exact locations in the axis plane.



Minimum Origin Version Required: Origin 2015 SR0

6.12.23.2 What you will learn


This tutorial will show you how to:

- Generate a 3D ternary scatter plot.
- Draw drop lines for data points


6.12.23.3 Steps

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data project and browse to folder *3D Ternary Surface*.
2. Activate the worksheet **3D Ternary Scatter** in **Book1F**, and highlight col(C) and col(D). Select **Plot: 3D Surface:3D Ternary Colormap Surface** to generate a colormap surface.
3. Double-click on the plot to open the **Plot Details** dialog box. Highlight **Layer1** in the left panel and click on the **Planes** tab in the right panel. Set **Prism** as **Whole Prism** and enable **Plane Border**.




- Return to the left panel, click on **Layer1** (take care not to clear the check box beside the Layer1 icon) and highlight the plot beneath the Layer1 icon. Go to the bottom of the Plot Details dialog box and change **Plot Type** to **3D Scatter/Trajectory/ Vector**.




- Return to the left panel, click on **Original** (beneath the plot). In the right panel, go to the **Symbol** tab and duplicate the following settings:




- Now we will draw the drop lines. In the left panel, select the scatter plot (Original). In the right panel, select the **Drop Lines** tab. Select the **Parallel to Z Axis** check box. Change **Style** to **Short Dot**, **Width** to **1**, **Color** to **Gray** and **Drop to** to **Z=Axis Begin Plane**. Click **OK** to close the Plot Details dialog box.




- Double-click the axis to bring up the **Axis Dialog** box. In the left panel, press **CTRL** key to select **X, Y, Z** and **Zh** axes. Then, go to **Grids** tab to customize **Major Grid Lines** settings as shown in the following image. Click **OK**.




- To customize the scale and the major ticks of the X/Y/Z axis, press **CTRL** key to select the **X, Y** and **Z** axes in the left panel, and then go to **Scale** tab to set **Major Ticks > Value** to **0.2**, as shown in the image below:



9. To customize the scale and the major ticks of the Zh axis, select **Zh** axis and then go to Scale tab, customize the scale range and **Major Ticks > Value** as shown in the following:




- Click once inside the layer frame (but not on the plot) to enable the move/resize/rotate functions. Drag to rotate the plot for better viewing. Alternately, you can use the tools on the **3D Rotation** toolbar.



6.13 Plot Functions with Parameters Defined in a Worksheet

6.13.1 Summary

Origin can plot functions. It also can plot functions with parameters defined in a worksheet. The function graph can be updated automatically as the parameters in the worksheet change.



Minimum Origin Version Required: Origin 8.0 SR6

6.13.2 What you will learn


This tutorial will show you how to:


- Define variables from a worksheet in the **Set Values** dialog box.
- Plot a function graph with parameters.
- Update a graph automatically when parameters are changed.


6.13.3 Steps

Let us use this function as an example: $y=p_0+p_1*x+p_2*x^2$


1. Set up a worksheet with three parameters p_0 , p_1 , p_2 stored in Column A, Column B, Column C as shown below.





2. Click on the **Add New Columns** button  on the **Standard** toolbar to add a new column to the worksheet.





3. Highlight Column D and then select **Column: Set Column Values**. Select **Auto** from the **Recalculate** drop-down. Type the [script](#) shown below to define the parameters in the **Before Formula Scripts** edit box. Click the **OK** button to close the dialog box.




Note that there is a green lock icon  on the top right corner of Column D which indicates that the Recalculate Mode is Auto.



4. Click on the **New Function** button  on the **Standard** toolbar (If there is not **New Function** button, select **View: Toolbar** to open the **Customize** dialog, and then go to **Button Groups** tab, select **Standard** group, and then drag the **New Function** button to **Standard** toolbar.). The **Plot Details** dialog opens.
5. In the **Plot Details** dialog, set the options as follows and click the **OK** button to close the dialog box.



Click on the **Rescale** button  on the **Graph** toolbar to adjust the graph's scales.




- The function graph can be updated automatically when the parameters in the first row of the worksheet change. Change the value in the first row of Column 2 from 2 to 3. Click outside this cell to finish editing.

The screenshot shows a spreadsheet window titled "Book1" with a table. The table has four columns: A(Y), B(Y), C(Y), and D(Y). The first row contains the labels "Long Name", "p0", "p1", and "p2". The second row is labeled "Units". The third row is labeled "Comments". The fourth row contains the values "1", "3", and "1". The cell containing "3" is highlighted with a pink box. The fifth row is empty. The spreadsheet interface includes a "Sheet1" tab at the bottom and navigation arrows.

	A(Y)	B(Y)	C(Y)	D(Y)
Long Name	p0	p1	p2	
Units				
Comments				
1	1	3	1	
2				

The function graph updates to reflect this change.



6.13.4 Scripts

The script used in the **Before Formula Scripts** edit box of the **Set Values** dialog box is:

```
p0=col(1)[1]; //Specify Column A for p0.

p1=col(2)[1]; //Specify Column B for p1.

p2=col(3)[1]; //Specify Column C for p2.
```


The function in the **F1(x)** edit box of the **Plot Details** dialog box is as follows:

```
p0+p1*x+p2*x^2
```

6.14 Windrose Graph

6.14.1 Summary

Windrose graphs are used to present wind speed data and wind direction data collected over time at a particular location. This tutorial will demonstrate how to create windrose graphs from both raw and indexed data:



Minimum Origin Version Required: Origin 9.1 SR0

6.14.2 What will you learn

This tutorial will show you how to:

- Create a windrose graph from binned data
- Customize the direction tick labels on the windrose graph
- Create a windrose graph from raw data


6.14.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to this graph in Origin Central. (Select **Help: Origin Central** menu or press **F11** key, and then open **Graph Sample: Specialized Graphs**)

6.14.3.1 Part 1: Create a Windrose Graph from Binned Data


1. Open **Tutorial Data.opj** and browse to the **Wind Rose** folder in **Project Explorer** (PE).
(If you don't have the project file, please import the sample data from [here](#)).
2. Activate the **Book6E** workbook. Highlight all worksheet columns and click the **Wind Rose - Binned Data** button on the **2D Graphs** toolbar as shown below or select **Plot: Specialized: Wind Rose-Binned Data** from the main menu.




The wind rose graph should look like the following image:




- To change the wind direction to show only N,E,S,W double-click on the angular axis (the outermost ring) to open the **Axis** dialog box. Go to **Scale** tab and choose **Angular** axis in the left panel. Under **Major Ticks** section, set **Type** to **By Increment** and **Value** to **90**




4. Go to **Tick Labels** tab, make sure the **Angular - Outer** axis is selected in the left panel, and duplicate the following settings:



5. Click **OK**. The graph should look like this:




6. Click on the **Text Tool** button **T** to add a **Text** object as graph title. And enter *Sample of Wind Rose (Binned Data)* in that **Text** object.




6.14.3.2 Part 2: Create a Windrose from Raw Data


1. Go to the project folder *Statistical and Specialized Graphs: Specialized: Wind Rose* and activate the **Book7E** workbook, **Raw Data** worksheet. (If you don't have the project file, please import the [sample data](#) from here).
2. Highlight columns A & B. Click the **Wind Rose - Raw Data** button on the 2D Graphs toolbar as shown below or select **Plot: Specialized: WindRose - Raw Data** from the main menu.



3. Use the settings below to create the wind rose graph:



The final graph should resemble the image shown below:



6.14.4 Sample Data

6.14.4.1 Binned Data

To import **Binned Data** to a worksheet, copy the **Binned Data 1** (including the heading) and select **File: Import Wizard**. Select the **Clipboard** checkbox in the **DataSource** group and click the **Finish** button to import the data into Origin.



Direction	0-4	4-8	8-12	12-16	16-20
-----------	-----	-----	------	-------	-------

Tutorials for Origin

22.5	3.125	3.125	3.125	6.25	0
45	0	3.125	3.125	0	0
67.5	0	6.25	0	0	0
90	0	0	0	0	3.125
112.5	0	0	0	0	0
135	3.125	0	0	0	3.125
157.5	0	0	9.375	3.125	0
180	3.125	3.125	0	3.125	3.125
202.5	0	0	0	0	0
225	0	0	3.125	0	0
247.5	0	3.125	0	3.125	3.125
270	0	0	0	0	3.125
292.5	0	6.25	3.125	0	0
315	0	0	3.125	3.125	0
337.5	0	0	0	0	0
360	0	6.25	0	0	0
382.5	0	0	0	0	0

6.14.4.2 Raw Data

To import **Raw Data** to worksheet, you can copy the **Raw Data** (including the heading) and then select **File: Import Wizard**. Select the **Clipboard** checkbox in **DataSource** group and then click **Finish** button to import the data into Origin.



Direction	Speed
311.5	12.75
142.7	11.18
161.6	5.9
277.3	8.24
155.3	13.46
40.8	8.57
43.4	4.38
1.3	10.91
78.8	18.72
237.8	16.22
114.6	0.88
2.1	12.05

Tutorials for Origin

290.5	4.6
174.1	3.29
267.6	16.64
8	5.6
213.9	8.04
134.8	17.26
137.6	11.87
46.1	5.48
4.5	13.47
311.2	10.17
154.4	11.17
176.2	18.91
348.1	4.11
225.2	6.65
236.4	12.87
11.7	1.07
278.9	4.36
356.5	5.01


58.9	7.3
161.8	15.6

6.15 2D Vector Graph

6.15.1 Summary

A vector plot is a multidimensional graph used in industries such as meteorology, aviation, research, and construction that illustrate flow patterns (e.g. of wind, water, magnetic fields, etc.). Both direction and magnitude are represented in a vector graph. Origin includes two types of vector plots:

1. **Vector XYAM** - takes a starting XY location for the vector tail (by default), an angle and a magnitude.
2. **Vector XYXY** - takes two XY positions and connects them with a vector.



Minimum Origin Version Required: Origin 2015 SR0

6.15.2 What you will learn

This tutorial will show you how to:

- Use Two data organizing mode to plot a vector graph.
- Use Plot Setup to assign plot data

6.15.3 Steps

This tutorial is associated with <Origin EXE Folder>\Samples\Tutorial Data.opj.


Also, you can refer to these graphs in Origin Central. (Select **Help: Origin Central** menu or press **F11** key , and then open **Graph Sample: Specialized Graphs**)



To create a vector plot, you need four data columns, and to organize your data into two modes:

6.15.3.1 Vector XYAM

XYAM stands for X, Y, Angle and Magnitude. Vectors will start from point (X, Y), and rotate a specified angle. The following example uses XYAM data mode to create a vector graph.

1. Open **Tutorial Data.opj** and browse to the **2D Vector** folder in **Project Explorer (PE)**.
2. Activate the data worksheet **Book8E**. Without highlighting any columns, select **Plot: Specialized: Vector XYAM** from the main menu to open the **Plot Setup** dialog. Assign columns A, B, D, C to X, Y, A, M as shown below, then click **OK** to plot the graph.



In order to show all three panels in **Plot Setup** dialog, please expand **Plot Type** panel by clicking  and expand **Available Data** panel by clicking  again.

Please refer to [Plotting using Plot Setup](#) for more information.

3. Select **Format:Plot Properties...** to pull up the plot level of the **Plot Details** dialog. In the **Vector** tab change the **Magnitude Multiplier** drop-down list to 75. Click the **OK** button to close **Plot Details** dialog.
4. Double-click the X or Y axis to open the **Axis** dialog. Go to the **Line and Ticks** tab, in the left panel, hold **Ctrl** key to select both **Bottom** and **Left** icons, check the **Use Same Options for Bottom and Top** check box. This will apply the settings in bottom X to top X, and those in left Y to right Y.
5. Go to the **Tick Labels** tab, hold **Ctrl** key to select both the **Top** and **Right** icons in the left panel, check **Show** check box. Click **OK** to apply the setting and close the **Axis** dialog.
6. Right click on the legend box to bring up the context menu. Select **Properties...** to open the **Object Properties** dialog. Type **I(1) Field Strength** in the text box and click **OK**.
7. Add a layer title: **Spot Write Effectiveness**.

6.15.3.2 Vector XYXY

Another data organizing mode is XYXY; where the first X, Y is the vector starting point, while the last X, Y is the ending point.


To create such a vector graph, activate workbook **Book9E** under the *2D Vector* folder, highlight all of the four data columns in it, and select **Plot: Specialized: Vector XYXY** from the main menu. Delete the axis titles if necessary.

6.16 Piper Diagram

6.16.1 Summary

Piper diagram (or Trilinear diagram) is used as an effective graphical representation of chemistry in water samples in hydro-geological studies. The percentage values of six ion groups are considered in the plot, they are calcium, magnesium and sodium plus potassium cations, and sulfate, chloride and carbonate plus hydrogen carbonate anions.

The cations and anions are shown by two separate ternary plots and both are then projected onto a rhomb. In Origin they are plotted as a three layer graph.




Minimum Origin Version Required: 9.1 SR0

6.16.2 What will you learn

This tutorial will show you how to:

- create a piper plot from percentage data
- customize the gap between ternary and rhomb in piper graph
- add data labels in the piper plot

6.16.3 Steps

1. Start a new workbook and click the  button to import the file **Piper.dat** under *<Origin EXE Folder>\Samples\Graphing* path.
2. In the imported worksheet, column **A** is the Sample ID. Column **B** through **G** are the percentage values for the six ion groups in the order of **Ca, Mg, Na+K, Cl, SO4**, and

CO₃+HCO₃. column **H** is the amount of total dissolved solids in water. The percentage for cation groups is relative to the total amount of cations and that of anion groups is calculated by the same manner.

Note: We have some built-in workbook templates to help you convert data from different units (MEq/mgL/PPM) to percentage (open from **File>New:From Template:**). For details, please refer to [this help file](#).

- Highlight column **B** through **G** and select **Plot:Specialized:Piper** from the top menu to open the **plotpiper** dialog.
- Select column **A** for **Sample ID** and column **H** for **Total Dissolved Solids**.

Plotting: plotpiper

Create piper plots or add more data to it

Input [Piper]Piper!2:7

Column order of input data need to range as Ca, Mg, Na+K, Cl, SO₄,CO₃+HCO₃

Sample ID [Piper]Piper!A''Sample ID''


Total Dissolved Solids [Piper]Piper!H''Total Dissolved Solids (TDS)''

Output Graph [<new template:=piper>]<new>

OK Cancel

Note: You can select an existing piper diagram as the **Output Graph** and add the selected new data into this piper diagram.

- Click **OK** to generate the piper plot:




Sample ID and TDS are optional when plotting piper diagram. If Sample ID is specified, symbol color and shape will be controlled by it. If TDS is specified, open circle in the rhomb (Layer 1) will show and the size will be controlled by it. Also Piper diagram shows each sample in legend.


6.16.4 More Customization Steps

The following steps can further customize the graph to be exactly the same as the image in **Summary**.


1. To change the gap between the ternary plots and the rhomb, double click the bottom left ternary to open the **Plot Details** dialog. On the left panel, select **Layer 2**. On **Size/Speed** tab, change the **Left** value to be **130**, so that the distance between the top vertex of rhomb and the top vertex of the ternary in Layer 2 will be 130% of the side length of rhomb. Click **Apply** button.



- To change the symbol color or shape increment list, select the data plot under **Layer 1** node on the left panel. Then go to the **Color List** or **Shape List** tab to customize them.




- To add **Sample ID** as data label in the rhomb, Select 1st data plot under **Layer 1** node on the left panel. Go to **Label** tab and set as follows:



To add data labels to two ternaries in the graph, please select plot under **Layer2** and **Layer3** nodes in the **Plot Details** dialog and do the same.

4. The 2nd data plot under **Layer1** node in the **Plot Details** dialog is the open circle for TDS. Select the data plot on left panel and select the **Symbol** tab. You can see the Size of the open circle is controlled by Col(H). The Scaling Factor is auto determined to get a proper display. Change the **Scaling Factor** to **0.03** to see the change.
5. By default Sample ID shows in legend. To show sampling location's information in legend, right click on the legend and select **Legend:Point by Point...** to open the **Update Legend Point by Point** dialog. Select **Custom** for the **Label Form** drop-down list and then select **wcol(1): wcol(9)** from the menu. wcol(9) refers to the 9th's column in worksheet, which is the Sampling Location column.



6.17 Waterfall

6.17.1 Waterfall

- [2D Waterfall](#)
- [3D Waterfall](#)

6.17.2 2D Waterfall

6.17.2.1 Summary

Origin's **Waterfall** plot uses a dataset stored in a parameter row to set the Z offset and create a color map with Y or Z values.

6.17.2.2 What you will learn

This tutorial will demonstrate how to:


- Create a 2D Waterfall color map with Y or Z values
- Customize colormap levels and palette

6.17.2.3 Steps


This tutorial is associated with the **Tutorial Data** project: <Origin EXE Folder>\Samples\Tutorial Data.opj.

Create Waterfall with Y Colormap


1. Open the **Tutorial Data** project and browse to folder *Waterfall* in **Project Explorer**. Select the **Book4G** window to activate it. Click in the upper left corner of the worksheet to select all data.
2. Right-click and select **Plot** from the menu, point to **Y-offset/Waterfall**, and select **Waterfall Y:Color Mapping** to create a Waterfall with Y color mapping. (Alternatively, select the **Waterfall Y:Color Mapping** button from the 2D Graphs toolbar.) A graph resembling the image below will appear:



Note that the values stored in the user-defined parameter row **Frequency (Hz)** have been automatically picked up as the Z Value Source. Confirm this by double-clicking the plot to open the **Plot Details** dialog box and selecting **Layer1** in the left panel. Select the **Waterfall** tab and observe that the **Z Value Source** is set to **Frequency (Hz)**.




- With the Plot Details dialog box still open, in the left panel, select the first line plot under Layer1. Select the **Colormap** tab in the right panel. Click on the **Level...** column header to open the **Set Levels** dialog box. Set levels as shown below:




Click **OK** to close the Set Levels dialog box.

4. Click on the **Fill...** column header to open the **Fill** dialog box. Select **Load Palette**, and choose the **Rainbow** palette from the palette list. Click **OK** button to close the **Fill** dialog box.




Click **OK** to apply these settings and close the **Plot Details** dialog box.


5. Double-click the plot's Z axis to open the Axis dialog box. Go to the **Scale** tab and set the major tick **Value** to **50**.



6. Go to the **Grid** tab. Press the **Ctrl** key to select the **X** and **Y** axes in the left panel, and the clear the **Minor Grids** check box.




Click **OK** to apply changes and close the dialog box. The final graph should look like this:




Create Waterfall with Z Colormap

1. In the Project Explorer (usually at the left of the screen), browse to **\2D and Contour Graphs\Waterfall**. Select the **Book4G** window to activate. Click in the upper left corner of the worksheet to select all data.
2. On the main menu, click **Plot**, then point to **Y-offset\Waterfall**, and then select **Waterfall Z:Color Mapping** to create a Waterfall with Z color mapping. (Alternatively, select the **Waterfall Z:Color Mapping** button from the 2D Graphs toolbar.)




3. Double-click the plot to open the Plot Details dialog box. In the left panel, select the first line plot under Layer1. Select the **Colormap** tab in the right panel. Click the **Level...** column header to open the Set Levels dialog box. Set **Major Levels** to **10**.




Click **OK** to close the Set Levels dialog box.

4. Click the **Fill...** column header to open the Fill dialog box. Select **Limited Mixing** and set the **From** color to **red** and the **To** color to **blue**. Click **OK** to apply these settings and close the dialog box. Click **OK** to close the Plot Details dialog box.



5. Double-click the Y axis to open the **Axis** dialog box. Set the vertical **Increment** to **50**. Select the **Grid Lines** tab. Select **Horizontal** from the **Selection** box, and clear the **Minor Grids** check box. Select **Vertical** from the **Selection** box and clear the **Minor Grids** check box. Click **OK** to close the Axis dialog box.


Your final graph should look like this:



6.17.3 3D Waterfall

6.17.3.1 Summary

Origin features an OpenGL-supported 3D waterfall graph. The 3D waterfall is a specific type of 3D wall graph with a wall width = 0. You can [rotate, resize, stretch and skew the graph](#) as with other Origin 3D graphs.



Minimum Origin Version Required: 2015 SR0

6.17.3.2 What you will learn


This tutorial will show you how to:

1. Plot a 3D waterfall graph
2. Add a plane at the specified position in the graph
3. Skew the 3D waterfall graph


6.17.3.3 Steps

This tutorial is associated with the Tutorial Data project: <Origin EXE Folder>\Samples\Tutorial Data.opj.


1. Open the Tutorial Data project and browse to folder *3D Waterfall*.
2. Activate workbook **Book41** by locating it in Project Explorer and double-clicking to show the window. Highlight all columns. Select **Plot: 3D XYY: 3D Waterfall** from the main menu to plot a 3D waterfall graph.




3. Select **Format:Layer Properties** from the menu to open the **Plot Details** dialog box. Go to the **Planes** tab, check the box to add an XY plane to the graph, uncheck the **Enable** check box in the **Plane Border** group, then set the remaining controls as shown in the following image:




- Click the arrow icon to the left of **Layer1** to show all plots in the layer. Select the first plot in the layer (take care not to clear the check box next to the dataset icon), then click the **Pattern** tab and set the **Fill Color** as *LT Gray*.




- Click **OK** to close the dialog box. Double-click on a graph axis to open the **Axis** dialog box. Clear the **Use Only One Axis For Each Direction** check box. Go to the **Scale** tab and select **Z** axis icon in the left panel and set **From** and **To** to *0.8* and *3.2*, and set the increment value of **Major Ticks** to *0.2*.




- Go to the **Tick Labels** tab, make sure **Top - Z** icon is selected and clear the **Show** check box to hide the tick labels on top Z axis.



6. Go to the **Line and Ticks** tab, make sure **Top - Z** icon is selected and set **Major Ticks** and **Minor Ticks** to **None**.



7. Click **OK** to close the dialog. Click on the cube to activate the five red graphical editing icons. Click on the fourth button - the **Skew** button - and drag the X/Y hotspots to skew the graph in X/Y direction so that it looks approximately like this:



6.18 Open-High-Low-Close-Volume Stock Chart

6.18.1 Summary

This tutorial will show you how to create a stock chart to display open, high, low, and close prices, along with trading volume.



Minimum Origin Version Required: Origin 2016 SR0


6.18.2 What you will learn

- Set a column format
- Create a stock chart with open, high, low, and close prices, and trading volume
- Set axis Scale Type to skip market-closed days
- Set format for major and minor tick labels, respectively


6.18.3 Steps

1. Download the source data file from our [ftp](#) and import it into Origin. When importing this file, keep the system default settings.
2. Set column A as Date format. Double click on the header of column A to bring up the **Column Properties** dialog. Activate the **Properties** tab, under the **Options** branch, select *Date* from the


Format drop-down list, and then select *Custom Display* from the **Display** drop-down list. Type *dd-'MMM'-yyyy* in the **Custom Display** combo box. Click **OK** button.




3. Highlight all columns in the worksheet, and then choose **Plot: Stock: OHLC-Volume** to create a graph.
4. Double click on the bottom X axis of Layer2 to open the **X Axis** dialog. Switch to the **Scale** tab. You can see the **Type** is set to **Discrete** by default. This is why the X axis skips all weekends and holidays automatically.




5. Change the axis rang From 3/5/2001 To 5/4/2001.



6. Under the **Major Ticks** branch, make sure **Type** is set to *By Increment*. Type *1week* for **Value**.
7. Under the **Minor Ticks** branch, make sure **Type** is set to *By Counts*. Type *5* for **Count**. Click **Apply** button. You can see weekend and holidays are skipped clearer.




8. To show weekdays of minor tick, switch to the **Tick Label** tab. Activate the **Minor Tick Labels** sub-tab. Select **Show at each Minor Ticks** for **Minor Tick Labels**. Type **100** for **Offset Major by (%)**. Type **D6** for **Display Format**. For details about **Display Format** options, refer to [Origin Formats](#). Click **Apply** button



Click OK button to close the dialog.

9. Double click on the left-Y axis in Layer1 to open the **Axis' dialog again. Switch to Vertical icon in the Scale** tab. Change **To = 22**.



10. Click **OK** button to finish the axis setting. The Final graph should appear as shown below:



7 Data Management

- [Working with Multi-Sheet Workbooks](#)
- [Adding Objects to Worksheet](#)

7.1 Working with Multi-Sheet Workbooks

7.1.1 Summary

Origin workbooks are similar to spreadsheets and can have multiple worksheets. Multi-sheet workbooks allow for better organization and higher information density.


7.1.2 What you will learn

This tutorial will teach you how to:


- Add and arrange worksheets.
- Handle metadata.
- Split the worksheet into Panels using Dividers.

7.1.3 Steps


7.1.3.1 Adding and Arranging Worksheets


1. Click the **New Project** button  on the **Standard Toolbar**.
2. Right-click on the **Sheet1'** *tab and choose Name and Comments*. Enter **Subjects** as the **Short Name** in the **Name and Comments** dialog.
3. Right-click on the tab of the sheet that was renamed in the last step, and choose **Add**. A second sheet, named **Sheet1**, will be added to the book.
4. Double-click on the new **Sheet1** tab and enter **2nd Test** as the name in the font box that appears. (Alternately, right-click and use the the **Name and Comments** option again.)
5. Right-click on the **2nd Test** name and choose **Insert**. A new sheet, named **Sheet1**, is inserted between **Subjects** and **2nd Test**. Rename the new sheet **1st Test**.
6. Left-click and hold down the mouse button on the **1st Test** sheet name, drag the mouse over the Origin Workspace and release. The **1st Test** sheet will now appear in its own workbook.

7. Select **Window: Tile Vertically** to arrange the workbooks side by side as shown below:



8. Drag **2nd Test** to the second workbook. This will move the **2nd Test** sheet from the original workbook to the new workbook as shown below:





9. Click the **Save** button . The **Save As** dialog will open since the project is yet to be saved. Save this in the User Files Folder as **Multi-Sheet Workbooks.opj**

Note: It is also possible to drag and drop sheets within the workbook to change the order. Right-click on any sheet name and note these additional options: **Duplicate Without Data**, **Duplicate**, **Delete** and **Navigate**.


7.1.3.2 Handling Metadata

Add Metadata to the Worksheet


1. Click the **New Project** button  on the **Standard Toolbar**.
2. Select **Format: Worksheet** from the Origin menu (Alternatively press **F4** or double-click on the gray area to the right of the columns). The **Worksheet Properties** dialog opens:




3. On the **View** tab, click the **Edit Column Label Rows** button. The **Column Label Rows** dialog opens.
4. Right-click on the table and select **Add User-Defined Parameter**. Scroll down to note that a **UserDefined** label has been added. The **Show** box is checked by default.





5. Double-click on the **UserDefined** text (or single-click and press F2), and change the **UserDefined** text to **Wavelength (nm)**.
6. Click in the box to the left of **Wavelength (nm)** and drag it to the top of the list, dropping it above **Long Name**. This will change the order of the rows as shown below:





7. Click **OK** to close the Column Label Rows dialog.
8. Select the **Format** tab in the **Worksheet Properties** dialog, and choose **LongName** from the **Apply To** drop-down. Check the **Rich Text** box.




9. Click **OK** to close the **Worksheet Properties** dialog box.
 10. Highlight the **Comments** row and click the **Merge Cells** button  on the **Style Toolbar** to create a row with one cell.
 11. Enter the values shown below in the Columns A and B header region (**Wavelength** to **Comments**).
- (Note: Once the Rich Text box is checked for specified cells, double-clicking in the cells to edit them will activate the format buttons . These can be used to apply rich text formatting as shown below):

	A(X)	B(Y)
Wavelength (650	700
Long Name	1 st Sample	2 nd Sample
Units	nm	nm
Comments	IR	
F(x)		
1		
2		
3		

View Metadata in the Workbook Organizer

1. Click on the **New Folder** button .
2. Click on the **Import Single ASCII** button .

- Browse to file **S15-125-03.dat** in Origin's *Sample\Import and Export* folder. The **Show Options Dialog** checkbox should be deselected by default. Click **Open** to import the file to Origin.
- Right-click on the workbook window title and choose **Show Organizer** from the context menu. The **Worksheet Organizer** will appear at the bottom of the worksheet.
- Expand the **Imported Files** branch and view the stored metadata.




7.1.3.3 Splitting Worksheets into Panels using Dividers

Split from Menu


- Activate the worksheet and highlight a cell.
 - Select **Window: Split** from the Origin menu.
 - The worksheet or matrix sheet will be divided into 4 panels by a horizontal and vertical Divider at the highlighted cell. To move the Divider to a new location, drag it to the desired row or column.
 - Select **Window:Remove Split** from the Origin menu to hide the split pointers.
- (Note: This process is the same for worksheets and matrix sheets).

Split by Dragging the Divider

1. Point the cursor to the bottom right of the sheet at the end of the vertical scroll bar (for a horizontal Divider) or at the right end of the horizontal scroll bar (for a vertical Divider) as shown below:
2. When the pointer changes to a split pointer, drag it to the desired position. A horizontal or vertical Divider will be created.



A worksheet with horizontal and vertical Dividers is shown below:



7.2 Adding Objects to Worksheet

7.2.1 Summary


Both worksheet header rows and data cells can contain embedded objects, linked objects as well as formatted text. In addition, floating graphs can be added to the worksheet like Excel.


7.2.2 What you will learn



- How to insert various objects into a worksheet cell.
- How to add floating graph to worksheet.






7.2.3 Steps


7.2.3.1 Inserting Objects in Cells


1. Start with a New Project by clicking on the **New Project** button .
2. Click on the **Import Wizard** button . In the **Import Wizard - Source** page, browse to select *S15-125-03.dat* file in Origin's *Sample\Import and Export* folder. Click on the Finish button to complete the importing.
3. Highlight columns **A(X)** and **B(Y)**, choose **Plot: Symbol: Scatter** from the menu or click on the **Scatter Plot** button  to create a graph.




4. Return to the workbook and select the **Column: Add New Columns...** from the menu or click on the **Add New Columns** button  to add 3 columns.
5. Expand the workbook so you can see all 7 columns.
6. In the row 1 of **E(Y)**, type **New Features** and press Enter.
7. Select cell **E1**, and then click the **Bold** button  on the **Format Toolbar**.


8. Click the **Font Color** button  on the **Format Toolbar** and pick **Yellow** as the color.
9. Click the **Fill Color** button  on the **Style Toolbar** and pick **Blue** as the color.
10. Select the range **E1** to **F1**, click the **Merge cells** button .
11. Right-click on cell **G1** and choose **Insert Arrow: Left** from the context menu to insert a arrow to the cell.
12. Select the range **E2** to **G12**, click the **Merge cells** button .
13. Right-click on the cell and choose **Insert Graph**.
14. In the **InsertGraph** dialog, type **Graph1** in the large Graphs box or click on the **Browse** button  to select Graph1.




15. Click **OK** to close this dialog.
16. Right-click on **E13** to choose **Insert Images from Files** from the context emnu.
17. Click the **Browse** button  and change the **Files of Type** to **Bitmap (*.bmp)**.
18. In the Origin User File Folder, select the **Userdef.BMP**, click **Add File(s)** button and then click **OK** button.
19. Click **OK** button to close the **Inserlmg** dialog.
20. Right-click on cell **F13** to choose **Insert Notes**.
21. Double-click on cell **F13**. Modify the text and then close the **Notes** window. A note will be saved in the cell.
22. Right-click in **E14** and choose **Insert Sparklines** to open the **InsertSparklines** dialog.
23. In the dialog, click the **Data Columns** fly-out button to choose **C(Y)**. Uncheck **Long Name in 1st Column** check box.



24. Click **OK** to close the dialog. A sparkline will appear in the cell.
25. Click on cell **E15** and type: <http://www.originlab.com> and press Enter.
26. Click on the text in **E15** which opens your web browser to the OriginLab web site.
27. Click on cell **E16** to choose **Insert Variables** from the context menu. The **Insert Variable** dialog opens.
28. with the worksheet **Book1** is selected in the right panel, go to the **Info** tab, expand the **USER.VARIABLES** branch, select **SAMPLE** and then click on the **Insert** button. A variable will be inserted to the cell.




29. Double-click on the cell **E16**, the text will change to a variable string.




The Graph, Notes and Sparklines in the above lesson are all examples of embedded objects (the Insert Graph could be either Embedded or Linked.) Embedded objects present a visual of a hidden external object that can be opened by double-clicking. Changes to the object can be made and then the object window can be closed and the source worksheet cell is updated.

7.2.3.2 Adding floating Graph to worksheet

1. Continue the above project. Highlight Col(D) in Book1 to plot a line graph.



2. In Book1, right-click the empty area or title of the book to select **Add Graph** from the context menu. The **Graph Browser** dialog will appear.
3. In the **Graph Browser**, select Graph1 and click OK to go back to the worksheet.
4. The graph will be put onto the worksheet. Right-click and hold down the mouse button on the graph, drag it to the position you wish.



8 Data Exploration

- [Data Reader Tool](#)
- [Use Data Cursor to Show the Difference between the Data](#)

8.1 Data Reader Tool

8.1.1 Summary

The **Data Info** window is used to display the information of selected data points in a graph. Data values, column headers, or images in worksheet cells can be displayed in this window.


Minimum Origin Version Required: Origin 8.5 SR1

8.1.2 What you will learn


This tutorial will demonstrate how to:

- Use the **Data Info** window to view information for a selected data point in the graph.
- Customize the content displayed in the **Data Info** window.

8.1.3 Steps


1. Select **File: Open...** to open the *Alkanes.opj* in the <Origin Folder>\Samples\Data Exploration folder.
2. Highlight Column D in Book1 Sheet1, and select **Plot: Symbol: Scatter** to create a new graph.
3. Click the **Data Reader**  button from the **Tools** toolbar, and click on the isobutane data point on the new graph.

The **Data Info** window showing the X and Y coordinates of the data point selected will appear.




Long ...	Data (...)
X	Isobut...
Y	58.12


- Right-click on the **Data Info** window, and select **Preferences** from the context menu to open the **Data Info Report Settings** dialog.




- Click on the triangle button to the right of **Dialog Theme**, and select **Save to <Graph>** in the fly-out menu. The dialog settings will be saved to the active graph, and the customization will always be used for this graph.




- To remove the book and sheet name from the **Data Info** window select the on the **Title** tab. Select **None** in the **Report Title** drop-down list and click **Apply**.



7. On the **Rows** tab remove the X and Y coordinates in the right panel by highlighting <X> and <Y>, right-clicking and selecting **Delete** in the context menu.




8. Click on the **X Data** and **Y Data** button to add the sources of the X and Y data.
9. All the columns that can be added to the **Data Info** window are listed in the left panel. Highlight the **B, C, E, G, and H** columns and add to the right panel by clicking the right pointing arrow in the center of the dialog.




10. Select the **Columns** tab and right-click on the grey portion. Select **Add Column** to add a third column to the **Data Info** window. For the new column, set the **Type** as **Single Cell**, and select **J "Ball and stick model"** in the **Source** drop-down list. Set the width for the three columns to 15,


20, and 20.




11. On the **Display** tab, set **Minimum Font Size** and **Maximum Font Size** to 10 and 16 respectively. This will set how far the **Data Info** window can be resized.
12. Set the **Font Color** to **Royal**, and the **Background Color** to **White**.




13. Click on the **OK** button to close the dialog. The **Data Info** window will appear as shown below:

Long Name	Data (Reader)	Ball and stick mo...
Name	Isobutane	
Mass	58.12	
CAS number	75-28-5	
Formula	C4H10	
Appearance	Colorless gas	
Melting point	-159.6	
Boiling point	-11.7	

14. Resizing the **Data Info** window will reveal that the font size will not go below 10 or beyond 16.

Long Na...	Data (Reader)	Ball and stick ...
Name	Isobutane	
Mass	58.12	
CAS nu...	75-28-5	
Formula	C4H10	
Appeara...	Colorless gas	
Melting ...	-159.6	
Boiling p...	-11.7	

The lower and upper limit of font size are 10 and 16, when resizing the window.

Long Name	Data (Reader)	Ball and stick model
Name	Isobutane	
Mass	58.12	
CAS number	75-28-5	
Formula	C4H10	
Appearance	Colorless gas	
Melting point	-159.6	
Boiling point	-11.7	

8.2 Use Data Cursor to Show the Difference between the Data

8.2.1 Summary

In Origin, the Cursor tool is used to measure the X and Y distance between two points. You can place cursor objects on the same curve or on different curves, then use the **Data Info** window to display the relative positions of the cursor objects.

Minimum Origin Version Required: Origin 8.5 SR1


8.2.2 What you will learn

This tutorial will show you how to:


- Customize the Data Info window
- Read relative positions of two data points

8.2.3 Steps


1. Start with a new worksheet.
2. Select **File: Import: Multiple ASCII** from the main menu. Go to the folder *\Samples\Spectroscopy\Chromatography*, select *GPC Single Channel Chromatogram 1.dat* and *GPC Single Channel Chromatogram 3.dat*. Click **Add Files**, make sure that **Show Options Dialog** is selected, and click **OK**. This opens the **ImpASC** dialog box. In this dialog, set the **Import Mode** to **Start New Columns**, check the **Append Filename to Column Comment** check box and uncheck the **Include File Path when Appending Filename** check box in the **Re(Naming) Worksheet and Workbook** branch. Click **OK** to import these two files into a worksheet.




3. Highlight all columns and right-click to select **Set As: XY XY** from the context menu. With all columns highlighted, choose **Plot:Line:Line**.




4. Press and hold the **Data Reader** button and select the **Data Cursor** from the list.




5. The **Data Info** window opens.




6. Right-click on the **Data Info** window and select **Preferences...** from the shortcut menu. This opens the **Data Info Report Settings** dialog box.
7. Right-click inside the **Columns** tab and select **Add column** from the context menu. Repeat twice more to add a total of three columns.



8. Specify what info to read in the **Source** drop-down list for the three new added columns as below (note that clicking on a cell reveals a list control).




9. In the Columns tab, set the **Column Width** of these three new columns to 30, 30, and 40, respectively.




10. Click **OK** to close this dialog. The Data Info window will display three new columns.

Long...	Data...	Data (Cursor1)	Data (Cursor2)	Relative (Cursor2 - Cursor1)
X	0			
Y	1.5924			

- Double-click on a data point in the graph to add the first cursor. Select the **Data Cursor** button again and add another cursor to the graph by double-clicking on the desired data point.




Note: After you add all the columns in the **Data Info Report Settings** dialog, you can save the settings as a Theme by clicking the Save Theme button  and selecting **Save as...** from the context menu. This will save your modifications to the Data Info window so that in the future, you will not have to add columns, configure the dialog for cursor readout, etc.

- The Data Info window will be updated with the values of the two points and their relative values.

Long ...	Data (Reader)	Data (Cursor1)	Data (Cursor2)	Relative (Cursor2 - Cursor1)
X	16.65	9.7833	16.65	6.8667
Y	66.4181	66.54	66.4181	-0.1219

13. Right-click the **Data Info** window and select **Copy All** from the shortcut menu, then paste the table into a clean worksheet as shown below.



	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name					
Units					
Comments					
1	[GPCSingleChan]"GPC Single Channel Chromatogram"[1000]				
2	Long Name	Data (Reader)	Data (Cursor1)	Data (Cursor2)	Relative (Cursor2 - Cursor1)
3	X	16.65	9.7833	16.65	6.8667
4	Y	66.4181	66.54	66.4181	-0.1219

9 Importing Data

9.1 ASCII

- [Single ASCII](#)
- [Import Wizard](#)
- [Import Time Data](#)
- [Post Processing with Import Filter](#)

9.1.1 Single ASCII

9.1.1.1 Summary

The **File: Import: Single ASCII** menu allows you to automatically import a single ASCII file where the data columns are delimited orderly and it consists of few header lines (maybe just a short description for the file and then names and units for the columns).


Minimum Origin Version Required: Origin 8.0 SR6

9.1.1.2 What you will learn

This tutorial will show you how to Import ASCII files.

9.1.1.3 Steps


Using Windows Explorer, browse to the *\Samples\Import and Export* subfolder of the Origin program folder (by default installed in the Program Files folder). Open the file *S15-125-03.dat* in Windows Notepad. You can see that this file includes header lines and data lines. For Single ASCII files, Origin can auto detect file header/subheader and extract this information to the worksheet headers, such as *Long Name, Units*, etc.




Note: Header lines are lines of text that are not part of the data and do not share the same delimiter formatting as the data. Subheader lines also are not part of the data, but share the same delimiter formatting and therefore correspond to particular columns of data.

To Import this file

1. Select **File: Import: Single ASCII** from the menu to open the File Import dialog. Browse to the `\Samples\Import and Export` subfolder of the Origin program folder. Highlight the file `S15-125-03.dat`.
2. If you double-click this file or click the **Open** button, Origin will import the file automatically. To view the settings for how Origin will import the file, check the **Show Options Dialog** checkbox at the bottom of the dialog and then click **Open**. This will bring up the `impASC X-Function` dialog.



3. Expand the **Import Options: Header Lines** tree node.



By default, Origin auto detects the subheader, and data will be imported from subheader. In this example, Origin automatically set the first line,


Time Delta Temperature Magnetic Field Position

as the worksheet column Long Name and the second line,

(sec) (K) (Oe) (mm)

as Units.

4. Click **OK** to accept these settings and import data into worksheet.



9.1.2 Import Wizard

9.1.2.1 Summary

The **Import Wizard** allows you to preview your ASCII file. This is especially helpful when you are importing a file with many lines of header, and want to extract variables from both the file name and file headers for use in annotating a graph.


Minimum Origin Version Required: Origin 8.0 SR6


9.1.2.2 What you will learn

This tutorial will show you how to use the **Import Wizard**.

9.1.2.3 Steps


The **Import Wizard** allows you to import complicated ASCII files, extract variables from the import file name and header (for reuse in Origin), specify custom delimiters and date formats, or handle post-processing of your imported data using a custom LabTalk script. Another chief advantage of using the Wizard to import your data files is that you can save your custom settings to a filter that can be used repeatedly to import the same or similarly-structured files.

1. Create a new workbook. Click **File**, point to **Import**, and then click **Import Wizard** to open the *Import Wizard* dialog. Click the browser button  to the right of the **File** box. Browse to the *\Samples\Import and Export* folder and open the file *F1.dat*. Click **Next** to navigate to **File Name Options** page.
2. Make sure the **worksheet with file name** box is checked to rename worksheet by imported file name. Click **Next** to navigate to **Header Lines** page.
3. This page enables you to easily customize the worksheet headers. For example, to specify the worksheet long name, place your cursor on the relevant line in the lower panel, and then click the button next to *Long Names*.




Similarly, specify the *Unit* line and select <None> for *Comments*.

- Click **Next** three times to go to the **Data Columns** page. Select **(XYE)** from the *Column Designations* drop-down menu and click **Apply**.



- Click **Next** twice to go to the **Save Filters** page. To use these settings again, you can save this import procedure as a filter. Select the **Save filter** check box and type a filter name in the **Filter file name** text box (*MyFilter* in this example).



Click **Finish** to import the data.

9.1.3 Import Time Data

9.1.3.1 Summary

Origin interprets *Dates* based upon the Gregorian Calendar, while *Time* is interpreted in *hours:minutes:seconds*. When working with [Date and Time data](#), Origin displays these data in different formats, but internally uses underlying numeric values for calculations and certainly plotting operations. This tutorial shows you how to import custom date/time data.

Minimum Origin Version Required: Origin 8.0 SR3


9.1.3.2 What you will learn

This tutorial covers:

- How to import data using multiple delimiters.
- How to define a custom date/time format
- How to change the display settings for the custom date/time format

9.1.3.3 Steps

1. We will import `\Samples\Import and Export\Custom Date and Time.dat` in this tutorial. Before importing the file, let's look at the data structure first.



We can see that there is a space between *Date* and *Time*, and it uses Tab to separate *Time* from the rest of the data. So we will use multiple delimiters to import this data file.

2. Open the file in **Import Wizard**. Accept the default settings on all pages until you get to the **Data Columns** page. Origin will, by default, use Tab to separate the data into two columns. To divide *Date* and *Time*, check the **Tab** and **Space** checkbox in the **Column Separator** group.

Import Wizard - Data Columns

Column Separator

Delimiter Tab/Space Tab Comma
 Semicolon Space Other

Treat consecutive delimiters as one

Fixed Width

Column Designations

YYY
 Right click column heading to set format and designation for individual column.

Number of columns Custom Date Format <None>
 Text Qualifier <None> Custom Time Format <None>
 Keep target column format Numeric Separator 1,000.00
 Remove leading zeroes from numbers Add Sparklines Yes(if less than 50 columns)
 Force Rows to same size by filling missing value
 Column Width Preview (Click and drag edge of column header to resize columns)


A(Y)(T&N)	B(Y)(Tm)	C(Y)(T&N)
25.01.2004	09:39	85.55
25.01.2004	09:39	85.55
25.01.2004	09:39	85.55
25.01.2004	09:39	85.6
25.01.2004	09:39	85.5
25.01.2004	09:39	85.55
25.01.2004	09:39	85.4
25.01.2004	09:39	85.45
25.01.2004	09:39	85.4
25.01.2004	09:39	85.35
25.01.2004	09:39	85.25
25.01.2004	09:39	85.35
25.01.2004	09:40	85.2
25.01.2004	09:40	85.3
25.01.2004	09:40	85.25

Note in the preview box that the column title is **A(Y)(T&N)**, where **(T&N)** means the data format is *Text & Numeric*. Because the date uses "." to separate day, month and year, Origin by default treats the first column as *Text*. For the second *Time* column, Origin shows the underlying numeric values. To import data correctly, we should change the column properties.

- In the **Custom Date Format** edit box, enter:


```
dd'.'MM'.'yyyy
```

where *dd*, *MM* and *yyyy* mean the days, months, and year respectively. Since the "." is used as a separator, we need to put single quotation marks around it in the format specification. After entering the custom format, press the **Apply** button next to the edit box. Then right-click on the header of the first column in the preview and select *Date* from the context menu:



Then the column title will turn into **A(Y)(D)** which means this is now a *Date* data column.

- Similarly, right-click on the header of the second column and select *Time* to set that column as a time column:




You can see the time data display in long format. We can change the display setting after imported.

5. Click **Finish** button to import data. Then double-click the second column title to open the **Column Properties** dialog, and set the Time display as:

HH:mm:ss.##

The final worksheet data after imported will looks like:



Note: In the case of this particular data file, the first column simply has the exact same date in every row. So at this point you may want to set this first column as Disregard by right-clicking on the column header and selecting *Disregard* from the context menu. Then you can set the 2nd column as type X, and plot the data in the third column against the time data in the 2nd column.

9.1.4 Post Processing with Import Filter

9.1.4.1 Summary




The Import Wizard allows defining a custom filter to import ASCII and simple binary files. The filter can then be reused with similar data files once created. The filter mechanism also allows including LabTalk script lines that will then be run at the end of the import. This capability allows user to add post-processing script code to the filter.

Minimum Origin Version Required: Origin 8.0 SR6

9.1.4.2 What you will learn

- How to add post processing script to existing import wizard filter

9.1.4.3 Steps

1. Start a new workbook by clicking the **New Workbook** button  on the Standard toolbar.
2. Click the **Import Wizard** button  on the Standard toolbar to open the wizard.
3. In the **Data Source** group, click the  button to the right of **File** and navigate to and add the file **Samples\Import and Export\S15-125-03.dat**.
4. A suitable filter for importing this file already exists in the data folder. Click the **Next** button to proceed thru all the pages of the wizard till you get to the **Save Filters** page.

5. On this page, check the **Save Filter** checkbox and select the option of **In the User Files folder**. Then specify the filter name as **fil_01** in the **Filter file name(.OIF extension will be appended)** area.
6. Check the **Specify advanced filter options** checkbox and then click **Next**. This will bring you to the **Advanced Options** page.
7. On this page, copy and paste the following lines in the **Script after Each File Imported** edit box:

```
nlbegin iy:=(1,4) func:=gauss;  
  
nlfitt;  
  
nlend output:=1 autoupdate:=au_auto;
```

8. Click **Finish**. This will save the filter along with these added lines of script, and the file will be imported and the script will run. The workbook will then have three sheets, which will include the custom report sheet and the fitted curve sheet, which are results of Gauss function fit to column 4 of the imported data.
9. Start a new project and open import wizard again and add all three files **S15_125_03.dat**, **S21-235-07**, **S32-014-04** in the file open dialog.
10. Under *Import Filter*, check **List filters applicable to both Data Type and file name** checkbox and select **Select User File Folder:fil_01** from the **Import Filters for current Data Type** drop-down list.
11. Under *Target Window*, select **Start New Books** from the **Import mode** drop-down list then click **Finish**. Your modified filter will be used and after each file is imported, the 4th column will be fit with the Gauss function.

9.2 Tutorial: Importing Data

9.2.1 Summary

Origin provides flexible ways of importing data including simply dragging and dropping data files, using the ASCII import dialog to customize settings, using the Import Wizard for advanced customization and for extracting variables from header lines, and supporting custom file formats for many third-party files. This tutorial will highlight some of these features.

Note: This tutorial requires you to drag-and-drop data files onto Origin, so [please make sure you are not running Origin as administrator](#).


9.2.2 What you will learn

This tutorial will show you how to:

- Import files by drag-and-drop
- Import multiple ASCII files by customizing settings
- Saving settings for future use
- Import Wizard and import filters

9.2.3 Drag and Drop Importing of ASCII Files

1. Start with an empty worksheet. Open Windows Explorer to the **\Samples\Curve Fitting** subfolder of your Origin installation folder. Drag and drop the file **sensor01.dat** from the Windows Explorer window into the empty Origin worksheet.




2. Data comes into the sheet. Now select two files: **sensor02.dat** and **sensor03.dat** and drop into the same worksheet. You will see that the first file replaces the data already in the worksheet, and the others create new workbooks, as the default setting is to create new books for the 2nd file.




The default setting when dragging and dropping is to replace existing data. If you have some other data already in the sheet, you can drop the file onto the gray area outside of any window, or into a graph window, and Origin will create a new book and import the data.


9.2.4 Customizing ASCII Import Dialog Settings and Saving a Theme

ASCII import and custom-file-format import both provide an *options* dialog where a user can customize import settings and then save settings for later use on similar files.


1. Start with a new book and click the **Import Multiple ASCII** button  on standard toolbar.
2. Select the files **sensor01.dat**, **sensor02.dat** from **\Samples\Curve Fitting** and add to lower panel of the file dialog. Click the file name column header in lower panel to sort the files by name. Keep the **Show Options Dialog** box checked and click **OK**. This will open a dialog for import settings.




3. Change import mode to **Start New Sheets**. Expand **(Re)Naming Worksheet and Workbook** node and change settings so that only sheet gets renamed.



4. Click on right arrow button at the top of the dialog and select **Save As**, then give it a name such as **My Multifile Import** and click **OK**. This saves your settings to a theme file on disk.



5. Click **OK** and the 1st file gets imported into the current sheet, and a new sheet is created for the 2nd file. File names are used as sheet names.



- Now start a new book and invoke the menu **File: Recent Imports: impASC: My Multifile Import**. In the file dialog pick the three files: **step01.dat**, **step02.dat**, **step03.dat** from **\Samples\Curve Fitting**. Click the file name column header in lower panel to sort the files by name. Click **OK**. The settings from the theme you saved and selected here are used to perform the importing.

9.2.5 Saving ASCII Import Settings to Worksheet

Custom ASCII import settings can be saved either as a theme file to disk, or can be saved into the worksheet itself.


- Start with new book and invoke **File: Import: Single ASCII** from menu, and select the file **sensor01.dat** from **\Samples\Curve Fitting** subfolder, and keep the **Show Options Dialog** checked and click **OK**.
- In the **Import Options** dialog, select **No** with the **Add Sparklines** drop-down list. Expand **(Re)Naming Worksheet and Workbook** node and change settings so that only sheet gets renamed by file name, not book.
- Click on Top Arrow icon and select **Save to <Sheet>** and click **OK**. Then your custom settings get saved to the sheet and data is imported.
- Select **File: Save Template As** from the main menu. Enter **SensorImport** as the template name. Click **OK** to save the workbook template. This template contains both the import settings and the worksheet properties settings.
- Now we create a new workbook from this template. Click the **Open Template** button on the **Standard** toolbar. Select **SensorImport.otw** under your User Files Folder and then click **Open**. A workbook is created from the template.
- With this book active, drag and drop the file **sensor02.dat**. The data gets imported and only sheet name changes to the new file name. The sparklines were not turned on.




When saving custom settings to a worksheet, it is useful to then save the sheet, along with other desired analysis operations, as an **Analysis Template** for repeat analysis of similar data from multiple files. See the Batch Processing tutorial for details.


9.2.6 Import Wizard and Import Filters

The Import Wizard allows you to step through your data file, customize settings including how to parse header lines to create variables, and then save all of your custom settings as an import filter (.OIF) file for repeat use. The filter file can reside in the data folder, in the **\Filters** sub folder of your **User Files Folder**, or even saved to the worksheet itself for use with **Analysis Templates**. The Wizard is typically useful when the file has header lines that need to be parsed, or the file needs custom settings such as fixed width, or for executing LabTalk script at the end of the import for post processing.

1. Start with a new book. Click on the Import Wizard button  in the Standard toolbar to launch the wizard.
2. Select the file **\Samples\Import and Export\S15-125-03.dat**.
3. Note that the **Import Filter for Current Data Type** drop-down changes to show **Data Folder: VarsFromFileNameAndHeader**, this is a filter already created for this file and shipped with Origin, and is automatically picked up from the same folder as the data file you chose. Then change **Import Mode** to **Replace Existing Data**.



4. Click **Next** and walk through the pages. Notice controls on **Header Lines** pages that allows flexible definition of where the header lines end, where the sub header lines are located, and what gets assigned to long name and units etc.
5. For this file the **Variables Extraction** and **Variables Extraction by Delimiter** page define how to parse the header lines to extract values from them.
6. Click **Next** until you get to the **Save Filters** page. Check the **Save filter** box and change the radio button to **In the Window**. This will save the filter in the active worksheet.




- Now check the **Specify advanced filter options**. It brings you to a last page where script (to run at the end of the import) can be specified. In **Script after Each File Imported** edit box enter:


```
col (DegC) =col (2) -273.15;

col (DegC) [u] $= (\+ (0) C) ;

col (DegC) [1] $=Delta Temperature;
```



- 8.
9. Click **Finish**, the file gets imported and the import filter is now saved in your worksheet. The fifth column is a column added by the script. It is the Delta Temperature data in Degree Celsius.
10. With the worksheet active, click **Import Wizard** button again and pick file **\S21-235-07.dat**. Note that the **Import Filter for Current Data Type** drop-down shows **<use filter in active window>**, so Origin picks up the filter settings that were saved in the worksheet.



11. Click **Finish** and the file gets imported and the script gets executed (the values in column 5 is updated).



You can save the import settings to the worksheet, perform analysis on the imported data, and save the workbook as an **analysis template** for repeat processing of similar data files. See the tutorial on batch processing for more information.

9.3 Import Data from a Database

9.3.1 Summary

Origin allows users to import data from a database through Query Builder or SQL Editor. The former provides graphical dialog to create the SQL query, while the later allows users to use SQL string to quickly build the connection to the database, which thus is more convenient for skilled database users. SQL Editor also allows users to define LabTalk variables in the SQL script. Additionally, files can be saved as .ods/.odq files to quickly import the data. An .ods file will save the connection to the data source, while a .odq will save both the data source and query.

This tutorial will show you how to build the connection to a SQL server and extract desired data from specified tables using SQL Editor. The SQL database we use here is [AdventureWorks database](#). For detailed information of how to attach an AdventureWorks database, please refer to [CodePlex website](#).

Note: Query Builder is not supported in the 64-bit version of Origin.

Minimum Origin Version Required: Origin 8.5.1 SR0

9.3.2 What you will learn

This tutorial will show you how to:


- Import data using the SQL Editor.
- Use LabTalk substitution in the SQL Editor.
- Import data using a saved workbook window.
- Use a save .odq file to quickly re-build the connection.

9.3.3 Steps

Suppose we have already set up a SQL server named *AdventureWorks2008R2* on a server machine *lntilla*.

9.3.3.1 Import data using SQL Editor


1. Start with a new project. Click the **Open SQL Editor** button  to open the **SQL Editor**.




2. Now we are going to create the connection to the *AdventureWorks2008R2* database. Select **File: Edit Connection String...** from menu to open the **Connection String Editor** dialog. Enter the following SQL string and then click **OK** button:


```
Provider=SQLOLEDB.1;Password=microcal;Persist Security Info=TRUE;USER ID=sa;Initial Catalog=AdventureWorks2008R2;DATA SOURCE=lintilla
```

All tables in database *AdventureWorks2008R2* are listed in the left panel. The Connection string is in the Message tab.




Alternatively, you can achieve steps 2 by following:

- Click the **Create a new Data Source** button  to bring up the **Data Link Properties** dialog.
- Select Microsoft OLE DB Provider for SQL Server on the **Provider** tab. Click **Next>>** button.



- On the **Connection** tab that is active, specify the server information, including server name, login user name and password (if needed), and database name. Click **Test Connection** to make sure the connection is successful.



- Click **OK** button to finish configuration and import the table list to the **SQL Editor**.
3. Select **File: Save Connection As...** to save the data source file as MyDataSource.ods.
 4. Now we are going to extract data from 9 tables to construct the employee list. Enter the following SQL scripts in the right panel.

```

SELECT

    e.BusinessEntityID, p.Title, p.FirstName, p.MiddleName, p.LastName,

    p.Suffix, e.JobTitle, pp.PhoneNumber, pnt.Name AS PhoneNumberType,
    ea.EmailAddress,

    p.EmailPromotion, a.AddressLine1, a.AddressLine2, a.City, sp.Name AS


```


```
StateProvinceName,  
  
    a.PostalCode, cr.Name AS CountryRegionName,  
  
    p.AdditionalContactInfo  
  
FROM  
  
    HumanResources.Employee AS e INNER JOIN  
  
    Person.Person AS p ON p.BusinessEntityID = e.BusinessEntityID INNER  
JOIN  
  
    Person.BusinessEntityAddress AS bea ON bea.BusinessEntityID =  
e.BusinessEntityID INNER JOIN  
  
    Person.Address AS a ON a.AddressID = bea.AddressID INNER JOIN  
  
    Person.StateProvince AS sp ON sp.StateProvinceID = a.StateProvinceID  
INNER JOIN  
  
    Person.CountryRegion AS cr ON cr.CountryRegionCode =  
sp.CountryRegionCode LEFT OUTER JOIN  
  
    Person.PersonPhone AS pp ON pp.BusinessEntityID = p.BusinessEntityID  
LEFT OUTER JOIN  
  
    Person.PhoneNumberType AS pnt ON pp.PhoneNumberTypeID =  
pnt.PhoneNumberTypeID LEFT OUTER JOIN  
  
    Person.EmailAddress AS ea ON p.BusinessEntityID = ea.BusinessEntityID
```

Notes: Double click on the item to enter its name.

Alternatively, you can use Query Builder to build the SQL scripts in steps 4. That is,

Note: Query Builder is only available for Origin 32-bit. If you only have Origin 64-bit installed on your machine, you should use **SQL Editor** to build the SQL scripts in steps 4.

- Click the **Create new SQL statements using graphical Query Builder tool** button  to open the **Query Builder** dialog. All tables in *AdventureWorks2008R2* are listed in the right panel.




- Drag and drop the following 9 tables to the Main panel:

HumanResources.Employee
Person.Person
Person.BusinessEntityAddress
Person.StateProvince
Person.Address
Person.CountryRegion
Person.PersonPhone
Person.PhoneNumberType

Person.EmailAddress

- Drag main key **BusinessEntityID** from table *HumanResources.Employee* and drop it to that key in table *Person.BusinessEntityAddress* to join these two table. A join line will connect between them.




- Select the following columns from corresponding tables to add them to the lower panel.

Table	Column
HumanResources.Employee	<ul style="list-style-type: none"> ○ BusinessEntityID ○ JobTitle
Person.Person	<ul style="list-style-type: none"> ○ Title ○ FirstName ○ MiddleName ○ LastName ○ Suffix ○ EmailPromotion ○ AdditionalContactInfo

Person.Address	<ul style="list-style-type: none"> ○ AddressLine1 ○ AddressLine2 ○ City ○ PostalCode
Person.StateProvince	<ul style="list-style-type: none"> ○ Name
Person.CountryRegion	<ul style="list-style-type: none"> ○ Name
Person.PersonPhone	<ul style="list-style-type: none"> ○ PhoneNumber
Person.PhoneNumberType	<ul style="list-style-type: none"> ○ Name
Person.EmailAddress	<ul style="list-style-type: none"> ○ EmailAddress



In the lower panel, drag and drop the first cell of a row to re-arrange column order as desired.




- Select Ascending from Sort Type drop-down list in the first row *HumanResources.Employee* to sort the whole worksheet according to this column ascendingly.

Output	Expression	Aggregate	Alias	Sort Type	Sort Order	Grouping	Criteria
<input checked="" type="checkbox"/>	HumanResources.En		e	Ascending	1	<input type="checkbox"/>	
<input checked="" type="checkbox"/>	HumanResources.En		e			<input type="checkbox"/>	
<input checked="" type="checkbox"/>	Person.Person.Title		p			<input type="checkbox"/>	
<input checked="" type="checkbox"/>	Person.Person.Firstn		p			<input type="checkbox"/>	
<input checked="" type="checkbox"/>	Person.Person.Middl		p			<input type="checkbox"/>	
<input checked="" type="checkbox"/>	Person.Person.Lastn		p			<input type="checkbox"/>	

- Click the **OK** button to generate the SQL scripts and return to SQL Editor.



5. Click the **Preview the result data** button  to preview the data. If the preview is fine, click the **Import data to worksheet** button  to import these data. Once imported, the worksheet is connected to the database, and a yellow icon will appear at the top-left of the worksheet.



	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	BusinessEntityID	Title	FirstName	MiddleName	LastName
Units					
Comments					
F(x)					
1	1	Ken	J	Sánchez	
2	2	Terri	Lee	Duffy	
3	3	Roberto		Tamburello	
4	4	Rob		Walters	
5	5	Ms. Gail	A	Erickson	
6	6	Mr. Jossef	H	Goldberg	
7	7	Dylan	A	Miller	
8	8	Diane	L	Margheim	
9	9	Gigi	N	Matthew	
10	10	Michael		Raheem	
11	11	Ovidiu	V	Cracium	

6. Select **File: Save Connection and Query As...** from menu to save the connection and query as a ODQ file MyQuery.odq. Close the **SQL Editor**.



9.3.3.2 Import data using the saved workbook window

1. Activate the workbook (Book1). Select from menu item **Worksheet: Clear Worksheet** and click **OK** for the warning message to proceed.
2. Keep Book1 active and select **File: Save Window As...** from menu and save the workbook as MyData.ogw. The database information will be saved along with this .ogw file.
3. Click the **New Project** button  on the **Standard** toolbar to start a new Origin project. Open the saved window file MyData.ogw by **File: Open**.
4. Click the **Import data** button  to import the data into the worksheet from the database.

9.3.3.3 LabTalk Support in SQL Editor


This section will show you how to extract employee list of only Washington State by using a pre-defined Labtalk variable. We will also re-use the .ods and .odq file saved in the previous section.

Tutorials for Origin

1. Start with a new project. Click the **Open SQL Editor** button  to open the **SQL Editor**.
2. Click the **Open file**  button to open the previously saved file **MyQuery.odq**. Tables of *AdventureWorks2008R2* are listed in the left panel and the SQL scripts on the right.

Now we are going to add a condition to only import those in Washington State. A LabTalk variable **strCond** is defined to represent the Washington State.


3. Select **Query: LabTalk...** to open the **LabTalk Support Setting** dialog.



4. Check the box to enable LabTalk substitution.
5. Type the script



```
string strCond$ = "Washington";
```


6. in the **Before Query Script** box. Click **OK**.




7. Type

```
WHERE sp.name = '%(strCond$)'
```

8. to the end of the SQL scripts. Click the  button to preview the query string in the SQL Editor box. Click the **Preview the result data**  button.



9. Click the **Import data to worksheet** button  to import these data. Compare to the worksheet we got in the first section, only employees in Washington State are imported this time.

9.4 Import Data from a Database for Analysis

9.4.1 Summary

This tutorial shows how to import data from database into Origin worksheet by using SQL Editor. And then perform some operations on the data, such as filter, statistics, etc., so to get the desired results for the graphing.

The SQL database we use here is [AdventureWorks database](#). For detailed information of how to attach an AdventureWorks database, please refer to [CodePlex website](#).

Minimum Origin Version Required: Origin 9.0 SR0

9.4.2 What you will learn

This tutorial will show you how to:

- Import data using SQL Editor.
- Apply data filter to the worksheet data.
- Perform descriptive statistics on columns.
- Make graphs such as column plot, etc.

9.4.3 Steps

Suppose we have already set up a database named *AdventureWorks2008R2* on a server machine - *myServer* - running SQL Server, with user name as "accounting", and password as "mydatabase".


9.4.3.1 Import Data from Database

1. To connect the database, we use a connection string:


```
Provider=SQLOLEDB.1;Password=mydatabase;Persist Security Info=True;


User ID=accounting;Initial Catalog=AdventureWorks2008R2;Data
Source=myServer
```


2. Activate an empty worksheet and open SQL Editor by clicking the **Open SQL Editor** button on the **Database Access** toolbar.





3. Select menu item **Edit Connection String...** from SQL Editor's **File** menu, in the open dialog, put the connection string (see step 1 above) to the text box. And then you can click the **Test** button to test if the connection is fine. If fine, click the **OK** button to connection to the database.




4. From the top left panel, find the table *Production.Product*, and then double click it to add it to the top right panel. Then you can click the **Preview the result data** button  to view the data in the bottom panel.



- Click the **Import data to worksheet** button  to import the data in the table to the active worksheet.




6. Click the minimum button on the title bar of **SQL Editor** dialog to make it shrink, and then right click on the worksheet tab and add a new worksheet from the context menu by item **Add**.



7. Click the minimum button of **SQL Editor** dialog again to expand the dialog. And select menu item **Query: LabTalk...** to open the **LabTalk Support Settings** dialog. Check the **Enable LabTalk (%,\$) Substitution** checkbox, and put the following script to the text box.

```
string strDateBegin1$ = "1/1/2006";
string strDateEnd1$ = "12/31/2006";
string strDateBegin2$ = "1/1/2007";
string strDateEnd2$ = "12/31/2007";
```

8. The dialog will look like this.



9.

10. Click **OK** to go back SQL Editor. Then put the following SQL script to the top right panel to replace existing content *Production.Product*. This script is going to query three columns from the database, one is the product's category name, other twos are line total for each category on year 2006 and 2007 respectively.

```

select TABLE2006.Name, TABLE2006.LineTotalFor2006,
TABLE2007.LineTotalFor2007

from

    (select Production.ProductCategory.Name,
LINE2OALANDNAME2006.LineTotalFor2006

    from

        (select sum(SALEANDPRODUCT2006.LineTotal) as
LineTotalFor2006, Production.ProductSubcategory.ProductCategoryID

        from

            (select SALEINFO2006.LineTotal,
PRODUCTINFO2006.ProductSubcategoryID

            from

                (select Sales.SalesOrderHeader.OrderDate,

```

```

Sales.SalesOrderDetail.LineTotal, Sales.SalesOrderDetail.ProductID

        from Sales.SalesOrderHeader

        inner join Sales.SalesOrderDetail

        on
Sales.SalesOrderHeader.SalesOrderID=Sales.SalesOrderDetail.SalesOrderID

        where Sales.SalesOrderHeader.OrderDate
between '%(strDateBegin1$)' and '%(strDateEnd1$)' as SALEINFO2006

        inner join

        (select Production.Product.ProductID,
Production.Product.ProductSubcategoryID

        from Production.Product) as

PRODUCTINFO2006

        on
SALEINFO2006.ProductID=PRODUCTINFO2006.ProductID) as SALEANDPRODUCT2006

        inner join Production.ProductSubcategory

        on
SALEANDPRODUCT2006.ProductSubcategoryID=Production.ProductSubcategory.Prod
uctSubcategoryID

        group by Production.ProductSubcategory.ProductCategoryID)
as LINETOALANDNAME2006

        inner join Production.ProductCategory

        on
LINETOALANDNAME2006.ProductCategoryID=Production.ProductCategory.ProductCa
tegoryID) as TABLE2006

inner join

        (select Production.ProductCategory.Name,

```

Tutorials for Origin

```
LINETOTALANDNAME2007.LineTotalFor2007

    from

        (select sum(SALEANDPRODUCT2007.LineTotal) as
LineTotalFor2007, Production.ProductSubcategory.ProductCategoryID

    from

        (select SALEINFO2007.LineTotal,
PRODUCTINFO2007.ProductSubcategoryID

    from

        (select Sales.SalesOrderHeader.OrderDate,
Sales.SalesOrderDetail.LineTotal, Sales.SalesOrderDetail.ProductID

    from Sales.SalesOrderHeader

    inner join Sales.SalesOrderDetail

    on

Sales.SalesOrderHeader.SalesOrderID=Sales.SalesOrderDetail.SalesOrderID

    where Sales.SalesOrderHeader.OrderDate
between '%(strDateBegin2$)' and '%(strDateEnd2$)' ) as SALEINFO2007

    inner join

        (select Production.Product.ProductID,
Production.Product.ProductSubcategoryID

    from Production.Product) as
PRODUCTINFO2007

    on

SALEINFO2007.ProductID=PRODUCTINFO2007.ProductID) as SALEANDPRODUCT2007

    inner join Production.ProductSubcategory

    on
```

```

SALEANDPRODUCT2007.ProductSubcategoryID=Production.ProductSubcategory.Prod
uctSubcategoryID



        group by Production.ProductSubcategory.ProductCategoryID)
as LINETOALANDNAME2007


        inner join Production.ProductCategory

        on

LINETOALANDNAME2007.ProductCategoryID=Production.ProductCategory.ProductCa
tegorID) as TABLE2007

on TABLE2006.Name=TABLE2007.Name
    
```

11. Click **Preview the result data** button  and you can see that the four defined LabTalk variables are used in the SQL script. You can click the last button  on the toolbar to view the result after substitution.



The screenshot shows the SQL Editor interface. The query editor contains the following SQL code:

```

erDate, Sales.SalesOrderDetail.LineTotal, Sales.SalesOrde
erID=Sales.SalesOrderDetail.SalesOrderID
Date between '1/1/2006' and '12/31/2006') as SALEINFO2006
ID, Production.Product.ProductSubcategoryID
INFO2006
.ProductID) as SALEANDPRODUCT2006
    
```

The toolbar includes a 'Preview' button (highlighted with a pink box) and a 'Substitution' button. The 'Preview' window shows the following data:

No.	Name	LineTotalFor2006	LineTotalFor2007
1	Clothing	485587.15284	1.01198E6
2	Bikes	2.64864E7	3.49233E7
3	Accessories	92735.35171	590257.58519
4	Components	3.61009E6	5.48551E6

12.


13. Click the **Import data to worksheet** button  to import the queried data into the newly created worksheet.

	A(X)	B(Y)	C(Y)
Long Name	Name	LineTotalFor2006	LineTotalFor2007
Units			
Comments			
F(x)			
1	Clothing	485587.15284	1.01198E6
2	Bikes	2.64864E7	3.49233E7
3	Accessories	92735.35171	590257.58519
4	Components	3.61009E6	5.48551E6
5			
6			
7			
8			
9			
10			
11			


14. Close SQL Editor with saving and finish the data import.

9.4.3.2 Data Filter and Statistics


1. Go to the first worksheet with the imported data from Production.Product in the above section.
2. Select column I (long name is StandardCost), and then add a data filter to this column by clicking the **Add/Remove data filter** button on the **Worksheet Data** toolbar.




3. Then there will be a filter icon on the top left corner of the column header. Click on it, and then select **Greater Than...** from the context menu.




- There will be a dialog open, just keep the default **Value** to be 0 and click **OK** button.




- Do the same as step 2 on column P (long name is ProductLine), so to add a filter to this column.
- Click on the filter icon, and then uncheck (**Blank or Missing Values**) checkbox from the context menu.



7. Select column I and J (StandardCost and ListPrice), then select menu **Statistics: Descriptive Statistics: Statistics on Columns** to open the **Statistics on Columns** dialog.
8. In the open dialog, set **Grouping Range** to be column P. You can just click the triangle button to select column P from list on the right. And in the **Plots** tab, check **Box Charts** checkbox.




9. Click **OK** button to get the results.




9.4.3.3 Radar Plot


1. Go to the second worksheet with the imported data from database in [Import Data from Database](#) subsection.
2. Highlight all three columns, and then select menu **Plot: Specialized: Radar** to make a radar plot.




3. Double click on the *Clothing* axis to open the **Axis Dialog** with **Scale** selected on the left panel. Clear the **Use Same Options for All Axes** checkbox at top left corner and then click the **Select Others** button in the top right corner and select "Select Similar in All Axes". Then set **From** to 0, and choose **By # of Majors** for **Major Ticks** with value of 6.



4. From the left panel, select **Tick Labels** for **Axis1 - Clothing**, and then click the **Select Others** button in the top right corner and select "Select Similar in All Axes". Then set **Show Tick Labels** to *Before Axis*, **Display** to *Decimal: 1000*, and **Divide by Factor** to 1000000.



5. From the left panel, select **Scale** for **Axis1 - Clothing**, and then change **To** value to 1.5 in the right panel. Repeat this operation for **Axis3 - Accessories** and **Axis4 - Components**, with values of 0.7 and 6 respectively.
6. Click **OK** button.



We can see that, for all four categories, line totals for 2007 is bigger than that for 2006. And Bikes is the biggest.

9.5 Importing Multiple Files into Workbooks Cloned from Active Workbook

9.5.1 Summary

Origin provides a quick yet powerful way to clone current workbook/sheet when importing data, so that each new data will be imported to workbook/worksheet with same customization and analysis. This feature is implemented for most of Origin's supported import file types, e.g., ASCII, CSV, Excel, etc. This tutorial will highlight this feature with commonly used ASCII files.

9.5.2 What you will learn


This tutorial will show you how to:


- Create a Prototype Workbook
- Import Multiple Files into the Cloned Workbook

9.5.3 Import Multiple ASCII Files into Cloned Workbooks

Create a Prototype Workbook


In this example we will import a file and do a linear fitting with it.


1. Start a new project. Click the **Import Single ASCII** button  on standard toolbar.
2. Browse to **Origin Installation Path\Samples\Curve Fitting** folder to select *Sensor01.dat*.
3. Check **Show Options Dialog** checkbox and click **Open** button.
4. Under **Import Options** -> **(Re)Naming Worksheet and Workbook** node, uncheck **Rename Sheet with (Partial) Filename** checkbox.
5. Click **OK** button to finish import. You can see after import, Sheet name is still **Sheet1**.
6. Highlight column **B** (*Sensor Output*) and choose **Plot: Symbol: Scatter** to plot a scatter graph.
7. Double click on X axis to open the Axis dialog. Activate **Scale** tab. Choose both **Horizontal** and **Vertical** on left panel and set **Rescale** as **Auto**. Click **OK**.
8. Choose **Analysis: Fitting: Linear Fit** menu to open **Linear Fit** dialog. Select **Recalculate** mode as **Auto**, click **OK** button to perform the fit. Select **No** radio box and click **OK** button in appeared prompt.
9. Right click in gray area on **Sheet** worksheet and choose **Add Graph...** context menu. Choose **Graph1** and click **OK**. Scatter plot with linear fit curve will show as a floating graph on **Sheet1**.




Import Multiple Files into the Cloned Workbook

Now we want to import more Sensor data and do the same linear fit.

1. Make sure **Sheet1** sheet is active and click the **Import Multiple ASCII** button  on standard toolbar.
2. Select the files *Sensor02.dat*, *Sensor03.dat* from **\Samples\Curve Fitting** and add to lower panel of the file dialog. Keep the **Show Options Dialog:<sheet>** box checked and click **OK**. This will open a dialog for import settings.
3. Expand **Import Options** node and select **Import Mode** as **Start New Books**. To clone current workbook, select **<clone>** from **Template Name** drop-down list.



4. Click **OK** button to import multiple files. Each data file is stored in a new workbook with same analysis done as in prototype workbook.



9.6 SQL Editor for Database Analysis

9.6.1 Summary

Origin supports importing data from many popular databases using ADO or ODBC. This tutorial illustrates how to use the SQL editor to setup a database connection in an Origin worksheet. Once this connection is made, with the proper SQL query you can bring in new data by simply pressing a button. Additionally, data filter and recalculation features allow you to set up an Analysis template which will automatically refresh a report to reflect new data re-imported from the external database.

The SQL database we use here is [AdventureWorks database](#). For detailed information of how to attach an AdventureWorks database, please refer to [CodePlex website](#).

Minimum Origin Version Required: Origin 9.0 SR0

9.6.2 What you will learn

This tutorial will show you how to:

- Connect to a database and import data using a query in SQL Editor
- Use the Pivot Table feature to rearrange the data so a column graph can be made to show Total Sales by Product Types for a specific year

- Insert the graph into the worksheet as a floating graph so the workbook is a self-contained unit that includes the database connection, the data, and the graph. This workbook can then be saved as an Analysis Template
- Change the query and re-import the data into the saved Analysis Template so the report updates automatically

9.6.3 Steps

Set up a database named *AdventureWorks2008R2* on a server machine. Use your own information for the following fields:


SQL Server: *myServer*

User name: *myUsername*

Password: *myPassword*

9.6.3.1 Import Data from Database


1. Activate an empty worksheet and open SQL Editor by clicking the **Open SQL Editor** button on the **Database Access** toolbar.



2. Connect to a database by selecting menu item **Edit Connection String...** from SQL Editor's **File** menu. Paste the following connection string in the text box:

```
Provider=SQLOLEDB.1;Password=myPassword;Persist Security Info=True;User  
ID=myUsername;Initial Catalog=AdventureWorks2008;Data Source=myServerName
```

3. Click the **Test** button to test if the connection is working. If it is, click the **OK** button to connect to the database.



4. Copy and paste the following query into the SQL Editor text box. The query shows data for the year 2003:

```
SELECT CR.Name As CustomerCountry,
       Pr.Name As ProductName,
       Pr.Color As ProductColor,
       PC.Name As ProductCategory,
       PS.Name As ProductSubcategory,
       SOH.OrderDate As OrderDate,
       SOD.OrderQty As OrderAmount,
       SOD.LineTotal As TotalCost
FROM Person.CountryRegion AS CR
INNER JOIN Person.StateProvince AS SP
ON SP.CountryRegionCode = CR.CountryRegionCode
INNER JOIN Person.Address AS A
```

Tutorials for Origin

```
ON A.StateProvinceID = SP.StateProvinceID

INNER JOIN Person.BusinessEntityAddress AS BEA

ON BEA.AddressID = A.AddressID

INNER JOIN Person.Person AS P

ON P.BusinessEntityID = BEA.BusinessEntityID

INNER JOIN Sales.PersonCreditCard AS PCC

ON PCC.BusinessEntityID = P.BusinessEntityID

INNER JOIN Sales.SalesOrderHeader AS SOH

ON SOH.CreditCardID = PCC.CreditCardID

INNER JOIN Sales.SalesOrderDetail AS SOD

ON SOD.SalesOrderID = SOH.SalesOrderID

INNER JOIN Production.Product AS Pr

ON Pr.ProductID = SOD.ProductID

INNER JOIN Production.ProductSubcategory AS PS


ON PS.ProductSubcategoryID = Pr.ProductSubcategoryID

INNER JOIN Production.ProductCategory AS PC


ON PC.ProductCategoryID = PS.ProductCategoryID

WHERE SOH.OrderDate BETWEEN '1/1/2003' AND '12/31/2003'
```

5. Click the preview button to view the data the query produced in the bottom panel.




- Save the query to the active worksheet by selecting **File: Save to Active Worksheet**. Now this query will remain intact with this specific worksheet. Close the SQL Editor.
- The icon on the top left of the workbook indicates the sheet contains an SQL query and you can use the import tool button to bring in data from a database.




9.6.3.2 Data Filter and Statistics

1. Origin has a data filter feature similar to Excel. We can use this feature to choose specific data for graphing and analysis without removing the rest of the data.
2. Select *column E* (Long Name: Product Subcategory). In order to choose just the bike data for analysis, add a data filter to this column by clicking the **Add/Remove data filter** button on the **Worksheet Data** toolbar.




3. A filter icon will appear on the top left corner of the column header. Click on it, and from the list that appears select all the Bike categories: *Mountain Bikes*, *Road Bikes* and *Touring Bikes*.




4. If a reminder message about hidden data appears, select the **Yes** radio button and click **OK**.
5. The sheet will now show data for just the *Bikes*. The rest of the data is hidden and removing the filter will show it again.
6. In order to create a Column Plot, the data needs to be rearranged using the Origin Pivot Table feature. Go to **Worksheet: Pivot Table: Open Dialog...**
7. In the dialog that opens set the **Row Source** as *Customer Country*.
8. Set the **Column Source** as *Product Subcategory* (the column with the filter on it).
9. In order to see the Total Sales for the year, set the **Summarize by** option as **Sum** , and set the **Pivot Table Data Source** option that appears as *Total Cost*.




10. Click **OK** and Origin will place the manipulated data into a new sheet named *Pivot1* in the same workbook as the sheet containing the original data.
11. Click on the green lock located on the top right of the first column and set the **Recalculate Mode: Auto** in the context menu. This will make the pivot table manipulation update if the data is re-imported from the SQL Editor.




12. Now highlight the pivoted data and click on the **Column Plot** button to create a column plot.




9.6.3.3 Customize Graph and Create Analysis Template

1. Double click the Y axis title and set it as **Total Sales (\$)**
2. Make sure the graph is set to recalculate automatically; the green lock on the top left of the graph should have a triangle on it:  If not click on it and set recalculate as auto as was done for the pivot table analysis in Step 10 of the last section.
3. Double click on the Y Axis to open the **Axis** dialog.
4. On the Y axis **Scale** page, set the **Rescale** dropdown to **Auto**. Click OK.




5. Right click on the graph and select **Add/Modify Layer Title** from the context menu. Set the Title as **Bike Sales by Year**. If needed, a year title can be added this way as well.
6. Add the graph to the worksheet with the original data by right clicking gray area in worksheet and from the context menu selecting **Add graph**.
7. In the **Graph Browser** dialog, select the graph and click **OK**. Resize and move as needed.
8. Now that the customization is complete, save the workbook as an Analysis Template. Go to **File: Save Workbook as Analysis Template...** or right click on the .worksheet title bar and select **Save as Analysis Template...** as shown below.




9. Name the template and then **Save**.


9.6.3.4 Change Query and Re-import Data to Automatically Update Analysis

1. Go to **File: Recent Books** and select the analysis template name you just saved from the context menu. This will open a blank analysis template.




2. Click on the SQL Editor button to open the SQL Editor. Since the query was saved with the worksheet it is intact. Change it to show data for the year 2004 and then exit out of the Editor.



3. Re-import the data using the SQL Import button used in Step 7 of of the first section and reapply the filter with the **Reapply data filter** :  button.
4. Close the SQL Editor

5. All the data will update. The graph now shows the Bike Sales for the year 2004, and the year title has changed to reflect this.
6. Your project now has two books; *Book1* has the data for the year 2003, *Book2* has the data for the year 2004.



You can use this template and the SQL re-import feature to find the Bike sales for as many years as needed without creating a new query, graph or having to redo the analysis and customization.

9.7 Digitizer

- [Digitizer Tool](#)
- [Enhanced Digitizer](#)

9.7.1 Digitizer Tool

9.7.1.1 Summary

The Digitizer helps you to capture data from images of graphs. You can import image files of graphs into Origin and digitize data points one by one.


9.7.1.2 What you will learn


- How to capture data from images of graphs using the Digitizer Tool.
- How to modify the position of the picked points



- How to delete the extra points


9.7.1.3 Steps


Capture data points


1. Select **Tools: Digitizer...** from the main menu to open the **Digitizer** dialog.
2. Click the **Import**  button on the dialog box toolbar, and select the *Digitizer_image.png* under <Origin EXE folder>\Samples\Import and Export\ path. The image is imported. Note that there are two pairs of XY axes showing in the image; one red and one blue.




3. Click on the **Rotate Image**  button (dialog box toolbar), and click the button  to slightly rotate the image in the counter-clockwise direction. Note that the rotation increment can be specified in << >> **Increment (degree)** the text box.






When the graph axes in the image are aligned along the bottom/top and left/right edges, click once more on the **Rotate Image**  button, to leave Rotation mode.




- Click on the **Edit Axes**  button in the dialog. Using your mouse, drag the two pairs of axis lines so that they coincide with minimum and maximum axis values. Note that when a line is selected, its corresponding row in the Digitizer dialog is also selected. Enter the appropriate


coordinate value (0, 8, -20, 120) in the **Axis Value** column.





5. After locating the axes, click the **Pick New Points**  button. Move the cursor  sequentially over the points in the phosphorus plot (filled symbol), double-clicking on each point (or single-click and press *Enter*). The **GetPoints** dialog displays coordinate values, while the Data Display window shows image pixel values.






6. When you have added all points for the phosphorus plot, click the **Done** button.




7. Click on the **Go to Data**  button to show the resulting worksheet which contains the values of picked data points.





	A(X)	B(Y)	C(L)
Long Name		PickedY1	
Units			
Comments			
Scale Type	Linear Scale	Linear Scale	
1	0.99155	7.02021	
2	1.98773	7.02021	
3	2.98391	5.71946	
4	4.00983	7.67059	
5	4.97256	10.2721	
6	5.99847	1.7359	
7	6.99465	4.33741	
8			
9			
10			
11			


8. Click on the **Go to Image**  button to return to the original image. Click on the **Start New Data**  button to start digitizing the second plot (potassium = open symbol). Note that two new columns of data points are created in the result worksheet.
9. Click on the **Pick New Points**  button to get the points for the second plot, repeating the procedures followed in steps 5 and 6.

10. Click on the **Go to Data**  button and two datasets result shows in the worksheet.



	A(X1)	B(Y1)	C(L1)	D(X2)	E(Y2)	F(L2)
Long Name		PickedY1			PickedY2	
Units						
Comments						
Scale Type	Linear Scale	Linear Scale		Linear Scale	Linear Scale	
1	0.99155	7.02021		0.99155	38.07572	
2	1.98773	7.02021		1.98773	12.30452	
3	2.98391	5.71946		2.98391	21.5724	
4	4.00983	7.67059		3.98009	85.55324	
5	4.97256	10.2721		4.97256	43.36003	
6	5.99847	1.7359		5.99847	48.56305	
7	6.99465	4.33741		6.96491	96.77225	
8						
9						
10						
11						


11. Click on the **Go to Image**  button. This takes you to your imported image file. Click on the **Go to Graph**  button and note that this opens a graph window containing plots of your digitized data points.




12. When you close the **Digitizer** dialog, a Digitizer... **Digitizer...** button appears on the image. Clicking on the button, you can reopen the **Digitizer** dialog.

Move and delete the picked points

Following the steps in the above section, you will easy to get the points from the image. But if the picked points are on the incorrect position or extra, as point **A** and **B** in the below image, you can modify or delete them.



1. To modify the position of point **A**, click on it and move the cursor to the correct position. Or you can use **Arrow** keys to move the selected point.



2. To delete the point **B**, click to select it and right-click to choose **Delete** in the context menu. Or you can press **Delete** key to delete the selected point.

9.7.2 Enhanced Digitizer

9.7.2.1 Summary

The Enhanced Digitizer supports auto tracing and digitizing in 2D Cartesian, polar and ternary coordinate systems.

NOTE: The Enhanced Digitizer is built into Origin 2015 SR0 and later versions. If you are running Origin 9.1, the Enhanced Digitizer is available as an add-on tool from [the OriginLab File Exchange](#). The Enhanced Digitizer is not supported by versions prior to Origin 9.1 SR1.


9.7.2.2 What You Will Learn


This tutorial will show you how to:

- Set axes in the image.
- Manually and automatically capture data points.
- Set axes for polar and ternary coordinate systems.


9.7.2.3 Steps

Import Image and Clear Gridlines

1. Select the **Digitize Image**  button on the **Standard** toolbar.
2. Browse to the folder *<Origin EXE Folder>\Samples\Import and Export* and open **TwoPeaks.bmp**.
There are three line plots in the image: the black plot is the baseline and the red and blue plots are spectra.




3. In the Digitizer dialog, there are hints at the bottom of the Axes tab to guide you through each step.





4. Select **Image:Remove Cartesian Gridlines** to remove the gridlines.
 You can also choose **Image: Rotate...** and **Image: Clear Background** menus to rotate the image and clear background noise and color fills.


Edit Axes

Before capturing data points, you need to setup axes on the image so that there is a reference for calculating the XY coordinates of the data points that will be captured later.


1. Click the **Edit Axes**  button or make sure it is pressed.
2. Four lines will appear framing the image. Drag each line so that it lines up at a location where you know the axis values and enter the axis value in the corresponding row in the Digitizer dialog.

Use the Zoom and Pan  button on the **Tools** toolbar or hold down **A** and use the mouse wheel to zoom in and pan the image. Then fine tune the line location. Press **Ctrl+W** to restore the original image size.









- After editing Axes, you can right click and save Axes settings in order to load them in the future for similar images.



Capture Data Points

Besides the **Manually Pick Data Points** method, the Enhanced Digitizer provides four automatic digitizing methods to capture data points. They are all under the **Digitize** menu and have corresponding buttons.


Name	Icon	Function
Manually Pick Points		Double click on every spot you want to capture a point.

Auto Trace Line By Points		Double click on a curve on the image and data points will automatically be captured along the curve.
Auto Pick Points By Grids		Drag a rectangle on a desired area of the image and data points will be captured where ever the gridlines in rectangle intersect with the image curve.
Area Auto Trace		This is a hybrid of the previous two methods. Drag a rectangle on a desired area of the image. Data points will automatically be captured along the curve.
Boundary- Limited Area Auto Trace		Similar to the Auto Trace Area button except that points are created only within the selected area.


Manually Pick Points

Let's manually capture some points on the red line.


1. Click the **Manually Pick Points** button.



2. Double click on the red curve to pick a point.
The **Magnifier** window on the **Data** tab of the Digitizer dialog provides a blown up view of where the cursor is. You can also use the Zoom and Pan tool mentioned in the Edit Axes section to zoom and pan the image to pick points more precisely.
3. Pick several more points and click the **Done** button. The **Number of Points** on Line 1 of the **Data** tab shows the number of points that were captured for Line 1.



If you want to move or delete a captured point, click the captured point in the image to select it. Use the arrow keys on the keyboard to move the point or press the **Delete** key to delete it.




You can click the **Manually Pick Points** button again to pick more points for line 1.

Auto Trace Line by Points

Multiple digitizing methods can be used on same line as long as the line is highlighted on the **Data** tab of the Digitizer dialog. Let's pick more red points for Line 1 using the **Auto Trace Line by Points** method.

1. Click the **Auto Trace Line by Points** button.

- Double-click on red points to the left side of the peak and the right side of the peak. Every time you double click a point, Origin auto traces to find more points along the curve. Click the **Done** button.



- There are in total 122 points captured on the red line.

Line	Number of Points	Pixel Reduction Factor
1	122	<auto>

- Click the **Go to Data**  button to see the results in a worksheet.

DigiData			
	A(X1)	B(Y1)	C(L1)
Long Name		PickedData	
Units			
Comments			
F(x)			
Scale Type	Linear Scale	Linear Scale	
1	14.37284	0.30375	
2	15.56915	0.32705	
3	16.93636	0.35035	
4	17.44906	0.39695	
5	17.96176	0.44937	
6	18.13266	0.50762	
7	18.47446	0.56587	
8	18.64536	0.62412	
9	18.81627	0.68237	
10	19.15807	0.74062	

Auto Pick Points by Grids

Next let's use the **Auto Pick by Grids** method to digitize the black baseline.

1. Activate the image window.


2. Click the **New Line**  button. The **Data** tab will start a new row for Line 2.

Note: All plots in this image use the same XY axis so we don't need to edit the axes again.


However, in case you have images with multiple axes, you can setup a new axis for each new line of data.


3. Select the **Auto Pick Points by Grids** button.


4. Click and drag to create a rectangle on a portion of the black baseline as shown below:



Some points on the red and blue lines are captured as well.





5. To remove unwanted points, click the **Delete Points**  button.
6. Drag a rectangle box over the unwanted points and release the mouse button to delete them.



With this method, only 57 points are captured.



Axes Data		
Line	Number of Points	Pixel Reduction Factor
1	122	<auto>
2	57	<auto>


- If you are not satisfied with the result, click the **Delete Line**  button to delete Line 2 on the Data tab of the Digitizer dialog and click the **New Line**  button to start over.

You can use the **Settings: Digitize Settings...** menu to customize the grids density.

Area Auto Trace/Boundary-Limited Area Auto Trace

Let's use these two methods to digitize the blue line.


- Click the **New Line**  button.
- Click the **Area Auto Trace**  button.
- Click and drag a rectangle over some part of the blue curve. Points will be auto created along the blue curve beyond the rectangle.






Line	Number of Points	Pixel Reduction Factor
1	122	<auto>
2	57	<auto>
3	61	<auto>

- Select the **Boundary-Limited Area Auto Trace**  button.


- Click and drag a rectangle over some part of the blue curve. Points will be auto created only within the rectangle you drew. Unlike in the **Auto Pick Points by Grids** method, the **Boundary-Limited Area Auto Trace** method creates more points than just where the curve intersects with the grids.




- Click the **Reorder Points**  button to set the captured points in order.
- Click the **Set Label**  button.
- Click on the selected peak point of blue line and press the **Enter** key.
- Enter **Blue Peak** in the dialog to add a label to the peak of the blue line.




- To add another label on the peak of the digitized red line, click the **Set Label** button again to release it first.
- Select Line 1 to show digitized red points on the Image. Repeat the same process, this time set the label as **Red Peak**.

12. Select the **Go To Data**  button. You can see the Labels added are in corresponding Label rows.


	A(X1)	B(Y1)	C(L1)	D(X2)	E(Y2)	F(L2)	G(X3)	H(Y3)
Long Name		PickedDat			PickedDat			PickedDat
Units								
Comments	Data for the Red Curve			Data for the black baseline			Data for the Blue Curve	
F(x)	Curve			baseline			Curve	
Scale Type	Linear Scale	Linear Scale		Linear Scale	Linear Scale		Linear Scale	Linear Scale
19	18.75201	0.59941		19.26297	0.12288		16.70818	0.29722
20	18.92233	0.71564		20.96617	0.11126		17.73009	0.26235
21	18.92233	0.77376		22.66936	0.09963		18.92233	0.24492
22	19.09265	0.83187		24.37256	0.08801		20.45521	0.2333
23	19.09265	1.00621	Red Peak	26.07576	0.08801		22.1584	0.22167
24	19.26297	0.9481		27.77895	0.09963		23.8616	0.22167
25	19.26297	0.88998		29.48215	0.09963		25.5648	0.21586
26	19.43329	1.12244		31.18534	0.10545		27.26799	0.23911
27	19.43329	1.06433		32.88854	0.12869		28.97119	0.26816
28	19.60361	1.29678		34.59174	0.14031		29.99311	0.29141
29	19.60361	1.25029		36.29493	0.14613		30.8447	0.33209
30	19.60361	1.18055		37.99813	0.12869		31.35566	0.38439

13. With the image window active, click the **Go To Graph**  button.

All the curves resulting from the picked points will show in one graph window.




14. You can save the project with the Digitizer in it. When you open the project in the future, there will be a Digitizer... button on the image and you can click it to continue Digitizing.




Set Axes for Polar and Ternary Plots

The following section only explains how to define axes for images with polar or ternary coordinate systems using the Enhanced Digitizer. Once the axes are defined the same methods outlined above can be used to digitize the image.


Polar Coordinates

1. Click the **Import**  button in the Digitizer dialog.
2. Browse to the *<Origin EXE Folder>\Samples\Import and Export* folder and select **PolarCoordinate.bmp**.

The data plots in this image are in the polar coordinate system.




3. By default the Digitizer uses the Cartesian Coordinate system. Select **Axes:Polar Coordinate...** menu to open the **Polar Coordinate Settings** dialog box.




4. We can accept the default orientation and theta unit and click **OK**. Two line objects with anchor points show on the image.

To set the axes for polar coordinates, we need to make sure each line object follows the same radius line, i.e. **P1 & P2**, or **P3&P4** need to be at the same angle.




- Drag each line's anchor points to known positions. Note: You can press the **Space** key to make the cursor bigger so that it is easier to locate the desired position.




- Enter the corresponding **Theta** and **Radius** values on the Axes tab of the Digitizer.

Axes		Data		
Name	Color	Theta	Radius	Image Pixel
P1	■	0	5	(355, 247)
P2	■	0	20	(512, 247)
P3	■	90	5	(301, 194)
P4	■	90	20	(301, 37)

Ternary Coordinate


- Click the **Import**  button in the Digitizer dialog.
- Browse to the <Origin EXE Folder>\Samples\Import and Export folder and select **TernaryCoordinate.bmp**. The data plots in this image are in the ternary coordinate system.

3. Select **Axes:Ternary Coordinate...** to open the **Ternary Coordinate Settings** dialog.



4. Specify the **Axes Orientation** and **Range of Variables** (i.e. whether the ternary plot is normalized to 0 - 1 or 0 - 100). For this example, accept the default settings and click **OK**. Three anchor points are added to the image.
5. Drag these three points to the three vertices of the ternary plot.

- Similarly to the polar coordinate anchor point control, the row of selected anchor points in the graph will be highlighted on the **Axes** tab:



- The **Axes Values** of each point are **X Y Z** respectively. The X, Y, Z values of **P1** in the ternary image are **0 0 1** because P1 is at the end of the Z axis. Similarly P2 and P3 lie at the end of the X axis and the Y axis, so the X,Y, Z values should be 1 0 0 and 0 1 0 respectively. Logically therefore, P1, P2 and P3 can't be same values.

9.8 Update Database Importing By LabTalk Substitution

9.8.1 Summary

This tutorial shows how to import data from database into Origin worksheet by using SQL Editor with LabTalk substitution. And then make a column plot for the imported data. Then update the worksheet data and the plot by changing the defined LabTalk variables.

The SQL database we use here is [AdventureWorks database](#). For detailed information of how to attach an AdventureWorks database, please refer to [CodePlex website](#).

Minimum Origin Version Required: Origin 8.5.1 SR0

9.8.2 What you will learn

This tutorial will show you how to:

- Import data using SQL Editor.
- Use LabTalk substitution in SQL statement.
- Make column plot.
- Update database importing by LabTalk substitution.

9.8.3 Steps


Suppose we have already set up a database named *AdventureWorks2008R2* on a server machine - *myServer* - running SQL Server, with user name as "accounting", and password as "mydatabase".

9.8.3.1 Import Data from Database and Make Column Plot


1. To connect the database, we use a connection string:

```
Provider=SQLOLEDB.1;Password=mydatabase;Persist Security Info=True;
User ID=accounting;Initial Catalog=AdventureWorks2008R2;Data
Source=myServer
```

2. Activate an empty worksheet and open SQL Editor by clicking the **Open SQL Editor** button on the **Database Access** toolbar.



3. Select menu item **Edit Connection String...** from SQL Editor's **File** menu, in the open dialog, put the connection string (see step 1 above) to the text box. And then you can click the **Test** button to test if the connection is fine. If fine, click the **OK** button to connection to the database.



4. Select menu **Query: LabTalk...** from SQL Editor to open **LabTalk Support Settings** dialog. In this dialog, check the **Enable LabTalk (%,\$) Substitution** checkbox, and then put the following LabTalk script to **Before Query Script** textbox.

```
string myStartDate$ = ""; // For the first date substitution

string myEndDate$ = ""; // For the second date substitution


string myStrName$ = ""; // For the name

if(exist(startDate$, 18) == 18) // startDate$ has been defined
{
    myStartDate$ = startDate$; // Use the defined start date
}

else
{
    myStartDate$ = "1/1/2006"; // Use this date
}

if(exist(endDate$, 18) == 18) // endDate$ has been defined
{
    myEndDate$ = endDate$; // Use the defined end date
}
```

```
}  
  
else  
  
{  
  
    myEndDate$ = "12/31/2006"; // Use this date  
  
}  
  
if(exist(strName$, 18) == 18) // strName$ has been defined  
  
{  
  
    myStrName$ = strName$; // Use the defined name  
  
}  
  
else  
  
{  
  
    myStrName$ = "LineTotalFor2006"; // Use this name  
  
}
```



5.

6. Click OK to go back SQL Editor. In the right text box, put the following SQL statements.

```

select Production.ProductCategory.Name, LINETOALANDNAME2006.%(myStrName$)
from

        (select sum(SALEANDPRODUCT2006.LineTotal) as %(myStrName$),
Production.ProductSubcategory.ProductCategoryID

from

        (select SALEINFO2006.LineTotal,
PRODUCTINFO2006.ProductSubcategoryID

from

        (select Sales.SalesOrderHeader.OrderDate,

```

```

Sales.SalesOrderDetail.LineTotal, Sales.SalesOrderDetail.ProductID

        from Sales.SalesOrderHeader

        inner join Sales.SalesOrderDetail

        on
Sales.SalesOrderHeader.SalesOrderID=Sales.SalesOrderDetail.SalesOrderID

        where Sales.SalesOrderHeader.OrderDate
between '%(myStartDate$)' and '%(myEndDate$)' as SALEINFO2006

        inner join

        (select Production.Product.ProductID,
Production.Product.ProductSubcategoryID

        from Production.Product) as

PRODUCTINFO2006

        on
SALEINFO2006.ProductID=PRODUCTINFO2006.ProductID) as SALEANDPRODUCT2006

        inner join Production.ProductSubcategory


        on
SALEANDPRODUCT2006.ProductSubcategoryID=Production.ProductSubcategory.Prod
uctSubcategoryID

        group by Production.ProductSubcategory.ProductCategoryID)
as LINETOALANDNAME2006

        inner join Production.ProductCategory


        on
LINETOALANDNAME2006.ProductCategoryID=Production.ProductCategory.ProductCa
tegoryID


```



7.

8. As we can see that there are three LabTalk variables are used in the statements.


9. Just click the last button  on the toolbar, we can see the substitutions.




10. Select menu **File: Save to Active Worksheet** to save these settings to the worksheet, and then select menu **Query: Import** to import the data into worksheet, and then close SQL Editor. We can see the imported data form the image below, the Long Name for column B is "LineTotalFor2006", which is set in the LabTalk variable.

	A(X)	B(Y)
Long Name	Name	LineTotalFor2006
Units		
Comments		
F(x)		
1	Bikes	2.64864E7
2	Components	3.61009E6
3	Clothing	485587.15284
4	Accessories	92735.35171
5		
6		
7		
8		

11. Highlight column B from the worksheet, then select menu **Plot: Column/Bar/Pie: Column** to make a column plot.



9.8.3.2 Update Database Importing By LabTalk Substitution

1. Activate the worksheet with data from database above. Click **Open SQL Editor** button  and SQL Editor opens again, with the saved settings.
2. Select menu **Query: LabTalk** to open **LabTalk Support Settings** dialog. Now, change the values of these three variables: *myStartDate\$, myEndDate\$, and myStrName\$*.

```
string myStartDate$ = ""; // For the first date substitution

string myEndDate$ = ""; // For the second date substitution

string myStrName$ = ""; // For the name

if(exist(startDate$, 18) == 18) // startDate$ has been defined

{

    myStartDate$ = startDate$; // Use the defined start date

}

else

{

    myStartDate$ = "1/1/2007"; // Use this date

}

if(exist(endDate$, 18) == 18) // endDate$ has been defined

{

    myEndDate$ = endDate$; // Use the defined end date

}

else

{

    myEndDate$ = "12/31/2007"; // Use this date

}

if(exist(strName$, 18) == 18) // strName$ has been defined
```




```

{
    myStrName$ = strName$; // Use the defined name
}

else
{
    myStrName$ = "LineTotalFor2007"; // Use this name
}


```



- 3.
4. Click OK to go back to SQL Editor. Choose menu items **File: Save to Active Worksheet** and **Query: Import** orderly. Then close SQL Editor.

- Now we can see that the data in worksheet is changed, and the graph is also updated.

	A(X)	B(Y)
Long Name	Name	LineTotalFor2007
Units		
Comments		
F(x)		
1	Bikes	3.49233E7
2	Components	5.48551E6
3	Clothing	1.01198E6
4	Accessories	590257.58519
5		
6		
7		
8		



- Maybe you have note the **if-else** statements when defining the LabTalk variables. Here is showing how to use *startDate*\$, *endDate*\$, and *strName*\$.
- In Script Window (if not open, open it by menu **Window: Script Window**), run the following script (copy and paste it to Script Window, and then select them and press Enter button). Now, we have defined three LabTalk string variables.

```
string startDate$ = "1/1/2006";

string endDate$ = "12/31/2006";

string strName$ = "LineTotalFor2006";
```

8. With the data worksheet active and open SQL Editor again. Now just select menu **Query: Import**, and then we can see the data and graph both are updated, by using the LabTalk string variables defined just now.
9. The conclusion is that the "global" LabTalk variables (here "global" means the LabTalk variables can be "seen" by SQL Editor) can be also used in SQL Editor for the substitutions.

9.9 Update Graph By Reimport Data From Database

9.9.1 Summary

This tutorial will give an overview of the different ways you can analyse and manipulate a database within Origin. Some of the features shows here include using the SQL Editor in conjunction with Labtalk, using Data Filters, Set Column Values, Pivot Table and general statistics.

The SQL database we use here is [AdventureWorks database](#). For detailed information on how to attach an AdventureWorks database, please refer to [CodePlex website](#).

Minimum Origin Version Required: Origin 9.1 SR0

9.9.2 What you will learn

This tutorial will show you how to:

- Import data using SQL Editor.
- Use LabTalk substitution in SQL statement.
- Create pivot table.
- Apply data filter to worksheet data.
- Make bar plot and 100% stacked bar plot.
- Customize elements of the graph.
- Add a button to a graph for running LabTalk script.
- Make a dialog for specifying date.
- Update database import by LabTalk substitution.

9.9.3 Steps


Suppose we have already set up a database named *AdventureWorks2008R2* on a server machine - *myServer* - running SQL Server, with user name as "accounting", and password as "mydatabase".

9.9.3.1 Import Data from Database and Make Column Plot


1. To connect the database, we use a connection string:

```
Provider=SQLOLEDB.1;Password=mydatabase;Persist Security Info=True;  
  
User ID=accounting;Initial Catalog=AdventureWorks2008R2;Data  
Source=myServer
```

2. Activate an empty worksheet and open SQL Editor by clicking the **Open SQL Editor** button on the **Database Access** toolbar.



3. Select menu item **Edit Connection String...** from SQL Editor's **File** menu, in the open dialog, put the connection string (see step 1 above) to the text box. And then you can click the **Test** button to test if the connection is fine. If fine, click the **OK** button to connection to the database.



4. Select menu **Query: LabTalk...** from SQL Editor to open **LabTalk Support Settings** dialog. In this dialog, check the checkbox, and then put the following LabTalk script to **Before Query Script** textbox.

```
string pastFrom$ = "";  
  
string pastTo$ = "";
```

```
string curFrom$ = "";

string curTo$ = "";

if(exist(strPast1$, 18) == 18) // Check if strPast1$ has value

{

    // If strPast1$ has value

    pastFrom$ = strPast1$; // Assign strPast1$ to pastFrom$

}

else // If strPast1$ is not defined

{

    pastFrom$ = "1/1/2006"; // Assign a const string to pastFrom$

}

if(exist(strPast2$, 18) == 18)

{

    pastTo$ = strPast2$;

}

else

{

    pastTo$ = "3/31/2006";


}

if(exist(strCurrent1$, 18) == 18)

{
```

Tutorials for Origin

```
    curFrom$ = strCurrent1$;
}
else
{
    curFrom$ = "4/1/2006";
}
if(exist(strCurrent2$, 18) == 18)
{
    curTo$ = strCurrent2$;
}
else
{
    curTo$ = "6/30/2006";
}
```



- 5.
6. Click OK to go back SQL Editor. In the right text box, put the following SQL statements.

```
select OrderDateTotalDueAndProductSubcategoryID.OrderDate as 'Order Date',
'Date Range' =
    case
        when OrderDateTotalDueAndProductSubcategoryID.OrderDate <
'&(amp;curFrom$)' then 'Past'
        else 'Current'
    end,
Production.ProductSubcategory.Name as 'Subcategory Name',
```

```

        OrderDateTotalDueAndProductSubcategoryID.TotalDue as 'Total Due'

from

        (select OrderDateAndTotalDue.OrderDate,
OrderDateAndTotalDue.TotalDue, Production.Product.ProductSubcategoryID

        from

                (select Sales.SalesOrderHeader.OrderDate,
Sales.SalesOrderDetail.ProductID, Sales.SalesOrderHeader.TotalDue

                from Sales.SalesOrderHeader

                inner join Sales.SalesOrderDetail

                on

Sales.SalesOrderHeader.SalesOrderID=Sales.SalesOrderDetail.SalesOrderID

                where (Sales.SalesOrderHeader.OrderDate between

'%(pastFrom$)' and '%(pastTo$)'

                or Sales.SalesOrderHeader.OrderDate

between '%(curFrom$)' and '%(curTo$)')) as OrderDateAndTotalDue

                inner join Production.Product

                on OrderDateAndTotalDue.ProductID=Production.Product.ProductID) as


OrderDateTotalDueAndProductSubcategoryID

inner join Production.ProductSubcategory

on

OrderDateTotalDueAndProductSubcategoryID.ProductSubcategoryID=Production.P
roductSubcategory.ProductSubcategoryID


```

7.

8. As we can see that there are three LabTalk variables are used in the statements.

9. Just click the last button on the toolbar, we can see the substitutions.




10. Select menu **File: Save to Active Worksheet** to save these settings to the worksheet, and then select menu **Query: Import** to import the data into worksheet, and then close SQL Editor. We can see the imported data as the following image shows.

Long Name	A(X) Order Date	B(Y) Date Range	C(Y) Subcategory Name	D(Y) Total Due
Units				
Comments				
F(x)				
1	1/1/2006	Past	Helmets	17837.328
2	1/1/2006	Past	Helmets	27058.3881
3	2/1/2006	Past	Helmets	33502.0313
4	2/1/2006	Past	Helmets	101020.1731
5	2/1/2006	Past	Helmets	29945.0453
6	2/1/2006	Past	Helmets	25793.0294
7	2/1/2006	Past	Helmets	96861.429
8	2/1/2006	Past	Helmets	33750.5413
9	2/1/2006	Past	Helmets	43565.0481
10	2/1/2006	Past	Helmets	69598.4079
11	2/1/2006	Past	Helmets	23634.3103
12	3/1/2006	Past	Helmets	35612.3114
13	3/1/2006	Past	Helmets	40595.2909
14	3/1/2006	Past	Helmets	109340.8212

9.9.3.2 Pivot Table and Data Filter

1. Start with the imported data. Select column C, and then choose menu item **Worksheet: Pivot Table** to open the **Data Manipulation\Worksheet: wpivot** dialog.
2. In the dialog, select column B for **Pivot Table Column Source** by clicking the triangle button to the right. Choose *Sum* for **Summarize by**. Then you can see **Pivot Table Data Source** row shows above, just choose column D for it by clicking the triangle button to the right. Expand the **Options** node, set **Sort Output Columns** to *None*.



3. Click **OK** button to create a pivot table by using the settings.

	A(X)	B(Y)	C(Y)
Long Name	Subcategory Name	Sum of Total Due	
Units			
Comments		Past	Current
F(x)			
UserParam1			
1	Road Bikes	3.06176E7	3.64231E7
2	Mountain Bikes	1.70997E7	1.61741E7
3	Road Frames	3.18541E6	1.24385E7
4	Jerseys	4.65086E6	8.19067E6
5	Mountain Frames	5.33087E6	7.42407E6
6	Helmets	3.85929E6	7.63626E6
7	Caps	2.32567E6	2.82706E6
8	Socks	1.99051E6	2.23712E6
9			
10			

4. Add two more columns to the **Pivot1** worksheet by menu **Column: Add New Columns**.

Add New Columns



How many columns do you want to add to the worksheet?

2

OK

Cancel

5. Change the Long Name of them to *Percent Change* and *Gain/Loss* respectively. And set their values by context menu **Set Column Values...**. In the **Set Values** dialog, set formula to be " $\text{col}(b)=0 ? 100 : 100 * (\text{col}(c) - \text{col}(b)) / \text{col}(b)$ " and " $\text{col}(D) > 0 ? 12 : 2$ " respectively. And change **Recalculate** to *Auto*.




The result looks like:

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	Subcategory Name	Sum of Total Due	Percent Change	Gain/Loss	
Units					
Comments		Past	Current		
F(x)				100 : 100*(col(c)-cl(D) > 0 ? 12	
UserParam1					
1	Road Bikes	3.06176E7	3.64231E7	18.96106	12
2	Mountain Bikes	1.70997E7	1.61741E7	-5.41335	2
3	Road Frames	3.18541E6	1.24385E7	290.48293	12
4	Jerseys	4.65086E6	8.19067E6	76.11112	12
5	Mountain Frames	5.33087E6	7.42407E6	39.26575	12
6	Helmets	3.85929E6	7.63626E6	97.86706	12
7	Caps	2.32567E6	2.82706E6	21.55917	12
8	Socks	1.99051E6	2.23712E6	12.38901	12
9					
10					

- Highlight column B, and then select menu **Column: Filter: Add or Remove Filter** to add a filter to this column.

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	Subcategory Name	Sum of Total Due	Percent Change	Gain/Loss	
Units					
Comments		Past	Current		
F(x)				100 : 100*(col(c)-cl(D) > 0 ? 12	
UserParam1					
Filter		Empty			
1	Road Bikes	3.06176E7	3.64231E7	18.96106	12
2	Mountain Bikes	1.70997E7	1.61741E7	-5.41335	2
3	Road Frames	3.18541E6	1.24385E7	290.48293	12
4	Jerseys	4.65086E6	8.19067E6	76.11112	12
5	Mountain Frames	5.33087E6	7.42407E6	39.26575	12
6	Helmets	3.85929E6	7.63626E6	97.86706	12
7	Caps	2.32567E6	2.82706E6	21.55917	12
8	Socks	1.99051E6	2.23712E6	12.38901	12

- Click on the filter icon, and then select **Greater Than...** from the context menu. And set value to zero in the open dialog.





- Click **OK** button to apply the filter, and it looks like this.

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	Subcategory Name	Sum of Total Due	Percent Change	Gain/Loss	
Units		Past	Current		
Comments					
F(x)				100 : 100*(col(c)-cl(D) > 0 ? 12	
UserParam1					
Filter		Greater than 0			
1	Road Bikes	3.06176E7	3.64231E7	18.96106	12
2	Mountain Bikes	1.70997E7	1.61741E7	-5.41335	2
3	Road Frames	3.18541E6	1.24385E7	290.48293	12
4	Jerseys	4.65086E6	8.19067E6	76.11112	12
5	Mountain Frames	5.33087E6	7.42407E6	39.26575	12
6	Helmets	3.85929E6	7.63626E6	97.86706	12
7	Caps	2.32567E6	2.82706E6	21.55917	12
8	Socks	1.99051E6	2.23712E6	12.38901	12

Note: Here no data satisfy the filter, so it looks nothing change. This filter is for future use.


9.9.3.3 Create Graph and Customize Graph

- Start with the data in the **Pivot1** worksheet. Highlight column C, and then select menu **Plot: Column/Bar/Pie: Bar** to create a bar plot. Again, highlight column D, and create a 100% stacked bar by menu **Plot: Column/Bar/Pie: 100% Stacked Bar**. Please go to the **Format: Layer Properties** dialog, **Display** tab and check on **Clip Data to Frame** checkbox.




2. Activate one of the graphs, choose menu **Graph: Merge Graph Windows** to open the **Graph Manipulation: merge_graph** dialog. In the dialog, set **Merge** to *Specified*, and then make sure *Graph2* is followed by *Graph1* in **Graphs**. Clear **Keep Source Graphs** checkbox. And under


Arrange Settings node, change **Number of Rows** to 1, and **Number of Columns** to 2.



3. Click **OK** button to merge the two graphs.



4. Select one of two legends, and then press Delete key to delete it. Do the same to delete another legend, the two bottom axes, tick labels for the vertical axis of the right plot, the vertical axis title of the right plot.
5. Double click on the bottom axis title of the left plot, and then change the title to "%(?Y) from Last Season". Do the same to change the bottom axis title of the right plot to "Current Season Sales".
6. Double click on the bottom axis tick label of the left plot to open the **Axis Dialog**. In the dialog, choose **Scale** tab and **Horizontal** and then change **From** -100 To 200. Set the Major Ticks **By Increment** value to 50.




7. Switch to **Line and Ticks** tab and **Left** page, and then change **Thickness** of **Line** to 0.5 in the right panel. Switch to **Bottom** page, and uncheck **Show Line and Ticks** box. Click **OK** to apply.


8. Double, click the X axis of the right graph, Switch to **Tick Labels** tab, and then set **Divide by Factor of Display** to 1000000. Click **Apply** button.
9. Select **Scale** tab and **Horizontal** page from the left panel, and set **Value of Major Ticks** to 10.
10. Select **Special Ticks** tab **Bottom**. Type "40 x10\+(6)" for Axis End row. Click **Apply** button.

At Axis Value	Label	Show
Axis Begin	<auto>	Auto
Axis End	40 x10\+(6)	Show
	<auto>	<input checked="" type="checkbox"/>

11. Select **Line and Ticks** tab and **Left** page, and set **Thickness of Line** to 0.5 in the right panel. Swithc to **Bottom** page, and uncheck **Show Line and Ticks** box. Click **OK** to apply.
12. Double click on the bar plot on the right to open the **Plot Details** dialog. Select **Layer2** level in the left panel, then choose **Link Axes Scales** tab and set **Link to** to *Layer1*, and **X Axis Link** to **Straight (1 to 1)**.



13. Select the plot under **Layer2** from the left panel, and in the **Pattern** tab of the right panel, focus on **Fill** group, and select **Individual Color: LT Cyan** for **Color**.




14. In the right panel, go to **Label** tab and enable **Enable** checkbox. Then change the following values:

Size: 14


Horizontal Offset: 3

Label Form: Custom


Format String: $\$(Y/1000000,.1)$



15. Switch to the plot under **Layer1'** in the left panel. Go to **Pattern** tab in the right panel, set **Color to Indexing: Col(E): "Gain/Loss"** in the Fill group.



16. Go to **Label** tab, set **Size** to 10, and check the checkbox to the left of **Hide Label if Column/Bar Height Less than (%)**.
17. Click **OK** button to finish the settings. Delete the vertical axis tick label of the right plot.



9.9.3.4 Add Button to Run LabTalk Script

1. Click the "T" button on the standard toolbar, and then add a text object in the bottom right corner, text says "Update".
2. Open the context menu of the newly added text object, and then select **Programming Control...** from the menu to open the **Programming Control** dialog.
3. Set **Script, Run After** to *Button Up*, and put the following script to the bottom text box. Click **OK**.

```
double pastDate1 = date(1/1/2006);

double pastDate2 = date(3/31/2006);

double currentDate1 = date(4/1/2006);

double currentDate2 = date(6/30/2006);

// Check if strPast1$, strPast2$, strCurrent1$, strCurrent2$ exist the
same time
```



```

if((exist(strPast1$, 18) == 18) && (exist(strPast2$, 18) == 18) &&
(exist(strCurrent1$, 18) == 18) && (exist(strCurrent2$, 18) == 18))
{

    // If yes, set to double value, so to show on the dialog

    pastDate1 = date(strPast1$);

    pastDate2 = date(strPast2$);

    currentDate1 = date(strCurrent1$);

    currentDate2 = date(strCurrent2$);

}

// Dialog for date settings

GetN (Last Season) :@G

    (From) pastDate1:@FD0

    (To) pastDate2:@FD0 (-) :@G

(Current Season) :@G

    (From) currentDate1:@FD0

    (To) currentDate2:@FD0 (-) :@G

(Set Date);

// Get the set dates, and convert to string

string strPast1$ = $(pastDate1, D0);

string strPast2$ = $(pastDate2, D0);


string strCurrent1$ = $(currentDate1, D0);

```


Tutorials for Origin

```
string strCurrent2$ = $(currentDate2, D0);  
  
// Reimport data from database according to the set dates  
  
dbimport iw:=[book1]sheet1!;  
  
run -p au; // Update the recalculation  
  
range rPivot = [Book1]Pivot1!; // Pivot table range  
  
layer.x.to = rPivot.maxRows+0.5; // Set to value of vertical axis  
  
rPivot.runfilter(); // Run the data filter
```


4. The text object now looks like a button.



- 5.
6. Click this button, a dialog will pop up with the default dates (for the first time, if not the first time, the dates set last time are shown).



- Now, let's change the period, such as Last Season From 2/1/2007 To 4/30/2007, and Current Season From 5/1/2007 To 7/31/2007.




- Click **OK**, and we can see data imported from database is updated, and of course Pivot1 worksheet is recalculated with the new imported data. So the graph is updated too. Here, we can see result after applying the data filter.

The screenshot shows the Origin software interface with a data table. A Pivot table filter is applied to column B, with the filter text 'Greater than 0' visible in the Filter row. The table contains the following data:

	A(X)	B(Y)	C(Y)	D(Y)	E(Y)
Long Name	Subcategory Name	Sum of	Total Due	Percent Change	Gain/Loss
Units					
Comments		Past	Current		
F(x)				100 : 100*(col(c)-cl(D) > 0 ? 12	
UserParam1					
Filter		Greater than 0			
1	Road Bikes	6.81283E7	7.67252E7	12.61864	12
2	Mountain Bikes	2.46812E7	3.15341E7	27.76593	12
3	Road Frames	1.57909E7	3.64254E7	130.6738	12
4	Mountain Frames	1.07755E7	2.21088E7	105.17686	12
5	Wheels	1.25847E7	1.54854E7	23.04885	12
6	Jerseys	8.07883E6	1.82196E7	125.52316	12
7	Gloves	9.73933E6	1.51418E7	55.47092	12
8	Helmets	8.65663E6	1.45156E7	67.68159	12
9	Tights	8.23181E6	8.55148E6	3.8833	12
10	Handlebars	4.32357E6	1.03281E7	138.87918	12
11	Shorts	5.00309E6	8.28131E6	65.52408	12
12	Bib-Shorts	5.86904E6	7.377E6	25.69347	12
14	Caps	3.92397E6	5.14375E6	31.0854	12
17	Pumps	2.24935E6	3.04102E6	35.19548	12
18	Locks	2.22754E6	2.89081E6	29.77577	12
20	Headsets	1.71589E6	1.85905E6	8.34293	12
22	Forks	1.17444E6	1.60914E6	37.01322	12
30					

The Pivot table filter is set to 'Greater than 0'. The table is displayed in 'Sheet 1' with a 'Pivot 1' tab selected.



10 Exporting and Presentation

10.1 Exporting

10.1.1 Exporting

- [Exporting Graphs](#)

10.1.2 Exporting Graphs

10.1.2.1 Summary

When you have completed your graph for publication, exporting your final results is very easy with Origin. The graph export is highly customizable. You can specify the size of the image, the file format, and other advanced settings such as color format.

10.1.2.2 What you will learn


- How to export a graph and specify the settings.
- How to export specified graphs in the project.

10.1.2.3 Export a graph as an eps image


This tutorial is associated with the Contour project
(C:\ProgramData\OriginLab\94\Origin\Central\Graphing\Contour.opj)

Tutorials for Origin


1. In the Project Explorer, browse to *XYZ Contour* folder, and make the graph window active.




2. With the graph window active, select **File: Export Graphs** from the Origin menu to open the **expGraph** dialog.
3. Click the **Auto Preview** check box. Then the graph will auto preview the temporary copy in the right panel of the dialog.



4. Specify the following settings to export the graph:
 - Customize the **File Name** to **My Graph**.
 - Expanding the **Export Settings** node, select **Border** from the **Margin Control** drop-down list and type **3** in the **Clip Border Width** box.
 - Expanding the **Image Size** node, uncheck **Auto** check box for **Fit Width** and set width to **5**.




5. Click the triangle button to the right of the **Dialog Theme**. Select **Save As** from the shortcut menu. The **Theme Save as** dialog opens.



6. In the **Theme Save as** dialog, enter **My EPS Export** as **Theme Name**. And click **OK**.



7. Click the **OK** button in the **expGraph** dialog, then *My Graph.eps* is created in the **User File Folder**. And the graph path will display in the **Message Log**.




8. Repeat export a graph using the setting from above, select the theme **My EPS Export** in the fly-out menu of the export graph tool directly.





Or

Click the right-sided triangle button to the right of the Dialog Theme in the **expGraph** dialog. From the shortcut menu, pick **My EPS Export**. The settings from that theme will then be loaded in the dialog.





10.1.2.4 Export the specified graphs

1. Redo steps 1 and 2 from above.
2. In the **expGraph** dialog, select **Portable Network Graphics (*.png)** for **Image Type**.
3. Select **Specified** from the **Select Graph(s)** drop-down list. Click the  button to the right of the **Graph Page** edit box to open the **Graph Browse** dialog.




4. In the **Graph Browse** dialog, all the graphs in this project will list in the left panel of the dialog. Select **Graph3G** in the left panel, then the preview panel will show a preview of the graph.


- Click the  button to add the selected graph to the right panel, or double-click selected graph in left panel to add to the right panel.




- Then click **OK** button, the specified graphs will show in the **Graph Page** box.



- Expanding the **Image Size** node, select **pixel** from the **Specify Size in** drop-down list. And uncheck the **Auto** check box for **Fit Width** and set width to **600**.



8. Click **OK** button in the **expGraph** dialog, then two images are created. And the graph path will display in the **Message Log**.



```

Messages Log
[8/12/2015 15:05:01 expGraph]
Graph1B is exported to D:
\Documents and Settings
\Administrator\My Document\XYZ
Contour.png
Graph3G is exported to D:
\Documents and Settings
\Administrator\My Document
\Waterfall with Y Colormap.png

```

10.2 Presentation

10.2.1 Presentation

- [Pasting or Embedding Graphs in Other Applications](#)
- [Send Graphs to PowerPoint](#)

10.2.2 Pasting or Embedding Graphs in Other Applications

10.2.2.1 Summary

It is possible to insert Origin graphs to other applications(e.g.Microsoft® PowerPoint/Excel/Word),either by object linking or embedding. Both linked and embedded graphs can be later edited with Origin.

The difference is that embedded graph is contained in the destination file while the linked graph is not. A linked graph can be dynamically updated if the source graph is changed.

10.2.2.2 What you will learn


This tutorial will show you:

- How to insert an Origin graph to other applications as linked/embedded graphs.
- How to edit linked/embedded graphs after inserting to other applications.


10.2.2.3 Steps

Tutorials for Origin


1. Launch Origin, open the OffsetY.opj project from <Origin program folder>\Samples\Graphing\. This project contains a graph (Graph 1).



2. With the graph window active, select **Edit: Copy Page**.
3. Switch to Microsoft® PowerPoint 2007, create two new slides.
4. Go to the first slide, click the **Paste** button, in the fly-out menu choose **Paste Special**.
5. In the **Paste Special** dialog, select the **Paste Link** radio button and then choose **Origin Graph Object** in the **As** list. Click OK to close the dialog. In the first slide the graph is pasted as a linked object.




6. Go to the second slide, open the **Paste Special** dialog again similarly as the previous step.
7. This time, select the **Paste** radio button then choose **Origin Graph Object** in the **As** list. Click OK to close the dialog. In the second slide the graph is pasted as an embedded object.




8. Go back to the OffsetY.opj file in Origin, double click on the olive dot plot in Graph 1, bring up the **Plot Details** dialog, change the symbol color to **Violet** and click OK to close the dialog.
9. Now switch to PowerPoint, in the first slide, right click on the linked graph, and choose **Update Link** from the fly-out menu. The color of the dot plot in this graph will be changed to violet.


Tutorials for Origin



10. Go to the second slide, right click on the embedded graph, and choose **Graph Object:Edit** to reopen the graph in Origin. Note that the graph name is **Graph in Presentation 1**, indicating that the graph is contained in the destination file.



11. In the **Graph in Presentation 1**, change the color of olive dot plot to blue similar as previously, and close Origin. Note that the linked graph in slide 1 and the embedded graph in slide 2 looks different now.



10.2.3 Send Graphs to PowerPoint

10.2.3.1 Summary

This tutorial will show you how to send the specified graphs to an existing PowerPoint file by inserting graphs from a specified slide on and also copy that slide style, logo, layout, etc. User will no longer need to set Slide Master in PowerPoint.

Minimum Origin Version Required: 2016 SR0

10.2.3.2 What you will learn

This tutorial will show you how to:




- send specified graphs to existing PowerPoint file.


10.2.3.3 Steps

This tutorial is associated with the Column and Bar project: *C:\ProgramData\OriginLab\ (version number) \Origin\Central\Graphing\Column and Bar.opj* and the PPT file: *<Origin EXE Folder>\Samples\Import and Export\Column_Plots_in_Sample_OPJ.pptx*


We are going to send most graphs in **Column and Bar** project to the above PPT file which consists of four slides: 1st slide is title; 2nd slide is table of contents; 3rd slide is blank; 4th slide is End page. All the sent graphs will be inserted into this PPT file starting from the 3rd slide and using the same style as starting slide.

1. Open the sample project **Column and Bar**

- Click the **Send Graphs to Powerpoint** button  to open the **pef_pptslide** dialog.
- Select **Specified** for the **Select Graph(s)** drop-down list, click the browse button  beside the **Graph Page** box to open the **Graph Browser**. In this dialog, select **Active Folder(Recursive)** for the top-left drop-down list, and then select all graph listed in the left panel except **Graph 5B**, click the right arrow button  to move them to right panel as below:



- Click OK button. All selected graphs will be listed in the **Graph Page** text box, you can reorder the graphs. Expand the **Slide Margin** branch, set the **Top Margin(%)** text box to 8.






5. Select **Top of Slide** for the **Title Line** drop-down list and set **Title Mode** to **Window Long Name**.

Title Line	Top of Slide
Title Mode	Window Long Name

6. Set **Starting Slide Index** to 3 to insert all these graphs to the existing PPT file by starting from the 3rd slide with same style as starting slide. Then set **Slide Mode** to **Start New**.

Starting Slide Index	3	<input type="checkbox"/> End
Slide Mode	Start New	

7. Click the browse button  beside the **Load File/Template(Optional)** box to locate the existing PPT file *Column_Plots_in_Sample_OPJ.pptx* under the *<Origin EXE Folder>\Samples\Import and Export* folder. Then specify the path to save the new PPT file in the *Save File As(Optional)* text box.

Load File/Template(Optional)	C:\Program Files\OriginLab\Origin2016_	
Save File As(Optional)	D:\PPT files\Column Bar plots.ppt	

PPT will be closed at the end.

8. Then you will get the final PPT file.

11 Collaboration and Connectivity

11.1 Connectivity

11.1.1 Connectivity

11.1.1.1 Excel

- [Working with Excel](#)

11.1.2 Excel

11.1.2.1 Excel

- [Working with Excel](#)

11.1.2.2 Working with Excel

Summary

Origin provides flexible ways to interact with Excel. You can either import Excel data into an Origin workbook, or open an Excel book inside Origin. If you require full access to all of Origin's graphing and analysis features, you will probably want to import your Excel data files into Origin. If it is important to maintain a separate Excel workbook file—perhaps, so that other colleagues who do not work with Origin have access to that file—you will probably want to open your Excel data files directly. We give a brief introduction to working with Excel in this tutorial.

What you will learn


This tutorial will show you how to:

- Copy-Paste data from Excel with full precision.
- Import an Excel file into an Origin workbook.
- Open an Excel file in Origin.
- Save an Excel file with path relative to the Origin Project file.


Copy-pasting Data from Excel

It may be desirable at times to simply copy+paste data from Excel to Origin instead of importing or opening Excel. These steps show that such a copy-paste operation can bring in data with full precision.


1. Launch Excel and Origin separately.
2. Open the file <Origin Installation Folder>\Samples\Graphing\ExcelData.XLS in Excel.
3. Select columns B through L. Right click, bring up the **Format Cells** dialog, and set the number of decimal places to 2. Now Excel will show fewer decimal places.



4. Click on the top left cell in the Excel sheet to select the entire sheet, right-click and select **Copy**, or use the keyboard shortcut **CTRL+C** to copy.




- 5. In a new book in Origin, place the cursor in row 1 of column 1 and press **CTRL+V** or right click and **Paste**.



- 6. Note that the numbers come into Origin with full precision, not the number of displayed digits in Excel. As shown in the example below, the number circled value is displayed with 2 decimal places in Excel (0.35) but imported with all three decimal places into Origin (0.348).

C7(Y)	C8(Y)	C9(Y)	C10(Y)	C11(Y)
56.39	0.348	0.307	0.915	
55.91				
55.48				
58.74				
61.63				
63.3				
65.17				
63.07				
60.87				
59.5				
58.74				


- 7. In Origin, right click on the row 1 header and select **Set as Comment** to make this row an Origin column comment.



8. Right click on row 1 again and select **Set as Long Name**. This makes rows 1 and 2 in Excel the worksheet header in Origin:

	A(X)	B(Y)	C1(Y)	C2(Y)	C3(Y)	C4(Y)	C5(Y)
Long Name	Year	Domestic crude oil production	Crude oil imports	Petroleum products imports	Total imports	Crude oil exports	Petroleum products exports
Units							
Comments	(All quantities in millions of barrels/day)						
F(x)=							
1	1/1/1973	9.21	3.24	2.78	6.03	0	0.2
2	1/1/1974	8.77	3.47	2.42	5.89	0	0.2
3	1/1/1975	8.37	4.1	1.75	5.85	0	0.
4	1/1/1976	8.13	5.28	1.81	7.09	0	0.2
5	1/1/1977	8.25	6.57	2	8.57	0.05	0.1
6	1/1/1978	8.71	6.2	1.8	8	0.16	0.
7	1/1/1979	8.55	6.28	1.7	7.99	0.24	0.2
8	1/1/1980	8.6	4.98	1.39	6.37	0.29	0.2


9. You can now double click column 1, set it as **Date**, and plot the data.




Importing Excel File

Origin supports importing Excel files directly into Origin workbooks. Multiple sheets are supported and controls are available for setting specific rows in the Excel sheet to be brought into an Origin worksheet as header information such as Long Name or Comments. If you want to perform analysis or data manipulation operations on your Excel data, we recommend importing your data into Origin.

1. With a new book active in Origin, use the menu **File: Import: Excel (XLS, XLSX, XLSM)...**
2. Select the file **<Origin Program Folder>\samples\graphing\Excel Data.xls** and make sure the **Show Options Dialog** is checked.




3. In the dialog that comes up, leave the **Use Excel COM Component to Import** check box checked.
4. Set **Index of Rows for Comments From** to 1
5. Set **Index of Rows for Long Name** drop-down to 2 and click **OK** to Import.



6. Click and select the **Comments** cell under column 1, hold the **CTRL** key and drag the bottom right point of the selected cell to stretch across all columns with data, thus copying the same comments to all columns.

	A(X)	B(Y)	C1(Y)
Long Name	Year	Domestic c	Crude oil i
Units			
Comments	(All quantities in millions of barrels/day)		
1	1/1/1973	9.21	3.24
2	1/1/1974	8.77	3.47

- 7. Press **F4** to bring up the format dialog, switch to the **Format** tab, change the **Apply To** dropdown to **Comments** and set **Dynamic Merge** to **Horizontal**. Click **OK**.




This merges the comments cells and shows the title in the center of all the data columns as shown below:

C2(Y)	C3(Y)	C4(Y)	C5(Y)	C6(Y)	C7(Y)
Petroleum	Total impor	Crude oil e	Petroleum	U.S. petrole	World petro
(All quantities in millions of barrels/day)					
2.78	6.03	0	0.23	17.31	56.39
2.42	5.89	0	0.22	16.65	55.91
1.75	5.85	0	0.2	16.32	55.48


Open Excel File in Origin

At times it may be desirable to keep the data in an external XLS file while opening the file inside Origin as an Excel window and then working with the data. When you open Excel (.XLS or .XLSX) files as Excel workbooks in Origin, an OLE instance of Microsoft Excel is launched. You can plot directly using Excel workbook data, but many analysis features as well as 3D plotting are inaccessible.


1. Select **File: Open Excel...** and select the file **\Samples\Graphing\Excel Data.xls**.
2. A new Excel window opens inside the Origin workspace. When this window is active, the Origin main menu has different entries, some of which are specific to Excel. The Excel toolbars are also available.




3. Highlight the Excel data range **A3:A26** and right click. Select **Format Cells** to make sure that the data is **Date** format.




4. Now select the **Plot** menu in Origin and select the **Multi-Y: Double-Y** plot type.
5. Select **A3:A26** in the Excel sheet and click **X** in the **Select Data for Plotting** dialog to assign the X data.




6. Select **B3:C26** in the Excel sheet and click **Y** in the **Select Data for Plotting** dialog to assign the Y data. Select **Multiple Layers** from the **Plot Into** drop-down.




7. Click **Plot** to create a double-y plot as shown below:




8. By default, Origin displays the tick labels for time on the X axis in MM/DD/YYYY format. Double-click the X axis to open the **Axis dialog**. Select the **Horizontal** icon in **Scale** tab and change the scale from **1/1/1970** to **1/1/2000**.



Select the **Bottom** icon in the **Tick Labels** tab and change the **Display** to year.



Click **OK** to apply the settings and close the dialog. The graph should resemble the following image:






After opening Excel in Origin, switching to another Origin window, causes a toolbar spacer to become visible where the Excel menu used to be. To remove it, right click and select **Hide Toolbar Spacer** or **Hide Toolbar Spacer Always**.


Setting External Excel File Path Relative to OPJ Path

The Origin Project can contain an Excel window which is linked to an external Excel file. In such a case it may be beneficial to save the Excel file in the same folder as the Origin project, or a subfolder under the Origin project folder. This will make the two files more portable, as seen in the following steps:

1. Close Excel if it is running.
2. Perform the steps under the **Open Excel File in Origin** section above, and (optionally) create a plot.
3. Save the OPJ to a folder location such as "C:\My Files\My Project.opj".
4. Right-click on the Excel window and select **Save Workbook As**. Save it in a (new) subfolder under the OPJ save location, such as "C:\My Files\Data\My Data.xls".



5. Right click again on the Excel window title and select **Properties**. Check the box that says **Relative to current project (opj) path**. Note that the Excel file path in the box below changes to a relative path of "Data\My Data.xls".



- Save the OPJ again. Now you can copy the entire subfolder structure, starting from where the OPJ is saved, and put it on an external memory device (i.e., a memory stick or similar), or zip the entire folder structure. When taken to another computer and opened, Origin will look relative to the OPJ path to find the Excel file.



If your Excel file is in a different location and you want to save it to the same path as the OPJ, you can open the Excel file in Origin, then right click the title, select **Properties** and click the **Switch to OPJ path upon Saving** button. On saving the OPJ, the Excel file will be copied from its current location to the same path where OPJ is saved.

12 Programming

12.1 LabTalk

12.1.1 LabTalk

[Get Started with LabTalk](#)

[LabTalk Language Fundamentals](#)

[Range Notation in LabTalk](#)

[Objects in LabTalk](#)

[Use X-Function in LabTalk](#)

[Debug LabTalk Script](#)

[Graphing and Exporting with LabTalk](#)

[Mathematical Analysis with LabTalk](#)

[Curve Fitting and Batch Processing with LabTalk](#)

[Peak Analysis with Labtalk](#)

[Statistics with Labtalk](#)

[Signal Processing with LabTalk](#)

[Creating OPX for Custom Tools with Labtalk](#)

- [How to share Origin C based LabTalk Functions](#)

12.1.2 How to share Origin C based LabTalk Functions

12.1.2.1 Introduction

This tutorial will show you how to share code with other users by distributing OPX files. In this example, only Origin C files are distributed. However, please note that OPX distribution can include any file types including (but not limited to) project files, templates and toolbars.

12.1.2.2 Tutorial

The following procedure will show you how to distribute your Origin C code to other Origin users. In this example, we will be packaging an Origin-C function in a file (*MyCode.c*) in a folder (*MyFunctions*) under the **User Files Folder (UFF)**.

Tutorials for Origin

1. Create File Locations

The **Source Path** for your files should be available on any computer your OPX is targeted for. The easiest way to do this is to make a subfolder of the Origin **UFF**. Any of the files and folders of the **UFF** can then be added to your OPX for distribution. So, create a subfolder named *MyFunctions* under the **UFF**.

2. Copy Files to the Source Path

Copy all the files to be packaged to the subfolder created in the last step. Here there is only a C file (*MyCode.c*). The function in this file is shown below.

```
void get_data_from_wks()

{

    Worksheet wks = Project.ActiveLayer();

    if( !wks )

    {

        out_str("Please keep a worksheet active with data");

        return;

    }

    // The following settings to set range as whole worksheet,

    // index offset is 0, -1 means last row/column.

    // Change r1, c1, r2, c2 to specify worksheet sub range,

    // for example, r1 = 0, c1 = 1, r2 = -1, c2 = 2 to

    // select all rows from column 2 to column 3.
```

```
int r1 = 0; // first row

int c1 = 0; // first column

int r2 = -1; // last row

int c2 = -1; // last column

//construct a data range object from worksheet all data

DataRange dr;

dr.Add("X", wks, r1, c1, r2, c2);

// get data from worksheet to vector by column one by one

matrix mData;

dr.GetData(mData); // get all data to matrix

for(int nColIndex = 0; nColIndex < mData.GetNumCols(); nColIndex++)

{

    vector vOneCol;

    mData.GetColumn(vOneCol, nColIndex);


    double min, max;

    vOneCol.GetMinMax(min, max);
```

```
printf("Maximum value of %d column = %f\n", nColIndex+1, max);  
  
}  
  
}
```

3. Create a Package

Open the **Package Manager** by selecting **Tools: Package Manager...** Then fill in the dialog as the following image shows.



- The **Module Name** will appear as the name of the package for uninstall purposes.
- **Origin Version Required** means the minimum version of Origin required for this package. You want to enter the version number like 8.0988, and not like 8.0SR6.

- To force the Origin C source file to the System Folder Workspace, use the `run.addoc()` method in the **After Installation** branch of **LabTalk Script**. In this example, it looks like the following:

```
run.addoc(%YMyFunctions\MyCode.c);
```

- Click the **Add Files** or the **Add Folder** button and browse to and add any files required. In this example, browse to the subfolder (*MyFunctions*) under the **UFF** and add the C file (*MyCode.c*). Then the path of the **UFF** will show as the source path, and the files will list in the lower panel.
4. Save the Package

Select the **File: Save** menu of this **Package Manager** dialog. In the pop-up **Save As** dialog, enter a name (in this example, can be *MyCode*) for this package, and then save it as an OPX file.

5. Distribute the Package

Send the saved OPX file to other users. The user who gets this package can drag and drop the OPX onto Origin to install it, and then the functions in the C file are available.

- Drag and drop *MyCode.opx* onto Origin to install it. After installation, the function `get_data_from_wks` defined in *MyCode.c* can be used as a LabTalk command.

```
get_data_from_wks;
```

12.2 Origin C

12.2.1 Origin C

- [Introduction to Origin C and Code Builder](#)
- [The Code Builder Workspace](#)
- [Adding New Origin C Functions to Origin](#)
- [Organizing and Accessing Origin C Functions](#)


- [Tutorial:Calculating Double Integral with NAG Functions From Origin C](#)
- [Tutorial:Calling NAG Functions From Origin C](#)
- [Accessing Internal Origin Objects by Origin C](#)
- [Create and Update Apps for Origin](#)

12.2.2 Introduction to Origin C and Code Builder

12.2.2.1 Summary

[Origin C](#) supports a nearly-complete ANSI C language syntax as well as a subset of C++ features including internal and DLL-extended classes. In addition, Origin C is "Origin aware". This means that Origin objects such as worksheets and graphs are mapped to classes in Origin C, allowing direct manipulation of these objects and their properties from Origin C.

Origin C's integrated development environment (IDE) is called Code Builder. Code Builder provides standard tools for writing, compiling, and debugging your Origin C programs. Once an Origin C function is compiled and linked, the function can be called in various ways from the Origin or Code Builder workspaces.

To open Code Builder, click the  button on the Origin Standard toolbar, or press ALT + 4 from the keyboard.

Minimum Origin Version Required: Origin 9


12.2.2.2 What you will learn

This tutorial will show you how to:

- Create an Origin C function.
- Debug and Run the Function.
- Run the Function Using the Custom Routine Button.

12.2.2.3 Steps

Create an Origin C Function

1. In Code Builder, start with a new workspace (**File: New Workspace...**). On the Code Builder **Standard** toolbar, click the **New**  button to open the **New File** dialog.
2. Select **C File** to create a .c file. Type **Tutorial** in the **File Name** text box. In the **Location** text box, specify the *User Files Folder/OriginC* folder to save your source file. Make sure that the

Add to Workspace box is checked. Click **OK**. A file named Tutorial.c is created and opened in the Code Builder workspace.

```

31 // Start your functions here.
32 void new_wks()
33 {
34     Worksheet wks;
35     wks.Create("Origin"); // create a Worksheet window with template -
36     // Origin
37     vector& vecX = wks.Columns(0).GetDataObject();
38     vector& vecY = wks.Columns(1).GetDataObject();
39
40     vecX.Data(1, 10, 1);
41     vecY.Data(0.1, 1, 0.1);
42
43     vector<string> vsLongName =
44     {
45         ... "Index" ...

```

4. Copy and paste the following code beneath the line that reads "// start your functions here.":

```

void new_wks()
{
    Worksheet wks;

    wks.Create("Origin"); // create a Worksheet window with template -
    Origin

    vector& vecX = wks.Columns(0).GetDataObject();

    vector& vecY = wks.Columns(1).GetDataObject();

    vecX.Data(1, 10, 1);

    vecY.Data(0.1, 1, 0.1);

```



```
vector<string> vsLongName =  
  
    {  
  
        "Index",  
  
        "Data"  
  
    };  
  
for (int nCol = 0; nCol < wks.GetNumCols(); ++nCol)  
  
    {  
  
        Column col (wks, nCol);  
  
        col.SetLongName (vsLongName [nCol] );  
  
    }  
  
}
```

5. This new_wks function will create a worksheet using the **Origin** template. It fills the first column with numbers from 1 to 10, incrementing by 1. The second column is filled with numbers from 0.1 to 1, incrementing by 0.1. Lastly, it sets the Long Names of the first and second columns as **Index** and **Data**, respectively.

6. Click the **Save** button .



Mini-Tutorial: Find more examples of the usage of **GetDataObject** and use a bookmark to quickly navigate to a marked line.

1. Click line 33 and click the **Toggle Bookmark** button .
2. Select **GetDataObject()** in line 37 and click the **Find in files** button .
3. In the **Find in Files** dialog box, set **In files/file types** as ***.c,*.cpp** and **In folder** as **<program folder>\OriginC**. Check all the boxes in this dialog and click the **Find** button.

4. In the **Find Results** window, double-click any line containing **GetDataObject()**. This opens the file containing this string and jumps to the related section.
5. To back to the line marked in step1 activate the **Bookmarks** window. Double click the bookmark added in step 1 of this mini-tutorial and the cursor jumps to line 33 in the Tutorial.c file.

Origin 2015 provides some useful tools:

- **Quick open files**

Prss SHIFT + ALT + O or select **Tools: Quick Open Files** to open the **Quick Open Files** dialog.


- **Switch between .h and .c/.cpp file**


When open a .h file, press CTRL + ALT + O to open the corresponding .c or .cpp file, and vice versa.

- **Find symbols**

Press SHIFT + ALT + S or select **Tools: Find Symbols** to open the **Find Symbols** dialog.

Debug and Run the Function

1. On the Code Builder **Standard** toolbar, click the **Build** button . This compiles the new_wks function and performs linking (Please make sure the **Tutorial.c** file is active).




- Click the space just to the left of lines 34, 35, 37, 50. A red ball icon will be placed at the beginning of each line, indicating that you added breakpoints to these lines. These breakpoints are listed in the **Breakpoints** window.
- In the **Breakpoints** window, clear the box before **tutorial.c, line 35** to disable this breakpoint. Note that the breakpoint icon before line 35 becomes a hollow circle icon.




To delete a breakpoint, you can click on the breakpoint icon before the corresponding line, or right-click on the breakpoint in the **Breakpoints** window, and select **Delete Breakpoint**.


- Right-click on the breakpoint of line 37. Select **When Hit...** to open a dialog. Check the box before **Print a message**. In the text box under **Print a message:**, append the text **test code runs to here.** . Click **OK** to finish. Note that this breakpoint's icon is now a diamond.




- Right click on the breakpoint at line 50. Select **Condition...** to open a dialog. Enable **Condition** and type **nCol==1** in the text box. Click **OK**.




6. To run this code, type the function name **new_wks** in the upper panel of the **LabTalk Console** window.
7. Press ENTER. A yellow arrow will appear upon the first breakpoint icon, indicating which line of code is executed to.
8. Press F8 to continue debugging the code. You will see the yellow arrow icon moving to the line 50.
9. In the **Command & Results** window, the message added in the breakpoint of line 37 is printed in the lower panel.





10. Activate the **Variables** window. The variable names are listed in the first column and their values are listed in the second column. Check the value of **nCol**.



11. Press F5 to run over all codes, the yellow arrow will disappear.
12. Return to the Origin workspace. You can see that a workbook is created as in the following image.






Run the Function Using the Custom Routine Button

1. Hold the CTRL + SHIFT keys and click the **Custom Routine** button . It will open the Custom.ogs file in Code Builder.
2. With the cursor at line 11, click the **Comment** button  to comment out line 11.
3. Type the following code at lines 12 and 13.

```
Run.LoadOC(%YOriginC\Tutorial.c); // %Y is user file folder

new_wks();
```

4. This code will load the **Tutorial.c** file we added in the previous section and run the **new_wks()** function.
5. Press the **Save** button .
6. Return to the Origin workspace. Click the **Custom Routine** button . A new worksheet will be created and filled with data as it was in the previous section.



	A(X)	B(Y)
Long Name	Index	Data
Units		
Comments		
1	1	0.1
2	2	0.2
3	3	0.3
4	4	0.4
5	5	0.5
6	6	0.6
7	7	0.7
8	8	0.8
9	9	0.9
10	10	1
11		
12		

12.2.3 The Code Builder Workspace

12.2.3.1 Summary

In this tutorial, we will create a workspace in the Code Builder of Origin, add a source file with a new function, then build, test and save the workspace file. Also, we will configure the appearance of the Code Builder.

Minimum Origin Version Required: Origin 2016 SR0

12.2.3.2 What you will learn

This tutorial will show you how to:

- Build a Workspace File

- Build Workspace Folders
- Build on Startup
- Configure Code Builder Interface
- Create an App Using Apps folder in Workspace
- Use Hot Key to speed up your work


12.2.3.3 The Workspace File

A workspace is a collection of files that can be opened by a single menu option (**File: Open Workspace...**) in Origin's Code Builder. Any text file can be a part of the collection. They do not necessarily have to be source code files; they could be notes, for example.


All files opened in the Multiple Document Window by a workspace can be edited and saved individually. In addition to files being opened in the Multiple Document Window, source code files can be added to the Workspace Window with the **File: Add to Workspace** menu option.

By including source code files in the Workspace Window, you can build individual or multiple files with the appropriate menu option or toolbar button. Header files can be referenced within source files and do not need to be loaded in the Workspace Window or even open in the Multiple Document Window. Since you can save a workspace with a new name, you can have multiple workspace files. However, only one workspace file can be opened at a time.

To create a workspace:

1. On the **Standard** toolbar, click the **Code Builder** button .
2. From the Code Builder menu, select **File: New Workspace**. This creates a new workspace with the default name of "Untitled.ocw".
3. From the Code Builder menu, select **File: New**. This opens the **New** File dialog.
4. Choose **C File**, and type **foo** in the **File Name** text box. The **Add to Workspace** and **Fill with Default Contents** check boxes should be selected. You may accept the default Location. Click **OK**.
5. In FOO.C, starting below the line that says "\\start your functions here", type the following:

```
void bar()  
  
{  
  
    printf("Hello World!\n");  
  
}
```

6. Click the **Build** button  (or use the hotkey **Shift+F8**). Origin automatically saves the source file and compiles and links the function.
7. From the Origin menu choose **Window: Script Window**.
8. To test our new function, type:


```
bar
```

9. Press **ENTER**

Origin responds by typing **Hello World!**

10. From the Code Builder menu, choose **File: Save Workspace As....**

The figure shows the foo.ocw workspace file containing a single source file, foo.c, in the Multiple Document Window. The file has been added to the Workspace Window. The Output Window shows that the file has been compiled. The source file contains a single function "bar ()" which is listed in the tree structure of the workspace.



12.2.3.4 Workspace Folders

The Code Builder workspace has six subfolders named Packages, Project, System, Temporary, User [AutoLoad] and User. Files added by user, such as foo.c that you just added, are placed in the User subfolder. Origin, itself, uses Origin C for many analysis routines. When these routines are accessed, the Origin C source files are loaded into either the System subfolder or the Temporary subfolder in the Workspace. The Project subfolder is reserved for files that are saved and loaded with the Origin project. This aspect of attaching a file to the project is described in a separate tutorial.

12.2.3.5 Build on Startup

If you right click on "Origin C Workspace", the shortcut menu has a **Build on Startup** option. When this option is checked, the last workspace you saved will be loaded when you restart Origin. All source files in the Workspace will be built and all functions in the source files will be available for immediate use.


For information on building individual source files on startup by including information in the ORIGIN.INI file, please view [Build on Startup](#)

This concludes the tutorial on the **Code Builder Workspace**.


12.2.3.6 Configure Code Builder Interface

User can configure code builder interface including the fonts and colors, the brackets color, the icons size and so on.


1. Open **Options** dialog in **Code Builder** by select **Tools: Options** in main menu. Go to the **Fonts and Colors** tab, change the **Theme** to **Dark**. An interface with dark background and light font is obtained. You can further adjust the font size or type in this dialog.




2. In **Options** dialog, go to the **General** tab, change the properties for **Enable Multiple Colored Brackets** to **True**. The nested "(" in code will be shown in multiple color.



3. Open **Customize** dialog in Origin's main interface by select **View: Toolbars** in main menu. Go to the **Options** tab and check on **Use Large Icons** box, then you can get large icons for buttons in Toolbars.



4. You can control the show or hide of each panel by selecting or unselecting them from **View** in main menu, the selected panel will be shown in **Code Builder**.




12.2.3.7 Create an App Using Apps folder in Workspace

To create an App package, you need to combine the use of **Apps** folder in Code Builder workspace and the [Package Manager](#). Following steps will show you how to create the package for an App.

1. On the **Standard** toolbar, click the **Code Builder** button  to open Code Builder.


Tutorials for Origin

2. Make sure **Workspace** window is open, if not you can select menu **View: Workspace** to open it. Right click on the **Apps** folder in **Origin C Workspace** and select **New** to add a new folder.




3. Right click on the newly added folder *Untitled* and select **Rename** to name the folder as "MyApp".


4. Right click on *MyApp* folder and select **Add Files...** to open **Add Files to Workspace** dialog. Browse to select all prepared files and click **Open** button to add them to current folder.



5. Right click *MyApp* folder to select **Generate** and you will be directed to the [Package Manager](#).



6. You can find the added files in the lower panel of **Package Manager**. Now you can input some basic information about *MyApp* under **Package** node as shown below. To make the App display as an icon in **App Gallery**, you need to prepare a 32*32 (in pixels) bmp image and input its name with extension in **Icon** edit box. Then you can input some LabTalk script in **Launch Script** field to tell Origin what to do when launching the App.



7. Select **File: Save** to save the package as an OPX file. Later you can drag and drop this OPX file into Origin workspace to install this App.

12.2.3.8 Frequently Used Hot Keys

The **Hotkey** in Code Builder make the coding work efficiency. The following parts introduce the useful hotkey one by one.

Firstly, please download [this zip file](#), extract it and then browse to the `\Origin C Examples\Programming Guide\Practical Examples` subfolder to add **AccessMatrix. c** by right-clicking the user folder and select "Add Files"**Ctrl+F2** and **F2**

Ctrl+F2 add a Toggle Bookmark at the specific line. You can use hotkey **F2** to go to next Toggle Bookmark.

```

57
58 //set and get Matrix data by vector
59 vector vDataRad; //declare a new vecto
60 int nRows, nCols;
61
62 nCols = MatData.GetNumCols(); //get the M
63 nRows = MatData.GetNumRows();
64
65 for(int ii = 0; ii < nRows * nCols; ii++)
66 {
67     vDataRad.Add(ran());
68     vDataRad[ii] *= 10;

```

- **Ctrl+F3** and **F3**

Ctrl+F3 highlight all the select word ("MatData") in code. You can use hotkey **F3** to go to the next highlighted "MatData".

```

Matrix MatData; //new Ma
MatData.Attach(ml);

MatData.SetSize(3,4); //set the

matrix mat = //declare
{
    {1, 2, 3, 4},
    {5, 6, 7, 8},
    {9, 10,11,12}
};

MatData = mat; //put the m

//set and get Matrix cell data
[2][3] = 100; //set one cell v

double dVal = MatData[1][3]; /
out_double("The Value on Corrid

//set and get Matrix data by ve
vector vDataRad; //declare a
int nRows, nCols;

nCols = MatData.GetNumCols(); /
nRows = MatData.GetNumRows();

```

- **Ctrl+]]**

This hotkey help you to go to matching brace in the code.

- **F9**

This hotkey add a Toggle Breakpoints at the specific line.

```

52 //set and get Matrix cell dat
53 MatData[2][3] = 100; //set o
54
55 double dVal = MatData[1][3];
56 out_double("The Value on Corr

```

- **Ctrl+/** and **Ctrl + Shift + /**

This hotkey **Ctrl+/** comment the selected lines, while **Ctrl + Shift + /** uncomment them.

- **Ctrl+Alt+O**

After constructing the *.c and *.h files with the same name, you can use hotkey **Ctrl+Alt+O** to switch between them.

```

// test.h
struct layer{
    double a1;
    double a2;
    double a3;
    double aw;
    double f1;
    double f2;
};

//test.c
#include <Origin.h>
#include "test.h"
////////////////////////////////////
int Main()
{
    layer S1;
    S1.a1 = 500.;
    S1.a2 = 2.;
    S1.a3 = 7.;
    S1.aw = 1.3;
    S1.f1 = 23.24;
    S1.f2 = 0.5;
    return 0;
}

```

Please refer to [Hotkeys in Code Builder](#) for more hotkeys information.

12.2.4 Adding New Origin C Functions to Origin

12.2.4.1 Summary

Functions written in Origin C are accessible from various locations within the Origin interface, such as the Script Window, provided they meet the following criteria: the function should return either void (as in the previous tutorial), double, string, or vectors of type double or string. Variables passed to the function from Origin should be of type double or string, or vectors of these types. Functions that do not meet these criteria are not callable from the Origin interface, but can be called within other Origin C functions. Note that although an Origin C function that accepts and returns type int can be called from the Origin interface, the data may be truncated since the interface only supports type double.

In this tutorial, you will be introduced to writing a math function that returns computed values. We will first create a function that returns type double to Origin, and then we will create a function that returns vectors of type double.

Minimum Origin Version Required: Origin 8.0 SR0

12.2.4.2 What you will learn

How to add a new function and how to run this function in the Script Window.

12.2.4.3 Steps

1. Start a new Origin C file in **Code Builder**.
2. Enter the following code:

```
double myfunc1(double x, double a)
{
    return sin( a * x );
}
```

3. Click the **Build** button  to compile the function.

This function can now be called from the Origin interface, in places such as the Script Window.

4. Go to the Script Window, and type in the following lines, pressing **ENTER** at the end of each line:

```
y = myfunc1(2, 3)
y =
```

You can also use worksheet cells instead of absolute numbers:

5. Make a worksheet active, enter a number in the first row of column A. Then type the following into the Script Window and press **ENTER**:


```
col(B)[1] = myfunc1(col(A)[1], 3)
```

Note that a function such as myfunc1, that accepts and returns type double, can also be used to perform vector operations.

6. Fill rows 1 through 10 of Column A with numbers, and type the following into the Script Window:

```
col(B) = myfunc1(col(A), 3)
```


In the above example, Origin calls the myfunc1 function for each row of column A. For performing vector operations as above, it is more efficient to write functions that accept and return vectors.

7. Go back to Code Builder and add the following function to the same file, and compile the file by clicking the **Build** button 

```
vector<double> myfunc2(vector<double> vecIn, double a)
{
    vector<double> vecOut;

    vecOut = sin( a * vecIn );

    return vecOut;
}
```

8. Go back to the Origin interface, fill Column A with some new numbers, and type the following into the Script Window:

```
col(B) = myfunc2(col(A), 3)
```

The function myfunc2 is called only once for computing the entire column.

Note that you can use such functions in other places such as the "Set Column Values" dialog. The Auto Update feature of "Set Column Values" can be enabled by checking the appropriate check box in this dialog. As long as the Origin C function is compiled and ready to be called from Origin, any changes to the source column will result in an update of the destination column.

12.2.5 Organizing and Accessing Origin C Functions

12.2.5.1 Summary

Techniques for using your Origin C functions.

Minimum Origin Version Required: Origin 8.0 SR0



12.2.5.2 What you will learn

This tutorial will show you how to:

- Save your Origin C Function with your Project
- Associate your Programs with Visual Objects
- Load and Compile your Origin C Function from script

12.2.5.3 Saving your Origin C Function with your Project

One way to load and compile your Origin C function is to save the Origin C file as an attachment to your Origin Project (*.OPJ) file. When a project file is opened, all files attached to it are separated out and stored in a temporary folder. In addition, any Origin C file that was attached is also automatically loaded into the Code Builder workspace, and compiled. The function is then ready to be called upon opening the Origin Project file.

1. Start a new Origin project file by clicking on the **New Project** button  on the **Standard Toolbar**.
2. On the **Standard Toolbar**, click the **Code Builder** button .
3. From the Code Builder menu, select **File: New**. This opens the **New File** dialog box.
4. In the top list-box, select **C File**.
5. In the **File Name** text box, type: **Test**. Keep the **Add to Workspace** check box selected. Click **OK**. The file Test.c is added to the workspace.
6. Select and copy the following function, and paste it into the Test.c file. Be sure to paste the text below the line that reads "//start your functions here."

```
void Plot_Data(string strTemplate, string strData)
{
    // Create a graph window from a Template

    GraphPage gp;

    BOOL bOK = gp.Create(strTemplate, CREATE_VISIBLE);

    if( !bOK )

        return;

    // Attach the first layer (0) to a GraphLayer object

    GraphLayer gl = gp.Layers(0);

    //Attach a dataset to a Curve object

    Curve crv(strData);
```

```

// Add the Curve to the graph layer

int nPlot = gl.AddPlot(crv);

if(nPlot >= 0)

{

    // Set plot color to Green(2)

    gl.DataPlots(nPlot).SetColor(2, TRUE);

    // Rescale this graph layer



    gl.Rescale();

}

}

```

The Plot_Data function takes two arguments: (1) the template name and (2) the name of a Y dataset to include (plot) in the layer.

7. Click the **Build** button  to compile and link the file.
8. Drag-and-drop the file Test.c from the User subfolder branch of the Workspace tree, to the Project subfolder. (**Hint:** You may need to first expand the User subfolder branch to display the Test.c entry prior to dragging the file).
9. Go back to the Origin interface and save the project by clicking the **Save** button  on the Standard Toolbar. Give the project the name Test.OPJ, and save it in a location of your choosing.
10. The Origin C file, Test.c, is now saved with the Project. To verify this, close the project, and go back to Code Builder. You will see that there are no entries under the Project subfolder of the Workspace tree. Now go back to Origin interface and reopen the project. Go to Code builder and verify that Test.c is now listed under the Project subfolder (**Hint:** you may need to expand the Project subfolder branch to see the Test.c entry).

12.2.5.4 Associating your Programs with Visual Objects

You will now learn how to create a button on a worksheet and program the button to call the Origin C function in the Test.c file that you saved with the project.

1. Open the Test.OPJ project that you saved under step 9 ([previous section](#)).
2. Highlight the A(X) and B(Y) columns, right-click and select **Fill Columns With: Row Numbers**.
3. From the menu, select **Format: Worksheet** to open the **Worksheet Properties** dialog box.
4. In the **Size** tab, **Worksheet Measurement** branch, set the **Gap from Top** to **40** and click **OK** to close the dialog.

	A(X)	B(Y)
Long Name		
Units		
Comments		
1	1	1
2	2	2
3	3	3
4	4	4
5	5	5
6	6	6


The worksheet now has sufficient space above the column headings to add a text label. Right-click in the area directly above the two columns and choose **Add Text**.

5. At the cursor, type: **Plot Data**.
6. Click once outside the text label to deselect it.
7. Right-click on the text label and choose **Programming Control** to open the **Programming Control** dialog box. (**Hint**: Please choose **Label Control** in Origin 7.5)
8. From the **Script, Run After** drop-down list, choose **Button Up**.
9. Type the following script in the text box at the bottom of the dialog box:

```
Plot_Data("scatter", "book1_b");
```

10. Click **OK**.

Your text label will now look like a button.



11. Click the **Plot Data** button on your worksheet.

12. The Plot_Data function in your Test.c file is called, and a scatter plot is created.

Notes: The script behind the button assumes that you have data in column B(Y) of the Data1 worksheet and that there is an associated X data set.

12.2.5.5 Loading and Compiling your Origin C Function from Script

In this tutorial we learned how to save an Origin C function along with the project file and then access the function from the Origin interface. Saving an Origin C file with a project limits access to functions within that file to only that project. When a new project is opened, the functions are not available any more.

To access functions in an Origin C file that is saved on disk, the file can be programmatically loaded and compiled using LabTalk script. The script command for performing the programmatic load and compile is run.LoadOC. Refer to the **LabTalk** Help files (**Help: Programming: Labtalk**) for more information on using this command.

This concludes the **Origin C Functions** tutorial.

12.2.6 **Tutorial: Calculating Double Integral with NAG Functions From Origin C**

12.2.6.1 Summary

Origin/OriginPro includes the complete NAG Mark 9 numerical library. This library provides multiple method for numerical integration. All functions are accessible from Origin C. In this tutorial, you will call NAG functions to perform the double integration. Note that an infinite NAG integrator is used here.

12.2.6.2 What you will learn

This tutorial will show you how to:

- Call NAG functions in Origin C
- Solve definite double Integral using the NAG integration routine

12.2.6.3 Example and Steps

To calculate the double integration. You need to call function in NAG library category [D01 Quadrature](#). This category provides functions for the numerical evaluation of definite integrals in one or more dimensions. Two function with different algorithm is available for double integral, which is [nag_multid_quad_adapt_1](#) and [nag_multid_quad_monte_carlo_1](#). In this tutorial, you will learn to use them to solve the integral formula below:

$$\int_0^1 \int_0^1 xy(x+y)dxdy$$

You are recommended to read the relevant tutorial [Calling NAG Functions From Origin C](#), to study how to run and test the code below for calculation. Then you can copy and paste the code into new created .c file in **Code Builder** and run the compile and build process. Below is the Origin C code with comments:

Using *nag_multid_quad_monte_carlo_1*

```
#include <Origin.h>

#include <OC_nag.h>

#define MAXCLS 20000 //maximum number of integrand evaluations to be allowed

double NAG_CALL f(Integer ndim, double x[], Nag_User *comm)

{

    return x[0]*x[1]*(x[0]+x[1]); //define the function formula

}
```

```
int multid_quad_monte_carlo()
{
    Integer exit_status = 0, k, maxcls = MAXCLS, mincls;

    Integer ndim =2; // the number of dimensions of the integral

    NagError fail;

    Nag_MCMethod method;

    Nag_Start cont;

    Nag_User comm;

    double a[2], b[2], acc, *comm_arr, eps, finest;

    comm_arr=NULL;

    if (ndim < 1){

        printf("Invalid ndim.\n");

        exit_status = -1;

        return exit_status;

    }

    for (k = 0; k < ndim; k++){

        a[k] = 0.0; // the lower limits of integration

        b[k] = 1.0; // the upper limits of integration

    }
}
```

Tutorials for Origin

```
eps = 0.01; //the relative accuracy required

mincls = 1000; //minimum number of integrand evaluations to be allowed

method = Nag_ManyIterations;

cont = Nag_Cold;

/* nag_multid_quad_monte_carlo_1 (d01xbc).

* Multi-dimensional quadrature, using Monte Carlo method,

* thread-safe

*/

nag_multid_quad_monte_carlo_1(ndim, f, method, cont, a, b, &mincls, maxcls,eps,
&finest, &acc, &comm_arr, &comm, &fail);

if (fail.code == NE_NOERROR || fail.code == NE_QUAD_MAX_INTEGRAND_EVAL){

    if (fail.code == NE_QUAD_MAX_INTEGRAND_EVAL){

        printf("Error from nag_multid_quad_monte_carlo_1
(d01xbc).\n%s\n",fail.message);

        exit_status = 2;

    }

    //output the calculation results

    printf("Requested accuracy = %7.2e\n", eps);

    printf("Estimated value = %7.5f\n", finest);
```



```

    printf("Estimated accuracy = %7.2e\n", acc);

    printf("Number of evaluations = %6d\n", mincls);
}

else{

    printf("Error from nag_multid_quad_monte_carlo_1
(d01xbc).\n%s\n", fail.message);

    exit_status = 1;
}

/* Free memory allocated internally */

if (comm_arr)

    NAG_FREE(comm_arr);

return exit_status;
}

```

Then you can call the functions in LabTalk Console. The results will be like this:

```

Requested accuracy = 1.00e-002

Estimated value = 0.33326

Estimated accuracy = 2.23e-004

Number of evaluations = 1552

```

Using *nag_multid_quad_adapt_1*

```

#include <OC_nag.h>

#include <Origin.h>

```

Tutorials for Origin

```
#define NDIM 2 //the number of dimensions of the integral

#define MAXPTS 1000*NDIM //maximum number of integrand evaluations to be allowed

double NAG_CALL f(Integer n, double x[], Nag_User *comm)

{

    return x[0]*x[1]*(x[0]+x[1]); //define the function formula

}

int multid_quad_adapt()

{

    Integer exit_status = 0;

    Integer ndim = NDIM;

    Integer maxpts = MAXPTS;

    double a[2], b[2];

    Integer k;

    double finval;

    Integer minpts;

    double acc, eps;

    Nag_User comm;

    NagError fail;
```

```

for (k = 0; k < 2; k++)

{

    a[k] = 0.0; //the lower limits of integration

    b[k] = 1.0; //the upper limits of integration

}

eps = 0.001;

minpts = 0;

nag_multid_quad_adapt_1(ndim, f, a, b, &minpts, maxpts, eps, &finval,&acc,
&comm, &fail);

if (fail.code != NE_NOERROR && fail.code != NE_QUAD_MAX_INTEGRAND_EVAL)

{

    printf("Error from nag_multid_quad_monte_carlo_1
(d01xbc).\n%s\n",fail.message);

    exit_status = 1;

    return exit_status;

}

//output the calculation results

printf("Requested accuracy = %7.2e\n", eps);

printf("Estimated value = %7.5f\n", finval);

printf("Estimated accuracy = %7.2e\n", acc);

```

Tutorials for Origin

```
    return 0;  
  
}
```

Then you can call the functions in LabTalk Console. The results will be like this:

```
Requested accuracy = 1.00e-003
```

```
Estimated value = 0.33333
```

```
Estimated accuracy = 3.33e-016
```

12.2.7 Tutorial: Calling NAG Functions From Origin C

12.2.7.1 Summary

Calling a NAG function from an Origin C function is very much like calling any other Origin C function. You must familiarize yourself with the desired NAG function to gain an understanding of what parameters the function requires to be passed as arguments and what parameters the function returns. Once familiar with the function, you must develop code that follows the function's requirements.

The NAG header file containing the function's prototype must be included, required parameters must be correctly declared, sized, and initialized, and the function call must follow the function's prototype as described in header file. The objective of this tutorial is to demonstrate how to call a NAG function from an Origin C function.

Minimum Origin Version Required: Origin 8.1 SR1

12.2.7.2 What you will learn

This tutorial will show you how to:

- Understand NAG functions
- Get Ready to Debug Sample Code
- Include the NAG Header
- How to See the Declaration of NAG Function
- How to Get NAG Error Code
- How to Use Function Pointer

12.2.7.3 Understand NAG Functions

The primary resource for understanding NAG functions is [NAG library](#). The library also can be found in Origin C Reference. For example, d01sjc NAG function:

1. From the Origin menu select Help:Programming:OriginC. In the Origin C Reference book, expand the Global Functions book, expand the NAG Functions book, and choose Accessing NAG Functions Category and Help.
2. Select Quadrature (d01) category and then select nag_1d_quad_gen_1 (d01sjc) function.
3. The selected page is one PDF file. Study the nag_1d_quad_gen_1 function as needed to understand the description of the function, the function's prototype, and the description of all arguments. Sample data and an example program calling the function are also often included.

Secondary resource for understanding the Origin C NAG functions is Examples book. From the Origin menu select Help:Programming:OriginC, expand Examples book, expand Analysis book, choose Accessing NAG Functions, there are some examples to show how to call NAG functions in Origin C.

12.2.7.4 Get Ready to Debug Sample Code

The best way to understand how to write an Origin C function that calls a NAG function is to step through an example function in Debug mode. Follow the steps below to set up Origin and Code Builder to execute such a sample Origin C function in Debug mode.

1. From the Code Builder menu, select **File: New**. This opens the **New File** dialog box.
2. In the **File Name** text box, type: **TestNAG**, Keep **Add to Workspace** checkbox is checked. Click **OK**. The file TestNAG.c is added to the workspace.
3. Select and copy the following function, and paste it into the TestNAG.c file. Be sure to paste the text below the line that reads "// Include your own header files here."

```
// Include your own header files here.

#include <OC_nag.h>

// Start your functions here.

//NAG_CALL denotes proper calling convention. You may treat it like a function
pointer

//and define your own integrand
```

Tutorials for Origin

```
static double NAG_CALL f_callback_ex(double x, Nag_User *comm)
{
    int *use_comm = (int *)comm->p;

    return (x*sin(x*30.0)/sqrt(1.0-x*x/(PI*PI*4.0)));
}

void nag_d01sjc_ex()
{
    double a = 0.0;

    double b = PI * 2.0; // integration interval

    double epsabs, abserr, epsrel, result;

    // you may use epsabs and epsrel and this quantity to enhance your desired
precision

    // when not enough precision encountered

    epsabs = 0.0;

    epsrel = 0.0001;

    // The max number of sub-intervals needed to evaluate the function in the
integral

    // The more difficult the integrand the larger max_num_subint should be

    // For most problems 200 to 500 is adequate and recommended

    int max_num_subint = 200;
```

```

Nag_QuadProgress qp;

NagError fail;

Nag_User comm;

static int use_comm[1] = {1};

comm.p = (Pointer)&use_comm;

//Note:nag_1d_quad_gen (d01ajc) has been replaced by nag_1d_quad_gen_1
(d01sjc) at Mark 25

d01sjc(f_callback_ex, a, b, epsabs, epsrel, max_num_subint,&result, &abserr,
&qp, &comm, &fail);

// For the error other than the following three errors which are due to bad
input parameters

// or allocation failure NE_INT_ARG_LT NE_BAD_PARAM NE_ALLOC_FAIL

// You will need to free the memory allocation before calling the
integration routine again to

// avoid memory leakage

if (fail.code != NE_INT_ARG_LT && fail.code != NE_BAD_PARAM && fail.code !=
NE_ALLOC_FAIL)

{

    NAG_FREE(qp.sub_int_beg_pts);

    NAG_FREE(qp.sub_int_end_pts);

```

Tutorials for Origin

```
        NAG_FREE(qp.sub_int_result);

        NAG_FREE(qp.sub_int_error);

    }

    printf("%10.6f", result);

}
```

12.2.7.5 Include the NAG Header


```
#include <OC_nag.h>
```

This header file containing all the header files of NAG functions, and all type define and error code define. So just include this one function should be enough.

12.2.7.6 How to See the Declaration of NAG Function

See the declaration of NAG functions from the header file:

1. Activate TestNAG.c file that created in above section, move scroll bar to find out #include <OC_nag.h> line.
2. Right click anywhere in the line and select **Open "OC_nag.h"**. This opens the NAG header file.
3. Move scroll bar to find out #include <NAG_MARK25\oc_nag_all.h> line, and also right click to select **Open "NAG_MARK25\oc_nag_all.h"**. This opens the header file containing all nag headers at Mark25.

4. In the Search combo box  type **nagd01.h** and press **ENTER** button to find out this line. Function **d01sjc** belongs to d01 category, so the header file name should be nagd01.h.
5. Right click anywhere of this line to choose **Open "nagd01.h"**. This opens the header file including the prototype of the functions.
6. In the Search combo box, type **d01sjc** and press **ENTER** button to go to the declaration of this function.

To see the declaration of functions from NAG PDF:

- [NAG PDF Online](#)
- [NAG PDF Files](#)

12.2.7.7 How to Get NAG Error Code


1. Reactivate the TestNAG.c window in Code Builder. In this file, the **NagError** variable **fail** is defined and passed as last argument to function **d01sjc**.
2. NAG function returns error code into NagError variable code item. In this example, can access NAG error code by **fail.code**.

How to know what error codes will be got:

3. Open Origin C Help from Origin menu **Help: Programming: OriginC**, expand Origin C Reference book, Global Functions book, NAG Functions book and choose Accessing NAG Functions Category and Help.
4. In **Chapters of NAG C Library** table, choose **d01** to enter Quadrature page, select d01sjc in the table of this category to open the PDF help of this NAG function.
5. Drag scall bar to page down to **6 Error Indicators and Warnings** part, there list all error codes for this function and the related description. Can directly use these error codes in Origin C if included correct header file (include <OC_nag.h>, this header containing all NAG headers), for example NE_INT_ARG_LT, NE_BAD_PARAM, NE_ALLOC_FAIL used in TestNAG.c file.

12.2.7.8 How to Use Function Pointer

1. Open nagd01.h file from Origin program path \OriginC\system\NAG_MARK25 folder.
2. In this file, find out the declaration of **d01sjc** function. The first argument type of this function is **NAG_D01SJC_FUN**.
3. Double-click **NAG_D01SJC_FUN** to high-light it. From menu choose **Edit: Find in Files** to open **Find in Files** dialog. Set settings same as the following picture, click Find button.



4. Searching result display in Output window. Double click nag_types.h line to go to this file, **typedef NAG_D01_TS_FUN NAG_D01SJC_FUN** line, you can find the define of NAG_D01_TS_FUN nearby.
5. The define of NAG_D01_TS_FUN is

```
typedef double (NAG_CALL * NAG_D01_TS_FUN)(double, Nag_User *comm);
```

6. User defined function should keep the same return type and argument list as this define. And **NAG_CALL** denotes proper calling convention and it should be used in your own function.
7. Activate TestNAG.c file. There is a function named **f_callback_ex** and it used as function pointer in **d01sjc** as the first argument.

```
double NAG_CALL f_callback_ex(double x, Nag_User *comm)
{
    int *use_comm = (int *)comm->p;

    return (x*sin(x*30.0)/sqrt(1.0-x*x/(PI*PI*4.0)));
}
```

12.2.8 Accessing Internal Origin Objects by Origin C

12.2.8.1 Summary

Internal Origin objects (such as Project Explorer folders, Origin windows (pages), layers, plots, graphic objects, data sets, etc.) are accessed using Origin C classes. To access or programmatically control an internal Origin object, you must attach it to an Origin C object.

To attach something to an internal Origin object you must first "find" it using the properties, methods, and collections of a container class. Common container classes include the Project, Folder, Page, GraphPage, Layer, GraphLayer, Worksheet, MatrixLayer, and Collection classes. Once found, an internal Origin object can easily be attached to an Origin C object of the appropriate type.

The internal Origin object is then programmatically controlled by manipulating the class methods and properties of the attached Origin C object. The objective of this tutorial is to demonstrate how to find particular internal Origin objects, attach things to those objects, and access the objects by manipulating the methods and properties of the attached Origin C objects.

Minimum Origin Version Required: Origin 8.1 SR1

12.2.8.2 What you will learn





This tutorial will show you how to:

- Access Worksheet Related Objects
- Access Graph Related Objects

12.2.8.3 Accessing Worksheet Related Objects


Familiarity with the Origin C Project class (Project.h), the Collection class (Collection.h), and the Folder class (Folder.h), is valuable when attempting to understand how to find particular internal Origin Objects. Users may find it helpful to preview these classes in the **Origin C Reference: Classes** book of **Origin C Help** or in the above header files located in the ..\Origin\OriginC\system subfolder.

To begin this tutorial:

1. Download [this zip file](#), extract it.
2. On the **Standard** toolbar, click the **New Project** button .
3. On the **Standard** toolbar, click the **Code Builder** button .
4. On the **Code Builder** menu, select **File: New Workspace**.
5. On the **Code Builder** menu, click the **Open** button .
6. Open the unzipped folder created at step 1, browse to the `\Origin C Examples\Programming Guide\Introduction to Accessing Origin Objects` folder in the Origin software directory, select `AccessWorksheetObjectsTutorial.c`, check the **Add to Workspace** check box and click **Open**.
7. On the **Code Builder** toolbar, click the **Rebuild All** button . This compiles and links the file.
8. On the Code Builder **View** menu, verify that the **LabTalk Console** (Command & Results) and the **Local Variables** windows are visible (the corresponding menu items should be checked).
9. From the **Code Builder** menu, select **Tools: Customize**. Select the Toolbars tab and make sure that the **Debug** toolbar check box is selected.
10. In Code Builder, activate `AccessWorksheetObjectsTutorial.c`.
11. Near the top of the file, locate and click on the line:

```
PageBase pb;
```

You can position the cursor anywhere on the line.

11. From the Code Builder menu, select **Debug: Toggle Breakpoints**. Alternately, press **F9** or click the **Toggle Breakpoint** button  on the **Debug** toolbar.


A brown circle is displayed in the gray margin to the left of the above line indicating that a Debug breakpoint has been set for that line.



Tutorials for Origin


12. In the Code Builder workspace, activate the LabTalk Console (Command & Results window) and type in the following:

```
AccessWorksheetObjectsTutorial
```




13. Press **ENTER** to execute the function.



14. On the **Debug** toolbar, press the **Step Into** button 
15. Press the **Step Into** button  repeatedly, stopping to read the comments for each statement. Periodically stop and resize and/or reposition the Local Variables window to view the current run-time value of each variable.




12.2.8.4 Accessing Graph Related Objects

1. Return to the *Origin* workspace and, on the **Standard** toolbar, click the **Open** button .
2. Browse to the \Samples\Origin C Examples\Programming Guide\Introduction to Accessing Origin Objects subfolder, select AccessGraphObjectsTutorial.OPJ, and click **Open**. You may be prompted to save changes to an untitled project. Click **No** and a worksheet and graph should open.
3. From the Code Builder menu, select **File: New Workspace**. Click **No** when prompted to save workspace changes.
4. In Code Builder, click the **Open** button .
5. Browse to the \Samples\Origin C Examples\Programming Guide\Introduction to Accessing Origin Objects subfolder, select AccessGraphObjectsTutorial.c, select the **Add to Workspace** check box, and click **Open**.
6. Click the **Rebuild All** button  to compile and link the file.

7. On the Code Builder **View** menu, verify that the **LabTalk Console** (Command & Results) and the **Local Variables** windows are visible (the corresponding menu items should be checked).
8. From the Code Builder menu, select **Tools: Customize**. Select the Toolbars tab and make sure that the **Debug** toolbar check box is selected.
9. In the Code Builder workspace, activate `AccessGraphObjectsTutorial.c`.
10. Near the top of the file locate and click on the line:

```
GraphPage gp;
```



You can position the cursor anywhere on the line.

11. From the Code Builder menu, select **Debug: Toggle Breakpoints**. Alternately, press **F9** or click the **Toggle Breakpoint** button  on the **Debug** toolbar.

A brown circle is displayed in the gray margin to the left of the above line indicating that a Debug breakpoint has been set for that line.

12. Activate the LabTalk Console (Command & Results window) in Code Builder and type the following:

```
AccessGraphObjectsTutorial
```

13. Press **ENTER** to execute the function.
14. On the **Debug** toolbar, press the **Step Into** button .
15. Press the **Step Into** button  repeatedly, stopping to read the comments for each statement. Periodically stop and resize and/or reposition the Local Variables window to view the current run-time value of each variable.

This concludes the **Internal Origin Objects** tutorial.

12.2.9 Create and Update Apps for Origin

12.2.9.1 Summary

Apps are custom applications for Origin that perform specific graphing and/or analysis tasks. Origin users can browse for Apps and download and install them from the [File Exchange](#) area of the OriginLab website. Origin users can also create Apps and share with other on File Exchange. This tutorial provides the guidelines for making an App and detailed steps to build, upload and modify an App.

12.2.9.2 What you will learn

This tutorial will show you how to:

- Build an App
- Upload an App to File Exchange Website
- Modify an App and Submit for Approval

12.2.9.3 App Files Specifications

The following files are supported/needed for Apps:

Icon files

Icon file (Required)

This should be a png file with size of 32*32 in pixels. This icon will be displayed in the [Apps Gallery](#) window in Origin.

Small icon file (Optional)

This should be a bmp file with size of 16*16 in pixels, and 16 color (4 Bits). It will be available from **View: Toolbars: Apps button group** in Origin. It can be used as a button, by adding to a toolbar.

Programming files

X-Function, *.ogs, *.c, *.h and DLL files are supported. Note that X-Function file name should not be the same as *.c file name if both exist.

Other files

Any other files such as documentation (*.chm, *.pdf), image files, sample data, etc, can be included.

12.2.9.4 Building an App

1. Locate the **Apps** folder under the **AppData** area of your Origin installation. You can enter the following command in Command/Script Window to locate this folder:


```
%@A=; // The output can be, e.g., C:\Users\XXX\AppData\Local\OriginLab\Apps\
```

2. Open the folder in the path found in step1, create a subfolder in this location. Note that the subfolder name will be used as your App name. Place all your files for the App in this subfolder.


3. Start Origin and click **Code Builder** button  in Origin main interface.

4. In **Code Builder** window, right click on the **Apps** folder in the left **Workspace** panel. Select **Add Existing Folder** from the shortcut menu and browse to add the folder created in step 2. Expand the folder in Workspace panel. All files in the folder will be listed.

Note that if you have no existing App folder, you can choose **New** from the shortcut menu to create a new sub-folder in Apps folder. If you right click on a file, you can choose to remove the file. Right click on the folder, and you can add more files, even files not located in current folder.



5. Right click on the newly created App folder in Code Builder's Workspace panel, and choose **Generate** from the shortcut menu. It will open the **Package Manager** dialog.



6. In **Package Manager** dialog, do the following:

- **Package branch:**

- **Name**

- Do not change the **Name** field, otherwise the folder name will also be changed.

- **Description**

- Input descriptions of the App in this field. The descriptions will be shown in the file exchange web's **Summary** section.

- **Version**

- Set current App version. You can use two decimal digits, e.g. 1.11.

Origin Version Required

Set the required Origin version. For Origin 2016, you should type 9.3 instead of 2016.

- **App branch:**

Icon

Set it to file name for icon to be displayed in Apps Gallery window.

Icon (Small)

Set it to file name for small icon used in toolbar.

Launch Script


LabTalk script to run after you click the App icon. If you want to open an X-Function dialog, you can write your script such as: `xfname -d`; You can also have your script point to a section in ogs file, and run that section, e.g. `run.section(%Afoldername\ogsname,sectionname)`.

Enable by Window

Specify the active window type(s) for which the App should be enabled. e.g. for Latex App, Graph window should be active.

- **LabTalk Script branch:**

Specify LabTalk script for before, after installation and before uninstalling.



7. When settings are done in **Package Manager**, click **File: Save** from the menu. The .opx file will be saved. The opx name can be different from the folder name. The opx file for an App is ready now. You can simply drag-and-drop the file onto Origin to install. Note that you may need to run Origin **not as administrator** to be able to drop the file onto Origin.

Uploading App to File Exchange Website

When the App package file is ready, you can upload it to File Exchange website to share with the public. To do it, follow the steps below:

1. Go to [File Exchange Website](#), click **Submit a file** on the bottom right to open **Submit File** page. Select **File Type** as **App** and fill in other needed information, **File Category**, **Created using Origin:**, etc. Note the information contained in the App package will be automatically extracted, such as, **Minimum Origin Version Required**, **Title**, **Summary**.
2. Upload the App OPX package file, screenshot image, click **Submit** button to submit your App and create a File Exchange tool page for it.

3. You can then download the OPX file from the web page you have created, and drag-and-drop onto Origin to test it. A package ID will be assigned to the opx during the download process.
4. You can continue editing the web page for your App. Once finished, you can click **Update** button to update the web page.
5. When you are ready to publish your App, press the **Request Approval** button on the bottom of **Update** form. You will be notified by OriginLab through email when your App has been approved. The approval status is also shown on the **Update File** page as indicated by **OriginLab Tested**, **OriginLab Approved** checkboxes.
6. Once your App got approved, it will be automatically shown on the **Tools: Apps on file Exchange** menu list.

Modifying an App

Modify App Settings

1. Select **Tools: Package Manager** from Origin menu. Select **Tools: Browse Installed Package in Package Manager** dialog's menu. Select the App and click **Open** button.
2. You can change the settings in the dialog. If your files in the folder are modified, you can click **Repack Files** button.
3. Click **File: Save** to save the App OPX package.


Add, Remove or Change Files in App Folder

When you need to add files, remove files or change file names in App folder, you can perform these operations by right clicking on the App folder in the **Workspace** panel on [Code Builder](#) and selecting corresponding option from the shortcut menu. When done, click **Generate** from the shortcut menu to regenerate the App package.

Note that when removing files or changing file names, original files should be kept in the App folder under path `C:\Users\XXX\AppData\Local\OriginLab\Apps\` even if they are not being used, otherwise old settings in the opx will not be kept in **Package Manager** dialog when you click **Generate** button.

Upload Modified OPX to File Exchange Page

Log in Origin website, go to the File Exchange page you have created for your App and upload the updated OPX file to the File Exchange page. Update the web page as needed, including notes on what has been updated in current App version. Users would know this update from menu **Tools: Apps on File Exchange: * YourApp (installed)** as indicated by the asterisk symbol * if this App was previously installed.



Request Approval from OriginLab

Click the **Request Approval** button in the File Exchange webpage of your App and wait for OriginLab to notify you.

12.3 X-Functions

12.3.1 X-Functions

- [Command Window and X-Functions](#)
- [Introduction to X-Functions](#)
- [How to Create a Wizard](#)

12.3.2 Command Window and X-Functions

12.3.2.1 Summary

Many of Origin's analysis tools and other data processing tools have been implemented using X-Functions. The Command Window provides a convenient way to run these functions.

Another important use for the Command Window is to send LabTalk script commands to Origin. Script commands can range from simple math and data operations, to user-created X-Functions or Origin C functions.

Minimum Origin Version Required: Origin 8.0 SR6


12.3.2.2 What you will learn

This tutorial will introduce you to the Command Window and show you how to:

- Perform simple calculation
- Access worksheet cells/columns
- Access X-Functions

12.3.2.3 Command Window

The Command Window consists of two panels: the **Command Panel** and **History Panel**:



The Command Window is normally located at the bottom right corner of the screen, but if it is not visible, you can access it by pressing **Alt+3** or by selecting **View: Command Window**.

When typing in the Command Panel, the Auto Complete support allows you to choose among X-Function script commands and OGS files in the current working folder. The command and OGS file

name will be respectively preceded by Xf and LT. You can move up and down the list using the arrow keys; pressing Enter selects the item. After your selection, press the space bar and the Auto Complete now shows you the available options for the command.

12.3.2.4 Examples

Perform Calculations

The Command Window can be used as a calculator or to access any of Origin's mathematical functions. See the examples below.


Single Line

One of the more basic uses for the Command Window is as an interface to perform simple calculations. For example, type the following:

```
2+2=
```

Press **ENTER**. Origin returns

```
2+2=4
```



Multiple Lines

If you are typing multiple lines of scripts, first edit it in Code Builder (**View:Code Builder**) or any text editor, such as Windows Notepad, ending each line with a semi-colon, and then Copy + Paste the script in the Command Window, and press **ENTER** to execute. For example, paste the following script in the Command Window and **ENTER**:

```
sum = 0;

loop(ii, 1, 10)


{

    sum += ii;

}

sum = ;
```

Origin returns: SUM=55




Functions

Any mathematical function, built-in as well as user-created, can be executed from the Command Window. For example, type:

```
ln(10) =
```

Origin returns natural logarithm value of 10.



Access Worksheet Values

You can also use the Script Window to read and write worksheet values, or to perform math operations on datasets.

1. Enter the following data into a fresh worksheet:

The screenshot shows a worksheet window titled 'Book1' with a table containing the following data:

	A(X)	B(Y)
Long Name		
Units		
Comments		
1	1	6
2	2	7
3	3	8
4	4	9
5	5	10

2. To return the value in the first cell of the second column, type the following:

```
cell(1,2)=
```

3. Press **ENTER**. Origin returns: CELL(1,2)=6

You can also use the column name and row number to reference cell values.

4. Type the following:

```
col(B)[1]=
```

5. Press **ENTER**. Origin returns: COL(B)[1]=6


Notes: In addition to using the column name, you can also use the dataset name. In LabTalk, the syntax for naming datasets is *worksheetName_columnName*. So, For example, *Book1_A[1]=* would return the first element of column A in worksheet Data1. Also, if the worksheet that you are referencing is the active window, you can use the LabTalk string variable %H, in place of the worksheet name. For example, %H_A[1].

To subtract the value in row 1 of column A, from all the values in column B...

6. Type the following:

```
col(B)=col(B)-col(A)[1]
```

7. Press **ENTER**. Your worksheet now reads:



	A(X)	B(Y)
Long Name		
Units		
Comments		
1	1	5
2	2	6
3	3	7
4	4	8
5	5	9

Let's use what we have learned about executing multiple lines of script in the Script window. We will multiply every value in a column of data by some constant b.

8. Type the following:

Tutorials for Origin

```
b=3;
```

Press **CTRL+ENTER**. Recall that this gives us a carriage return without executing the command.

9. Now type:

```
col(A)=col(A)*b;
```

Again, Press **CTRL+ENTER**.

10. Choose **Edit** from the Script window's menu bar. **Script Execution** should have a check mark next to it; if not, single-click on the menu item to place a check mark there.

11. Now, select the two lines of script that you just entered into the Script window and press **ENTER**.

Your worksheet now reads:

	A(X)	B(Y)
Long Name		
Units		
Comments		
1	3	5
2	6	6
3	9	7
4	12	8
5	15	9

Notes: The following C notation is also supported:

```
b=3;
```

```
col(A)*=b;
```


You can also use linear interpolation or extrapolation on a specified *X dataset* to find the corresponding interpolated or extrapolated value in a *Y dataset*. This requires using a new notation with parentheses () instead of brackets [].

In this example, book1_b is a Y dataset and (4) is a value in an X dataset (book1_a) for which you want to find a corresponding, interpolated Y value.

12. Type the following:

```
book1_b(4) =
```



13. Press **ENTER**. Origin returns: BOOK1_B(4)=5.333333



This is a line plot of our simple worksheet data. You can see that our interpolated Y value – the one corresponding to X = 4 – is 5.333333.

14. If the columns you work with are in different worksheet/workbook, you should use the range variables to represent the worksheet columns. For example, this script calculates the sine value on Book1 column A, and puts the result in Book2 column A (You must have Book2 before hitting Enter):

```
range a = [Book1]Sheet1!Col(A);  
  
range b = [Book2]Sheet1!Col(A);  
  
b = sin(a);
```



Access X-Functions

Origin 8 provides a large collection of X-Functions for performing a wide variety of data processing tasks. Of this collection, many of the X-Functions are accessible from LabTalk script. The functions accessible from script provide a powerful environment for users to create custom script code for their routine tasks.


X-Functions that are accessible from script can be listed in the Command Window, and you can also obtain help on the command syntax as well as make use of auto completion of commands for such functions.

X-Functions accept data range string or range variable for specifying source and destination data for the operation. For example, the smooth X-Function under signal processing can be accessed from the Command Window as follows:

1. Import the file `\Samples\Signal Processing\Signal with Shot Noise.dat`.
2. In the Command Window, type the following:

```
smooth iy:=Col(2) method:=1 npts:=200
```

- When you press **ENTER**, the result will append to the source worksheet.



- For help in using this smooth X-Function, you can type

```
help smooth
```

- to open the corresponding Help.

12.3.3 Introduction to X-Functions

12.3.3.1 Summary

X-Functions provide a structured programming environment that offers a framework for building Origin tools. Different from the simple GetN box, creating tools by using X-Functions allows the user to focus on the actual data processing code and not have to worry about codes for the user interface. Most of the dialogs/functions in Origin 8 are X-Functions, and many of them can be run from both menu and command line mode. The flexibility of running X-Functions makes them an attractive approach to customizing Origin

Minimum Origin Version Required: Origin 8.0 SR0


12.3.3.2 What you will learn


- How to create an X-Function
- How to make the X-Function script accessible

- How to use the X-Function in dialog mode

12.3.3.3 Create an X-Function

1. Select **Tools: X-Function Builder** or press **F10** to open the **X-Function Builder** dialog
2. Set **Name**, **Label** and **Data** of the 1st variable as **ix**, **Source** and **<active>**
3. Right click in the list panel and select **Add Variables** from the context menu.
4. Set **Name**, **Label**, **Input/Output** and **Data** of the 2nd variable as **ox**, **Destination**, **Output** and **<new>**
5. Select **File:Save** to save the x-function as vcopy



6. Click  to open **Code Builder**
7. Add the following codes in the vcopy function in code builder

```
void vcopy(const vector& ix, vector& ox)



{


    if (!ix || !ox)
        XF_THROW(CER_NO_DATA);

    ox = ix;
```

}

12.3.3.4 Making the X-Function Script Accessible

1. Click the **Return to Dialog** button in **Code Builder**
2. In the **X-Function Builder**, save your changes 
3. Open the X-Function in **Tree View** by clicking 
4. Open the **Usage Context** branch. Make sure the **Labtalk** check box is selected




5. Save the x-function and close the **X-Function Dialog**
6. Fill column(A) with row numbersw in the active worksheet (Highlight column(A), right-click and select **Fill Column with: Row Numbers**)
7. Type the following script in the command window, Column(A) will be copied to Column(B)


```
vcopy col(a) col(b)
```

12.3.3.5 Using the X-Function in Dialog Mode


1. Open the **X-Function Dialog** and open VCOPY.OXF in **Tree View**

2. Open the **Usage Context** branch
3. Open the **Menus** branch, make sure **Simple GetNBox** is selected from the **Auto GetN Dialog** list box



4. Save the x-function and close the **X-Function Dialog**
5. Type following script in the command window, Dialog of VCOPY.OXF will be opened

```
vcopy -d
```



12.3.4 How to Create a Wizard

12.3.4.1 Summary

A wizard is a graphical user interface that includes a series of dialogs to direct a user to complete a mission step by step. A wizard makes a complex task easier to perform. Origin provides several classes in Origin C for users to develop a wizard. The dialog for each step in the wizard can be created using an X-Function.

In this example, the wizard will perform a normality test and then a one-sample t-test for data in a column. The normality test's result can be shared in one-sample t-test.

Note: This tutorial requires [the Develop Kit](#).

Minimum Origin Version Required: Origin 8.1SR0


12.3.4.2 What you will learn

- How to create an X-Function.
- How to share a variable or a DataRange in different steps.
- How to call an X-Function in OriginC.
- How to create a wizard.


12.3.4.3 Create four X-Functions

1. Select **Tools: X-Function Builder** or press **F10** to open **X-Function Builder dialog**


2. Add the variables as follows and save the X-Function as "StatTest" in the User Files folder, User Files\X-Functions\Statistics\Hypothesis Testing.




3. Click the **New X-Function Wizard** button. Add the variables as follows and save the X-Function as "StatTestWizGoal" in the User Files folder, User Files\X-Functions\Statistics\Hypothesis Testing.



- Click the **New X-Function Wizard** button. Add the variables as follows and save the X-Function as "NormalityTest" in the User Files folder, User Files\X-Functions\Statistics\Hypothesis Testing.




- Click the **New X-Function Wizard** button. Add the variables as follows and save the X-Function as "OnetTest" in the User Files folder, User Files\X-Functions\Statistics\Hypothesis Testing.




Note that the X-Functions **NormalityTest** and **OnetTest** have the same variable "prob", which is a shared variable and will be declared in the source file.

12.3.4.4 Update X-Function's Property in Tree View

1. Open the X-Function **StatTest**. Click the **TreeView** button  to open the Tree View. Make the following settings in the Tree View.



2. Click the **Save OXF file** button to save the X-Function.
3. Open the X-Function **StatTestWizGoal**, **NormalityTest** and **OnetTest** respectively in X-Function Builder. Click the **TreeView** button  and type "Select Wizard Goal", "Normality Test" and "One-Sample t-test" in the **Description** edit box of each X-Function's Tree View, which will be shown in the dialogs.

12.3.4.5 Create Files for the Wizard

- Click the **Code Builder** button on the **Standard** toolbar. In Code Builder, click the **New** button. In the **New File** dialog, select **H File**, click the **Browse** button, and select the User Files folder, User Files\OriginC as the new header file's **Location**. Then type StatTestWiz in the **File Name** edit box. Click **OK** to close the dialog.

Add the following script to StatTestWiz.h file.

```
#ifndef __STAT_TEST_WIZ_H__

#define __STAT_TEST_WIZ_H__

#include <..\OriginLab\XFWiz.h>

#include <..\OriginLab\XFCore.h>

#include <..\OriginLab\XFWizard_utils.h>

class StatTestWizCore : public XFCore

{

public:

    StatTestWizCore();

public:

    void ChangeGoal(int nGoal);

    DataRange GetRange();

    int nStep;

protected:

};
```

Tutorials for Origin

```
int stat_test_run_wiz_nodlg(LPCSTR lpszThemeName = NULL, const XFWizTheme
*pXFWizTheme

= NULL, const XFWizInputOutputRange *pXFWizIO = NULL, DWORD dwOPUID = 0);

int stat_test_open_wiz_dlg(LPCSTR lpszThemeName = NULL, const XFWizTheme
*pXFWizTheme

= NULL, const XFWizInputOutputRange *pXFWizIO = NULL, DWORD dwOPUID = 0);

#endif // __STAT_TEST_WIZ_H__
```

Click the **Save** button to save StatTestWiz.h file.

- Repeat the same operation to create a new **C File**, StatTestWiz.c .

Add the following script to StatTestWiz.c file.

```
////////////////////////////////////

#include <..\OriginLab\XFWizManager.h>

#include <..\OriginLab\WizOperation.h>

#include <..\OriginLab\XFWizNavigation.h>

#include <..\OriginLab\XFWizScript.h>

#include <..\OriginLab\XFWizDlg.h>

////////////////////////////////////

// Include your own header files here.
```

```

#include "StatTestWiz.h"

enum

{

    GOAL_ALL = 0,

    GOAL_SIMPLE,

};

//Names of three X-Functions

#define STR_STEP_GOAL    "StatTestWizGoal"

#define STR_STEP_Normal "NormalityTest"

#define STR_STEP_TTest  "OnetTest"

//Names of steps shown in the wizard.

#define STR_LABEL_STEP_GOAL    "Goal"

#define STR_LABEL_STEP_Normal  "Normality Test"

#define STR_LABEL_STEP_TTest   "One-Sample t-test"

////////////////////////////////////

//Class StatTestWizTheme

class StatTestWizTheme : public XFWizTheme

{

```

Tutorials for Origin

```
public:

    StatTestWizTheme ();

};

//Name of the variable prob shared by X-Functions NormalityTest and OnetTest

#define STR_GETN_VAR_SHARED_NProb "prob"

StatTestWizTheme::StatTestWizTheme ()

:XFWizTheme ()

{

    m_saSharedList.Add(STR_GETN_VAR_SHARED_NProb); //Add the shared variable

}

////////////////////////////////////

class StatTestWizInputOutputRange : public XFWizInputOutputRange

{

};

////////////////////////////////////

//Class StatTestWizManager

#define STR_CLASS_NAME_TEST "StatTestWiz"
```

```

#define TEST_VERSION_NUMBER    1.0

class StatTestWizManager : public XFWizManager
{
public:
    StatTestWizManager(LPCSTR lpszThemeName = NULL, const XFWizTheme *pXFWizTheme
= NULL, const XFWizInputOutputRange *pXFWizIO = NULL, DWORD dwUIDOp = 0);

protected:
    virtual double GetVersion() { return TEST_VERSION_NUMBER; }

    virtual XFCore* CreateXFCore() { return new StatTestWizCore; }

    virtual XFWizTheme* CreateXFWizTheme() { return new StatTestWizTheme; }

    virtual XFWizInputOutputRange* CreateXFWizInputOutputRange()
        { return new StatTestWizInputOutputRange; }

    virtual string GetClassName() { return STR_CLASS_NAME_TEST; }
};

StatTestWizManager::StatTestWizManager(LPCSTR lpszThemeName, const XFWizTheme
*pXFWizTheme, const XFWizInputOutputRange *pXFWizIO, DWORD dwUIDOp)
: XFWizManager(lpszThemeName, pXFWizTheme, pXFWizIO, dwUIDOp)
{
    StringArray saMapXFNames = {STR_STEP_GOAL, STR_STEP_Normal, STR_STEP_TTest};

```

Tutorials for Origin

```
StringArray saMapXFLabels = {STR_LABEL_STEP_GOAL, STR_LABEL_STEP_Normal,  
  
                             STR_LABEL_STEP_TTest};  
  
m_saMapXFNames = saMapXFNames;  
  
m_saMapXFLabels = saMapXFLabels;  
  
ASSERT( m_saMapXFNames.GetSize() == m_saMapXFLabels.GetSize() );  
  
StringArray saDefaultXFNames = {STR_STEP_GOAL, STR_STEP_Normal, STR_STEP_TTest};  
  
m_saDefaultXFNames = saDefaultXFNames;  
  
m_strRunDlgName = _L("Stat Test");  
}  
  
////////////////////////////////////  
  
//Class StatTestWizCore  
  
StatTestWizCore::StatTestWizCore()  
  
:XFCore()  
  
{  
  
    StringArray vsXFsRecalculateShown = {STR_STEP_GOAL};  
  
    m_vsXFsRecalculateShown = vsXFsRecalculateShown;  
  
    nStep = GOAL_ALL;  
  
}
```



```
//Select steps in the Goal Step

void StatTestWizCore::ChangeGoal(int nGoal)

{

    XFWizNavigation *pXFWizNavg = (XFWizNavigation *)GetXFWizNavigation();

    ASSERT(pXFWizNavg);

    nStep = nGoal;

    if ( pXFWizNavg )

    {

        StringArray saXFNames;

        saXFNames.Add(STR_STEP_GOAL);

        switch (nGoal)

        {

            case GOAL_ALL:

                saXFNames.Add(STR_STEP_Normal);

                saXFNames.Add(STR_STEP_TTest);

                break;

            case GOAL_SIMPLE:

                saXFNames.Add(STR_STEP_TTest);

                break;

        }

    }

}
```

Tutorials for Origin

```
    }

    pXFWizNavg->SetSteps(saXFNames);

}

}

//Get input DataRange in the Goal Step.

DataRange StatTestWizCore::GetRange()

{

    XFWizNavigation *pXFWizNavg = (XFWizNavigation*)GetXFWizNavigation();

    XFWizInputOutputRange* pIORange = pXFWizNavg->GetXFWizInputOutputRange();

    DataRange drInput;

    if(!pIORange)

    {

        error_report("Fail to get io ranges!");

        return drInput;

    }

    Array<DataRange&> drs;

    //Get input DataRange.
```

```

if(!pIORange->Get(&drs, STR_STEP_GOAL, true))

{

    error_report("Fail to get range from WizCore!");

    return drInput;

}

drInput = drs.GetAt(0);

return drInput;

}

////////////////////////////////////////////////////////////////////////////////////////////////////////////////////////////////

int stat_test_run_wiz_nodlg(LPCSTR lpszThemeName, const XFWizTheme *pXFWizTheme,
const
XFWizInputOutputRange *pXFWizIO, DWORD dwOUID)

{

    TEMPLATE_run_wiz_nodlg(StatTestWizManager, lpszThemeName, pXFWizTheme,
pXFWizIO, dwOUID)

}

int stat_test_open_wiz_dlg(LPCSTR lpszThemeName, const XFWizTheme *pXFWizTheme,
const

```

Tutorials for Origin

```
XF WizInputOutputRange *pXF WizIO, DWORD dwOPUID)

{

    TEMPLATE_open_wiz_dlg(StatTestWizManager, lp szThemeName, pXF WizTheme, pXF WizIO,
dwOPUID)

}

int stat_test_run_wiz(UINT msg, const XF WizTheme *pXF WizTheme, const
XF WizInputOutputRange *pXF WizIO, DWORD dwOPUID, int nExeMode)

{

    TEMPLATE_run_wiz(StatTestWizManager, msg, pXF WizTheme, pXF WizIO, dwOPUID,
nExeMode)

}
```

Click the **Save** button to save StatTestWiz.c file.

Note that StatTestWiz.c should be compiled after the X-Function **StatTest** is compiled, since the included files in StatTestWiz.c are not yet in the workspace until the X-Function **StatTest** is compiled. In fact StatTestWiz.h is included in X-Function **StatTest**, so StatTestWiz.c will be compiled automatically when X-Function **StatTest** is compiled.

12.3.4.6 Add Script for X-Functions

Script for X-Function StatTest

In the **X-Function Builder**, click the **Open** button and open the X-Function StatTest. Click the **Edit X-Function in Code Builder** and add the following script.

- Include header files

```
#include <..\OriginLab\XF Wiz.h>

#include <..\OriginLab\WizOperation.h>

#include <..\OriginLab\XF Core.h>

#include <..\OriginLab\XF WizNavigation.h>
```

```

#include <..\OriginLab\XFWizManager.h>

#include <..\OriginLab\XFWizScript.h>

#include <..\OriginLab\XFWizDlg.h>

#include <..\OriginLab\XFWizard_utils.h>

#include <..\OriginLab\WksOperation.h>

#include <event_utils.h>

#include "StatTestWiz.h"

```

- StatTest()

Add the function body, which specifies the dialog mode.

```

if( script )

    stat_test_run_wiz_nodlg(tn);

else

    stat_test_open_wiz_dlg(tn);

```

- StatTest_before_execute()

Add the function body, which determines not to show this dialog before the wizard is opened.

```
nRet = XFEVT_PROCEED_NO_DLG;
```

Click **Compile** button to compile the file. Then click **Return to Dialog** button to return to **X-Function Builder**. In the **X-Function Builder**, click **Save OXF file** button to save the X-Function.

Script for X-Function StatTestWizGoal

Tutorials for Origin

Open the X-Function StatTestWizGoal. Click **Edit X-Function in Code Builder** button, add the following script.

- Include header files

```
#include "StatTestWiz.h"
```

- Add a static function `_check_input()`

This function is used to check whether the input DataRange is a single column.

```
static bool _check_input(const TreeNode trGetN, string& strErr)
{
    TreeNode trRange = trGetN.input;

    DataRange drInput;

    drInput.Create(trRange.strVal);

    if( drInput.GetNumRanges() == 0 )
    {
        strErr = "Input can't be empty, and it should be a valid column.";

        return false;
    }

    else
    {
        if( drInput.GetNumRanges() == 1)
        {
            Worksheet wksInput;
```

```

    int nC1, nC2;

    drInput.GetRange(wksInput, nC1, nC2);

    if( nC1 == nC2 )

        return true;

    }

    strErr = "Please select one column.";

    return false;

}
}

```

- StatTestWizGoal_event1()

Add the function body, which updates the dialog.

```

StatTestWizCore* pstatwc = (StatTestWizCore*)get_xf_core_handler(trGetN);

ASSERT(pstatwc);

//Update the Wizard page.

if ( 0 == lstrcmp(lpceszNodeName, "goal" ) )

    pstatwc->ChangeGoal(trGetN.goal.nVal);

//Error message is shown at the bottom of the dialog,

//and OK button is disenabled for incorrect choice of DataRange.

```

Tutorials for Origin

```
bOKEnable = _check_input(trGetN, strErrMsg);  
  
return false;
```

Click **Compile** button to compile the file. Then click **Return to Dialog** button to return to **X-Function Builder**, and click **Save OXF file** button to save the X-Function.

Script for X-Function NormalityTest

Open the X-Function **NormalityTest**. Click the **Edit X-Function in Code Builder** button and add the following script.

- Include header files

```
#include "StatTestWiz.h"  
  
#include <XFbase.h>
```

- Add a static function `_update_GUI()`

This function is used to update the dialog's edit boxes for normality test result.

```
static void _update_GUI(TreeNode& trGetN)  
  
{  
  
    vector vRes;  
  
    vRes = _norm_test(trGetN.nXFCorePointer.nVal, trGetN.type.nVal);  
  
    trGetN.stat.dVal = vRes[0];  
  
    trGetN.df.dVal = vRes[1];  
  
    trGetN.prob.dVal = vRes[2];  
  
}
```


- Add a static function `_update_strErr()`

This function is used to update the string shown at the bottom of the dialog.

```
static void _update_strErr(const TreeNode tr, string& strErr)
{
    if(tr.prob.dVal >= 0.05 && tr.prob.dVal <= 1)
        strErr = "At the 0.05 level, the data was significantly drawn from a
                normally distributed population.";
    else if(tr.prob.dVal < 0.05 && tr.prob.dVal >= 0)
        strErr = "At the 0.05 level, the data was not significantly drawn from a
                normally distributed population.";
    else
        strErr = "There is not enough information to draw a conclusion.";
}
```

Note that the string is divided into two lines shown in the page. It should be a command of one line in the script.

- Add a static function `_norm_test()`

This function is used to perform Normality Test using related X-Functions.

```
static vector _norm_test(const int nXFCorePointer, const int nType)
{
    StatTestWizCore* pstatwc =
    (StatTestWizCore*)get_xf_core_handler(nXFCorePointer);

    ASSERT(pstatwc);
}
```

Tutorials for Origin

```
vector vRes(3);

vRes[2] = -1;

DataRange drInput;

drInput = pstatwc->GetRange();

if( !drInput )

    return vRes;

vector<string> vsXFName = {"swtest", "kstest", "lillietest"};

XFBase xfNorm(vsXFName[nType]);

if( !xfNorm.SetArg("irng", drInput) )

{

    error_report("Failed to set argument image type");

    return vRes;

}

if( !xfNorm.SetArg("stat", vRes[0]) )

{

    error_report("Failed to set argument image type");

    return vRes;

}

if( !xfNorm.SetArg("df", vRes[1]) )

{

    error_report("Failed to set argument image type");
```

```

    return vRes;

}

if( !xfNorm.SetArg("prob", vRes[2]) )

{

    error_report("Failed to set argument image type");

    return vRes;

}

if( !xfNorm.Evaluate() )

{

    error_report("Failed to evaluate the stats X-Function.");

    return vRes;

}

return vRes;

}

```

- NormalityTest()

Update the function body, which exports the result into a worksheet when the **Next** button is pressed.

```

    DataRange drInput;

    StatTestWizCore* pstatwc =
(StatTestWizCore*)get_xf_core_handler(nXFCorePointer);

    ASSERT(pstatwc);

```

Tutorials for Origin

```
drInput = pstatwc->GetRange();

if( !drInput )

    return;

string strBook, strSheet;

if(!drInput.GetBookSheet(strBook, strSheet))

{

    error_report("Workbook and worksheet names can't be obtained.");

    return;

}

WorksheetPage wpData(strBook);

int nLayer = wpData.AddLayer("Normality Test");

if(nLayer >= 0)

{

    Worksheet wksRes = wpData.Layers(nLayer);

    vector<string> vsTypeName = {"Shapiro-Wilk", "Kolmogorov-
Smirnov", "Lilliefors"};

    vector<string> vsNProb = {"Prob<W", "Prob>D", "Prob>D"};

    vector<string> vsParaName = {"Statistic", "DF", ""};

    vsParaName[2] = vsNProb[type];
```

```

vector vRes;

vRes = _norm_test(nXFCorePointer, type);

wksRes.Columns(1).SetLongName(vsTypeName[type]);

for(int ii=0; ii<3; ii++)

{

    wksRes.SetCell(ii, 0, vsParaName[ii], false);

    wksRes.SetCell(ii, 1, vRes[ii]);

}

}

else

{

    error_report("New worksheet can't be created.");

}

```

- NormalityTest_event1()

Update the function body, which will update the results in the dialog as the method of normality test changes. Strings shown at the bottom of the dialog will also be updated.

```

_update_GUI(trGetN);

_update_strErr(trGetN, strErrMsg);

return true;

```

Tutorials for Origin

- NormalityTest_before_execute()

Update the function body, which will make the edit boxes for results grayed out, and show the result in the dialog.

```
trGetN.stat.Enable = false;  
  
trGetN.df.Enable = false;  
  
trGetN.prob.Enable = false;
```

Click the **Compile** button to compile the file. Then click the **Return to Dialog** button to return to **X-Function Builder**, and click the **Save OXF file** button to save the X-Function.

Script for X-Function OnetTest

Open the X-Function **OnetTest**. Click the **Edit X-Function in Code Builder** button and add the following script.

- Include header files

```
#include "StatTestWiz.h"  
  
#include <XFbase.h>
```

- Define strings

```
const vector<string> vsNull = {"Mean = ", "Mean <= ", "Mean >= "};  
  
const vector<string> vsAlter = {"Mean <> ", "Mean > ", "Mean < "};  
  
const vector<string> vsAcceptNull = {"Not significantly different from", "Not  
significantly greater than", "Not significantly less than"};  
  
const vector<string> vsRejectNull = {"significantly different from", "significantly  
greater than", "significantly less than"};  
  
const vector<string> vsProb = {"Prob>|t|", "Prob>t", "Prob<t"};
```

- Add a static function _update_null()

This function is used to update the **Null** edit box.

```
static void _update_null(TreeNode& trGetN, bool bMean = false)
{
    string strNull;

    strNull = vsNull[trGetN.tail.nVal] + ftoa(trGetN.mean.dVal);

    trGetN.null.strVal = strNull;

    if(bMean)
    {
        string strAlter = vsAlter[0] + ftoa(trGetN.mean.dVal) + "|";
        strAlter = strAlter + vsAlter[1] + ftoa(trGetN.mean.dVal) + "|";
        strAlter = strAlter + vsAlter[1] + ftoa(trGetN.mean.dVal);

        trGetN.tail.SetAttribute(STR_COMBO_ATTRIB, strAlter);
    }
}
```

- Add a static function `_check_sig_level()`

This function is used to check the **Significance Level** edit box value.

```
static bool _check_sig_level(TreeNode& trGetN, string& strErr)
{
    if( trGetN.siglevel.dVal > 0 && trGetN.siglevel.dVal < 1 )
```

Tutorials for Origin

```
{  
  
    return true;  
  
}  
  
else  
  
{  
  
    strErr = "Significance Level should be between 0 and 1.";  
  
    return false;  
  
}  
  
}
```

- Add a static function `_update_strErr()`

This function is used to define the string for the conclusion of t-test at the bottom based on P-value.

```
static void _update_strErr(const TreeNode tr, string& strErr)  
  
{  
  
    if(tr.tprob.dVal >= tr.siglevel.dVal && tr.tprob.dVal <= 1)  
  
        strErr.Format("Null Hypothesis is %s%. \r\nAlternative Hypothesis is %s%.  
  
        At the %s level, the population mean is %s the test mean(%s).",  
  
        vsNull[tr.tail.nVal], ftoa(tr.mean.dVal), vsAlter[tr.tail.nVal],  
ftoa(tr.mean.dVal),  
  
        ftoa(tr.siglevel.dVal), vsAcceptNull[tr.tail.nVal], ftoa(tr.mean.dVal) );  
  
    else if(tr.tprob.dVal < tr.siglevel.dVal && tr.tprob.dVal >= 0)  
  
        strErr.Format("Null Hypothesis is %s%. \r\nAlternative Hypothesis is %s%.  
  
        At the %s level, the population mean is %s the test mean(%s).",
```



```

        vsNull[tr.tail.nVal], ftoa(tr.mean.dVal), vsAlter[tr.tail.nVal],
ftoa(tr.mean.dVal),

        ftoa(tr.siglevel.dVal), vsRejectNull[tr.tail.nVal], ftoa(tr.mean.dVal) );

else

    strErr = "There is not enough information to draw a conclusion.";

}

```

Note that the command is divided into several lines shown in the page. It should be a command of one line in the script.

- Add a static function `_update_GUI()`

This function is used to update edit boxes for results in the dialog.

```

static void _update_GUI(TreeNode& trGetN)

{

    vector vRes;

    vRes = _one_sample_t_test(trGetN.nXFCorePointer.nVal, trGetN.mean.dVal,
trGetN.tail.dVal, trGetN.siglevel.dVal);

    trGetN.stat.dVal = vRes[0];

    trGetN.df.dVal = vRes[1];

    trGetN.tprob.dVal = vRes[2];

    trGetN.lcl.dVal = vRes[4];

    trGetN.ucl.dVal = vRes[5];

}

```

- Add a static function `_one_sample_t_test()`

Tutorials for Origin

This function is used to perform One-Sample t-Test using an X-Function.

```
static vector _one_sample_t_test(const int nXFCorePointer, const double dMean,
const int nTail, const double dSiglevel)

{

    DataRange drInput;

    StatTestWizCore* pstatwc =
(StatTestWizCore*)get_xf_core_handler(nXFCorePointer);

    ASSERT(pstatwc);

    vector vRes(6);

    vRes[2] = -1;

    drInput = pstatwc->GetRange();

    if( !drInput )

        return vRes;

    vRes[3] = 100 - 100*dSiglevel;

    XFBase xfTTest("ttest1");

    if( !xfTTest.SetArg("irng", drInput) )

    {

        error_report("Failed to set argument irng");

        return vRes;

    }

}
```

```
if( !xfTTest.SetArg("mean", dMean) )  
  
{  
  
    error_report("Failed to set argument mean");  
  
    return vRes;  
  
}  
  
if( !xfTTest.SetArg("tail", nTail) )  
  
{  
  
    error_report("Failed to set argument tail");  
  
    return vRes;  
  
}  
  
if( !xfTTest.SetArg("alpha", dSiglevel) )  
  
{  
  
    error_report("Failed to set argument alpha");  
  
    return vRes;  
  
}  
  
if( !xfTTest.SetArg("stat", vRes[0]) )  
  
{  
  
    error_report("Failed to set argument stat");  
  
    return vRes;  
  
}  
  
if( !xfTTest.SetArg("df", vRes[1]) )
```

Tutorials for Origin

```
{  
  
    error_report("Failed to set argument df");  
  
    return vRes;  
  
}  
  
if( !xfTTest.SetArg("prob", vRes[2]) )  
  
{  
  
    error_report("Failed to set argument prob");  
  
    return vRes;  
  
}  
  
if( !xfTTest.SetArg("lcl", vRes[4]) )  
  
{  
  
    error_report("Failed to set argument lcl");  
  
    return vRes;  
  
}  
  
if( !xfTTest.SetArg("ucl", vRes[5]) )  
  
{  
  
    error_report("Failed to set argument ucl");  
  
    return vRes;  
  
}  
  
if( !xfTTest.Evaluate() )  
  
{
```

```

    error_report("Failed to evaluate the ttest1 X-Function.");

    return vRes;
}

return vRes;
}

```

- OnetTest()

Update the function body, which exports the result into a worksheet when the **Finish** button is pressed.

```

    DataRange drInput;

    StatTestWizCore* pstatwc =
(StatTestWizCore*)get_xf_core_handler(nXFCorePointer);

    ASSERT(pstatwc);

    drInput = pstatwc->GetRange();

    if( !drInput )

        return ;

    string strBook, strSheet;

    if(!drInput.GetBookSheet(strBook, strSheet))

    {

        error_report("Workbook and worksheet names can't be obtained.");

        return;
    }

```

Tutorials for Origin

```
}  
WorksheetPage wpData(strBook);  
  
int nLayer = wpData.AddLayer("One-Sample t-test");  
  
if(nLayer >= 0)  
{  
    Worksheet wksRes = wpData.Layers(nLayer);  
  
    vector<string> vsParaName = {"t Statistic", "DF","", "Conf. Levels in %",  
"Lower Limits", "Lower Limits"};  
  
    vsParaName[2] = vsProb[tail];  
  
    vector vRes;  
  
    vRes = _one_sample_t_test(nXFCorePointer, mean, tail, siglevel);  
  
    wksRes.SetSize(-1, 4);  
  
    wksRes.Columns(0).SetLongName("Test Statistics");  
  
    string strNull = "Null Hypothesis is " + vsNull[tail] + ftoa(mean);  
  
    wksRes.Columns(1).SetLongName(strNull);  
  
    wksRes.Columns(3).SetLongName("Confidence Intervals for Mean");  
  
    for(int ii=0; ii<3; ii++)  
  
    {
```

```

        wksRes.SetCell(ii, 0, vsParaName[ii], false);

        wksRes.SetCell(ii, 1, vRes[ii]);

        wksRes.SetCell(ii, 2, vsParaName[ii + 3], false);

        wksRes.SetCell(ii, 3, vRes[ii + 3]);

    }

}

else

{

    error_report("New worksheet can't be created.");

}

```

- OnetTest_event1()

Update the function body, which will update results and show a conclusion at the bottom of the dialog according to the result. As settings change in the dialog, the **Null** edit box will be updated as the mean and hypothesis change, and the **Significance Level** edit box's value is checked.

```

if( 0 == lstrcmp(lpVtblNodeName, "mean") )

    _update_null(trGetN, true);

if( 0 == lstrcmp(lpVtblNodeName, "tail") )

    _update_null(trGetN);

if( 0 == lstrcmp(lpVtblNodeName, "siglevel") )

    bOKEnable = _check_sig_level(trGetN, strErrMsg);

_update_GUI(trGetN);

```

Tutorials for Origin

```
_update_strErr(trGetN, strErrMsg);
```

```
return false;
```

- OnetTest_before_execute()

Update the function body, to show/hide or disable the controls in the dialog.

```
StatTestWizCore* pstatwc =  
(StatTestWizCore*)get_xf_core_handler(trGetN.nXFCorePointer.nVal);  
  
ASSERT(pstatwc);  
  
trGetN.prob.Show = 1 - pstatwc->nStep;  
  
trGetN.prob.Enable = false;  
  
trGetN.null.Enable = false;  
  
trGetN.stat.Enable = false;  
  
trGetN.df.Enable = false;  
  
trGetN.tprob.Enable = false;  
  
trGetN.lcl.Enable = false;  
  
trGetN.ucl.Enable = false;
```

Click the **Compile** button to compile the file. Then click the **Return to Dialog** button to return to the X-Function Builder. Click the **Save OXF file** button to save the X-Function.


Close Origin. Then start Origin and you will notice that a new item **Stat Test** is added to Origin's menu **Statistics: Hypothesis Testing**.

12.3.4.7 How to Use the Wizard


The following example shows how to use the wizard.

1. Select a column in the worksheet.

2. Select **Statistics: Hypothesis Testing: Stat Test** from the Origin menu or type the command "StatTest -d" in the command window. The **Stat Test** wizard dialog will open.



3. Click the **Next** button. The **Normality Test** dialog is opened. The result is shown in the **Output** branch. A conclusion is drawn at the bottom of the dialog.



4. Click the **Next** button. The **One-Sample t-test** dialog is opened. The result is shown in the **Output** branch. A conclusion is drawn at the bottom of the dialog. Previous step's result of normality test is shown at the top. You can also change the setting in the dialog, and notice the result changes.

Stat Test

Dialog Theme

Goal
Normality Test
One-Sample t-test
Finish

Prev Next Finish Cancel

One-Sample t-test

Prob of Normality Test 0.73775

Test Mean 0

Null Hypothesis Mean=0

Alternate Hypothesis

- Mean <> 0
- Mean > 0
- Mean < 0

Significance Level 0.05

Conclusion

Null Hypothesis is Mean = 0.
Alternative Hypothesis is Mean <> 0.
At the 0.05 level, the population mean is Not significantly different from the test mean(0).

The screenshot shows the 'Stat Test' dialog box in Origin. The 'Dialog Theme' is set to a default. The workflow tree on the left shows 'Goal', 'Normality Test', 'One-Sample t-test' (highlighted in green), and 'Finish'. The 'One-Sample t-test' section is expanded, showing the following output:

Statistic	Value
Statistic	-1.50326
Degrees of Freedom	31
P-value	0.14289
Lower Confidence Limit	-0.6201
Upper Confidence Limit	0.09386

A pink arrow points to the 'Statistic' value of -1.50326, which is labeled 'Result' in pink text. Below the output table, the following text is displayed in red:

**Null Hypothesis is Mean = 0.
Alternative Hypothesis is Mean <> 0.
At the 0.05 level, the population mean is Not significantly different from the test mean(0).**

- Click the **Finish** button to end the wizard. Two worksheets for results are created.

	A(X)	B(Y)
Long Name	Shapiro-Wil	
Units		
Comments		
1	Statistic	0.97794
2	DF	32
3	Prob<W	0.73775

	A(X)	B(Y)	C(Y)	D(Y)
Long Name	Test Statisti	Null Hypoth		Confidence
Units				
Comments				
1	t Statistic	-1.50326	Conf. Levels in %	95
2	DF	31	Lower Limits	-0.6201
3	Prob> t	0.14289	Lower Limits	0.09386

Index

2	
2D Binning.....	582
2D FFT and Filter	367
2D Pie Chart of a Population Study	990
2D Vector Graph	1741
2D Waterfall.....	1748
3	
3D and Contour	18
3D Bar and Symbol	1536
3D Bar on Flatten Surface.....	1651
3D Bar with Labels	711
3D Pie Chart.....	1526
3D Scatter Plot with Line Projections of Core Drilling Locations	1531
3D Scatter with Colormap	1623
3D Scatter with Droplines.....	1632
3D Surface with Point Label.....	1659
3D Ternary Colormap Surface with Contour Lines Projection.....	1710
3D Ternary Scatter Plot with drop lines	1719
3D Vector	1527
3D Waterfall.....	1757
3Ys Y-YY	1085
A	
Accessing Internal Origin Objects by Origin C1995	
Add multiple fitted curves in a Histogram.....	1398
Adding a Data Plot to Existing Graph	757
Adding and Arranging Layers.....	856
Adding New Origin C Functions to Origin	1977
Adding Objects to Worksheet	1777
Analysis Template	32
Analysis Themes	542
Apps in Origin.....	34
B	
Bar and Scatter Plot with Error Bar	1009
Bar Graph of African Population	994
Basic 2D Plotting	737
Basic 3D Plotting	744
Batch Peak Analysis Using Theme with Script Before Each Process	435
Batch Processing Grouped Datasets Using Analysis Template with Multi-Data Sheets..	558
Batch Processing Multiple Datasets using Analysis Template.....	548
Batch Processing Multiple Files using Analysis Template	546
Batch Processing with Summary Report in External Excel File	550
Batch Processing with Word Template for Reporting.....	551
Box Plot.....	1225
C	
Categorical Values Ordering and Sharing	524
Cluster Analysis	675
Cluster Gadget.....	79
Clustered-Stacked Column Chart	1033
Coherence and Correlation.....	396
Color Map Surface Graph.....	1587
Colormap from Second Matrix	1579
Column Graph with Error Bars.....	1014
Column/Bar Gap/Offset Across Layers.....	1019
Combine Quick Peaks Gadget with Peak Analyzer	439
Combining Line and Contour Plots	1174
Command Window and X-Functions	2004
Compare Graphs Dynamically by Changing Data Filters.....	841
Complicated Fill Area	886
Connectivity	1937
Contour Graph with XY Data Points and Z Labels.....	1182
Contour Plot with Vector Overlay.....	1187
Contour Plots and Color Mapping.....	1156
Convert Data from Spherical Coordinate to XYZ and Make a 3D Plot	1679
Convolution	375
Copy and Apply a Plot Format to Another Plot	884
COX Model Estimator	661
Create an 8 layer multi-panel plot template .	1129
Create and Subtract Baseline with Peak Analyzer	425
Create and Update Apps for Origin	1999
Create Heat Map with Virtual Matrix and Colormap Bar Plot.....	1201
Creating a Custom Report Sheet.....	537
Creating a Graph	719

Tutorials for Origin

Creating Analysis Templates using Set Column Value	533	Fitting with an Ordinary Differential Equation	284
Creating and Using Analysis Templates	530	Fitting with Convolution	247
Creating Intersecting Surface Plots from Worksheets	1557	Fitting with Convolution of Two Functions	293
Cross Tabulation	574	Fitting with Integral using LabTalk Function ..	229
Curve Fitting	23	Fitting with Integral using NAG Library	222
Curve Intersection Gadget	64	Fitting With Multiple Independent Variables ..	198
D		Fitting with NAG Special Function	210
Data Filter	505	Fitting with Piecewise Functions	263
Data Reader Tool	1785	Fitting with Summation	240
Data Reduction	491	Fitting with Two Integrals using LabTalk Function	235
Data Selection	8	Flattened Colormap Surfaces with Increasing Z Offset	1705
Decimation and Signal Envelope	404	G	
Descriptive Statistics	563	Gadgets	21
Digitizer Tool	1859	Global Fit for Different Functions with Shared Parameters	177
Discriminant Analysis	683	Global Fitting with Parameter Sharing	173
Distribution Fit	588	Global Vertical Cursor	55
Distribution Fit with the Probability Density Function and Cumulative Distribution Function	272	Graph Templates and Batch Plotting	4
Double Y	1077	Grouped Box Chart with Color Indexed Data Points	1237
E		Grouped Box Plot	1340
Energy-Level Structure of the Er ³⁺ Ion in A YAG Crystal	1119	Grouped Column with Error Bars and Data Labels	1041
Enhanced Digitizer	1867	Grouped Stacked Column	1052
Error Bars with Fill Area	764	H	
Excel	1937	Histogram with Distribution Curve overlay ..	1431
Exporting	1921	How to Create a Wizard	2015
Exporting Graphs	1921	How to share Origin C based LabTalk Functions	1955
F		Hypothesis Tests	597
FFT and IFFT	335	I	
FFT Filter	341	I Shaped Box Plot	1251
Fill Partial Area between Curves	895	IIR Filter	362
Fit Curve Through Certain Points	265	Implicit Fitting with Three Variables	325
Fit Function with Non-constant Background ..	256	Import Data from a Database	1816
Fit Multiple Datasets by Fitting One and then Using Those Fit Parameters for Other Datasets	317	Import Data from a Database for Analysis ..	1828
Fitting Complex Function	244	Import Time Data	1802
Fitting Integral Function with a Sharp Peak ..	274	Import Wizard	1799
Fitting Integral Function with parametric limit using NAG Library	215	Importing Multiple Files into Workbooks Cloned from Active Workbook	1844
Fitting One Dataset as a Function of Other Datasets	196	Integrate Gadget	58
Fitting with a Piecewise Linear Function	278	Integrating Peaks	449
		Interpolate Gadget	76
		Intersecting Color Surfaces	1566

Introduction to Origin C and Code Builder ...	1959	Origin GUI	39
Introduction to X-Functions	2011	Overlapping Box Chart	1285
K		Overview of Customization	772
Kaplan-Meier Estimator.....	653	P	
L		Panel Graph with Inset Plots of High- resolution Electron Energy-loss Spectra... 1131	
LabTalk.....	1955	Parameter Initialization for Rational Functions	300
Line and Symbol	885	Parameters Initialization using LabTalk in NLFit.....	182
Line Graph with Masked Data.....	950	Parametric Surface with Colormap from Data	1591
Line Graph with Recession Bars.....	908	Partial Correlation Coefficient	594
Linear Fit for Kinetic Models.....	139	Partial Least Squares	693
Linear Fitting and Outlier Removal	135	Pasting or Embedding Graphs in Other Applications.....	1929
Lock Filter with Analysis.....	510	Peak Analysis	26
M		Peak Finding	445
Marginal Distribution Curve.....	1269	Peak Fitting	455
Mark out a segment of plot with different plot style	768	Peak Fitting with Baseline.....	455
Merge and Arrange Graphs	11	Peak Fitting with Preset Peak Parameters ...	462
Merging and Arranging Graphs.....	858	Peak Integration.....	449
Micro-Raman spectroscopy of complex nanostructured mineral systems	928	Picking and Marking Peaks	446
Modifying Derived Parameters in Build-in Functions.....	312	Piper Diagram	1743
Multi-Data Dot Chart	1375	Pivot Table	513
Multi-line-plot with Special Position Annotation Line.....	936	Plot and Customize Date Time Data on Graph	836
Multiple Axis Breaks.....	814	Plot from User Defined Graph Template	751
Multiple Axis Plot.....	1111	Plot Functions with Parameters Defined in a Worksheet.....	1724
Multiple Layers with Linked Axis	868	Plotting Overlapping Data and Setting Transparency	800
Multiple Surfaces in Same Layer	1610	Plotting using Plot Setup.....	805
My First Graph	1	Polar Contour.....	1433
N		Polar Crop.....	1458
Nonlinear Curve Fit Tool	151	Polar Graph with Columns and Stack Columns	1498
Nonlinear Fitting	150	Polar Graph with Custom Angular Scale	1516
Nonlinear fitting using Orthogonal Distance Regression	332	Polar Graph with Custom Radial Axes	1471
Nonlinear Fitting with System Function.....	162	Polar Graph with Multiple Layers.....	1484
Nonlinear Multiple Variables Fitting	308	Polar Plot with Error Bar	1452
Non-parametric Statistics Overview	642	Post Processing with Import Filter	1807
Notched Boxes with Variable Width Control	1354	Power and Sample Size	702
O		Presentation.....	1929
One Way ANOVA.....	608	Principal Component Analysis	666
One-Way Repeated Measures ANOVA.....	614	Publishing Graphs.....	16
Open-High-Low-Close-Volume Stock Chart	1763	Q	
Organizing and Accessing Origin C Functions	1979	Q-Q Plot.....	1412
Origin C	1959	Quick Fit Gadget.....	92

Tutorials for Origin

Quick Peaks Gadget	104	Transparent Parametric Surfaces combined with Scatter Plot	1671
Quick Sigmoidal Fit Gadget	109	Tutorial	
Quoting Built-in Functions in Your New Function.....	252	Calculating Double Integral with NAG Functions From Origin C.....	1983
R		Calling NAG Functions From Origin C.....	1989
Rise Time	410	Importing Data	1808
Rise Time Gadget	69	Two Way ANOVA	618
ROC curve.....	707	Two Way Repeated Measures ANOVA.....	624
S		Two-Level Grouped Box Chart	1301
Scatter Central Plot.....	942	Two-Way Mixed-Design ANOVA.....	629
Scatter Matrix	1421	U	
Scatter Plot of Decay and Recovery Curves..	917	Unbalanced Grouped Box Chart.....	1324
Send Graphs to PowerPoint.....	1933	Update Database Importing By LabTalk Substitution	1884
Setting Column Values.....	475	Update Graph By Reimport Data From Database.....	1894
Setting the Fix, Share Status or Bounds for Multiple Peak Parameters Simultaneously .	469	Use Data Cursor to Show the Difference between the Data.....	1789
Signal Processing	335	Use Script to Search for Baseline Anchor Points in Peak Analyzer	432
Simple Dot Chart.....	1367	User Defined Fitting Function	189
Single ASCII.....	1797	User Defined Fitting Function using GNU Scientific Library.....	201
Smart Peak Labels with Leader Line	759	User-Defined Arbitrary Tick Positions.....	825
Smoothing	347	Using Multiple Gadgets.....	121
Sound Processing	417	V	
SQL Editor for Database Analysis	1847	Variable Column Width	1067
Stack Column and Bar Charts of Rechargeable Battery Statistics	1073	Vertical 2 Panel Line	1103
Stack Column Plot with Different Positive and Negative Y Scale.....	1061	Video Tutorials	37
Stack Column With Labels	1025	W	
Stack Lines by Y Offsets	1096	Waterfall.....	1748
Stacked 3D Surface Plots	1603	Wavelet	378
Statistics	29	Weibull Fit.....	664
STFT (Short-Time Fourier Transform).....	355	Weibull Probability Plot	1404
Surface Fitting with Multiple Peaks	307	Windrose Graph.....	1730
Surface with Missing Values	1550	Working with Excel.....	1937
Surface with Symbols and Droplines	1571	Working with Multi-Sheet Workbooks	1771
Surface With Transparent Plane	1640	Worksheet Query	488
Symbol Plot with Color Transparency	956	X	
Symbol Plot with Size and Colormap from Other Columns	969	X-Functions.....	2004
T		XYZ Contour	1146
Ternary Contour	1168		
The Code Builder Workspace	1967		
Three-Way ANOVA.....	634		